

TENDER

TENDER NOTIFICATION NO. - **FCX/21221015**

FOR

**Repair/maintenance of existing sanitary installations
/drinking points etc. inside factory area.**

PRICE BID



FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION

BHARAT HEAVY ELECTRICALS LIMITED

(A Government of India Undertaking)

BHOPAL – 462 022 (M.P)

PREAMBLE OF PRICE BID

1.0 This Price Bid consists of Three Schedule:

1.1 Schedule A

Schedule A consists of One Annexure:

The evaluation currency for this tender shall be INR. Total price of the package consisting of **Annexure I** to be quoted by the bidders which shall form the basis for comparison for deciding lowest bid. For further processing and award, total quoted amount by the L1 (lowest) bidder for the package shall be used for deriving individual item rate by BHEL based on % (percentage) weightage specified at Annexure I of Price Schedule.

1.2 Schedule B

It consists of details of free issue materials by BHEL.

1.3 Schedule C

It consists of details of tools & tackles provided by BHEL either on higher basis or on free of cost basis which are mentioned in price bid.

2.0 The work to be carried out under the contract shall, except as otherwise provided in tender conditions, include all labour, materials, tools, plant, equipment, and transport which may be required in preparation of and for full & entire execution and completion of the Works. The descriptions given in the Schedule of Quantities shall, unless otherwise stated, be held to include waste on materials, carriage and cartage, carrying in return of empties, hoisting, setting, fitting and fixing in position and all other labours necessary in and for the full and entire execution and completion as aforesaid in accordance with good practice and recognized principles as laid down in Technical Specification & elsewhere in Tender Specification.

3.0 The price bid should not contain any condition. Conditional price Bids shall be summarily rejected.

4.0 The bidder should not leave any column blank in Price Schedules.

5.0 Price Quoted shall include all taxes, & duties except **GST**.

6.0 Unless otherwise specified in the items involving cement, reinforcement steel or structural steel, these items shall be issued free of cost by BHEL.

FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION**Price Schedule**

Repair/maintenance of existing sanitary installations /drinking points etc. inside factory area.

SUMMARY

	Details ANNEXURE	Total Amount (Rs.)
	Total price of the package consisting of Annexure-I.	

Amount in words: Rs.

.....

.....

NOTE:

- 1 The evaluation currency for this tender shall be INR. Total price of the package consisting of **Annexure-I** to be quoted by the bidders which shall form the basis of comparison for deciding lowest bid.
For further processing & award total quoted Amount for the package by the L1 (lowest) bidder shall be used for deriving Individual item rate by BHEL based on % (percentage) weightage specified at **Annexure-I** of Price Schedule.
- 2 In case of “discrepancy in words and figures”, the same shall be adjusted in accordance with following rule:
 - (a) If, in the price structure quoted for the required goods/ services/ works, there is discrepancy between the unit price and the total price (which is obtained by multiplying the unit price by the quantity), the unit price shall prevail and the total price corrected accordingly, unless in the opinion of the purchaser there is an obvious misplacement of the decimal point in the unit price, in which case the total price as quoted shall govern and the unit price corrected accordingly.
If there is an error in a total corresponding to the addition or subtraction of subtotals, the subtotals shall prevail and the total shall be corrected.
 - (c) If there is a discrepancy between words and figures, the amount in words shall prevail, unless the amount expressed in words is related to an arithmetic error, in which case the amount in figures shall prevail subject of (a) and (b) above.
 - (d) If there is such discrepancy in an offer, the same shall be conveyed to the bidder with target date upto which the bidder has to send his acceptance on the above lines and if the bidder does not agree to the decision of the purchaser, the bid is liable to be ignored.

FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION**Price Schedule A : Anneuxre - I**

Name of work :Repair/maintenance of existing sanitary installations /drinking points etc. inside factory area.

Sr. No.	DSR-12 Items	Item Description	Qty.	Unit	% Weightage of item amount against total amount
1		Carriage of materials by mechanical transport including loading, unloading and stacking --- 1 Km lead			
(a)	1.1.1	Lime, Moorum, building rubbish	10.00	cum	0.1608
(b)	1.1.2	Earth	0.25	cum	0.0050
2		Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.			
	2.8.1	All kinds of soil.	0.50	cum	0.0159
3		Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth upto 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m :			
	2.10.1.2	Pipes, cables etc. exceeding 80 mm dia. but not exceeding 300 mm dia	25.00	metre	1.0052
4	2.25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	0.50	cum	0.0102
5	**	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:(Cement free issue by the Deptt.)			
(a)	4.1.3	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	4.00	cum	2.5023
(b)	4.1.8	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).	0.50	cum	0.3070

FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION**Price Schedule A : Anneuxre - I**

Name of work :Repair/maintenance of existing sanitary installations /drinking points etc. inside factory area.

Sr. No.	DSR-12 Items	Item Description	Qty.	Unit	% Weightage of item amount against total amount
6	**	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centering, shuttering, finishing and reinforcement - All work upto plinth level. (Cement free issue by the Deptt.)			
	5.1.3	1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	2.00	cum	1.3434
7		Centering and shuttering including strutting, propping, etc. and removal of form for:			
(a)	5.9.1	Foundations, footings, bases of columns, etc. for mass concrete.	5.00	sqm	0.1888
(b)	5.9.5	Lintels, beams, plinth beams, girders, bressumers and cantilevers.	5.00	sqm	0.3051
8	Ana. 5.22.6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. (Reinforcement bars will be supplied free of cost from BHEL store).			
		Thermo-Mechanically Treated bars.	50.00	Kg	0.0898
9	**	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills , facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. (Cement free issue by the Deptt.)			
		Granite of any colour and shade			
		Note: The colour of granite shall be zed black. Sample is to be got approved before fixing.			
	8.2.2.2	Area of slab over 0.50 sqm	35.00	sqm	22.1731

FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION**Price Schedule A : Anneuxre - I**

Name of work :Repair/maintenance of existing sanitary installations /drinking points etc. inside factory area.

Sr. No.	DSR-12 Items	Item Description	Qty.	Unit	% Weightage of item amount against total amount
10		Providing and fixing stone slab with table rubbed, edges rounded and polished, of size 75x50 cm deep and 1.8 cm thick, fixed in urinal partitions by cutting a chase of appropriate width with chase cutter and embedding the stone in the chase with epoxy grout or with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 6 mm nominal size) as per direction of Engineer-in-charge and finished smooth.			
	8.10.2	Granite Stone of approved shade.	2.50	sqm	1.6143
		Note: The colour of granite shall be zed black. Sample is to be got approved before fixing.			
11	9.84	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etc. complete.	20.00	each	4.0598
12		Providing and fixing aluminium sliding door bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with nuts and screws, etc., complete.			
	9.96.2	250 x 16 mm.	2.00	each	0.0708
13	9.119	Providing and fixing factory made P.V.C. door frame of size 50x47 mm with a wall thickness of 5 mm, made out of extruded 5mm rigid PVC foam sheet, mitred at corners and joined with 2 Nos of 150 mm long brackets of 15x15 mm M.S. square tube, the vertical door frame profiles to be reinforced with 19x19 mm M.S. square tube of 19 gauge, EPDM rubber gasket weather seal to be provided through out the frame. The door frame to be fixed to the wall using M.S. screws of 65/100 mm size, complete as per manufacturer's specification and direction of Engineer-in-Charge.	50.00	metre	4.1982

FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION**Price Schedule A : Anneuxre - I**

Name of work :Repair/maintenance of existing sanitary installations /drinking points etc. inside factory area.

Sr. No.	DSR-12 Items	Item Description	Qty.	Unit	% Weightage of item amount against total amount
14		Providing and fixing factory made panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19 mm x 19 mm for styles and 15x15 mm for top & bottom rails. M.S. frame shall have a coat of steel primers of approved make and manufacture. M.S. frame covered with 5 mm thick heat moulded PVC 'C' channel of size 30 mm thickness, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on both side forming styles and 5 mm thick, 95 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm shall be tapered in 45 degree on the inner side to form top and bottom rail and 115 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided both side of the panel. 10 mm (5 mm x 2) thick, 20 mm wide cross PVC sheet be provided as gap insert for top rail & bottom rail, paneling of 5 mm thick both side PVC sheet to be fitted in the M.S. frame welded/ sealed to the styles & rails with 7 mm (5 mm+2 mm) thick x 15 mm wide PVC sheet beading on inner side, and joined together with solvent cement adhesive. An additional 5 mm thick PVC strip of 20 mm width is to be stuck on the interior side of the 'C' Channel using PVC solvent adhesive etc. complete as per direction of Engineer-in-charge, manufacturer's specification & drawing. (Sample is to be got approved before fixing)			
	9.120.2	30 mm thick pre laminated PVC door shutters	10.00	sqm	5.1816
15	** 11.36	Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS:15622 (thickness to be specified by the manufacture) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risere of steps and dados over 12 mm thick bed of Cement Mortar 1:3 (1 Cement :3 Coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete. (Cement free issue by the Deptt.)	100.00	sqm	14.3016

FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION**Price Schedule A : Anneuxre - I**

Name of work :Repair/maintenance of existing sanitary installations /drinking points etc. inside factory area.

Sr. No.	DSR-12 Items	Item Description	Qty.	Unit	% Weightage of item amount against total amount
16	** 11.37	Providing and laying Ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours, such as White, Ivory, Grey, Fume, Red Brown, laid on 20mm thick Cement Mortar 1:4 (1 cement : 4 Coarse sand) including pointing the joints with white cement and matching pigment etc., complete.(Cement free issue by the Deptt.)	25.00	sqm	3.6476
17		Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion			
		(i) Single socketed pipes:			
(a)	12.41.1	75 mm dia.	15.00	metre	0.4097
(b)	12.41.2	110 mm dia.	20.00	metre	0.8904
18		Providing and fixing on wall face unplasticised-PVC moulded fittings/accessories for unplasticised - Rigid PVC rain water pipes conforming to IS : 13592 Type A including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion:			
		1) Coupler			
	12.42.1.1	a) 75 mm	3.00	each	0.0625
	12.42.1.2	b) 110 mm	3.00	each	0.0829
		2) Single tee with door.			
	12.42.3.1	a) 75x75x75 mm	2.00	each	0.0869
	12.42.3.2	b) 110x110x110 mm.	2.00	each	0.1259
		3) Single tee without door			
	12.42.4.1	a) 75x75x75 mm.	5.00	each	0.1933
	12.42.4.2	b) 110x110x110 mm.	5.00	each	0.2527
		4)Bend 87.5 degree			
	12.42.5.1	a) 75 mm bend.	2.00	each	0.0445
	12.42.5.2	b) 110 mm bend.	5.00	each	0.1657
		5) Shoe (Plain)			
	12.42.6.1	a) 75 mm Shoe.	5.00	each	0.1723
	12.42.6.2	b) 110 mm Shoe.	5.00	each	0.2994

FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION**Price Schedule A : Anneuxre - I**

Name of work :Repair/maintenance of existing sanitary installations /drinking points etc. inside factory area.

Sr. No.	DSR-12 Items	Item Description	Qty.	Unit	% Weightage of item amount against total amount
19		Providing and fixing unplasticised-PVC pipe clips of approved design to unplasticised-PVC rain water pipes by means of 50x50x50 mm hard wood plugs, screwed with M.S. screws of required length including cutting brick work and fixing in cement mortar 1 : 4 (1 cement : 4 coarse sand) and making good the wall etc. complete: .(Cement free issue by the Deptt.)			
(a)	12.43.1	75 mm.	2.00	each	0.0590
(b)	12.43.2	110 mm.	2.00	each	0.0661
20	**	12 mm cement plaster of mix:(Cement free issue by the Deptt.)			
	13.4.2	1 : 6 (1 cement : 6 coarse sand) .	10.00	sqm	0.2409
21	**	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sqm and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete including disposal of rubbish to the dumping ground within 50 metres lead: (Cement free issue by the Deptt.)			
	14.1.2	With cement mortar 1 : 4 (1 cement : 4 coarse sand).	20.00	sqm	0.7563
22		Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade.			
	14.45.1	Old work(one or more coats).	25.00	sqm	0.1360
23	14.46	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches, etc. complete.	25.00	sqm	0.0455
24	15.1	Demolishing lime concrete manually/ by mechanical means and disposal of material within 50 metres lead as per direction of Engineer-in-charge.	0.25	cum	0.0142
25		Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge.			

FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION**Price Schedule A : Anneuxre - I**

Name of work :Repair/maintenance of existing sanitary installations /drinking points etc. inside factory area.

Sr. No.	DSR-12 Items	Item Description	Qty.	Unit	% Weightage of item amount against total amount
(a)	15.2.1	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	3.00	cum	0.4888
(b)	15.2.2	Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	3.00	cum	0.3013
26	15.3	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.	0.25	cum	0.0594
27		Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.			
	15.7.4	In cement mortar.	5.00	cum	0.6879
28		Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge:			
	15.9.2	In cement mortar	0.25	cum	0.0410
29		Dismantling doors, windows and clerestory windows (steel or wood) shutter including chokhats, architrave, holdfasts, etc. complete and stacking within 50 metres lead:			
	15.12.1	Of area 3 sqm and below.	25.00	each	0.6173
30		Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead:			
	15.13.1	Of area 3 sqm and below.	2.00	each	0.0194
31		Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead:			
	15.23.1	For thickness of tiles 10 mm to 25 mm.	100.00	sqm	0.4929
32		Dismantling C.I. Or asbestos rain water pipe with fittings and clamps including stacking the material within 50 metres lead:			
	15.42.1	75 to 80 mm dia pipe.	5.00	metre	0.0253

FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION**Price Schedule A : Anneuxre - I**

Name of work :Repair/maintenance of existing sanitary installations /drinking points etc. inside factory area.

Sr. No.	DSR-12 Items	Item Description	Qty.	Unit	% Weightage of item amount against total amount
33		Dismantling G.I. Pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge:			
	15.44.1	15 mm to 40 mm nominal bore.	40.00	metre	0.4283
34	15.52	Dismantling of flushing cistern of all types (C.I./PVC/Vitrious China)including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	25.00	each	1.5898
35	15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	20.00	sqm	0.0728
36	15.57	Dismantling aluminium/Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable surplus material and stacking of serviceable material within 50 metres lead as directed by Engineer-in-Charge.	15.00	sqm	0.0579
37	**	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast iron P or S trap, 10 litre low level white P.V.C. flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required:(Cement free issue by the Deptt.)			
	17.1.1	White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests.	5.00	each	2.3829
38	**	Providing and fixing white vitreous china pedestal type water closet (European type WC pan) with seat and lid, 10 litre low level white PVC flushing cistern with manually controlled device (handle lever) , conforming to IS : 7231 , with all fittings & fixtures complete including cutting and making good the walls and floors whereere required. (Cement free issue by the Deptt.)			
	17.2.2	W.C. pan with ISI marked black solid plastic seat and lid.	5.00	each	2.2882

FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION**Price Schedule A : Anneuxre - I**

Name of work :Repair/maintenance of existing sanitary installations /drinking points etc. inside factory area.

Sr. No.	DSR-12 Items	Item Description	Qty.	Unit	% Weightage of item amount against total amount
39	** Ana	Providing and fixing white vitreous china flat back half stall urinal of size 580x380x350 mm with white PVC automatic flushing cistern, with fittings, standard size C.P. brass flush pipe, spreaders with unions and clamps (all in C.P. brass) with waste fittings as per IS:2556, C.I. trap with outlet grating and other coupling in C.P. brass including painting of fittings , cutting and making good the walls and floors wherever required: (Cement free issue by the Deptt.)(Excluding the cost of PVC automatic flushing cistern).			
	17.5.1	Single half stall urinals with 5 litre P.V.C. automatic flushing cistern	3.00	each	3.0065
40	** 17.8	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings.(Cement free issue by the Deptt.)	2.00	each	0.3575
41		Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS :7231, with all fittings and fixtures complete.			
	17.18.1	10 litre capacity - White.	2.00	each	0.3282
42		Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing:			
	17.32.4	Rectangular shape 1500 x 450 mm.	2.00	each	0.5134
43	**	Providing and fixing G.I. Pipes complete with G.I. fittings and clamps,i/c making good the walls etc. concealed pipe, including paintingwith anti corrosive bitumastic paint, cutting chases and making good the wall : (Cement free issue by the Deptt.)			
(a)	18.11.1	15 mm dia nominal bore	25.00	metre	1.2617
(b)	18.11.2	20 mm dia nominal bore	2.00	metre	0.1101
44		Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931:			
	18.49.1	15 mm nominal bore.	10.00	each	0.8246
45		Providing and fixing PTMT grating of approved quality and colour.			

FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION**Price Schedule A : Anneuxre - I**

Name of work :Repair/maintenance of existing sanitary installations /drinking points etc. inside factory area.

Sr. No.	DSR-12 Items	Item Description	Qty.	Unit	% Weightage of item amount against total amount
		Circular type:			
	18.58.1.1	100 mm nominal dia.	2.00	each	0.0184
46	18.63	Providing and fixing PTMT angle stop cock 15 mm nominal bore. Weighing not less than 85 gms.	10.00	each	0.3442
47	** Ana.	Providing and fixing square-mouth S.W. gully trap grade 'A' complete with C.I. Grating brick masonry chamber with water tight C.I. Cover with frame of 300x300 mm size (inside) the weight of cover to be not less than 4.50Kg and frame to be not less than 2.70Kg as per standard design:(Cement free issue by the Dept.)			
		180x150mm size P type.			
	19.4.3.1	With FPS bricks class designation 75	2.00	each	0.5247
48		Dismantling of old S.W. pipes including breaking of joints and bed concrete stacking of useful materials near the site within 50 mtrs lead and disposal of unserviceable materials into municipal dumps.			
	19.5.2	150 mm diameter	2.00	metre	0.0132
49	**	Making connection of drain or sewer line with existing man-hole including breaking into and making good the walls, floors with cement concrete 1 : 2 : 4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) cement plastered on both sides with cement mortar 1 : 3 (1 cement : 3 coarse sand) finished with a floating coat of neat cement and making necessary channels for the drain etc. complete:(Cement free issue by the Dept.)			
	19.21.1	For pipes 100 to 250 mm diameter	2.00	each	0.1174

FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION**Price Schedule A : Anneuxre - I**

Name of work :Repair/maintenance of existing sanitary installations /drinking points etc. inside factory area.

Sr. No.	DSR-12 Items	Item Description	Qty.	Unit	% Weightage of item amount against total amount
50		Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS : 733 and IS : 1285, fixed with rawl plugs and screws or with fixing clips, or with expansion hold fastners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing/panelling, C.P. brass/stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing and panelling to be paid for separately).			
		For fixed portion.			
	21.1.1.2	Powder coated Aluminium (minimum thickness of powder coating 50 micron).	50.00	kg	3.8722
51		For shutters of doors, windows & ventilators including providing and fixing hinges/pivots and making provision for fixing of fittings wherever required including the cost of PVC/neoprene gasket required			
	21.1.2.2	Powder coated Aluminium (minimum thickness of powder coating 50 micron).	50.00	kg	4.4143
52		Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS:12823 , grade I type II, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass/stainless steel screws, etc. complete as per architectural drawings and directions of Engineer-in-charge:			
	21.2.1	Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side.	5.00	sqm	0.9765
	Non Schedule Items				

FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION**Price Schedule A : Anneuxre - I**

Name of work :Repair/maintenance of existing sanitary installations /drinking points etc. inside factory area.

Sr. No.	DSR-12 Items	Item Description	Qty.	Unit	% Weightage of item amount against total amount
53	----	Brick work with Ghol bricks of class designation 50 and above in foundation and plinth in : in cement mortar 1:6 (1 cement : 6 coarse sand) : (Cement free issue by the Deptt.)	2.00	cum	1.4303
54	----	Brick work with Ghol bricks of class designation 50 and above in superstructure above plinth level up to floor V level in all shapes and sizes in cement mortar 1:6 (1 cement : 6 coarse sand). (Cement free issue by the Deptt.)	0.25	cum	0.2073
55	----	Half brick masonry with Ghol bricks of class designation 50 and above in foundations and plinth in:Cement mortar 1 : 4 (1 cement : 4 coarse sand) . (Cement free issue by the Deptt.)	0.25	sqm	0.0151
56	----	Half brick masonry with Ghol bricks of class designation 50 and above in superstructure above plinth level up to floor V level:Cement mortar 1 : 4 (1 cement : 4 coarse sand) . (Cement free issue by the Deptt.)	20.00	sqm	1.8836
57	----	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item):			
		With float glass panes of 5.00 mm thickness	5.00	sqm	0.6555
		(Weight not less than 12.27 kg/sqm)			
58	----	Providing and fixing with all accessories and Oval shape , Ivory colour counter top wash basin with CI/MS brackets,15mm C.P. brass Swan neck Pillar taps, 32mm C.P.Brass waste of standard pattern including painting of fittings and brackets. cutting and making good the walls wherever required as per instruction of Engineer in charge.	5.00	each	1.9429

FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION**Price Schedule A : Anneuxre - I**

Name of work :Repair/maintenance of existing sanitary installations /drinking points etc. inside factory area.

Sr. No.	DSR-12 Items	Item Description	Qty.	Unit	% Weightage of item amount against total amount
59	----	Providing and fixing CP brass urinal push cock of nominal size 15 mm dia and pvc lead connection of different sizes, on single half stall urinal and three half stall urinal and as per instructing of Engr-in-charge. (The above rate is inclusive of CP brass urinal push cock and pvc lead connection)	10.00	each	0.4665
60	----	Providing and fixing Health Faucet with Hose & Hook Complete near WC sheet including cutting and making good of walls where ever required.	5.00	No.	0.7036
61	----	Providing and fixing 15 mm nominal bore C.P. Brass TWO WAY BIB COCK including cutting and making good of walls where ever required.	5.00	No.	1.1744
Total : Annexure I					100.0000

FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION

Price Schedule B

Name of work :Repair/maintenance of existing sanitary installations /drinking points etc. inside factory area.

The following material free issue from BHEL stores.

- 1 Cement
- 2 Reinforcement Steel.

Price Schedule C

Name of work :Repair/maintenance of existing sanitary installations /drinking points etc. inside factory area.

- 1 Electricity charges at Rs.66.00/- per M.T. of fabrication of structural steel (if required)

Hire charges.

- i) Drill machine @ 252.00/- per day
- ii) Jack Hammer @108.00/- per day

} (Subject to availability)

Drill machine/jack hammer rod Rs. 100.00 per rod