

ELECTRICAL WORKS PART-B						
SL. NO.	DESCRIPTION OF ITEM(Providing & fixing)	UNIT	QTY.	RATE (INR)	AMOUNT (INR)	Weightage in %
1	Surface mounted modular switchboard with 6A socket (3PIN), 5 Nos. 6A switches- one set	set	4			0.907091%
2	Surface mounted modular switchboard with 2Nos. 6A socket (3PIN), 2 Nos. 6A switches - one set	set	16			2.759728%
3	Surface mounted modular switchboard with 16A socket (6PIN) with 16A switch - one set	set	4			0.587385%
4	Surface mounted modular switchboard with 2 Nos. 6A switches-- one set	set	4			0.449398%
5	18W LED Tube light and Fitting hardware	Nos	16			0.668502%
6	16 /18 inch Industrial Wall mounted Fan along with mounting hardware	Nos	8			10.487595%
7	Surface mounted modular with 6A socket (3PIN)-1set.	set	8			0.738944%
8	Ceiling Rose	No.	25			0.214991%
9	25MM PVC Conduit and Conduit accessories including bends & unions running on wall & ceiling.	Mtrs	420			13.300986%
10	Conduit bends & unions	Lot	1			1.719929%
11	Conduit Branching JBs	Nos.	35			0.263908%
12	Conduit Clamps	Nos.	600			1.696554%
13	2.5 SQMM PVC Insulated Flexible copper wire	Mtrs	1400			28.238205%
14	4 SQMM PVC Insulated Flexible copper wire for 16A sockets	Mtrs	300			9.048290%
15	Surface mounted modular 8 -WAY Distribution Box with 63A TPN MCB & 30mA RCCB TPN in the Incomer (With outgoing SP MCB ratings 5 Nos. 6A & 3Nos. 20A)	No.	2			12.605274%
16	4C X 50sq.mm Aluminium Armoured LT Cable	Mtrs	200			12.899845%
17	Flexible conduit	Mtrs	25			0.188506%
18	Erection consumable (Like locking wire,insulation tap,sealing compound/plug,washewrs etc)	Lot	1			3.224867%
	TOTAL (PART-B) Excluding GST					100.0%