



भारत हवी इलैक्ट्रिकल्स लिमिटेड
(भारत सरकार का उपक्रम)
BHARAT HEAVY ELECTRICALS LIMITED
(A Govt. of India Undertaking)



ANNEXURE H

ADDITIONAL RATES FOR OPERATIONS

Enquiry No.	H9ATX00001
Item & Scope of Work	Manufacturing, Supply/ Delivery of Structures of AHP/LHP/GHP OF A Thermal Power Plant with BHEL Free Issue Materials - Category-III, V, VI & VII
Project	2 x 660MW Maitree STPP, BIFPCL Bangladesh

OPERATIONS	S.No	Description	Location of Facility	UOM	Rate (Rs.)
RT	1	Radiographic test (for X ray-spot)	In-house/BHEL Approved	Square cm	1.20
	2	Radiographic test (for X ray- full)	Inhouse/BHEL Approved	Square cm	1.60
	3	Radiographic test (for gamma ray-spot)	Inhouse/BHEL Approved	Square cm	1.70
	4	Radiographic test (for gamma ray-full)	Inhouse/BHEL Approved	Square cm	1.70
UT	5	Ultrasonic test of weldment	Inhouse/BHEL Approved	Running Meter	3.00
Trial Assembly	6	Trial Assembly	Inhouse	Kg	7.39
Packing	7	Packing Crates	Inhouse	Kg	11.30

- All terms & conditions of the tender are as per the attached PQC, ITB, SCC and relevant annexures attached with the tender.
- Rates for the above special requirements like RT, UT, Trial Assembly & Packing Crates are as above in this tender. The above rates shall be applicable to all the subcontractors.
- As per QAP, all columns need to be trial assembled, match marked, and Segments of Silo needs to be trial assembled, match marked.
- As per communication from all DU's below 1.6MT to be packed in metal crates.
- The weight of Trail assembly and Metal crates are indicated in below table approximately. The actual requirement may vary depending on various factors.

CATEGORY	TRIAL ASSY (MT)	CRATES WT (WT)
CATEGORY - III PIPE/BELT CONVEYORS	300	130
CATEGORY - V SUPPORT STRUCTURES WITH CONCRETE SILO	225	67
CATEGORY - VI SUPPORT STRUCTURE WITH SS SILO	480	60
CATEGORY - VII SUPPORT STRUCTURES WITH MS SILO WITH SS LINER	480	57