NTPC LIMITED 1X800 MW SIPAT STPP (STAGE-III)

TECHNICAL SPECIFICATION

FOR

AIR CONDITIONING & VENTILATION SYSTEM

SPECIFICATION NO.: - PE-TS-520-553-002-A001 (REV-00)



BHARAT HEAVY ELECTRICALS LIMITED
POWER SECTOR
PROJECT ENGINEERING MANAGEMENT
BHEL SADAN
SECTOR-16A, PLOT NO.-25, NOIDA, INDIA



TITLE:

TECHNICAL SPECIFICATION FOR AC & VENTILATION SYSTEM FOR 1X800 MW SIPAT STPP (STAGE-III)

SPECIFICATION No: PE-TS-520-553-002-A001			
SECTION			
REV. 00	OCT 2025		
SHEET: 1 OF 2			

CONTENTS

SECTION – I: SPECIFIC TECHNICAL REQUIREMENTS

SUB- SECTIONS	TITLE	Page No
Sub-Section-A	INTENT OF SPECIFICATION	4-6
Sub-Section-B	PROJECT INFORMATION	7-9

Sub-Section-C	TECHNICAL SPECI	FICATIONS					
	Sub Section-C1	SPECIFIC POWER BUILDIN	10-26				
		TECHNIC	TECHNICAL SPECIFICATION FOR O&M SERVICES				
	Sub Section-C2	CUSTON	CUSTOMER SPECIFICATION				
		C2 - A	C2 - A TECHNICAL REQUIREMENT				
		C2 - B					
			FUNCTIONAL / PERFORMANCE / DEMOSTRATION / GUARANTEE TESTS/ PG TEST				
			DRAWINGS / DOCUMENTS SUBMISSION PROCEDURE /PACKING PROCEDURE				
			QUALITY ASSURANCE				
		C2 - C	C2 - C PAINTING SPECIFICATION				
•	Sub Section-C3	TECHNIC	TECHNICAL SPECIFICATION (ELECTRICAL PORTION)				
	Sub Section-C4	TECHNIC	TECHNICAL SPECIFICATION (C&I PORTION)				
Sub-Section-E	ANNEXURE-I			LIST OF MAKES OF SUB-VENDOR ITEMS	327-362		
	ANNEXURE-II			MANDATORY SPARE LIST	363		
	ANNEXURE-III			PAINTING & COLOUR SCHEME	364		
	ANNEXURE-IV			LIST OF TOOLS & TACKLES	365		
	ANNEXURE-V			DRAWINGS/DOCUMENTS SUBMISSION PROCEDURE	366		
	ANNEXURE-VI			MASTER DRAWING LIST WITH STATUS	369-377		
/ IIII ZAGAZ VIII		FORMAT FOR OPERATION AND MAINTENANCE MANUAL	378-380				
	ANNEXURE-VIII			SITE STORAGE AND PRESERVATION	381-397		
	ANNEXURE-IX		·	PACKING PROCEDURE	398		
7 HTTEXOTE X			CUSTOMER SPECIFICATION ERECTION CONDITIONS OF CONTRACT	399-412			
	ANNEXURE-XI		E-LEARNING MODULE				



TITLE:

TECHNICAL SPECIFICATION FOR AC & VENTILATION SYSTEM FOR 1X800 MW SIPAT STPP (STAGE-III)

SPECIFICATION No: PE-TS-520-553-002-A001			
SECTION			
REV. 00	OCT 2025		
SHEET: 2 OF 2			

SECTION - II

SUB SECTIONS	TITLE	Page No
Sub Section-1	INSPECTION AND TESTING WITH STANDARD QUALITY PLAN &	415-418
	SUB QR-FORMAT FOR CHILLERS	
Sub Section-2	LIST OF DOCUMENTS TO BE SUBMITTED WITH BID	419
Sub Section-3	COMPLIANCE CUM CONFIRMATION CERTIFICATE	420-421
Sub Section-4	PRE-BID CLARIFICATION SCHEDULE	422
Sub Section-5	NO DEVIATION CERTIFICATE	423
Sub Section-6	GUARANTEED POWER CONSUMPTION AC SYSTEM & VENTILATION SYSTEM	424-425
Sub Section-7	APPENDIX 1: TENDER STAGE DRAWINGS /DOCUMENTS	426



1X800 MW SIPAT STPP (STAGE-III) HVAC SYSTEM INTENT OF SPECIFICATION

SPECIFICATION No: PE-TS-520-553-002-A001			
SECTION: I			
Sub Section: A			
REV. 00	OCT 2025		
SHEET 1 OF 3			

SECTION-I

SUB-SECTION-A

INTENT OF SPECIFICATION



1X800 MW SIPAT STPP (STAGE-III) HVAC SYSTEM INTENT OF SPECIFICATION

SPECIFICATION No: PE-TS-520-553-002-A001		
SECTION: I		
Sub Section: A		
REV. 00	OCT 2025	
SHEET 2 OF 3		

1.0 INTENT OF SPECIFICATION

- 1.1 The specification covers design (i.e. preparation and submission of drawing /documents including "As Built" drawings and O&M manuals), engineering, manufacture, fabrication, assembly, inspection / testing at vendor's & sub-vendor's works, painting, maintenance tools & tackles, fill of lubricants, chemicals, reagents and consumables required for pre-commissioning, commissioning , performance testing, mandatory spares along with spares for erection, start-up and commissioning as required, forwarding, proper packing, shipment and delivery at site, unloading, handling, transportation, storage & preservation at site, in-site transportation, assembly, erection & commissioning, final painting at site, minor civil and structural work, trial run at site and carrying out Performance guarantee / Functional / Demonstration tests at site, training of customer/client O&M staff, handing over and handover in flawless condition to BHEL's customer of HVAC SYSTEM with mandatory spares as per the details in different sections / volumes of this specification and various pre award agreements for 1X800 MW SIPAT STPP (STAGE-III).
- 1.2 The contractor shall be responsible for providing all material, equipment & services, which are required to fulfil the intent of ensuring operability, maintainability, reliability and complete safety of the complete work covered under this specification, irrespective of whether it has been specifically listed herein or not. Omission of specific reference to any component / accessory necessary for proper performance of the equipment shall not relieve the contractor of the responsibility of providing such facilities to complete the supply, erection and commissioning, performance and guarantee/demonstration testing of **HVAC SYSTEM.**
- 1.3 It is not the intent to specify herein all the details of design and manufacture. However, the equipment shall conform in all respects to highest standards of design, engineering and workmanship and shall be capable of performing the required duties in a manner acceptable to purchaser who will interpret the meaning of drawings and specifications and shall be entitled to reject any work or material which in his judgement is not in full accordance herewith.
- 1.4 The extent of supply under the contract includes all items shown in the drawings, notwithstanding the fact that such items may have been omitted from the specification or schedules. Similarly, the extent of supply also includes all items mentioned in the specification and /or schedules, notwithstanding the fact that such items may have been omitted in the drawing. Similarly, the extent of supply also includes all items required for completion of the system and not withstanding that they may have been omitted in drawings / specifications or schedules.
- 1.5 The general term and conditions, instructions to tenderers and other attachment referred to elsewhere are made part of the tender specification. The equipment materials and works covered by this specification is subject to compliance to all attachments referred to in the specification. The bidder shall be responsible for and governed by all requirements stipulated herein.
- 1.6 While all efforts have been made to make the specification requirement complete & unambiguous, it shall be bidders' responsibility to ask for missing information, ensure



1X800 MW SIPAT STPP (STAGE-III) HVAC SYSTEM INTENT OF SPECIFICATION

SPECIFICATION No: PE-TS-520-553-002-A001			
SECTION: I			
Sub Section: A			
REV. 00	OCT 2025		
SHEET 3 OF 3			

completeness of specification, to bring out any contradictory / conflicting requirement in different sections of the specification and within a section itself to the notice of BHEL and to seek any clarification on specification requirement in the format enclosed under SEC-II of the specification within 10 days of receipt of tender documents. In absence of any such clarifications, in case of any contradictory requirement, the more stringent requirement as per interpretation of Purchaser / Customer shall prevail and shall be complied by the bidder without any commercial implication on account of the same. Further in case of any missing information in the specification not brought out by the prospective bidders as part of pre-bid clarification, the same shall be furnished by Purchaser/ Customer as and when brought to their notice either by the bidder or by purchaser/ customer themselves. However, such requirements shall be binding on the successful bidder without any commercial & delivery implication.

- 1.7 The bidder's offer shall not carry any sections like clarification, interpretations and /or assumptions.
- 1.8 Deviations, if any, should be very clearly brought out clause by clause along with cost of withdrawal in the enclosed schedule (in Sec II); otherwise, it will be presumed that the vendor's offer is strictly in line with NIT specification. If no cost of withdrawal is given against the deviation, it will be presumed that deviation can be withdrawn without any cost to BHEL/its customer.
- 1.9 In the event of any conflict between the requirements of two clauses of this specification & requirements of different codes/standards and between respective clauses of subsection C & sub-section D, more stringent clause as per the interpretation of the owner shall apply.
- 1.10 In case all above requirements are not complied with, the offer may be considered as incomplete and would become liable for rejection.
- 1.11 For definition of word like Contractor, bidder, supplier, vendor, Customer/ Purchaser Employer, consultant, please refer relevant clause of NIT.



1X800 MW SIPAT STPP (STAGE-III) AIR CONDITIONING & VENTILATION SYSTEM PROJECT INFORMATION

SPECIFICATION No: PE-TS-520-553-002-A001		
SECTION: I		
Sub Section: B		
REV. 00	OCT 2025	

SECTION: I

SUB-SECTION: B

PROJECT INFORMATION

LAUSE NO.	PROJECT INFORMATION					
1.00.00	BACKGROUND					
	Sipat STPP has an installed capacity of 2980 MW under commercial operation with Stage-I (3x660 MW) and Stage-II (2x500 MW). The present proposal is for Sipat STPP Stage-III (1x800 MW) with Ultra-super critical technology.					
2.00.00	LOCATION AND AF	PPROACH				
	Sipat STPP is located in Bilaspur district of Chhattisgarh, having latitude and longitude of 22° - 05' to 22° - 09' (N) and 82° -16' to 82° - 18' (E) respectively. The site is approximately 20 Km from Bilaspur city and is approachable via Bilaspur - Baloda State Highway which passes through Sipat.					
2.01.00	RAIL LINK					
		ead is Jairamnagar Railway mately 3 km from the project s	,	ipur-Kolkata		
2.02.00	AIRPORT					
	The nearest comme	rcial airport, Raipur is about 15	60 Km from the project s	site.		
	Vicinity Plan is placed at Annexure-I.					
3.00.00	CAPACITY					
	Ultimate Capacity: 3780 MW					
	Stage-I : 1980 MW (3x660 MW) – Under Commercial Operation					
	Stage-II : 1000 MW (2x500 MW) - Under Commercial Operation					
	Stage-III :	Stage-III : 800 (1x800 MW)- Present Proposal				
4.00.00	LAND					
	The project is envisaged to be accommodated with in the land already acquired. No additional land is proposed to be acquired for the project.					
5.00.00	WATER					
	Water cooled Condenser is envisaged for Sipat Stage-III of 1x800 MW Unit. The consumptive make-up water requirement for this Project would be about 2300 Cum/Hr with ash water recirculation system in operation.					
	Water requirement for Sipat STPP is being met from Right Bank Canal (RBC) originating from Hasdeo Barrage Pondage.					
	 STPP STAGE-III (1X800 MW) PC PACKAGE	TECHNICAL SPECIFICATION SECTION – VI, PART-A BID DOC. NO	SUB-SECTION-I-B PROJECT INFORMATION	PAGE 1 OF 19		



1X800 MW SIPAT STPP (STAGE-III) AC & VENTILATION SYSTEM SPECIFIC TECHNICAL REQUIREMENT

SPECIFICATION No: PE-TS-520-553-002-A001		
SECTION: I		
SUB-SECTION: C1		
REV. 00	OCT 2025	
SHFFT 1 OF 1		

CLARIFIED WATER ANALYSIS

S.No.	Constituent	Expected Clarified Water Analysis		Expected Circulating Water Analysis Considering 5 COC	
		Unit	Details	Unit	Details
1	Calcium	mg/l as CaCO3	166	mg/I as CaCO3	830
2	Magnesium	mg/l as CaCO3	35	mg/I as CaCO3	175
3	Sodium	mg/l as CaCO3	25	mg/I as CaCO3	125
4	Potassium	mg/I as CaCO3	8	mg/I as CaCO3	40
5	Total Cations	mg/l as CaCO3	234	mg/I as CaCO3	1170
6	Bicarbonates	mg/I as CaCO3	75	mg/I as CaCO3	375
7	Carbonates	mg/l as CaCO3	0.1	mg/I as CaCO3	0.5
8	Nitrate	mg/l as CaCO3	0	mg/I as CaCO3	0
9	Chloride	mg/l as CaCO3	78	mg/I as CaCO3	390
10	Sulphate	mg/l as CaCO3	81	mg/I as CaCO3	405
11	Total Anions	mg/l as CaCO3	234	mg/I as CaCO3	1170
12	Silica-Total	mg/l as SiO2	23	mg/l as SiO2	115
13	Silica-Colloidal	mg/l as SiO2	3	mg/I as SiO2	15
14	Silica- Reactive	mg/l as SiO2	20	mg/l as SiO2	100
15	Total Organic Carbon (TOC)	mg/l	8	mg/l	40
16	Iron (Total)	mg/l as Fe	0.3	mg/l as Fe	1.5
17	pH Value	-	7.2-8.7	-	7.2-8.7
18	Turbidity	NTU	10	NTU	50



1X800 MW SIPAT STPP (STAGE-III) AC & VENTILATION SYSTEM TECHNICAL SPECIFICATION

SPECIFICATION No: PE-TS-520-553-002-A001	
SECTION: I	
Sub Section: C	
REV. 00	OCT 2025

SECTION: I

SUB-SECTION: I-C
TECHNICAL SPECIFICATION



	SPECIFICATION	No: PE-TS-520-553-002-A001
SECTION: I SUB-SECTION: C 1		
		C 1
	REV. 00	OCT 2025
	SHEET 1 OF 9	

SECTION: I

SUB SECTION: C-1

TECHNICAL SPECIFICATION



SPECIFICATION No: PE-TS-520-553-002-A0		No: PE-TS-520-553-002-A001
	SECTION: I	
SUB-SECTION: C 1		C 1
	REV. 00	OCT 2025
	SHEET 2 OF 9	

1. FUNCTION

The purpose of the system is to provide Air Conditioning & Ventilation system for different areas of 1X800 MW Sipat TPS under the scope of this tender.

2. SYSTEM DESCRIPTION

- 2.1 Central Air Conditioning System with Water Cooled Chiller for Main Plant areas (Control Room, CER, UPS & Battery Charger room (except battery room), SWAS room, Water Analysis Lab, Office Area in Control Tower etc.
 - 2.1.1 As per spec. clause no. 3.01.00 a) of Section VI, part B, sub section A-17.
 - 2.1.2 All the pumps shall be horizontal split casing type. Fans in cooling tower shall be top discharged mounted at top of cooling tower.
 - 2.1.3 Chilled water & Condensate water pipes shall be routed outside of the CCR & CER area and pipes supporting arrangement shall be suitably done from outside of the control tower area.
 - 2.1.4 Fresh Air fan with damper (for each AHU room): 1X100 % or 2X50 %
 - 2.1.5 VAV shall be provided for regulating the air flow in the Office Area above the CCR area.

2.2 Central Air Conditioning System with Water Cooled Chiller for ESP Control Room

- 2.2.1 As per spec. clause no. 3.01.00 b) of Section VI, part B, sub section A-17.
- 2.2.2 All the pumps shall be horizontal split casing type. Fans in cooling tower shall be top discharged mounted at top of cooling tower.
- 2.2.3 Fresh Air fan with damper (for each AHU room): 1X100 % or 2X50 %

2.3 Offsite Building. Offsite Control Rooms/Rio Room Etc.

- 2.3.1 Please refer Customer spec. clause no. 3.01.00 e) of Section VI, part B, sub section A-17.
- 2.3.2 Split AC shall be supplied along with isolation switch, i.e MCB of suitable rating as specified, voltage stabilizer, cabling, all supporting structure, refrigerant piping to suite actual site condition, drain piping up to nearest drain etc.

2.4 Evaporative Cooling System for Main Power House & ESP cum FGD building

- 2.4.1 As per spec. clause no. 2.00.00 a) & b) of Section VI, part A, sub section A-12.
- 2.4.2 Five (5) nos. Containerized Air washer shall be placed on operating floor towards "A" row. No separate masonry room is required to place these air washers.
- 2.4.3 Another 5 nos. Containerized Air Washers shall be placed on Deaerator floor towards "BC" bay). No separate masonry room is required to place these air washers.
- 2.4.4 One (1) No. of Containerized Air Washer shall be placed in CD bay for Boiler MCC, cable vault of Boiler MCC, Cable vault of CCR and Cable vault of UPS
- 2.4.5 Fan Filtration Unit shall be provided for Pressurization of all Staircase wells in TG Hall C row side and also all doors/shutters provided this side shall have a provision of Air Curtains to avoid ingress of coal/ash dust from boiler side.



	SPECIFICATION	No: PE-TS-520-553-002-A001
SECTION: I SUB-SECTION: C 1		
		C 1
	REV. 00	OCT 2025
SHEET 3 OF 9		

2.5 Evaporative Cooling System for ESP Control room (Non-A/C areas Switchgear and cable gallery areas)

- 2.5.1 As per spec. clause no. 2.00.00 c) & d) of Section VI, part A, sub section A-12.
- 2.5.2 UAF shall be placed at the roof of ESP Control building

2.6 Ventilation System for Miscellaneous areas

- 2.6.1 Mechanical Ventilation (using roof extractors/Supply/ Exhaust Fans and fresh air intake/ back draft dampers) shall be provided for various other areas/buildings. For ventilation of battery rooms and oil rooms, flame proof motor shall be provided.
- 2.6.2 Ventilation provision for Auxiliary Buildings in various locations (offsite area) is envisaged as per specification, section-VI, part-A, Sub Section A 12, clause number 2.00.00.e) & f).
- 2.6.3 RE unit/ wall mounted axial fans shall be selected so as to have motor rating as under:

1	Roof extractor units with 15 mmwc static pressure.		
	Capacity	Motor rating	Roof / Slab opening
а	50,000 CMH	5.5 KW	1320mm
b	40,000 CMH	5.5 KW	1320mm
С	20,000 CMH	2.2 KW	1140mm
2	Axia	al flow supply fans with 30 mm	wc static pressure.
	Capacity	Motor rating	Wall opening
а	10,000 CMH	2.2 KW	1000mmx1000mm
b	7,500 CMH	1.5 KW	1000mmx1000mm
С	6,000 CMH	1.1 KW	600mmx600mm
d	4,000 CMH	0.75 KW	500mmx500mm
3	Axial flow supply fans with 20 mmwc static pressure.		
	Capacity	Motor rating	Wall opening
а	15,000 CMH	2.2 KW	1000mmx1000mm
а	10,000 CMH	1.5 KW	800mmx800mm
b	7,500 CMH	1.1 KW	700mmx700mm
С	6,000 CMH	1.1 KW	600mmx600mm
d	4,000 CMH	0.75 KW	600mmx600mm
4	Axial flow exhaust fans (Bifurcated type) with 15 mmwc static pressure		
	Capacity	Motor rating	Wall opening
a	15,000 CMH	2.2 KW	1000mmx1000mm
b	10,000 CMH	1.5 KW	1000mmx1000mm
С	7,500 CMH	1.1 KW	1000mmx1000mm
d	4,000 CMH	0.55 KW	700mmx700mm
е	2,000 CMH	0.55 KW	700mmx700mm



	SPECIFICATION	No: PE-TS-520-553-002-A001
SECTION: I SUB-SECTION: C 1		
		C 1
	REV. 00	OCT 2025
SHEET 4 OF 9		

	Axial flow exhaust fans with 10 mmwc static pressure.		
	Capacity	Motor rating	Wall opening
а	15,000 CMH	1.1 KW	900mmx900mm
b	10,000 CMH	0.75 KW	900mmx900mm
С	7,500 CMH	0.55 KW	700mmx700mm
d	6,000 CMH	0.55 KW	600mmx600mm
	4,000 CMH	0.55 KW	600mmx600mm
е	2,000 CMH	0.37 KW	500mmx500mm
Exhaust fan (propeller type) with 5 mmwc static pressure.		atic pressure.	
	Capacity	Motor rating	Wall opening
а	1200 CMH	100 W	330 mm circular

- 2.7 DESIGN CRITERIA: As per section C2-A, Technical Specification Section-VI, part-B, sub section-A-01, clause no. 3.13.00 and 3.13.01.
- 2.8 Tentative Heat Dissipation data for various Air-Conditioned Rooms to be served with Central AC System

SI No.	Room Description	Tentative Heat Dissipation (kW)
1	AC Area at 0.0M, CEP VFD Room at 0.0M & 9.0 M Power House served by AHUs located at 9.0M elev.	125
2	CCR at 18.0M Power House & Office Area served by AHU at 28.0M elev.	135
3	ESP Control Room Building	50

Note: The above heat dissipation data is for the estimation of AHU capacities envisaged for various areas. However, total capacity of the working AHUs shall match with the working capacity of the corresponding chiller plant /condensing Unit. This heat dissipation data shall be finalized during detail engineering, any variation in the AHUs capacity of any area keeping overall capacity of working AHU's same corresponding to respective chiller capacities as already mentioned in BOQ shall not have any commercial impact.

3. LAYOUT CONSIDERATION:

3.1 AC PLANT -1

- 3.1.1 The central chilled water plant, Condenser Water & Chilled Water Pumps for AC Plant shall be housed in AC Plant Room at 0.0 M level in Control Tower area.
- 3.1.2 AHU Room at 9.0 M level of Power House Building in E-G-Bay between grid 12-13.
- 3.1.3 AHU Room at 30.0 M level of Power House Building in B-C Bay between grid 11a-14.
- 3.1.4 The Cooling Towers, Make-up water Storage Tank, Expansion Tank, water



SPECIFICATION No: PE-TS-520-553-002-A001	
SECTION: I	
SUB-SECTION: C 1	
REV. 00	OCT 2025
SHEET 5 OF 9	

softening plant and soft water storage tank shall be located at 34.5 M level in D-F Bay between grid 11a-13.

3.2 AC PLANT -2

- 3.2.1 Air Cooled Condensing Unit (1W+1S) shall be kept on the roof of the ESP Control Room.
- 3.2.2 AHUs shall be place inside AHU room at Roof of ESP control room

4. Terminal Points, Ducting Interface, and Performance Testing

4.1 Terminal Points:

For AC System: Terminal Points shall be downstream of the wall openings / floor openings of AHU Room. Final Connection of the high side Equipment with the ducting system shall be in the scope of bidder.

For Ventilation System: Terminal Points shall be flange of Volume Control Damper of the Ventilation equipment. (Air Washer/UAF). Final Connection of the high side equipment with the ducting system shall be in the scope of bidder.

4.2 Ducting System (Design & Approval):

The design, engineering, and drawing submission for approval from the end customer for AC & Ventilation System along with the entire ducting system & associated accessories shall be in the scope of the bidder.

4.3 Duct Leak/Smoke Test:

The Leak Test / Smoke Test required to establish a leak-proof ducting system shall be conducted by the Low side /Duct System Supplier. However, the bidder shall supervise and certify the execution of such tests to ensure that the ducting system performance meets the technical requirements.

4.4 Performance Guarantee (PG) Test:

The Performance Guarantee (PG) Test for the entire AC and Ventilation System (including ducting & accessories) shall be carried out by the bidder as per approved procedures to meet performance parameters as per the specification.

5. General

- 5.1 Basis of design all calculations including heat load calculations for summer seasons, equipment selection criterion, layout drawings/ schemes/G.A. dwg and documents like data sheet/ technical particulars etc are subject to Customer approval during detail engineering stage.
- 5.2 Bidders shall make Site visit in order to familiarize themselves with existing condition of site before submitting the bid in order to make their offer complete. BHEL shall also not entertain any cost implication for any lack of input data with regard to site during detail engineering.
- 5.3 All drawings and documents shall be computer based.
- 5.4 All commissioning spares & consumables for trouble free operation until handing over of the system shall be provided.



	SPECIFICATION	No: PE-TS-520-553-002-A001
SECTION: I SUB-SECTION: C 1		
		C 1
	REV. 00	OCT 2025
	SHEET 6 OF 9	

- 5.5 The bidder shall be responsible for providing necessary storage facilities for materials supplied.
- 5.6 Quality Requirements in the Technical Specification are indicating minimum requirements for inspection and testing. Vendor shall note that quality plan is subject to Customer & BHEL approval during detail engineering stage.

6.0 SCOPE OF SERVICES


Scope of services by bidder will include but not necessarily limited to the following:

- 6.1 Unloading, Storage, handling and transportation at site.
- 6.2 Erection & Commissioning of AC & Ventilation System.
- 6.3 Necessary supports and structures / frames etc. as required for supporting the duct / piping /equipment etc. as lump-sum basis is in the scope of Vendor and no unit rates shall be applicable for these items.
- 6.4 Minor civil work like chipping of foundation, grouting below base plate for all structures, equipment, grouting of anchor bolts wherever these are not placed in the foundation during casting of foundation itself including special type of grouting like GPX2 etc, making opening to suit / finishing of opening after completion of AC Equipment erection, sealing of duct / pipe opening.
- 6.5 Making Good / Repairing / replacement of and damaged done by bidder to adjacent structure, pipes etc. while erecting equipment's related to AC & Ventilation System.
- 6.6 Drain piping up to the drain point to be provided by the Vendor.
- 6.7 Pre-Commissioning work such as flushing, hydraulic testing etc. Necessary consumables and instrumentation like refrigerant, grease, lubricants, anemometer, tachometer, ammeter, voltmeter etc. for inspection and testing at works as well as at site including precommissioning activities shall be arranged by the successful bidder at their own cost.
- 6.8 Inspection & testing, Performance Requirements and Performance Guarantees as per the specification.
- 6.9 Painting of equipment's, valves, pipes and other accessories within scope of supply.
- 6.10 Electrical scope as per enclosure elsewhere in the specification.
- 6.11 Training of plant Owner's personnel O&M operators' personnel on plant operation and maintenance as per Customer specification.
- 6.12 Relevant requirements as per GTR, GCC & SCC.
- 6.13 Any other service required for making the installation complete in all respect within battery limits and for satisfactory erection & commissioning of the system as well as to meet any statutory requirement relevant to the package, unless specifically EXCLUDED from scope of services.
- 6.14 For motorized fire damper / 3 Way valve actuators / motorized valves, power supply shall be derived by vendor from respective control panels. Suitable transformer shall be provided by bidder (if required) to derive the power input. Further distribution through junction box / distribution board shall be in vendor scope and shall have provision for isolation of individual fire damper/ valves.
- 6.15 Bidder should suitably group the signals coming from various instruments etc. & the same shall terminate in local JB, from Local JB common cable to DCS / panel / MCC shall be selected. Any Electrical / C&I items and accessories like junction box, glands etc. shall be included by vendor in his scope.



SPECIFICATION No: PE-TS-520-553-002-A001	
SECTION: I	
SUB-SECTION: C 1	
REV. 00	OCT 2025
SHEET 7 OF 9	

6.16 Supports required for supporting the fan and/or filter section for Axial fans shall be under bidder's scope.



- 6.17 All VVFD drives shall be provided with enclosure.
- 6.18 3 phase 3 wire supply shall be provided for the equipment's (Chiller, AHUs, Pumps CT etc.). Any requirement of single-phase power supply for the internal operation of the equipment shall be derived internally by the equipment supplier.
- 6.19 In case of chiller unit with multiple compressor, single source of power supply shall be provided by BHEL and further distribution shall be in the scope of the bidder.
- 6.20 Local push button station shall be provided for local operation of the Air Handling Unit (AHU), Air Washer Unit (AWU) and Unitary Air Filter (UAF). In case multiple AHU's, AWU or UAF are kept in a room or in vicinity, common Local Push Button Station shall be provided for local operation of all the AHU / UAF / AWU in the room or located in vicinity.
- 6.21 Ducting layout for the AC and Ventilation System shall be in bidder scope.

7.0 Operation services & consumables

- 7.1 Commissioning of various AC and Ventilation System & Equipment's under scope of this tender is expected in phased manner depending upon front availability and other site conditions. Bidder shall include in their scope operation of such AC plants & Ventilation equipment's which are commissioned, until final handing over of complete system to customer. Consumables like chemicals for softening plant, lube oils, refrigerants, etc. during this period of operation shall also be considered by bidder in their scope. Any shortcoming in the System which may have happened during the operation of the plant, due to regular wear and tear or otherwise, shall be made good before handing over of complete AC & ventilation system to customer.
- 7.2 Instruments to be used for PG test shall be additionally supplied over and above the instruments shown in tender P&IDs. PG test equipment being supplied, installed and commissioned for each unit, shall be retained by employer after completion of PG test.



	SPECIFICATION	No: PE-TS-520-553-002-A001
SECTION: I SUB-SECTION: C 1		
		C 1
	REV. 00	OCT 2025
SHEET 8 OF 9		

7.3 Water softening plant – Water softening plant shall be complete in all respect with ACF, DMF, Softener, Pumps for water softening plant, pumps for regeneration, pumps for transferring softening plant reject and cooling tower blow down to CMB, chemical cleaning/dozing pump with necessary tank and circulating water system. Dedicated control panel shall be provided each softening plant with proper interlock of pump, desired parameter of soft water quality. Power of pump shall be routed through control panel of softening plant having inbuilt starter panel. A single source supply feeder shall be provided for each softening plant which shall be terminated at control panel. Soft water outlet quality shall be maintained such that it shall not be corrosive in any condition by blending clarified water maintaining quality of soft water within acceptable limit suitable for chiller. Cooling coil and pipe. Provision for Blowdown, corrosion inhibitor, scale inhibitor and chemical dosing shall also be provided along with suitable quantity of salt.

8.0 EXCLUSIONS

Items of works listed below are excluded from scope of the air-conditioning & Ventilation System supplier.

- 8.1 Construction of AC plant room, air handling unit room, foundations for AC equipment's i.e. Chillers, Condensing Units, Package AC, AHU, Pumps, roof/wall openings for ducts, dampers/louvres.
- 8.2 False ceiling, drop ceiling.
- 8.3 Slab cut out for running ducts, pipes, cables, grilles/dampers. Underground masonry trenches and masonry risers.
- 8.4 Various cable & pipe trenches, pipe pedestals, drains, sumps, insert plates for pedestals for pipe supports.
- 8.5 DCS Control panel for Operation and control of AC System and Ventilation System. However, all logic for implementation of control and monitoring from DCS shall be provided by successful bidder during detail engineering.
- 8.6 For Electrical scope, refer Electrical scope matrix sheet.

9.0 PAINTING / CORROSION PROTECTION REQUIREMENT

Refer customer specification, C-2A.

10.0 CONTROL PHILOSOPHY

Control of both AC & ventilation system shall be done from DCS based control panel located CCR area at 18.0M. Refer Customer Specification in Sub Section C2 A for details.

11.0 QUALITY ASSURANCE, QUALITY PLANS, INSPECTION & TESTING PROCEDURE:

As per the details given elsewhere in the specification.

12.0 SUB-VENDOR ITEMS

Sub-Vendor for AC & Ventilation System is enclosed under Annexure-I, Sub-Section - E




SPECIFICATION No: PE-TS-520-553-002-A001					
SECTION: I					
SUB-SECTION: C 1					
REV. 00	OCT 2025				
SHEET 9 OF 9					


13.0 DOCUMENTS TO BE SUBMITTED WITH THE BID


The documents to be submitted with the bid shall strictly as per list given under **SECTION-II**. Any documents other than those indicated in the list will not be reviewed and will not be considered as part of bid.


14.0 DRAWINGS/ DOCUMENTS REQUIRED DURING DETAIL ENGINEERING


List of drawings / documents along with submission schedule is attached in Annexure-VI, Sub-Section –E






















PE-TS-520-553-002-A001
Rev. No. 00

Date : OCT 2025

1.0 OPERATION AND MAINTENANCE SERVICES

The bidder scope also covers the Operation and Maintenance (O&M) services for Preventive and Breakdown maintenance from the date of successful commissioning till handing over to end customer. However, actual date of start of O&M services shall be communicated to successful bidder by BHEL site personnel.

Bidder to note that the spares and consumables required for maintenance of the equipment during this O&M period shall be in bidder's scope of supply. Bidder shall use only genuine parts as mentioned in O&M Manual. Any damage or malfunction caused by the use of unauthentic parts or unqualified personnel shall be responsibility of bidder and as a consequence of above bidder is required to replenish the unauthorized part and abridge the qualified person without any commercial implication to BHEL.

O&M Services scope also covers all regular maintenance by trained service engineers and supply of genuine parts and lubricants as per the original equipment manufacturer's recommendations.

For the purpose of Operation of Air Conditioning System, One-day shall be considered as 24 hours i.e. 3 shifts of 8 hours each. The AC System (along with related accessories) shall be operated on Round-the-clock basis on all the days of the year including Sundays and Public Holidays

O & M Personnel should be acquainted with local language. Governmental / Statutory approval w.r.t. O&M service as applicable shall be in bidder's scope.

Total duration of the Operation and Maintenance services has been envisaged as per price format for individual AC System / buildings identified in price format/specification. The duration of operation & maintenance services can be increased or decreased as per requirement and payment in such case shall be made on pro-rata basis.

The operation and maintenance services can be continuous or intermittent as per site requirement for individual AC System / buildings identified in price format/specification.

Bidder has to compulsorily maintain log book for the O & M staff engaged for O&M jobs and submit to Engineer-in charge for certification for realization of the bills. After certification of the bill by Engineer in charge of BHEL, bidder shall claim the amount after completion of minimum 30 days.

Depending on start of O&M services, there is a possibility that some period of O&M services and Warranty period may overlap. However, it is clarified that any maintenance required or any spare of AC System required to be replaced during Warranty period (as part of warranty clause requirement) shall not be made part of O&M Services. Bidder may take care of this fact while working out the prices of O&M services



PE-TS-52	0-553-002	-A001	
Rev. No.	00		

Date : OCT 2025

Wherever AC system has been written in O&M Service Specification, the same shall be deemed as complete AC System.

The vendor shall deploy following minimum manpower for Operation of AC System.

- i. Two qualified and experienced operator per shift on "Round the Clock" basis throughout the year for all days of the year including Sundays & Public Holidays. There must be minimum 30 minutes overlapping between two shift operators to get familiarize with the status of AC System.
- ii. One Helper per shift on "Round the Clock" basis throughout the year for all the days of the year including Sundays and Public Holidays. The helper shall assist the Ventilation System Operator in day to day operation of AC System and accessories and shall assist him for keeping AC System equipment's in neat and tidy condition.

1.1 Responsibility of System Operator

- i. AC System operator shall be responsible for proper sequential operation of AC System in a predefined sequence and stopping the same (when necessary) as per the procedural practice. In case of any abnormality (like non-availability of power supply at incomer of Ventilation System), he shall immediately report the matter to BHEL site Engineer for further action. Similarly, any malfunctioning in the system shall be immediately reported by him to BHEL site Engineer for suitable corrective actionirrespective of time of occurrence of malfunctioning / abnormality in the system. A log book of all such outrages shall be maintained by AC system operator, which shall be shared with BHEL site engineer on periodic basis.
- ii. AC System operator shall take hourly readings of all the parameters of AC System / Equipment's including reading on main electrical panel of AC System.

1.2 Responsibility of Helper.

- i. The AC System helper shall assist AC System operator for day to day smooth operation of AC System, like Checking of water levels of cooling tower, cleaning of Tanks, cleaning of strainers, checking water parameters of softening plant cleaning of AHU filters and other filters etc. as and when required. He shall be responsible for keeping all the equipment's of AC System as applicable in clean and tidy condition. He shall also carry out general cleaning of all AC equipment including Electrical Panels (Part of AC System), etc. on regular basis.
- ii. The helper shall work under the control of AC System operator and shall always ensure that unusable junk materials are not allowed to be kept in AC plant room or ahu room.



)	E-	T	S	-5	2	0	-5	5	3.	-0	0	2	-1	A	0	0	1
	_	-	_	_	_	_	_	_	_	_	_	_		•	_	_	_

Rev. No. 00

Date : OCT 2025

iii. Under such eventuality, he will report the matter to Plant Operator, who in turn will take suitable action including reporting the matter to BHEL site Engineer.

- 1.2.1 All the log book registers shall be arranged by vendor. Log book register duly paged and bounded will be maintained in good condition by vendor.
- 1.2.2 All the necessary tools & tackles and other materials, required for operation of AC System shall be kept by vendor under the control of AC System operator. These tools & tackles shall be separate from tools & tackles (as per price format) which shall be handed over to customer in new condition. Required testing instruments like refrigerant leak detector, Multi Meter (for Electrical portion of AC System), Sling psychrometer, Line Tester, Tool Kit, Torch, vacuum pump, oil charging pump, Pressure testing kit etc. should also be always available with Plant Operator.
- 1.2.3 In case of any operator / helper being on leave, vendor shall immediately take advance action and provide substitution so that minimum manpower as indicated above is not reduced on any day. In case a particular shift duty Operator or helper does not turn up due to any reasons, the earlier duty person shall continue to make sure that System never remains unattended.

2.0 Maintenance of AC System

- i. Maintenance work under scope of the vendor shall broadly include but in no way limited to the following:
- a) Preventive maintenance of the plant.
- b) Servicing of the plants and associated equipment's at regular interval
- c) Attending to complaints.
- d) Replacement of worn out or defective components
- e) Replacing of consumables as and when required.
 - No consumable or any other items of system shall be arranged by Customer and no extra payment shall be made by customer in this regard.
- ii. Vendor shall be responsible at all time, during the entire period of contract for satisfactory performance of Ventilation system (including accessories) with zero down time. During emergency or breakdown, vendor's Engineer along with related technicians shall be available immediately even though it may be beyond normal working hours or on public holidays till the AC System is restored back into normal satisfactory condition. Response time for attending breakdown complaints shall not exceed 2 hours.



PE-TS-520-553-002-A001	
Rev. No. 00	

Date : OCT 2025

iii. Defective / worn out components shall be replaced only by genuine and original parts. OEM or its authorized dealer's invoice shall be submitted as proof of using genuine parts. All common spares required for Ventilation system shall normally be kept available in the plant by the vendor. However, for critical spares, the same shall be made available in not more than 72 hours from the time of break-down requiring such spare.

- iv. Preventive Maintenance, servicing of AC System equipment's and accessories etc. shall be done by vendor in a planned manner in consultation with concerned customer's engineer. Preventive maintenance and service should be done as per the recommendations / guidelines of various OEMs
- v. Major servicing & over handling of equipment's like fans, pumps, piping / ducting works, valves etc. shall be done by vendor once in a year.
- vi. In case any repair/services of particular equipment of system is to be carried out by vendor through OEM (or their authorized dealer), all the arrangements including tools, O&M spares etc. shall be the total responsibility of vendor.
- vii. Vendor shall arrange and maintain separate logbook register for services / maintenance of AC System. Record of work done for services/maintenance repairs etc. shall be recorded by vendor's engineer in this register. This register shall always be with updated records & shall be produced to customer's engineer on weekly basis or as & when required by him.
- viii. Vendor shall arrange and maintain sufficient stock of spares and consumable at site. Similarly, all necessary tools & instruments required for the purpose of servicing / maintenance / routine testing etc. shall also be arranged by vendor and should be available at site at all times.
- ix. Repairs / servicing works shall normally be done by vendor at site up to maximum possible extent. However, in case any equipment or accessories is essentially required to be taken by vendor out of the plant premises for repairing / servicing, all necessary arrangements including to and fro transportation shall be the responsibility of vendor. Vendor shall also inform concerned customer's engineer for doing procedural formalities (like issue of gate pass etc.), prior to taking out the materials out of Plant premises.
- x. In case bidder fails to supply the spares required for maintenance of the equipment, same shall be provided by BHEL at Bidders risk and cost.
- xi. Vendor shall be fully responsible for safety of his personal at all times. Vendor shall also be responsible for taking all safety precautions at all the times, especially during servicing / preventive maintenance and repairs of Ventilation System equipment's etc.



PE-TS-520-553-002-A001	
Rev. No. 00	

Date : OCT 2025

- xii. All the safety controls, inter locking etc. shall be positively checked at least once a month and same shall be recorded by vendor engineer
- xiii. Technicians & helpers engaged by the vendor shall wear uniform with nameplate for easy identification, while being within plant premises
- xiv. Vendor's engineer shall be focal point for customer. He shall report to customer engineer on daily basis, for taking necessary instructions and to update the status of Ventilation system
- xv. If any damage to the equipment and its accessories has happened due to improper maintenance by bidder shall be recovered from the bidder.
- xvi. Bidder is to arrange all the safety gears like helmets, air plugs, safety shoes etc. during the maintenance for the O&M Staff.
- xvii. Bidder shall have to maintain storage shed along with site office during O & M contract also
- xviii. Fabrication and erection of platform/extra support for **Ventilation** areas if felt necessary during operation and maintenance of the system has to be done by the bidder.

Notes:

- 1. The bidder shall take approval from Engineer-in charge of BHEL by submitting organization Chart of O&M staff for this site clearly indicating man power deployment with their educational background & experience with supporting documents.
- 2. The bidder shall be solely and wholly responsible for safety and security of workers engaged in the job and the BHEL property. In case of any accident the contractor shall pay proper compensation to the workers as per workmen's compensation act and repair/replace BHEL property at their own cost & arrangement. The bidder shall also make adequate provision of insurance for their workers at their own cost to cover them against the risk of accident.
- 3. The bidder and their workers engaged in the job shall follow all safety rules at the time of execution of work. It shall be responsibility of the bidder to supply all safety equipment as necessary to its O&M staff.
- 4. Beyond general shift if any trouble/breakdown occurs in the plant, Maintenance team must reach the plant without any delay along with Engineer/Site In-charge.
- 5. No Person from the list of manpower shall leave the plant site without prior permission from the Engineer in charge of BHEL.
- 6. However, in operation part, if any person is absent, substitute must be given immediately otherwise proportionate deduction will be made

बीएचई एल HHHEL

TECHNICAL SPECIFICATION 1X800 MW SIPAT STPP STAGE III AIR CONDITIONING AND VENTILATION SYSTEM O & M SERVICES

PE-TS-520-553-002-A001
Rev. No. 00

Date : OCT 2025

7. The replacement / substitute personnel for maintenance, manpower shall have the same educational qualification and experience.

- 8. If any additional manpower is required during O&M whatsoever under the scope of contract the same shall be made available by bidder in time within the cost. To cater the need of time bound maintenance jobs, the bidder shall depute additional manpower without any cost implication to BHEL
- 9. During execution of work if any personnel is found not suitable for the job or his presence inside powerhouse premises is felt undesirable, the personnel has to be replaced within 15 days.

10. BHEL will not be responsible for payment towards idle labor charges

Statutory Compliance by the bidder:

All Statutory compliances related to Labor, Health & Safety, Quality & Environment protection and insurance shall be as GCC applicable for the tender.



1X800 MW SIPAT STPP (STAGE-III) AC & VENTILATION SYSTEM CUSTOMER SPECIFICATION TECHNICAL REQUIREMENT

SPECIFICATION No: PE-TS-520-553-002-A001						
SECTION: I						
SUB-SECTION: C 2A						
REV. 00	OCT 2025					

SECTION: I

SUB-SECTION: C 2A

CUSTOMER SPECIFICATION TECHNICAL REQUIREMENT



1X800 MW SIPAT STPP (STAGE-III) AC & VENTILATION SYSTEM PROJECT SPECIFIC GENERAL REQUIREMENTS

SPECIFICATION No: PE-TS-520-553-002-A001					
SECTION: I					
SUB-SECTION: C2B					
REV. 00	OCT 2025				

SECTION: I

SUB-SECTION: C 2
PART-B

CUSTOMER SPECIFICATION PROJECT SPECIFIC GENERAL REQUIREMENTS

CLAUSE NO.	S	COPE OF SUPPLY AND SERV	ICES	एनदीपीसी NTPC	
1.00.00	AIR CONDITIONING	SYSTEM			
	condensing piping, valve (wherever a (ducting, filte grills, VAV	nir conditioning system consisting units, chilled water pumps & drivers & fittings, cooling towers, air happlicable), split air conditioners, fors, isolation/volume control dampers box as applicable, etc.) along it ion as per the detailed specification	es, condenser water pump andling units, VFD drives resh air fans, air distribu rs, motorized fire damper with all electrical equi	os & drives, for motors tion system s, diffusers, pment and	
	There shall screw chillin towers, etc. like control excitation co	air-conditioning system for mair oe one (1) central chilled water tyling units, chilled water pumps, core cater to the A/C requirement of the rooms, control equipment rooms on trol rooms (if applicable), SWAS a Area in Control Tower etc.	oe air-conditioning plant c ndenser water pumps, Al- ne areas identified for mair s, UPS/Battery charger re	HUs, cooling plant areas coms, static	
	There shall comprising AHUs, cooli	air-conditioning system for ESP one one (1) central, water cooled conference chilling units, chilled want towers, etc. to cater the A/C recontrol room buildings etc.	hilled water type air-condi ter pumps, condenser wa	tioning plant ater pumps,	
	d) VOID				
	'	r conditioners shall be provided fo	r AHP control room as de	tailed out in	
	f) VOID				
	 packaged/Split air-conditioners for various auxiliary control rooms/control equipmer rooms/RIO rooms/VFD rooms/etc. and office areas of all offsite buildings (under scope of the Bidder) as detailed out in Part-B of Technical Specification. h) Apart from the above, any area/building which are in the scope of the Bidder a require air conditioning, those areas/buildings shall be provided with air condition system, as detailed out in Part-B of Technical Specification. 				
	i) Supply of ma	andatory spares as specified.			
1	AGE-III (1X800 MW) C PACKAGE	TECHNICAL SPECIFICATION SECTION – VI, PART-A BID DOC. NO	SUB-SECTION-A-12 PLANT UTILITIES	PAGE 1 OF 11	

CLAUSE NO.	SCOPE OF SUPPLY AND SERVICES							
	j)	-	items which may not be specificate may not be specificate may not be specificate may be specificated as the system shall be specificated as the sp					
	k)	accessories a fully operation services which completeness	ioning system, the Bidder shall associated equipment, which al condition. The Bidder shall also may not be specifically stated in of the equipment/systems furnish requirements of these specification	are included in Bidder's o provide all material, equal the specifications but are ned by the Contractor and	scope, in a lipment and required for			
	1)	Control system of air-conditioning system is indicated in Sub-Section-IIC, Control & Instrumentation, Scope of Supply & Services, Part-A of Technical Specifications.						
2.00.00	VENT	ILATION SYSTE	EM					
	a)	General						
		Complete Ventilation system consisting of modular type air washer units, supply air fans, roof extractor fans, exhaust air fans, louvers, filters, ducting, diffusers, piping, instrumentation etc., for all the buildings which are in the scope of the Bidder, as per the detailed specification in Part-B of technical specification						
	b)	Turbine hall building and associated areas						
		type) (DIDW	Minimum ten (10) nos. of air washer units (of metallic construction-modula type) each of minimum capacity 1,00,000 m³/hr, with all accessories, 1 no DIDW centrifugal fan, 1 no. circulating water pump, etc. as detailed out it technical specification shall be provided for each unit.					
		type) centrif	Minimum one (1) no. of air washer unit (of metallic construction- modular type) of minimum capacity 50,000 m ³ /hr, with all accessories, 1 no. DIDW centrifugal fan, 1 no. circulating water pump, etc. as detailed out in technical specification shall be provided for boiler MCC of each unit.					
		locate these 60% o	ilation of turbine hall is further assisted by means of roof extractor ed suitably at the roof of TG hall building. The number and capacity of e roof extractor shall be selected in such a way that, it extracts approx. of total discharge of air washer units. This will maintain a positive sure within turbine hall and thus stop ingress of dusty outside air within					
	c)	E.S.P. Contro	I Room Building (Non-A/C area	s)				
		Minimum One (1) no. of Unitary Air Filtration (UAF) unit (of metallic construction-modular type) of minimum capacity 90,000 m ³ /hr, with all accessories, 1 No. DIDW centrifugal fan, 1 No. circulating water pump, etc. as detailed out in technical specification shall be provided for each unit.						
	d)	VOID						
SIPAT STA	AGE-III (1) C PACKA	•	TECHNICAL SPECIFICATION SECTION – VI, PART-A BID DOC. NO	SUB-SECTION-A-12 PLANT UTILITIES	PAGE 2 OF 11			

CLAUSE NO.		sco	DPE OF SUPPLY AND SERV	ICES	एन्द्रीपीसी NTPC		
	Note:	evaporative ve	D control room buildings are entilation system (UAF system) ear/Cable Vault, etc.) of comordingly.	shall be provided for nor	-A/C areas		
		A/C areas (MC	rative ventilation system (UAF sycC/Switchgear/Cable Vault, etc.) pon electrical/ control building(s).	pertaining to FGD system i			
	e)	building, pump water system Bidder's scope exhauster fans dampers' or 'fi rooms and oil	s areas: All other areas like houses, MCC/switchgear room control building, workshops, sto and shall be ventilated by a control of significant control building, workshops, sto and shall be ventilated by a control of shall be ventilated by a control of shall be sha	ns, electrical and C&I bares, cable vaults, etc. co combination of 'supply air fans' or 'supply air fans a st air fans'. For ventilation	ttery rooms, vered under fans & roof & back draft on of battery		
	f)	Apart from the above, any area/building which are in the scope of the bidder are require ventilation, those areas/buildings shall be provided with ventilation system, a detailed out in Part-B of Technical Specification.					
	g)	Supply of Mandatory spares as specified. Any additional items which may not be specifically stated in the specifications but at required for completeness of the system shall be supplied by the Contractor.					
	h)						
	i)	accessories are fully operations and services required for co	For ventilation system, the Bidder shall provide all instrumentation systems, accessories and associated equipment, which are included in Bidder's scope, in a fully operational condition. The Contractor shall also provide all material, equipment and services which may not be specifically stated in the specifications but are required for completeness of the equipment/systems furnished by the Contractor and for meeting the intent and requirements of these specifications.				
	j)	-	of ventilation system is indic n, Scope of Supply & Services, P				
3.00.00	СОМР	RESSED AIR S	YSTEM				
	a)	compressors for	nbers (2 working + 1 standby) oil or instrument air duty for the com essure, with their motor drives an	plete plant each of adequa			
	b) Three (03) numbers (2 working + 1 standby) Air Drying Plants (one for each instrument air compressor) of minimum capacity same as instrument air compressor with all interconnecting piping, valves, fittings, etc.						
SIPAT ST	AGE-III (1) C PACKA	•	TECHNICAL SPECIFICATION SECTION – VI, PART-A BID DOC. NO	SUB-SECTION-A-12 PLANT UTILITIES	PAGE 3 OF 11		

CLAUSE NO.	TECH	INICAL REQUIREMEN	гѕ	एनरीपीमी NTPC
3.13.00	AIR CONDITIONING AND	O VENTILATION SYSTEM		
	GENERAL REQUIREMEN	ITS		
		ipment and accessories sha maintenance of all equipmen		ay to facilitate
	Each equipment shall bolts, etc to facilitate r	be provided with suitable lift	ing arrangement, e.g. L	ifting lugs, eye
3.13.01	·	Air conditioning system		
	1. Design ambient c	onditions for all air conditioning	ng system shall be as in	dicated below:
	Season	Dry Bulb Temp. (Deg. C)	Wet Bulb Temp. (Deg.	C)
	Summer	44	25.5	
	Monsoon	38	27.8	
	Winter	15	10	
	3. All air conditioned control tower, etc relative humidity of the fresh air quand Room /FGD control System Control I change per hour tower & in other a hour. 5. Lighting load shale to conference room/rooms, control equinoms, control equinoms, control equinoms, conditioning space for return as	Air Conditioning system shall deareas like control room, control shall be maintained at 24 of 50% ± (plus or minus) 5%. In tity for air-conditioned areas for room, Control Room / Control Room Building, etc. shall be whichever is greater. However reas, etc. quantity of fresh air or general area shall be mining froom the same shall be mining froom the same shall be greater. The occupancy of the occupancy of the return air shall air shall be avoided. Further a in control tower, etc. where	ontrol equipment rooms deg. C ± (plus or minus deg. C ± (plus or minus of eg. C ± (plus of eg. Eg. C ± (plus of eg. C ± (plus of eg. C ± (plus of eg. Eg. C ± (plus of eg. E	, office area in) 1 deg. C and / AHP Control / UPS, Water son or 1.0 air area in control air changes per her. O Sq. M and for In the control on per 25 Sq.M use of plenum d ESP Control
STA	HERMAL POWER PROJECT GE-III (1X800 MW) PC PACKAGE	TECHNICAL SPECIFICATIONS SECTION-VI PART-B BID DOC.NO.	SUB SECTION-A-01 EQUIPMENT SIZING CRITERIA	PAGE 65 OF 87

TECHNICAL REQUIREMENTS CLAUSE NO. no intermediate or intervening floor are left non-air-conditioned, the space above false ceiling shall be used as return air plenum. The supply and return air ducts shall be provided with automatic (motorised) fire 8. dampers (of 90 minutes fire rating) at locations where ducts pass through walls (with perfect partition i.e. partition both above & below false ceiling) and floors. Operation of these dampers shall be interlocked with the fire alarm system and shall also be possible to operate manually from the remote control panel. Required electrical contacts shall be provided in control panel of A/C plant by the Contractor for further wiring upto fire alarm panels. 9. Soft water make up (if required) for complete air conditioning and ventilation system shall be provided by the bidder. 10. Design Chilled water flow shall not be less than 0.7 Cu.M/hr per TR air-conditioning load and design condensing water flow shall not be less than 1 Cu.M /hr per TR airconditioning load. 11. Coil face area of Air Handling units shall be designed considering a face velocity of not more than 2.5 m/sec. Water piping shall be sized for a maximum velocity of 2.0 m/sec. However, gravity flow / pump suction line shall be sized for a maximum water velocity of 1.5 m/sec. 12. Air distribution system shall be sized to have a constant frictional drop along its length and velocity through ducts shall not exceed 7.6 m/sec. Requirement of Underdeck Insulation (for A/C area) 13. 14. Underdeck insulation shall be provided if i) Non A/C area is located just above the A/C area. In this case, underdeck insulation shall be provided underneath of the ceiling of A/C area. ii) Non A/C area is located just below the A/C area. In this case, underdeck insulation shall be provided underneath of the ceiling of Non A/C area. iii) Underneath the ceiling of AHU room located below the non-A/C area or exposed to Atmosphere. Underneath the floor of AHU room located above the non-A/C area. v) Underneath the ceiling of A/C areas exposed to sun. For air handling unit (AHU) serving main plant control area, where microprocessor 15. based equipments are located, the dehumidified air shall be filtered at three different stages i.e. pre (coarse) filter followed by fine filter followed by HEPA filter before discharge it to conditioned space. For all other areas, AHU's shall be provided with two stage of filteration i.e. pre and fine filter. All fresh air supply fans shall also be filtered using pre and fine filter. A minimum design margin of ten (10) % shall be considered in design of AC Plant 16. Capacity for each area. Twenty (20) % design margin shall be considered for the cooling tower capacity over the selected A/C capacity provided. Head of the pumps shall take into account min. ten (10)% margin on friction head. For pumps, continuous motor rating (at 50°C ambient) shall be atleast 10% above the maximum load demand of the pump in the entire operating range. For other areas, where A/C load is of the order of 25-60 TR, Direct Expansion (D-X) 17. type air cooled condensing units along with AHUs shall be provided depending on

SIPAT SUPER THERMAL POWER PROJECT STAGE-III (1X800 MW) EPC PACKAGE TECHNICAL SPECIFICATIONS SECTION-VI PART-B BID DOC.NO. SUB SECTION-A-01 EQUIPMENT SIZING CRITERIA PAGE 66 OF 87

CLAUSE NO.	TEC	CHNICAL REQUIREMENTS	3	एनदीपीमी NTPC			
	the availability of space/ layout etc. For areas, where A/C load is of the order of 5 25TR, ductable split/packaged A/C shall be provided. Smaller areas which are away from the D-X type condensing unit /central chilling units which may require all conditioning upto 5 TR rating shall be served with Hi-wall Split/Cassette aid conditioner units as per requirement. Above 60TR of A/C load, chilled water type centralized A/C system shall be provided.						
	other valve (if	narge of pumps, outlet of chillers needed as per system requirem or remote operation of the Air con	nent) in the system				
	19. Mandatory Req	uirements to be followed for A/C I	Equipments:				
	19.1. Refrigerant	: Refrigerant shou	ıld be CFC/HCFC fre	e.			
	19.2. Insulation for A/C	air ducts: A/C ducts shall be insu	lated.				
	19.3. All types of Insula	tion used for HVAC application sh	nall be CFC/HCFC fre	ee.			
	20. During normal operation period, all the working equipment shall run on A.C. power supply. However, in case of complete black-out condition, DG sets being provided are required to cater the load of some of the air-conditioning equipment so that Main Plant Control Rooms and CER remain air-conditioned. The equipment to run on DG set are:						
	 1 No. Chilling ma 	chine					
	1 No. chilled wat	er pump.					
	• 1 No. condenser	water pump.					
	1 No. cooling tow	ver fan.					
	• 2 nos. AHUs for	CR & CER					
	1 No. fresh air fa	n.					
	21. As per ECBC codes minimum coefficient of performance (COP) and star rating for the chillers shall be as per BEE. Minimum Star Rating/Co-efficient of performance (COP) of the Chillers shall be as per ECSBC/BEE regulations/guidelines.						
3.13.02	DESIGN PHILOSOPHY	′ – Ventilation System					
STAC	HERMAL POWER PROJECT BE-III (1X800 MW) PC PACKAGE	TECHNICAL SPECIFICATIONS SECTION-VI PART-B BID DOC.NO.	SUB SECTION-A-01 EQUIPMENT SIZING CRITERIA	PAGE 67 OF 87			

TECHNICAL REQUIREMENTS CLAUSE NO. Minimum Air changes per hour in evaporative/ mechanically ventilated areas shall be as follows: i) For all evaporative cooled areas 20 ii) General areas iii) Hydrogen generation plant/MCC/ 30 Switchgear rooms and Battery rooms& other areas where gaseous fumes/ vapours are generated 2. However in areas producing lot of heat, temperature shall be the criteria as follows:-Inside temperature shall be minimum 3 deg.C below the design ambient temperature a) during summer for evaporative cooled areas. Inside Temperature shall be maximum 3 deq.C above the design ambient b) temperature during summer for mechanically ventilated areas. Note: (i) Dry bulb temperature during summer season shall be as mentioned in Air conditioning system as above. The criteria which gives higher number of air changes/higher quantity of air of either of condition (Cl. 1 or 2) flow shall be selected. (ii) To calculate air quantity based on air changes per hour (ACPH) method, height of operating floor (17M) in AB Bay shall be taken as 4 meter. All ventilation systems shall operate on 100% fresh air. Fan envisaged for MCC & Switchgear rooms shall be provided with pre-filters and fine filters and for other areas shall be provided with pre-filter only. 4. All the equipments of ventilation system shall be designed for continuous duty. 5. The supply air ducts of evaporative type ventilation system shall be provided with automatic (motorised) fire dampers (of 90 minutes fire rating) entry in switchgear room, cable galleries etc. The operation of these automatic dampers shall be interlocked with the fire alarm system and shall also possible from the control panel remote manually. Circulating water Capacity for Air washer units shall be minimum 1 Cu.M/hr per 1000 Cu.M /hr of air flow and for UAF it shall be minimum 0.7 Cu.M/hr per 1000 Cu.M /hr of air flow. Velocity through piping shall be limited to 2.0 m/sec and for gravity flow the same shall be limited to 1.5 m/sec. Air distribution system shall be sized to have a constant frictional drop along its length and air velocity through ducts shall not exceed 12.5 m/sec. 7. The air washer unit shall be designed for a maximum velocity of 2.7 m/sec and at least 90% saturation efficiency. All mechanically ventilated areas shall be positively ventilated. However, Battery rooms and other fumes/odour generating areas like fuel oil pump houses, central lube oil purification room etc. shall be negatively. Type of ventilation for various buildings shall be as follows:

S	S.No	Area	Type of Ventilation system
(i	i)	General area like pump house, compressor houses, etc.	Combination of Supply air fan & Exhaust air fans/Roof Extractor Fans

SIPAT SUPER THERMAL POWER PROJECT
STAGE-III (1X800 MW)
EPC PACKAGE

TECHNICAL SPECIFICATIONS
SECTION-VI PART-B
BID DOC.NO.

SUB SECTION-A-01
EQUIPMENT SIZING
CRITERIA
PAGE
68 OF 87

CLAUSE	NO.

TECHNICAL REQUIREMENTS



(ii)	MCCs and Switchgear room, Cable Vault (other than served by evaporative ventilation system), etc.	Supply air fans & Back draft dampers
(iii)	Battery rooms & other fumes/odour generating areas	Combination of Air Intake Louvers & Exhaust air fans
(iv)	Cable Galleries of TG Building, ESP Building and FGD Control Room Building	AWU/UAF systems along with back draft dampers
(vi)	Toilet/pantry etc.	Exhaust air fans
(vi)	For underground ventilation of CHP & Mill reject handling	Refer relevant clause in this sub section.

- 9. For pumps, continuous motor rating (at 50oC ambient) shall be atleast 10% above the maximum load demand of the pump in the entire operating range. For fans, compressors and blowers continuous motor rating (at 50oC ambient) shall be atleast 10% above the maximum load demand at the design duty point. However for V-belt driven fan, continuous motor rating (at 50oC ambient) shall be atleast 15% above the maximum load demand at the design duty point.
- 10. Supply air fans, exhaust air fans & ventilations of each area shall be provided with local starter panels.
- 11. All staircase wells in TG hall C-row side, shall be pressurized and also all doors/ shutters provided this side shall have a provision of air curtains to avoid ingress of coal/ash dust from boiler side.

SIPAT SUPER THERMAL POWER PROJECT STAGE-III (1X800 MW) EPC PACKAGE

TECHNICAL SPECIFICATIONS SECTION-VI PART-B BID DOC.NO. SUB SECTION-A-01 EQUIPMENT SIZING CRITERIA PAGE 69 OF 87

CLAUSE NO.	TECHNICAL REQUIREMENTS एन्स्योमी NTPC							
	AIR CON	DITIONING & VETILATION SYS	STEM					
1.00.00	GENERAL							
1.01.00	This section of specification covers details of system specifications, detailing the areas to be air conditioned, basis of design, brief description of the system, equipment and services to be furnished by bidder. The supply, delivery and erection of the entire equipment listed here shall be in bidder's scope of work.							
2.00.00	CODES & STANDARD	s						
2.01.00	The design, manufacture and performance of equipment shall comply with all currently applicable statues, regulations and safety codes in the locality where the equipments are to be installed. Nothing in this specification shall be considered to relieve the bidder of this responsibility.							
2.02.00	Unless otherwise specified, equipment shall conform to the latest applicable BEE , ECBC , Indian or IEC standard. Equipment complying with other authoritative standards such as British, USA, ASHRAE etc. will also be considered if it ensures performance equivalent or superior to Indian Standard.							
3.00.00	REDUNDANCY OF EQ	UIPMENTS						
3.01.00	Redundancy of various	A/C system equipments shall be	as follows:					
	 a) For Main Plant Areas [control room, control equipment room, UPS room, battery charger, static excitation control room (if applicable) SWAS room & water analysis lab]: i) Vapor compression type water chilling units: 3x50% ii) Chilled water pumps: 3x50% iii) Condenser water pumps: 3x50% iv) Cooling Towers: 3x50% v) AHUs: At least one (1) no. unit, capacity same as each working unit shall be provided as common standby. b) For ESP control rooms, For office area in control tower: i) Air cooled (D-X Type) condensing units: 2X100% ii) AHUs: 2x100% 							
	c) VOID							
	d) VOID							
	e) 100% standby shall be provided for control rooms/RIO room/VFD rooms/etc. served be ductable split/package type air conditioners.							
STA	THERMAL POWER PROJECT GE-III (1X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION-VI, PART-B	SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 1 OF 30				

CLAUSE NO.	TECHNICAL REQUIREMENTS						
	At least one (1) no. unit, capacity same as each working unit as a common stands be provided for control rooms/RIO room/etc. served by non-ductable split (casset wall) type air conditioners.						
	•	No stand-by shall be provided for office areas of offsite buildings (like O&M store, Ga Complex, O&M workshop, etc.).					
	g) Fresh air fans shall be	g) Fresh air fans shall be 1 x 100 % capacity for each AHU room					
	centralized A/C syste	em) sha	s/areas (located in buildi all be provided with stand er design criteria stipulate	dalone A/C system as	standby. Type		
	features like indication	n, mar	ne provided with bypass nual and Auto set point fa by from 50% to 125%, by	acility, control power s	source, capable		
3.02.00	Redundancy of ventilation	on syst	em equipments shall be a	as follows:			
	a) Pump and fan for Air	washe	r / UAF units shall be 1x1	00% for each unit.			
4.00.00	EQUIPMENT DESCRIP	TION -	- AIR CONDITIONING S	YSTEM			
4.01.00	Vapour compression t	ype ma	achines				
4.01.01	Each chilling unit shall comprise of compressor with drive motor, Water Chiller/evaporator Chilled water pumps, Condenser Cooling Water pumps (if applicable) other accessories such as supporting structure, vibration isolators, insulation, piping, valves, instrumentation microprocessor / PLC based Control panel, etc. Chilling unit shall have stepless capacity Control. The screw/centrifugal compressor based chilling unit to be supplied shall be BEE/ARI /Eurovent/Equivalent standard certified (if applicable).						
4.02.00	Chilling Unit		T.W. (0)				
	Type		Water-cooled type. (Che be with multiple compre		hall preferably		
	Vibration isolators	:	Steel spring/ Neopre serrated rubber pad ty than 85%.	ne rubber cushy fo			
	Compressor Type Type of drive	:	Compressor shall hermetic/multiple herm Motor driven, along wit		(open/semi-		
	Capacity	:	Minimum capacity	shall be suitabevaporating tempe			
	Condenser		100				
	Type Fluid	:	Water cooled shell and Shell side – Refrige				
	T Idid	:		stant			
	Capacity	:	: To match with respective compressor and to provide atleast 2 deg. C sub-cooling. To store full charge of refrigerant.				
	Design fouling Factor	:	: Not less than 0.0002 (in MKS units)				
	Shell material	<u>:</u>					
	Tube material Fin material						
	Accessories	1:	: As required such as Purge and drain connections, relief				
			valves, liquid line s				
STA	THERMAL POWER PROJECT AGE-III (1X800 MW) EPC PACKAGE	TEC	CHNICAL SPECIFICATION SECTION-VI, PART-B	SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 2 OF 30		

CLAUSE NO.	TECHNICAL REQUIREMENTS				
			charging, flow switche temperature indicators a		
	Refrigerant	:	The refrigerant shall be other environment friend	e R-134a/R-410A/R-	
	Steel structure		The complete condensi on steel structure and	ng/ chilling unit shal	
	In lat to make make ma	₩	vibration isolators		
	Inlet temperature Leaving temperature differential		33-36 o C. Maximum 5 o C.		
	Evaporator	+			
	Type	+-	Shell and tube type		
	Superheating of	†÷	At least 2 deg.C		
	Design Fouling Factor	+÷	Minimum 0.0001 (MKS i	unita)	
	<u> </u>	+÷		,	
	Fluid	∔ :		Refrigerant	
		:		Water	
	Capacity	<u> </u> :	To match with respective		
	Shell material	<u> :</u>	Mild steel (IS: 2062) / S		
	Tube material		Plain tube internally /exmanufacturer's standard		er as per th
	Fin material	1:	Integral		
	Accessories	: Purge and drain connections, Isolating valves switches, Pressure & temperature indicators at outlet, Anti-freeze thermostats, electronic expansion or float assembly as applicable, pilot solenoic Relief valves, Operating thermostats for capacity supporting frame, etc.		s at inlet ar pansion valv enoid valv	
	Steel Structure	:	: The complete condensing/ chilling unit shall be mounte on steel structure and shall be provided with necessar vibration isolators.		
4.03.00	Condensing Unit -Air-Coo Condensing unit Type Vibration isolators		Air cooled scroll type Steel spring / Neopre	ne rubber cushy fo	pot type wit
	Compressor	_	isolation efficiency not le	ess than 85%.	
	Туре	:	The Compressor shall hermetic type or sen capacity control (minimum)	ni-hermetic type w	
	Type of drive	:	Motor driven.		
	Refrigerant	:	The refrigerant shall be other environment friend		-407C or ar
	Accessories		High/Low pressure cutouts, oil pressure switches, relie valves, pressure gauges at each stage, lube oil an control oil pressure gauges, suction & discharge sto valves, Muffler, Crank case heaters, oil filters, magnetic of separators, temperature indicators for lube oil/heaters, of level indicators, safety thermostat for crank case heate		
	<u> </u>	 		shall be suitable	
	Capacity		identified/selected at condensing temperature		

CLAUSE NO.	TECHNICAL REQUIREMENTS						
4.04.00	Air H	andling Unit (AHI	J)				
4.04.01	steel efficie disch case return AHU (whe comr	Each AHU shall consist of casing, fan impeller section, cooling coil section, damper section, steel frame with anti vibration mountings (AVMs) having minimum 85% vibration dampening efficiency and flame retardant, water proof neoprene impregnated flexible connection on fan discharge. Isolation dampers at the suction and discharge of each AHU shall be provided, in case return air duct is directly connected to AHU. However, in case AHU room is used for return air, isolation dampers are required to be provided only at AHU discharge of each AHU. Pre-filter at the suction and fine (micro-vee type) and absolute (HEPA type) filters (wherever applicable) at the discharge of each individual AHU, and heater section in the common discharge of AHUs. NRD shall be provided at outlet of each AHU when multiple AHU used for a common plenum.					
4.04.02	(insid sheet polyu reinfo	The casing of AHUs shall be of double skin construction. Double skin sandwich panels (inside and outside) shall be fabricated using minimum 0.63 mm (24g) galvanized steel sheet (thickness of galvanization as per manufacturer's standard), with 25mm thick polyurethane foam insulation of minimum 38 Kg/Cum density in between. Suitable reinforcements shall be provided to give structural strength to prevent any deformation/buckling.					
4.04.03	Steel Fire	. It shall be isolate	d from bott	ton	n floor panel throug	mum 1.2 mm thick 5 h 25mm thick heavy ane foam. Drain pa	duty treated for
4.04.04	firmly					ss copper tubes with ed with suitable dra	
4.04.05 4.04.06	filter remo		Inspection	n d	loor shall be provi	orm inside the plenu ded at the plenum o	
	a)	Fan Type		:	Double Width D	ouble Inlet (DWDI)	Centrifugal
	b)	Fan impeller		:	Backward curved	blades	
	c)	Casing material		:			
	d)	Impeller material		:			
	e)	Shaft		:	EN 8 Steel		
	f)	Fan bearings		:		e, permanently lubrion life of 10,000 operat	
	g)	Critical speed		:		d of rotating assemble the operating speed.	y shall be at
	h) Drive : Motor driven with removable belt guard. Motor rating (at 50 deg.C ambient) shall be atleast fifteen percent (15%) above the maximum load demand of drives at the design duty point.						
	i)	Fans		:	For AHUs of ca Bidder may offer equal capacity fo	pacity 50,000 CMH two (2) Nos. centril or each AHU provic ommodated within	fugal fans of led all such
SIPAT SUPER THERMAL POWER PROJECT STAGE-III (1X800 MW) EPC PACKAGE					L SPECIFICATION DN-VI, PART-B	SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 4 OF 30

CLAUSE NO.	TE	CHNICAL REQUIREMENTS		एनटीपीसी NTPC		
4.04.07	Mixing Box:					
		omplete with fresh and return return air is ducted back to the A		g box shall be		
4.04.08	Pan Humidifier:					
	resin bonded fiber glass humidifier shall be com valve with stainless ste	made of 22 gauge SS 304 tars insulation (min. 24 Kg/m3 dens plete with stainless steel immers eel ball, sight glass, overflow a Step controller shall be provide ent.	sity) with 0.5 mm GSS sion heaters, safety th nd drain connections	S cladding. The nermostat, float s, steam outlet		
4.05.00	NON DUCTABLE SPL CONDITIONERS	IT (HI-WALL/CASSETTE), DUG	CTABLE SPLIT, PA	CKAGED AIR-		
4.05.01	Air conditioners shall in general consist of the following: i) Casing ii) Hermetically sealed rotary/scroll Compressor iii) Air-cooled condenser iv) Evaporator and condenser cooling fan v) Cooling coil vi) Filters vii) Piping, valves, refrigerant strainer, etc. viii) Controls, instruments, control panel/starter panels. ix) Vibration isolator pads, ducting (if applicable), etc. as required. x) Refrigerant as per manufacturer practice. Note: (1) Humidity control inside air-conditioned space served by split air conditioners (Hiwall / Cassette/ Ductable) is not envisaged.					
4.05.02	,	reau of Energy Efficiency (BEE), punted Cassette Type Unit (Multi	•	ovt of India.		
4.03.02	The housing of the ur	nit shall be powder coated gal erence in capacity should hav	vanized steel. All th			
	Unit shall have four-way	supply air grills on sides and re	turn air grill in center.			
	Each unit shall have hig	h lift drain pump and very low op	erating sound.			
4.05.03	PACKAGED AIR-CONI	DITIONERS				
	(a) Packaged air conditioners shall be an encased assembly as a self-contained unit primarily for floor mounting, designed to provide free delivery of conditioned air to the conditioned space. It shall include a primary source of refrigeration for cooling and dehumidification, means for circulating and cleaning air and means for heating and humidifying air. Fresh air fan shall be provided in PAC Room.					
STA	THERMAL POWER PROJECT GE-III (1X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION-VI, PART-B	SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 5 OF 30		

CLAUSE NO.	TECHNICAL REQUIREMENTS ですより類似						
	 (b) The cabinet, housing the components of packaged air conditioners, shall be of heavy gauge sheet steel and suitable for floor mounting. The access panels shall be of easily removable type. The entire casing shall be thermally insulated with 25 mm thick insulation of totally flame proof type (T.F. type). Suitable drain connection shall be provided for removal of condensate collected inside a tray under cooling coil. (c) Controls shall be so provided that failure of one equipment of PAC will automatically trip that PAC unit. (d) HP and LP cutout shall be provided for compressor protection. A thermostat with adjustable setting shall also be provided in the return air circuit to control the room temperature by ON-OFF mode. (e) Provision shall also be made for manual re-starting and stopping of the compressor. (f) Interlock shall be provided such that compressor can start only starting the air handling fan. (g) Interlock shall be provided so that compressor can start only if condenser fan in running. Further if the condenser fan stops, the compressor shall also trip. (h) To control the humidity throughout the year, the humidistat shall be interlocked with humidifier and reheater. 						
4.06.00	numidifier and reheater. COOLING TOWERS (for chilling units)						
4.06.01	Туре		Induced draf discharge	t, cross or counter flo	w, vertical		
4.06.02	Casing & Sump tank	:	F.R.P/G.R.P				
4.06.03	Fan	:	Cast Aluminum / FRP Propeller type and mublade aerofoil construction with adjusta pitch.				
4.06.04	Fill	:	Non combustible PVC or equivalent				
4.06.05	Louvers	:	F.R.P. /PVC/ Aluminum.				
4.06.06	Nozzles	:	Brass with chrome plating / Polypropylene.				
4.06.07	Eliminators	:	In removable sections to reduce the drift loss to 0.2% of water flow.				
4.06.08	Supporting structure	:	Mild steel with spray galvanization or epopainting.				
4.06.09	Strainer at water outlet	:	Plate strainer made of GI/SS wire mesh of 1 gauge.				
4.06.10	Bird screen on top of tov	wer :	25 mm square made of GI/SS wire mesh of 16				
4.06.10A	WBT for CT Design, App	oroach & Range :	gauge. 29 Deg. C,	4 Deg. C & 4 Deg. C	respectively		
4.06.11	Distribution Pipe (if any)		Galvanized	• •			
4.06.12	Accessories	a) b)	Make up o back up ga	ection with isolation v connection with ball ate valve and a bypa anual operation.	 float valve, 		
SIPAT SUPER THERMAL POWER PROJECT STAGE-III (1X800 MW) EPC PACKAGE		TECHNICAL SPEC SECTION-VI, F		SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 6 OF 30		

CLAUSE NO.	TE	CHNICAL REQUIREMENTS		एनटीपीसी NTPC			
		the towers	onnection. connection to conne wherever applicable. or in louvers/fan deck.				
5.00.00	EQUIPMENT DESCRIP	TION - VENTILATION SYSTEM	1				
5.01.00	Air Washer Unit						
5.01.01	Each double skin Air Washer Units (Modular Type which shall be completely enclosed ,Evaporative System) shall consist of the various Sections such as Air washer chamber / Casing, Tank, Distribution plates, set of metallic/fabric filters at suction, suction louvers, bird screens, water headers, Spray nozzle, piping, pumps, valves, Drift eliminators, Fans, and all other required accessories.						
	Housing/Casing of Air \	Washer Unit					
	thick Double Skin Pan 0.8 mm Galvanized shi insulation injected in be	The housing/casing of the Air Washer Unit shall be double skin construction. (25±2) mm thick Double Skin Panels shall be made of 0.80 mm pre-painted sheet on outer side and 0.8 mm Galvanized sheet (275 GSM) inside with 40kgs/cub mtr density, fire retardant P.U. insulation injected in between. This panel shall be screwed on to the aluminum frame work with soft rubber Gasket in between to make the joints air tight.					
	make the joints air tigh	ction shall be jointed together w nt with suitable size air tight a re fan section housing shall be	ccess door at variou	s sections for			
5.01.02	The air washer tank shall be fabricated from MS plate of minimum 6 mm thick and inside and outside surface of the tank shall be spray galvanized (minimum 60 microns DFT). Minimum depth of the tank shall be 800 mm. Tank construction shall be such that the suction screen can be replaced while the unit is operating. Tank shall be provided with overflow, drain with valve, float valve makeup connection with a gate valve backup, quick fill connection with globe valve etc. The overflow pipe shall be connected to drain pipe after isolating valve on drain pipe.						
5.01.03		all be fabricated out of 18G ga minimum 50% free area.	Ivanized steel sheets	& galvanized			
5.01.04		pank construction (one uni-flow a be galvanised. Cat Walks of su					
5.01.05	type. The nozzle shall be spaced to give a uniform	be of brass or bronze with chron be designed to produce fine ato coverage of the air washer sec ange of 1.4 to 2.4 Kg/cm2	mized spray and sha	all be properly			
5.01.06	The eliminator plates shall be of 24G thick GS sheets class 275 or from 100% virgin PVC of minimum finished thickness of 2 mm. The eliminator section made of GSS shall have minimum six bends. The PVC eliminators shall be UV stabilized using Titanium di-oxide and shall withstand the weathering test as per IS:4892 for 500 hrs. Type test report of the compound testing carried out in any reputed laboratory shall be submitted for approval. All supports, tie rods and space bar shall be of either galvanised steel or PVC construction and shall be complete with suitable drip tray and drain pipe.						
5.01.07	An airtight inspection doo each air washer unit.	or of 600mm X 700mm size and	a water marine light b	pe provided for			
STA	THERMAL POWER PROJECT AGE-III (1X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION-VI, PART-B	SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 7 OF 30			

CLAUSE NO.	TE	CHNICAL REQUIREMENTS		एनटीपीमी NTPC			
5.01.08	Suitable number of brass screen shall be provided in the air washer tank to arrest the dirt entering the circulating water pump suction. Suitable GI grid shall be used inside the screen for reinforcement						
5.01.09	The specification for centrifugal fans shall generally be as indicated below. Centrifugal fans for air washer units shall be of DIDW type.						
5.01.10	Saturation efficiency of A	ir Washer units shall be minimur	n 90%.				
5.01.11		pe provided at various elevation its if required to be placed on t					
5.02.00	Unitary Air Filtration						
5.02.01	Each modular unitary air filtration shall consist of Casing, Tanks, Fans, Distribution plates, Moisture eliminator and water repellant type nylon filter with frame and support, Header and standpipe with support, Spray and flooding type nozzle. Screen type suction strainer, Pumps, Necessary controls & Instrumentation, and all other required accessories.						
5.02.02	The housing/ casing of air washer unit shall be double skin construction. Double skin panels shall be made of 22G galvanized sheet on outer side and 20G galvanized sheet inside with 25mm thick polyurethane foam insulation of minimum 38 kg/cub. Mtr. Density in between. Thickness of galvanization shall be minimum 60 microns DFT. Frame work for section shall be joined together with soft rubber gasket in between to make the joints air tight. The entire fan section shall be mounted on rolled formed GSS channel frame work.						
5.02.03	The unitary air filtration tank shall be fabricated from MS plate of minimum 6 mm thick and inside and outside surface of the tank shall be spray galvanized (minimum 60 microns DFT). Minimum depth of the tank shall be 800 mm. Tank construction shall be such that the suction screen can be replaced while the unit is operating. Tank shall be provided with overflow, drain with valve, float valve makeup connection with a gate valve backup, quick fill connection with globe valve etc. The overflow pipe shall be connected to drain pipe after isolating valve on drain pipe.						
5.02.04		nall be fabricated out of 18G ga h minimum 50% free area.	Ivanised steel sheets	& galvanised			
5.02.05		all be one-bank construction. Al of suitable width shall be provid					
5.02.06	cleaning type. The nozing properly spaced to give	all be of brass or bronze with zle shall be designed to produce a uniform coverage of the air all be in the range of 1.4 to 2.4 K	e fine atomized sprawasher section. The	y and shall be			
5.02.07	The eliminator plates shall be of 24G thick GS sheets class 275 or from 100% virgin PVC of minimum finished thickness of 2 mm. The eliminator section made of GSS shall have minimum six bends. The PVC eliminators shall be UV stabilized using Titanium di-oxide and shall withstand the weathering test as per IS:4892 for 500 hrs. Type test report of the compound testing carried out in any reputed laboratory shall be submitted for approval. All supports, tie rods and space bar shall be of either galvanised steel or PVC construction and shall be complete with suitable drip tray and drain pipe.						
5.02.08		ors of suitable size shall be proon for easy accessibility and ma itary air filtration.					
STA	THERMAL POWER PROJECT AGE-III (1X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION-VI, PART-B	SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 8 OF 30			

CLAUSE NO.	TE	CHNICAL F	REQUIREMENTS		एनरीपीमी NTPC			
5.02.09	Suitable number of brass screen shall be provided in the air washer tank to arrest the dirt entering the circulating water pump suction. Suitable GI grid shall be used inside the screen for reinforcement.							
5.02.10		The specification for centrifugal fans shall generally be as indicated below. Centrifugal fans for UAF units shall be of DIDW type.						
5.02.11	All equipments, compo specification requiremen				n line with the			
5.02.12	Saturation efficiency of	Unitary Air Fi	Itration (UAF) units	shall be minimum 60°	%.			
5.02.13	UAF units placed on the	roof shall be	e provided with stee	l shed (open).				
5.03.00	Centrifugal Fan							
5.03.01 5.03.02	The casing shall be of welded construction fabricated with heavy gauge galvanised sheet steel or MS sheet with spray galvanization (minimum 60 micron DFT). The minimum thickness of casing shall be 3 mm. It shall be rigidly reinforced and supported by structural angles. The seams shall be permanently sealed air-tight. Split casings shall be provided on larger sizes of fans. Casing drain with valves shall be provided wherever required. The impeller shall have die-formed backward-curved blades tie welded to the rim and back plate to have a non overloading characteristic of the fan. Rim shall be spun to have a smooth contour. If required intermediate stiffening rings shall be provided. Shaft sleeves shall be furnished wherever required. The impeller, pulley and shaft sleeves shall be secured to the shaft by key and/or nuts.							
5.03.03	The bearing shall be self aligning, heavy duly ball, roller or sleeve bearing. They shall be adequately supported. They shall be easily accessible and lubricated properly from outside.							
5.03.04	Inlet guard shall be spun to have a smooth contour. Inlet screen, if provided, shall be of galvanised wire mesh of 25 mm square.							
5.03.05	rubber pad or cushy foo	Base plate with necessary number of spring type vibration isolators or ribbed neoprene rubber pad or cushy foot mounting shall be provided. The vibration isolators should have a minimum of 70% efficiency.						
5.03.06	The first critical speed speed.	of the rotatir	ng assembly shall b	e at least 25% abov	e the opening			
5.03.07	The fans shall be provid HP. All V-belt shall be of to the fan inlet. There s ambient) shall be atleas at the design duty point.	equipped with hall be a mir st fifteen perd	n removable belt gua nimum of two belts	ards that do not impe per drive. Motor ratin	de the air flow g (at 50 deg.C			
6.00.00	BALANCE EQUIPMEN	T SPECIFIC	ATION					
6.01.00	CENTRIFUGAL PUMPS	S						
	a) Type	:	Horizontal Centrifu	ıgal, Axially split type	casing pump			
				discharge horizont vided for modular air				
	b) Impeller	:	Closed type		_			
	c) Material of Const	ruction	20/ Ni O	0.240 O= FO 222				
	i) Casing ii) Impeller	:	2% Ni Cast Iron : I Bronze IS:318 Gr-					
SIPAT SUPER THERMAL POWER PROJECT TECH			AL SPECIFICATION ON-VI, PART-B	SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 9 OF 30			

CLAUSE NO.	TECHNICAL REQUIREMENTS
	iii) Wearing rings : Bronze iv) Shaft : SS 316
	v) Shaft sleeve : SS 316 vi) Lantern ring : Brass / Bronze vii) Packing : Asbestos free
	viii) Base Plate: Carbon steel as per IS:2062ix) Speed: Maximum 1500 rpm
	x) Other requirements : To refer to Annexure-I titled "Horizontal Pumps" of this sub section.
6.02.00	Material of Construction for Piping & Fittings
	a) Piping for Chilled and Condenser water lines: Heavy grade-IS:1239 or Equivalent upto150 NB and Grade 410 of IS:3589 or Equivalent for pipes beyond 200 NB with thickness as indicated in Annexure-II
	b) Circulating water piping of Ventilation System Heavy grade-IS: 1239 or Equivalent upto150 NB and 200 NB with thickness as detailed at Annexure-II. The piping upto 100 mm diameter shall be of galvanized stee (galvanization shall be as per IS: 4736) and those above 100 mm dia. shall be black steel. The piping shall be calculated as the second shall be black steel.
	c) Refrigerant piping: Seamless steel tubes conforming heavy grade IS:1239 or copper tubes as per IS:2501 (copper material as per IS:191 hard copper grade).
	d) Drain piping : Same as (a) above & galvanized as per IS:4736.
	e) Fittings 1) The steel fittings shall conform to ASTM A234 Gr WPB and dimensional standard to ANSI B 16.9/ANS B16.11 / equivalent for sizes 65 NB and above. 2) For sizes 50 NB and below, the material shall conform to ASTM A-105. 3) All steel flanges shall be of slip on type and shall conform to ANSI B 16.5 4) For pipe sizes above 350 NB, fabricated fittings from sheets of adequate thickness may be used. The bend radius in case of mitre bends shall be minimum 1.5 times the nominal pipe diameter and angle between two adjacent sections shall not be more than 22.5 deg and shall be as per BS:2633/BS:534. 5) Fittings, flanges and pipe joints of refrigerant piping shall conform to ANSI B31.5
6.03.00	VALVES
6.03.01	Technical data sheet of the various types of valves (Gate, Globe, Butterfly and check valve) shall be as per Annexure-III .
6.03.02	Valves shall have full sizes port and suitable for horizontal and as well as vertica installation.
6.03.03	Valves for regulating duty shall be of globe type suitable for controlling throughout its lift.
6.03.04	All safety /relief valves shall be so constructed that the failure of any part does not obstruct the free discharge.
6.03.05	Valves shall be furnished with back seating arrangement for repacking while working under full working pressure.
STA	THERMAL POWER PROJECT SECTION-VI, PART-B SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM PAGE 10 OF 3

CLAUSE NO.	TECHNICAL REQUIREMENTS				
6.03.06	Manual gear operators be provided for valves of size 200 NB and above.				
6.03.07	All valves shall be supplied with companion flanges, nut, bolts & washers, etc.				
6.03.08	The refrigerant line valves shall have steel or brass body with TEFLON gland packing. The construction of disc shall be either globe or angle type. The valve seat shall have white metal lining or equivalent.				
6.03.09	Balancing / Controller Valves:				
	The valves of sizes 32 mm to 50 mm dia shall be of gun metal / cast iron construction with screwed ends. Whereas valves of sizes 65 mm and above shall be of cast iron construction with internal parts of SS 410 and EPDM / nitrile seat with flanged ends.				
6.04.00	AIR FILTERS				
6.04.01	Pre Filter				
	 Type: Flange / Cassette a) Fabric Filter*: Pre-filter shall contain washable non-woven synthetic fiber or High densit Polyethylene (HDPE) media having 18G GSS / 16G Al alloy frame. The filter medi shall be supported with HDPE mesh on air inlet side & Aluminium expanded metal o exit side or G.l. wire mesh on both sides. b) Metallic Filter*: Filter medium, aluminium alloy shall be supported on galvanized expanded meta casing. Frame shall be fabricated from aluminium alloy of minimum 16G thicknes conforming to IS: 737 or 18 gauge. * For air washer units taking suction from C-row side, only metallic pre-filters shall be provided. However, for other air washer units, Contractor may provide fabric of metallic pre-filters. 				
	3) Other requirements : (as applicable)				
	Suitable aluminium spacers be provided for uniform air flow;				
	b) Casing shall be provided with neoprene sponge rubber sealing.				
	c) Capable of being cleaned by water flushing.				
	d) Density of filter medium shall increase in the direction of air flow in case of metallic filter.				
	e) Filter media shall be fire retardant and resistant to moisture, fungi, bacteria of frost.				
	4) Efficiency:				
	Average arrestance of 65 - 80 % when tested in accordance with BS:6540/ASHRAE 52 - 76 / EN-779.				
	5) Minimum thickness : 50 mm				
	6) Face Velocity : Not more than 2.5 m/sec. 7) Pressure drop : Initial pressure drop - Not to exceed 5.0 mm WC at rate				
	flow.				
	Final pressure drop - Upto 7.5 mm WC. 8) Location : a) At the suction of each AHUs				
	: b) At the discharge of each Fresh air fan				
	: c) At the discharge of each Supply air fan				
SIPAT SUPER THERMAL POWER PROJECT STAGE-III (1X800 MW) EPC PACKAGE TECHNICAL SPECIFICATION SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM PAGE 11					

CLAUSE NO.	TECHNICAL REQUIREMENTS							
6.04.02	Fine	Filters (Microvee	type)					
	Type Fine filter shall conta Polyethylene (HDPE) m shall be supported with				a having 18G GSS / 1	16G	Al alloy frame. Th	ne filter media
	3)	Other requiremen		:	a) A neoprene sprovided on either b) Capable of being	er fa g cl ıll b	ace of the filter frar eaned by air or wa e fire retardant an	ne. ter flushing.
	4)	Efficiency		:	Average arrestance with BS:6540/ASHRA	> 6	00% when tested i	n accordance
	5) 6)	Minimum thickner Face Velocity		:	150 mm or 300 mm. Not more than 1.2	m/s	sec for 150 mm a	and not more
	7)	Pressure drop		:	than 2.4 m/sec. for 3 Initial pressure drop rated flow; Final pre-) -	Not to exceed 10	
	8)	Location		:	i) At the discharge of ii) At the discharge of iii) At the discharge of pressure 30mm iii)	f ea of ea of e	ich individual AHU ach Fresh air fan. each supply air fan	-
6.04.03	Abso	olute Filter / Hepa	Filter	ı	<u> </u>			
	1)	Media		:	100% sub-microscop	oic (glass fibers.	
	2)	Frame		:	Aluminium alloy of (IS: 737) with handles	s.		
	3)	Other requirement	nts	:	A neoprene sponge on either face of the	filte	er frame.	
	4)	Efficiency		:	99.97 % down to accordance with BS 209B.			
	5) Minimum thickness			:	300 mm			
	6)	Face Velocity		:	Not more than 1.2 m			14/0 -4
	7)	Pressure drop		:	Initial pressure drop rated flow; Final pressure drop -			o mm VVC at
	8)	Location		:	At the discharge of Equipment Room / Charger Rooms.			
6.05.00	LOW	PRESSURE AIR I	DISTRI	BU	TION SYSTEM			
6.05.01					shall be through gal alloy (grade 19000 /			
6.05.02	Thic	kness of rectangu	lar duc	ts	shall be as follows:			
		er Dimension of du	ıct (mm)	Thickness of GI Thickness of Aluminium s sheet(mm) (mm)			
		750 mm			0.63 (24 G)		0.80	
		to 1500 I to 2250			0.80 (22 G) 1.00 (20 G)		1.00 1.50	
	225	I & above			1.25 (18 G)		1.80	
6.05.03	Thic	kness of round du	icts sha	all l	pe as follows :			
STA					CAL SPECIFICATION TION-VI, PART-B		SUB SECTION-A-17 IR CONDITIONING AND /ENTILATION SYSTEM	PAGE 12 OF 3

CLAUSE NO.	TECHNICAL REQUIREMENTS						
	Diameter of Round	duct	Thickness of GI sheet	(mm) Thickness sheet (mm	of Aluminium		
	150 to 500		0.63		0.80		
	501 to 750		0.80		1.00		
	751 to 1000						
			0.80		1.00		
	1001 to 1250		1.00		1.50		
	1251 & above		1.25		1.80		
6.05.04	Duct Fabrication and			4 B10 (014 A 014 A			
	(a)		oe as per the latest relevar				
		, in cas	may be site fabricated or e of partly used factory f s.				
			e the buildings with larger				
	below 2250 m The duct supp The MS rods existing floor to with provision be provided b shall be taken support includ members, hod required shall	orts shall orts sha for the beams/w of neces y contraction from hing MS bks, das	MS rods and 50x50x3 m be supported by 10mm I all be at a distance of not not not all be at a distance of not not not all beams/roof beams/collessary auxiliary or special actor by dash fasteners fix orizontal/vertical bracings rods, MS angles and doubth fasteners coach screws ded by the bidder.	MS Rods and 40x4 nore than 2000 mm e building shall be umns as provided by steel members or be ted to the ceiling slat of the structures. A ble angles, auxiliary	0x3 MS angles. for A/C system. hung from the by the Employer by hooks or can ab. No supports all items of duct or special steel		
	ble connection	of fire	al duct connects to the inta retarding, at least 150 mn nated double layer canvas	n width shall be pro	vided of closely		
	noiseless flow	of air.	-sets and other transform The throat of every bran e main duct to which the br	ch duct shall be siz	zed to have the		
		caulke			ween masonry and duct work t of air from one space to the		
	g) Wherever pipe hangers or rods pass through the ducts, light and streamline ease ment around the same shall be provided to maintain smooth flow of air.						
	equipment to l lined with sub built up consti Access doors	oe servi stantial ruction, shall ha	e provided in the duct work ced. All access doors sha felt edging to prevent air structurally strong and ea ave two rust proof window ush with insulation or plast	all be of adequate s leakage. Access d ach shall have at le v sash of approved	ze and shall be cors shall be of ast two hinges. type. All doors		
	i) Where ever horizontal ducts are running outside the building and or at locations where it is not possible to support the ducts from Employers ceiling/floor due to not availability of the same, the base steel frame/truss work for supporting the ducts between two columns shall be provided by Employer. However, all other auxiliary steel members, hooks, rods, etc. for supporting the duct work with the base frame truss work shall be provided by the bidder. For vertical ducts running outside the building, bidder to take support from building columns and beams. However, other auxiliary steel members, hooks, rods, etc. for supporting the duct work with beam & columns shall be provided by the bidder.						
STA	THERMAL POWER PROJECT GE-III (1X800 MW) EPC PACKAGE	TE	CHNICAL SPECIFICATION SECTION-VI, PART-B	SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM			

CLAUSE NO.	TE	CHNICAL REQUIREMENTS		एनरीपीमी NTPC				
6.05.05	Splitters and dampers shall be provided for equipment/area isolation and for proportional volume control of system. The same shall be minimum 16 gauge GS sheet of quadrant type with suitable locking device, mounted outside of duct in accessible position.							
6.06.00	Factory fabricated ducts:							
	i) All ducting shall	be fabricated of LFQ (Lock Form	ning Quality) grade p	rime G.I.				
	ii) Unless otherwise specified here, the construction, erection, testing and performance of the ducting system shall conform to the SMACNA-1995 standards ("HVAC Duction Standards-Metal and Flexible-Second Edition-1995" SMACNA)							
	iii) All ductwork including straight sections, tapers, elbows, branches, show pieces, collars, terminal boxes and other transformation pieces must be factory fabricated by utilizing the machines and processes as specified in SMACNA or by equivalent technology. In equivalent method, the fabrication shall be done by utilizing the following machines and process to provide the requisite quality of ducts and speed of supply:							
	 a. Coil lines to ensure location of longitudinal seams at corners/folded edges only to obtain the required duct rigidity and low leakage characteristics. No longitudinal seams permitted along any face side of the duct. b. All ducts, transformation pieces and fittings to be made on CNC profile cutters for required accuracy of dimensions, location and dimensions of notches at the folding lines. c. All edges to be machine treated using lock formers, flangers and roll-bending for turning up edges. 							
	d. Sealant dis Pittsburgh longitudinal	pensing equipment should be ulock where sealing of longitudi joint is compulsory for the ducts	nal joints are specifi over 2" w.g. static pr	ed. Sealing of essure				
		onnectors shall be 4-bolt slip-on t y leakage additional sealant sha		uilt-in sealant, if				
	_	ducts shall have the thickness of		::				
	SI.No	<u> </u>	Τ					
	JI.IV	Size of Duct	Sheet Thickness	s				
	i)	upto 750 mm	0.63 mm					
	<u>ii)</u>	751 mm to 1500 mm 1501 mm to 2250 mm	0.80 mm 1.00 mm					
	iii)	2251 mm and above	1.25 mm					
6.07.00	Diffusers, Grills & Dan	npers:						
6.07.01		s with factory fitted volume conveyaporative cooling system areas		ided for all air-				
6.07.02	Return air diffusers of a	ir-conditioned areas shall be with	nout volume control da	ampers.				
		ouvers are required for all negative or ovided for all areas pressurized						
6.07.03	draft dampers shall be provided for all areas pressurized under ventilation system. For AC system the diffusers/grills shall be of extruded Aluminum of minimum 1.2 mm thick with powder coating. The color of power coating shall be as per the interior Décor. The diffusers/grills shall be of powder coated mild steel construction for Ventilation system.							
STA	 THERMAL POWER PROJECT GE-III (1X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION-VI, PART-B	SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 14 OF 30				

CLAUSE NO.	TEC	CHNICAL REQUIREMENTS		एनटीपीसी NTPC			
6.07.04	For AC system Supply air grills shall be of double deflection type and return air grills shall be of single deflection type. For ventilation system supply air grills shall be of double deflection type.						
6.07.05	The nozzle type diffusers shall be fabricated from minimum 1.5mm aluminium sheet. The base shall be fixed type. The nozzle shall be of volute design with the Spout diameter being half the base dia. and designed for low noise and long throw. The nozzle shall be able to rotate to any angle within the base. The whole assembly shall be powder coated as per interior decor.						
6.07.06	All volume control (VC grills/diffusers and shall	c) damper shall be operated be of GI sheet.	by a key from the	e front of the			
6.07.07	The thickness of VC dar be of minimum 22 gauge	mpers shall be of minimum 20 g e.	auge and thickness	of louvers shall			
6.07.08		e provided in the duct collar fles wherever required shall also		and proper air			
6.07.09	Fire dampers shall be minutes.	motor operated type and sha	ll have fire rating o	of minimum 90			
6.07.10	All plenum chambers of GS sheet and supported	connections to fans, dampers e on MS angle frames,	tc. shall be construct	ed in 18 gauge			
6.07.11	All ducting surfaces coming in contact with corrosive fumes or gases shall be painted with three coats of epoxy paint over a coat of suitable primer.						
6.07.12	Suitable number of VAV box (if applicable) shall be provided for optimum use of VFD driven AHU.						
6.08.00	Thermal and Acoustic Insulation						
6.08.01	A) Application with Glas	ss Wool					
	 (a.) All surfaces to be insulated both thermally and acoustically shall be thoroughly cleaned, dried and an adhesive (CPRX compound of Shalimar Tar Products or Equivalent) be applied @ 1.5 Kg /Sqm on the surface. (b.) Insulation material (either expanded polystyrene foam or Glass Wool/ Glass fiber or Equivalent) shall be struck to the surface. All the joints shall be sealed with bitumen. (c.) Insulation mass to be covered with 500 gauge polythene sheet with 50 mm overlaps and sealing all joints on hot side. (d.) Insulation Finish of types specified under shall be provided thereafter. 						
	B) Application with N	itrile Rubber:					
	(a) All surfaces to be ir	nsulated shall be properly cleane	ed.				
		e such as SR 998 or equivalent s nsulation material surfaces.	shall be applied over	the surfaces to			
		al shall than be pasted onto to air entrapment within.	he surfaces in a ma	anner to avoid			
		ss Cloth with a suitable adhesive the insulating material to avoid s		ivalent shall be			
	C) Application with F	Polyurethane Foam & Polyisog	cyanurate Foam	<u> </u>			
STA	THERMAL POWER PROJECT AGE-III (1X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION-VI, PART-B	SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 15 OF 30			

CLAUSE NO.		TECHNICAL REQUIREMENTS								
	(a) All surfaces to be insulated shall be cleaned.									
	(b) A suitable adhesive such as CPRX or Loid Bond 83 or equivalent shall be applied over the surface to be insulated and insulation material surfaces.									
		(c) Insulating material with aluminum foil lamination shall then be pasted onto the surface in a manner to avoid stretching and any air entrapment within.								
				with a suitable adhesivnaterial, to avoid surface			shall be ther			
	(e) lı	nsulation Finish of	types sp	ecified under shall be pr	ovided there	eafter.				
	D)	Application with (XLPE)	FR Clo	sed Cell Chemically C	ross Linked	Polyethy	rlene Materia			
		All surfaces to be noisture.	insulat	ed shall be properly o	cleaned of a	any dust	, grease and			
) í g	(b) A suitable adhesive, normally, a pressure sensitive acrylic base, such as SR 998/STAR Glue R242 or Neosole AA 900 or equivalent shall be used to paste the insulating material over the cleaned surface.								
	(c) XLPE cut to size for each surface, with overlaps provided for two faces shall be stuck to the surfaces in a manner to avoid air entrapment. The extent of over-lap shall be equivalent to the thickness of the material to be applied. The adhesive is applied on both the surfaces to be insulated and the insulation foam material.									
		Application of the i pround level, in a cl		g material to surfaces s t free area.	should prefe	rably be	carried out at			
	n	nm wide. The insu	ılation c	nal, shall be taped with sover the surface shall be 00mm, to provide a neat	e then held	in position				
6.08.02		of Insulation & Fi	-	, .						
	SI. No.	Surfac	e	Insulation Material	Insulatio n Form	Thick (mm)	Finish (mm			
	1.	Supply & return a duct of AC Syster		in bonded glass wool or	Roll /Slab	50	F-3			
				sed Cell Elastomeric ile Rubber	sheet	19	As per manufacture std.			
			Or I	Polyisocyanurate Foam	Slab	30	F-3			
	2.	Refrigerant (Suction and liqui lines)		sed Cell Elastomeric ile Rubber	tube	19	As per manufacture std.			
		·	Or Rig	d Polyurethane Foam	Pipe Section	50	F-1 (a)			
	3.	AHU drain pipe		sed Cell Elastomeric ile Rubber	tube	19	As per manufacture std.			
STA	THERMAL	· · · · · · · · · · · · · · · · · · ·		INICAL SPECIFICATION ECTION-VI, PART-B	SUB SECTION AIR CONDITION VENTILATION	NING AND	PAGE 16 OF 3			

CL	ΔΙ	ISF	NO	

TECHNICAL REQUIREMENTS



SI. No.	Surface	Insulation Material	Insulatio n Form	Thick (mm)	Finish (m
		or Rigid Polyurethane Foam	Pipe Section	50	F-1 (a)
4.	AHU condensate pan (insulation if required)	Mineral wool or resin bonded glass wool	Slab	25	As per manufactu std.
5.	Chilled water piping, valves & specialties	Resin bonded Mineral wool or resin bonded glass wool	Pipe section	75	F-1/F-3
		or Rigid Polyurethane Foam	Pipe Section	50	F-3
6.	Chiller (insulation if required)	As per manuf	acturer std		
7.	Chilled water pumps	Resin bonded Rockwool wool or resin bonded glass wool	Slab	75	F-1/ F-3
		or Rigid Polyurethane Foam	Slab	50	F-3
8.	Expansion tank with associated piping	Resin bonded Rockwool wool or resin bonded glass wool	Slab/ Pipe section	75	F-1/ F-3
		or Rigid Polyurethane Foam	Slab	50	F-3
9.	Acoustic insulation of duct	Resin bonded Glass wool	Slab	25	As per specificati
10.	Exposed air duct	Resin bonded Glass wool/Rockwool	Roll/Slab	50	F-4
		or Polyisocyanurate Foam	Slab	50	F-4(a)

6.08.03

Insulation Material	Code	Thermal conductivity	Density Kg/m ³
		(w/m/ ^o C	
Resin bonded glass wool	IS:8183	0.049 at 50oC	i) 24 (For Glass wool) ii) 48 (For Rockwool)
		0.043 at 50oC	iii) 48(For acoustic insulation)
Mineral wool pipe section. Min.Gr.2	IS:9842	0.043 at 50oC	144
Closed Cell Elastomeric Nitrile Rubber		0.036 at 20oC	40 – 60
Polyurethane Foam	IS12436	0.03 at 50 oC	34 + 2
Polyisocyanurate Foam		0.03 at 50 oC	34 + 2
Note: Insulation used fo	r HVAC app	olication shall be CFC/H	CFC free

6.08.04

The specification for various finishes shall be as follows

CLAUSE NO.		TE	CHNICAL REQUIREMENTS		एनहीपीसी NTPC
	a)	Step-1 Wrapp surface	Resin Bonded Glass Wool/Resin bing of Poly-Bonded Hessain (PE e of insulation with 50 mm overl nthetic adhesive like CPRX or E	BH – to act as vapour ap stitching and sea	seal) on outer aling of overlap
			rface then shall be wrapped w , butting all the joints and laced o		
		mm th	cement (4:1) plaster shall be ap ick, the second layer being bro g compound shall be added to th	ought to a smooth fi	nish. A water
	aa)	Wrapp	Vith Polyurethane Foam & Poly sing of two layers of 7 mil 10 x 10 ive such as SR 998 or Loid Bond) mesh glass cloth dip	
	b)	Finish F-2 Step-1 Insulati sealing	ion shall be covered with 500g of overlap with synthetic adhelent compound.	polythene with 50m	
		Step-2 Same	as Step-2 of Finish F-1 above.		
		Step-3 Same	as Step-3 of Finish F-1 above.		
	c)	Finish F-3 Step-1 Same	as Step-1 of Finish F-2 above		
		locking	olythene shall be covered with of joints with self-locking screws		
	Step-2 Sa Step-3 Sa Step-4 Ap wra wa		Same as Step-1 of Finish F-1 above. Same as Step-2 of Finish F-1 above. Same as Step-3 of Finish F-1 above. Application of 3 mm thick coat of suitable water proofing compound and wrapped with fibre glass RP tissue followed by final coat of 3 mm thick water proofing compound over the RP tissue. After the above treatment, 22G Aluminium sheet cladding, properly stiched		
	dd)	Finish F-4(a) (Wi Applica insulati 150 mr againsi	ints shall be provided over the enth FR Closed Cell Chemically Cration of aluminium sheet 22G clang material. Cladding sheet is hom C/c over tongue-in-groove joint twater ingress.	ross Linked Polyethyle adding to be provided eld in position with S ats applied with a felt	over the XLPE DST screws @
6.08.05	flange minim gauge Howe	es (100 mm and a num damage to the Aluminium shee	rs and hatches on equipment, bove), insulation shall be applie insulation by encasing the instruct metal boxes which are bolte the vapour seal between the stained.	d so as to facilitate r isulation in 24 gauge ed together around f	emoval without e GI box or 22 the equipment.
6.08.06	ACO	other centrifuga	DN a distance of 5 meters from AHU Il fan outlet shall be acoustically ass wool of 48 Kg/Cu.M. density	lined from inside wi	th 25 mm thick
STA	I THERMAI AGE-III (1) EPC PACI	•	TECHNICAL SPECIFICATION SECTION-VI, PART-B	SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 18 OF 30

CLAUSE NO.	TE	CHNICAL REQUIREMENTS		एनटीपीसी NTPC		
	Insulation shall b) Fibre glass tissue before applying	sheet having 5 mm dia perforation at 8 to 10 mm centre-to-centre distance Insulation shall be fixed on wooden frame of 600 x 600 mm dimension. b) Fibre glass tissue sheet shall be applied over the outer surface of insulation before applying perforated aluminium sheet. Application of acoustic insulation she inline with the requirements specified above.				
6.09.00	Axial Fans					
	b) The fan casing s c) Necessary rain adjustable damped of the speed o	Il have fixed / variable pitch cast shall be of heavy gauge sheet st protection cowl, inlet and ouper, vibration isolators, back drafthe fan shall not exceed 1000 and 1500 rpm for fan with inshaving static pressure of 30 ceed 1500 rpm for fan with impeller diameter of 450 rpm with impeller diameter of 450 rpm shall be atleast 25% above the ories like supporting structure etcy 1000 m³/hr & lower shall be of rizing pump house, fuel oil unlong, Gas rooms in TG building and, etc. shall be provided with spenses and shall be provided with sp	eel construction. tlet cones, bird pro- t dampers etc. shall be rpm for fan with impeller diameter 45 mm WC or above the eller diameter of above nm or less. The first of e operating speed. c. as required shall be propeller exhaust type eading pump house, d battery rooms of Te	tection screen, be provided. peller diameter 0 mm or less. e speed of the ve 450 mm and critical speed of e provided. e. central lube oil G building, AIS		
6.10.00	Roof Ventilators					
6.10.01	The roof extractors shal	I be "COWL" type.				
6.10.02	Casing shall be heavy omm diameter and 5 m	Impeller shall be of axial flow type, cast Aluminum in one piece and dynamically balanced. Casing shall be heavy gauge sheet steel construction of 3 mm thick for impeller upto 750 mm diameter and 5 mm for fans with impeller of diameter 750 and above. In casing access door with locking arrangement be provided.				
6.10.03	the extractor is installed	ned for weather protection of the d. Galvanised bird screen of 15 eel supports as required will be p	mm Square be pro			
6.10.04	The speed of the fan be	limited as per limitation given at	oove for axial fans.			
6.10.05		tection exhaust hood, transforma ors, bird screen, etc. as required		isolators, steel		
6.10.06	The vibration level for fa	ns shall be as per ISO: 14694.				
7.00.00	PLANT CONTROL OF	AC SYSTEM:				
7.01.00	Brief scheme of controlling the operation is described below. Detailed description of the control system for safe and efficient operation of the plant shall be elaborated, got approved from employer. The descriptions in the sub-sections of the control & instrument sections shall also be referred to.					
7.02.00	Control Scheme for Ai	r-Conditioning System				
7.02.01		ements specified below and generated in the respective control sy		cified under this		
7.02.02	The basic function of the system shall be to closely control and monitor temperature and humidity conditions inside the air-conditioned spaces, to optimize / minimize energy consumption by automated operation, to provide remote centralized monitoring & control for various mechanical facilities including sequential start/stop of the whole Air conditioning System, automatically calculate record and cooling load for each hour /day/season, to					
STA	THERMAL POWER PROJECT GE-III (1X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION-VI, PART-B	SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 19 OF 30		

CLAUSE NO.	TE	CHNICAL REQUIREMENTS		एनहीपीसी NTPC
	consumption for varying equipment for equal du operating unit and disp water valves to startup operation /duty cycling requirements and inside UPS and Battery Charg & FGD control room" st	data & alarms, to maintain regloads, duty cycling to operate ration, automatic startup of starlaying fault alarm status of the stop water flow through chilled, Programmed startup/stop of room temperature and humidite room, static excitation room (anall be maintained by controlling any modulating valve at chilled was	all the equipment incomby equipment in castripped unit, activating a condenser circuit. Individual AHU as y of "CR, CER, SWA as applicable)", "ESP of the chilled water flood	cluding standby se of failure of ig /deactivating For sequential per operating S control room, control rooms, w by means of
7.02.03	based dedicated control units with local start / DDCMIS based Contro FGD control room". Further	Air Conditioning system shall be lers to be provided by Contractorstop & indication for main plass I system of A/C plant for "Main ther these microprocessor-based th DDCMIS based Control panel	or for each Screw /ce nt A/C system in ac plant area", "ESP c d control panels of Cl	ntrifugal Chiller ddition to Main ontrol rooms &
7.02.04		n for "Water system control i Distributed Digital Control M		
		system of "office area in contro ontroller integrated GIU based C ice.		
7.03.00	Water Chilling Plant C	ontrol		
7.03.01	_	controls shall be provided as pointerface with control system acontrols.		
	Water chilling unit control system shall be designed to have a constant chilled water outlet temperature from evaporator at all load condition by means of controlling ON-OFF thermostat (one for each compressor). The closure of liquid line solenoid valve and tripping of compressor at lower water temperature and opening of solenoid valve and starting of compressor at high water temperature set point shall be automatic through the thermostat. Between the above set points the compressor capacity shall be controlled automatically through cylinder "load-unload" mechanism activated through the suction pressure or return chilled water temperature.			
7.03.02	_	I be equipped with superheat of valve which gets its impulse fruiller outlet.		
7.03.03		e cut-out and oil pressure (OP) of sure cut-out shall be automatic of of low oil pressure.		
7.03.04	1	close the liquid refrigerant line the operation of low pressure coer).		=
7.03.05	_	e heaters shall be interlocked verther, the safety thermostat shall isses above safe limit		
STA	THE EVERT TEMPERATURE IN THERMAL POWER PROJECT AGE-III (1X800 MW) EPC PACKAGE	SES ADOVE SAIE IIMIL. TECHNICAL SPECIFICATION SECTION-VI, PART-B	SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 20 OF 30

CLAUSE NO.	TE	CHNICAL REQUIREMENTS		एनदीपीसी NTPC
7.03.06	Provision shall also be r	nade for the manual restarting o	f the compressor.	
7.03.07	On-off type anti-freeze thermostats, one for each chiller shall be provided in addition to the controlling on-off thermostat for safety purpose and shall act in the event of failure of on-of thermostat to close the liquid line solenoid valve and also to simultaneously trip the compressor.			failure of on-off
7.03.08	each chiller and each co	Compressor starting/running shall be interlocked with the low / adequate flow at the outlet each chiller and each condenser and as well as with pressure in the inlet of the condenser In addition, closure or open status of various valves shall be used for interlock, alarm at control of Air Conditioning System.		
7.03.09	tower sump and opera	os shall be interlocked with the tion of cooling tower fans. High el by means of a separate level s	level in the cooling	_
7.03.10	The standby condenser water pumps, standby chilled water pumps & standby AHU shall be started automatically when the working equipments are stopped/ tripped. Auto/ Manu selecting and working/ standby selecting facility for the pumps/ AHU/ fresh air fan shall be provided.			Auto/ Manual
7.03.11	Closure of fire dampers	shall raise an alarm in the syste	m.	
7.03.12	There shall be provision for temperature and flow measurement in chilled water inlet an outlet line across AHUs to monitor the air conditioning load of each area.			water inlet and
7.03.13	Operation of air conditioning system shall be interlocked with the required minimum pressure and temperature of cooling tower at inlet to the condenser. Status indication condenser water pumps and associated cooling towers shall be provided in the contropanel of air conditioning plant.			us indication of
7.04.00	Air Handling Unit			
	a) Inside room temperature and humidity shall be maintained by controlling the chilled water flow by means of motor operated three way modulating valve and by varying the flow by means of VFD driven AHU's which shall get its signal from the Control system for main plant A/C system and ESP/FGD control rooms A/C system.			
	b) Humidity and temp. of humidification.	sensor shall actuate the PAN hu	midifier to obtain the	desired degree
		be interlocked with the running of rand safety thermostat (airstat).	AHU, temperature of	f return air,
	 d) Heater banks shall be interlocked with the running of AHU, temperature of return air humidity of return air and safety thermostat (airstat - located in front of the each heater in the supply air duct) e) AHU shall be started either locally or from the main control room of AC system by mean of Remote / Local selection facility. 			
	f) The closure of fire dampers, automatic tripping of AHU fans and fresh air fans shal interlocked with fire detection system.g) Each AHU room shall be provided with temperature transmitters in the chilled water			lled water
		and flow transmitter at chilled wa I of each area in control system.	nei odnet to calculate	anu uispidy
STA	THERMAL POWER PROJECT GE-III (1X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION-VI, PART-B	SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 21 OF 30

CLAUSE NO.	TE	CHNICAL REQUIREMENTS		एनशैपीमी NTPC		
7.05.00	a) The control and int this system also. b) Further the compre condenser water (if c) The standby conde automatically when	 b) Further the compressor starting/running shall be interlocked with the flow switches in condenser water (if applicable) circuit as well as with AHU motors. c) The standby condenser water pumps (if applicable) & standby AHU shall be started automatically when the working equipments are stopped / tripped. Auto/ Manual selector Switches and working / standby selector switches for the pumps, fresh air fans and AHU 				
7.06.00	Cassette /Hi-wall Split	Air Conditioners				
	Control and interlocks practice.	for these types of units shall I	be as per manufacti	urer's standard		
7.07.00	Miscellaneous Contro	Requirements				
	 a) Separate emergency local stop push button shall be provided for each pump compressor, fans etc. of A/C system. b) Status shall be provided of each pump, compressor, fans etc. of A/C system and Ventilation system on HMI system at control room. c) All the annunciations related to failure of equipments, tripping of equipments, source of failure / reason due to which the equipment is stopped/tripped, low & high limits of parameters such as level, temperature, pressure drop, pressure etc. shall be provided for each pump, fan, compressor, AHU, PAC, etc. of centralized A/C system. d) The fans (both supply and exhaust fans) associated with mechanical ventilation system shall be operated locally. e) Relative humidity and temperature measurement of all control rooms, CERs and all major air-conditioned areas shall be available in DDCMIS. Relative humidity and temperaturement for main plant control room and CERs to be available in multiple 					
8.00.00	numbers. PLANT CONTROL OF	VENTILATION SYSTEM				
8.01.00	GENERAL					
8.01.01		Iling the operation is described and efficient operation of the plar				
8.01.02	Control Scheme of Ve	ntilation System				
	The Ventilation system for main Plant area, ESP / FGD Control Building Area (excluding roof extraction fans, standalone Air supply and Air Exhaust fans) shall be controlled through microprocessor based Distributed Digital Control Monitoring and Information System (DDCMIS). This DDCMIS system shall perform all functions such as auto/manual operation of valves, pumps, drives, local/remote selection of operation, status indication, annunciation, interlock and protection of pumps/drives, etc.					
8.02.00	Air Washer Units (AWU) & Unitary Air Filtration Units (UAF)					
8.02.01	Air washer units shall be started/stopped by initiation from Main DDCMIS based control system of A/C plant (provided by contractor) for Main plant area and ESP/FGD control rooms. Starting/stopping of pumps shall be automatic upon such initiation.					
8.02.02	The operation of the put High level of the sump s	umps shall be interlocked with t shall be alarmed.	he low level of wate	r in the sump.		
STA	THERMAL POWER PROJECT AGE-III (1X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION-VI, PART-B	SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 22 OF 30		

CLAUSE NO.	TE	CHNICAL REQUIREMENTS		एनटीपीसी NTPC
8.03.00	Miscellaneous control	requirements		
8.03.01	Separate emergency local stop push button shall be provided for each pump, fans, etc. of Ventilation system.			
8.03.02	The status of each pump, centrifugal fans, etc. of centralized ventilation system is available on OWS in control room locally.			
8.03.03	All the alarms related to failure of equipments, tripping of equipments, source of failure / reason due to which the equipment is stopped / tripped, low & high limits of parameters such as level, temperature, pressure drop, pressure etc shall be provided for each pump, fan, AWU etc. in the control system.			of parameters
8.03.04	The fans (both supply shall be operated locally	and exhaust fans) associated v	with mechanical ven	tilation system
9.00.00	PAINTING:			
9.01.00	All the Equipments sha painting.	Il be protected against externa	I corrosion by provid	ling suitable
9.02.00	The surfaces of stainless steel, Galvanized steel, Gunmetal, brass, bronze and non-metallic components shall not be applied with any painting. The Contractor shall clean the external surfaces and internal surfaces before Erection by wire brushing and air blowing. The steel surface to be applied with painting shall be thoroughly cleaned before applying painting by brushing, shot blasting, etc. as per the agreed procedure.			an the external ving. The steel
9.03.00	For all the steel surfaces (external) exposed to atmosphere (outdoor installation), one (1) coat of red oxide primer of thickness 30 to 35 microns followed up with three (3) coats of synthetic enamel paint, with 25 microns as thickness of each coat, shall be applied. For plant at coastal area, epoxy resin based zinc phosphate primer followed by epoxy resin based paint pigmented with titanium di-oxide shall be used in place of enamel paints.			ee (3) coats of be applied. For by epoxy resin
9.04.00	For all the steel surfaces inside the building (indoor installation), One (1) Coat of red oxide primer of thickness 30 to 35 microns followed up with two (2) coats synthetic enamel paint, with 25 microns as thickness of each coat shall be applied. For plant at coastal area, epoxy resin based zinc phosphate primer followed by epoxy resin based paint pigmented with titanium di-oxide shall be used in place of enamel paints.			c enamel paint, stal area, epoxy
9.05.00	For centrifugal fans/axia (minimum 60 micron Dl	I/Roof extractor fans - Casing sh -T).	all have hot dip/ spra	y galvanization
9.05.00	However for all parts coming in contact with acid fumes (in Battery rooms), a coat of epoxy resin based zinc phosphate primer of minimum thickness 30 to 35 microns followed up with undercoat of epoxy resin based paint pigmented with Titanium dioxide of minimum thickness of 25 microns shall be applied and a top coat consisting of one coat of epoxy paint of approved shade and colour with glossy finish of minimum thickness of 25 microns.			
9.07.00	Touch up painting shall	be as per standard industrial pra	octice.	
10.00.00		ion Tank, Water Softening Plar the roof of respective building ur		C System shall
11.00.00	Centrifugal fans alongwith filter plenum of mechanical centralized ventilation system envisaged for AIS switchyard shall atleast be provided with steel shed (open).			
STA	 THERMAL POWER PROJECT \GE-III (1X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION-VI, PART-B	SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 23 OF 30

CLAUSE NO.	TE	CHNICAL REQUIREMENTS		एनरीपीमी NTPC	
				Annexure –I	
	GENERAL SPE	CIFICATION FOR HORIZONTA	AL PUMPS		
1)	SCOPE				
		ers the design, material, con performance at the Vendor's/Su ugal Pumps.			
2)	CODES AND STANDAR	RDS			
	Horizontal Centrifugal Pu and safety codes in the specifications shall be Equipment supplied sha	e design, material, construction, manufacture inspection and performance testing of rizontal Centrifugal Pumps shall comply with all currently applicable statutes, regulations disafety codes in the locality where the Equipment will be installed. Nothing in these ecifications shall be construed to relieve the Vendor of this responsibility. The uipment supplied shall comply with the latest applicable Indian Standards listed below. The ner National Standards are acceptable, if they are established to be equal or superior to			
3)	List of Applicable Standa	ards.			
	IS : 5120	rizontal Centrifugal Pumps for clear cold fresh water chnical requirements of roto dynamic special purpose pumps ntrifugal pumps for general refinery service. mps Handling Chemicals & corrosion liquids mps for process water draulic Institute Standards, USA ndards Methods for Liquid Penetration Inspection.			
	technical specifications	In case of any contradiction with aforesaid standards and the stipulations as per the technical specifications as specified hereinafter the stipulations of the technical specifications shall prevail.			
4)	DESIGN REQUIREMEN	TS			
a)	The Pump shall be capable of developing the required total head at rated capacity for continuous operation. Also the pumps shall be capable of being operated to give satisfactory performance at any point on the HQ characteristics curve. The operating range of the pump shall be 40% to 120% of the duty point unless otherwise mentioned elsewhere. The maximum efficiency of pump shall preferably be within \pm 10% of the rated design flow as indicated in data sheets.				
b)		curve shall be continuously rising ne of instability and with a mini ad.			
c)	Pumps of a particular category shall be identical and shall be suitable for parallel operation with equal load division. The head Vs capacity and BHP Vs capacity characteristics should match to ensure even load sharing and trouble free operation throughout the range. Components of identical pumps shall be interchangeable.				
STA	THERMAL POWER PROJECT GE-III (1X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION-VI, PART-B	SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 24 OF 30	

CLAUSE NO.	TE	CHNICAL REQUIREMENTS		एनरीपीमी NTPC		
				Annexure –I		
d)		ly without undue noise and vibra following values during operation		ribration limits		
	1500 rpm and below	75.0 micron 75	Bearing .0 micron .0 micron			
		ot exceed 85 dBA overall sound ressure reference for air sound race.				
e)	Motors shall be selected deg.C ambient) shall be pump in the entire operations.	The pumps shall be capable of starting with discharge valve fully open and close condition. Motors shall be selected to suit to the above requirements. Continuous Motor rating (at 50 deg.C ambient) shall be atleast ten percent (10%) above the maximum load demand of the pump in the entire operating range to take care of the system frequency variation and no case less than the maximum power requirement at any condition of the entire characteristic				
f)	equipment for the condit pumps are specified, the	The kW rating of the drive unit shall be based on continuously driving the connected equipment for the conditions specified. However, in cases where parallel operation of the pumps are specified, the actual motor rating is to be selected by the Bidder considering overloading of the pumps in the event of tripping of operating pump(s).				
g)		Pumps shall be so designed that pump impellers and other accessories of the pumps are not damaged due to flow reversal.				
h)	The Contractor under the pump and motor as a un	is specification shall assume fu it.	ll responsibility in the	e operation of		
5)	DESIGN CONSTRUCTION	ON				
a)		of various components of the pเ For material of construction of t				
b)	Pump Casing					
		Pump casing shall have axially split type construction as specified. The casing shall be designed to withstand the maximum shut-off pressure developed by the pump at the pumping temperature.				
	Pump casing shall be provided with a vent connection and piping with fittings & valves. Casing drain as required shall be provided complete with drain valves, piping and plugs. It shall be provided with a connection for suction and discharge pressure gauge as standard feature. It shall be structurally sound to provide housing for the pump assembly and shall be designed hydraulically to minimum radial load at part load operation.					
STA	THERMAL POWER PROJECT AGE-III (1X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION-VI, PART-B	SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 25 OF 30		

CLAUSE NO.	TE	CHNICAL REQUIREMENTS		एनटीपीसी NTPC	
				Annexure –I	
c)	Impeller				
		semi-closed or open type as sp tailed analysis of the liquid being		d designed in	
	movement by keying, pir	ecured to the shaft, and shall be ning or lock rings. On pumps we a lockout or cap screw which	vith overhung shaft, i	mpellers shall	
d)	Impeller/Casing Wearir	ng Rings			
	method of locking the we	ng rings shall be provided at suit earing ring shall be used. Weari s per manufacturer's standard pr	ng rings shall be prov		
e)	Shaft				
	The critical speed shall 130% of the rated speed	be well away from the operating	g speed and in no ca	ase less than	
	The shaft shall be ground and polished to final dimensions and shall be adequately sized to withstand all stresses from rotor weight, hydraulic loads, vibration and torques coming in during operation.				
f)	Shaft Sleeves				
	Renewable type fine finished shaft sleeves shall be provided at the stuffing boxes/mechanical seals. Length of the shaft sleeves must extend beyond the outer faces of gland packing of seal end plates so as to distinguish between the leakage between shaft and shaft sleeve and that past the seals/gland.				
		stened to the shaft to prevent an nould ensure concentric rotation.		ng. Shaft and	
STA	THERMAL POWER PROJECT GE-III (1X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION-VI, PART-B	SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 26 OF 30	

CLAUSE NO.	TE	CHNICAL REQUIREMENTS		एनदीपीसी NTPC	
				Annexure –I	
g)	Bearings				
	Heavy duty bearings, adequately designed for the type of service specified in the enclosed pump data sheet and for long, trouble free operation shall be furnished.				
	The bearings offered shall be capable of taking both the radial and axial thrust coming into play during operation. In case, sleeve bearings are offered additional thrust bearings shall be provided. Antifriction bearings of standard type, if provided, shall be selected for a minimum life 20,000 hrs. of continuous operation at maximum axial and radial loads and rated speed.				
	Proper lubricating arrangement for the bearings shall be provided. The design shall be such that the bearing lubricating element does not contaminate the liquid pumped. Where there is a possibility of liquid entering the bearings suitable arrangement in the form of deflectors or any other suitable arrangement must be provided ahead of bearings assembly.				
	Bearings shall be easily accessible without disturbing the pump assembly. A drain plug shall be provided at the bottom of each bearings housing.				
h)	Stuffing Boxes				
	Stuffing box design should permit replacement of packing without removing any part other than the gland.				
	Stuffing boxes of packed ring construction type shall be provided wherever specified. Packed ring stuffing boxes shall be properly lubricated and sealed as per service requirements and manufacturer's standards. If external gland sealing is required, it shall be done from the pump discharge. The Bidder shall provide the necessary piping valves, fittings etc. for the gland sealing connection.				
i)	Mechanical Seals				
	Wherever specified in pump data sheet, mechanical seals shall be provided. Unless otherwise recommended by the tenderer, mechanical seals shall be of single type with either sliding gasket or bellows between the axially moving face and shaft sleeves or any other suitable type. The sealing faces should be highly lapped surfaces of materials known for their low frictional coefficient and resistance to corrosion against the liquid being pumped.				
j)	The pump supplier shall coordinate with the seal maker in establishing the seal chamber of circulation rate for maintaining a stable film at the seal face. The seal piping system shall form an integral part of the pump assembly. For the seals under vacuum service, the seal design must ensure sealing against atmospheric pressure even when the pumps are not operating. Necessary provision for seal water supply along with complete piping fittings and valves as required shall form integral part of pump supply.				
k)	Pump Shaft Motor Shaft Coupling				
	The pump and motor shafts shall be connected with an adequately sized flexible coupling of proven design with a spacer to facilitate dismantling of the pump without disturbing the motor. Necessary coupling guards shall also be provided.				
SIPAT SUPER THERMAL POWER PROJECT STAGE-III (1X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATION SECTION-VI, PART-B	SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 27 OF 30	

TECHNICAL REQUIREMENTS



Annexure -I

l) Base Plate

CLAUSE NO.

A common base plate mounting both for the pump and motor shall be furnished. The base plate shall be fabricated steel and of rigid construction, suitably ribbed and reinforced. Base plate and pump supports shall be so constructed and the piping unit so mounted as to minimise misalignment caused by mechanical forces such as normal piping strain, internal differential thermal expansion and hydraulic piping thrust. Suitable drain troughs and drip lip shall be provided.

m) Assembly and Dismantling

Assembly and dismantling of each pump with drive motor shall be possible without disturbing the grouting base plate or alignment.

n) Drive Motor (Prime Mover)

The kW rating of the drive shall be based on continuously driving the connected equipment for the conditions specified. However, in cases where parallel operation of the pumps are specified, the actual motor rating is to be selected by the Bidder considering overloading of the pumps in the event of tripping of operating pump(s).

ANNEXURE-II

PIPING THICKNESS: Pipes for sizes 200 NB & above shall confirm to IS: 3589 Grade 410. The final thickness shall not be less then that specified as per IS: 3589 as indicated below.

Nominal pipe	Outside Diameter (mm)	Wall Thickness (mm)
Size (mm)		
200 NB	219.1	4.5
250 NB	273	5
300 NB	323.9	5.6
350 NB	355.6	5.6
400 NB	406.4	6.3
450 NB	457	6.3
500 NB	508	6.3
600 NB	610	6.3

ANNEXURE-III

I. DATA SHEET FOR WATER LINE GATE / SLUICE VALVES

1.0	1. Size Range	50 MM & Above		
2.0	2. Design Code	a) IS: 14846 or BS : 5150		
3.0	Pressure Rating	a) PN 1.0 (as per IS:14846)		
		b) PN 10 (as per BS:5150)		
4.0	Construction Features			
4.1	Stem	Outside screw and yoke type, rising stem		
4.2	Ends	Flanged, ANSI B16.5 Cl 150 (minimum)		
4.3	Bonnet	Bolted		
4.4	Wedge	Solid Wedge		

SIPAT SUPER THERMAL POWER PROJECT STAGE-III (1X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION-VI, PART-B	SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 28 OF 30
--	---	--	---------------

TECHNICAL REQUIREMENTS CLAUSE NO. 5.0 Operation by handwheel (Gear reduction unit for valve size 200 NB and above wherever applicable) 6.0 Seat Renewable a) Body Disc. Renewable 7.0 **Material of Construction** 7.1 Cast Iron to IS:210 FG-200 Body/Bonnet/Handwheel 7.2 Wedge Gland Cast Iron to IS:210 FG-200 S.S. 410 Stem 7.3 GM to IS:318 Gr.-2 7.4 **Body Seat** Wedge Seat 7.5 GM to IS:318 Gr.-2 7.6 Packing Non-Asbestos Back Seat Bushing GM to IS:318 Gr.-2 7.7 7.8 Carbon Steel to IS:1367, CL - 4.6/4.0 Bolts, Nuts, & Studs 8.0 **Accessories Required** Position Indicator Draining arrangement for Valve Seat Locking Facility with lock Gear reduction unit for valve size 200 NB and above. II. **DATA SHEET FOR GLOBE VALVES** 1.0 Size Range 50 MM & Above 2.0 Design Code BS: 5152 / Equiv. Pressure Rating 3.0 PN 10 (as per BS:5152) a) 4.0 **Construction Features** 4.1 Stem Outside screwed & rising spindle Flanged, ANSI B16.5 CI 125 / CI. 150 4.2 Ends Bolted 4.3 Bonnet Solid Wedge 4.4 Wedge by handwheel 5.0 Operation (Gear reduction unit for valve size 200 NB and above wherever applicable) 6.0 Seat a) Body Renewable Disc. Renewable 7.0 **Material of Construction** 7.1 Body/Bonnet/Handwheel Cast Iron to IS:210 FG-200 7.2 Wedge Gland Cast Iron to IS:210 FG-200 7.3 Stem S.S. 410 GM to IS:318 Gr.-2 7.4 **Body Seat** 7.5 Wedge Seat GM to IS:318 Gr.-2 7.6 Packing Non-Asbestos

		ion unit for valve 3 and above.		
STA	THERMAL POWER PROJECT GE-III (1X800 MW) EPC PACKAGE	TECHNICAL SPE SECTION-VI,	 SUB SECTION-A-17 AIR CONDITIONING AND VENTILATION SYSTEM	PAGE 29 OF 30

GM to IS:318 Gr.-2

Carbon Steel to IS:1367, CL - 4.6/4.0

7.7

7.8

8.0

a)

Back Seat Bushing

Bolts, Nuts, & Studs

Valve Seat

Accessories Required Position Indicator

Draining arrangement for

Locking Facility with lock

CLAUSE NO.	TECHNICAL REQUIREMENTS					
III.	DATA SHEET FOR CHECK VALVES					
	1.0	Size range	Below 50 NB		50 NB ar	nd above
	2.0	Design Code/rating	IS: 778		IS : 5312/	BS:5153
	3.0	Туре		Swing chec	ck type	
	4.0	Pressure Rating	a) PN 1.0 (as per l	IS:5312)		
			b) PN 10 (as per l	BS:5153)		
	5.0	End connection	Screwed ends B16.		Flanged	to Class 15 min
	6.0	Material Specifications				
		a) Body, cover, flap, hinges	GM to IS:318	Gr.2	Cast Iro	n IS:210 Gr. FG.200
		b) Hinge pin, door pin	HT Brass			SS
		c) Body seat ring, Disc. facing ring			GM to IS	S:318, LTB 2
		d) Gaskets		-	Non-	Asbestos
V.	DATA SHEET FOR BUTTERFLY VALVE					
	1 - 4 0	1 0: D		50 NANA 0	A.I.	
	1.0	Size Range		50 MM & /		
	2.0	Size Range Design Code	Double flanged or rate confirming 609/equivalent	· lugged wa	afer type c	
			rate confirming	· lugged wa	afer type c \ C-504/B	
	2.0	Design Code	rate confirming	· lugged water and the second representation in the second representation representation in the second representation representation representation representation representation representation representation representat	afer type o A C-504/B	S:EN:593/A
	3.0	Design Code Pressure Rating	rate confirming 609/equivalent	· lugged water and the second representation in the second representation representation in the second representation representation representation representation representation representation representation representat	afer type o A C-504/B	S:EN:593/A
	3.0	Design Code Pressure Rating End Connection	rate confirming 609/equivalent	· lugged water and the second representation in the second representation representation in the second representation representation representation representation representation representation representation representat	afer type c C-504/B 0 Class 125	S:EN:593/A
	3.0 4.0 5.0	Design Code Pressure Rating End Connection Material of Construction	rate confirming 609/equivalent Flanged as per AN	PN 10 NSI B.16.5	afer type of C-504/B	S:EN:593/A
	3.0 4.0 5.0 5.1	Design Code Pressure Rating End Connection Material of Construction Body & Disc	rate confirming 609/equivalent Flanged as per AN	PN 10 NSI B.16.5	afer type of Class 125	S:EN:593/A
	3.0 4.0 5.0 5.1 5.2	Design Code Pressure Rating End Connection Material of Construction Body & Disc Shaft Seat Rings Accessories Required	rate confirming 609/equivalent Flanged as per AN	PN 10 NSI B.16.5 Cast Ir	afer type of Class 125	S:EN:593/A
	3.0 4.0 5.0 5.1 5.2 5.3	Design Code Pressure Rating End Connection Material of Construction Body & Disc Shaft Seat Rings	rate confirming 609/equivalent Flanged as per AN	PN 10 NSI B.16.5 Cast Ir	afer type of Class 125	S:EN:593/A



SUB-SECTION-E-17

AIR CONDITIONING & VENTILATION SYSTEM

SIPAT SUPER THERMAL POWER PROJECT STAGE-III (1X800 MW) EPC PACKAGE TECHNICAL SPECIFICATION SECTION-VI, PART-B BID. DOCUMENT NO.:

CLAUSE NO.	QUALITY ASSURANCE (FIZE NTPC)						
	AIR CO	NDITIONINGAND VENTILATIO	N SYSTEM				
1.00.00	CHILLING UNIT	CHILLING UNIT					
1.01.00	Refrigerant Compresso	r (Screw/Scroll)					
1.01.01	Hydraulic/Pneumatic tes permitted.	t of castings of casings shall be	e carried out. No lea	akage shall be			
1.01.02	DPT of screw, impeller, s	haft, vanes, casing etc. after ma	chining shall be carrie	ed out.			
1.01.03	All rotating parts of screves 1940 Gr. 6.3/IS 21940.	w and centrifugal compressor st	nall be dynamically ba	alanced to ISO			
1.01.04	Leak tightness & vacuun be carried out. No leaka	n check for chilling units / comp ge shall be permitted.	ressor in assembled	condition shall			
1.01.05	Performance test of asset following :	embled compressor and Chiller	assembly shall be do	ne to check for			
		(free run) test of all types of c Vibration & Temp. rise of bearing		FAD (Free air			
	ii) Functional run te	est for Chiller assembly shall be	carried out.				
1.02.00	CONDENSER & EVAPO	RATOR					
1.02.01	DPT shall be carried out	on welds if applicable.					
1.02.02	10% RT of butt weld joint	on shell shall be carried out if a	pplicable.				
1.02.03	Dimensional check include	ding tube hole dia, ligament, pitcl	h etc. shall be carried	out.			
1.02.04		o tube sheet expansion shall l milar tube/tube sheet thickness PC review.					
1.02.05		t of Shell Side and Tube Side d out. 'No leakage' shall be perı		evaporator as			
2.00.00	AIR HANDLING UNIT						
2.01.00	For Fans refer tests as n	nentioned at 4.00.00					
2.02.00		led AHU (AHU casing and fan a and Temp. Rise of bearing sha		bjected to free easured during			
2.01.00	All cooling coil shall be p	neumatically tested and no leaka	age shall be permitted	l.			
3.00.00	CENTRIFUGAL PUMP						
3.01.00	UT on pump shaft (dia e after machining shall be o	qual to or above 40 mm) and Moarried out.	IPI/DPT on pump sha	aft and impeller			
3.02.00	All rotating components of the pumps shall be dynamically balanced to ISO-1940 Gr. 6.3/IS 21940.						
3.03.00	A standard hydrostatic test shall be conducted on the pump casing with water at 1.5 times the shut off pressure on the head characteristics curve or twice the rated pressure whichever is higher, for a minimum duration of 30 minutes.						
3.04.00	Standard Running Test						
STA	THERMAL POWER PROJECT GE-III (1X800 MW) PC PACKAGE	TECHNICAL SPECIFICATION SECTION-VI, PART-B BID DOC NO.:	SUB-SECTION-E-17 AC AND VENTILATION SYSTEM(MECH)	Page 1 of 3			

CLAUSE NO.	QUALITY ASSURANCE (ज़रीपीमी)				
	i) All pumps shall be tested in the manufacturer's works preferably with contract mot (or as specified in Engg Tech spec) for capacity, efficiency, head and brake hors power. Pump shall be given running test over the entire operating range covering from the shut-off head to the maximum flow. The duration of test shall be minimulated one (1) hr. A minimum of seven readings approximately equidistant shall be take for plotting the curves with one point at design flow. Testing of pumps shall be accordance with stipulations of Hydraulic Institute Standard (HIS) and/or as papplicable Indian Standard or equivalent. Acceptance norms shall be as papproved datasheet & HIS standard and/or as per applicable Indian Standard equivalent only.				
	ii) Noise and vibration shall be measured at shop for reference purpose only.				
	iii) Pumps shall be subjected to strip down examination visually to check for mechanical damages after testing at shop in case abnormal noise level and/or excessive vibration are observed during the shop test.				
	iv) NPSH test shall be conducted with water as the medium, if required as per approve data sheets.				
4.00.00	FANS:				
4.01.00	20% DPT of welding on fan hub, blades, casing and impeller as applicable shall be carrie out.				
4.02.00	DPT of fan shafts shall be carried out after machining.				
4.03.00	UT of fan shafts (dia equal to or above 40mm) shall be carried out.				
4.04.00	Rotating components of all fans shall be dynamically balanced to ISO-1940 Gr. 6.3/IS 21490				
4.05.00	All Fans shall be subjected to run test for 4 hrs. or till temperature stabilization is reached Vibration, Noise level, Temp. rise and current drawn shall be measured during the run test.				
4.06.0	One fan of each type and size will be performance tested as per corresponding BIS code AMCA for Air flow, Static Pressure, Speed, Efficiency, Power Consumption, Noise, Vibratio and Temp. Rise.				
5.00.00	LOW PRESSURE AIR DISTRIBUTION SYSTEM				
5.01.00	Functional test for fire damper along with solenoid shall be done.				
5.02.00	Prototype tests report of fire damper (duly approved/accepted by ENGG) for each type an size as per UL-555 for fire rating shall be furnished.				
5.03.00	Site Test- After completion, all ducting system shall be checked/tested for a leakages/tightness (smoke test) at site.				
6.00.00	INSULATION:				
6.01.00	Insulation material shall be tested for all mandatory tests only as per relevant code/standard				
6.02.00	Resin bonded mineral wool/Glass wool: Thermal conductivity tests (for thermal insulation only) shall be done the same density of material as applicable as per IS:3346 or equivalent standard//Engg spec.				
6.03.00	XLPE/Nitrile Rubber: Thermal conductivity tests (for thermal insulation only) shall be done as per relevant code for the same density and thickness of material and validity of test shall be as per relevant standard/Engg spec.				
7.00.00	COOLING TOWER				
7.01.00	UT of fan shaft and drive shaft (dia equal to or above 40mm) shall be carried out.				
7.02.00	DPT of fan hub and shafts shall be carried out after machining.				
STA	SIPAT SUPER THERMAL POWER PROJECT STAGE-III (1X800 MW) EPC PACKAGE TECHNICAL SPECIFICATION SECTION-VI, PART-B BID DOC NO.: SYSTEM(MECH) Page 2 of SYSTEM(MECH)				

CLAUSE NO.	QUALITY ASSURANCE एन्हेपीमी NTPC					
7.03.00	Color of fills shall be as pe	er approved data sheet.				
7.04.00	Fan assembly shall be sta	tically/dynamically balanced.				
7.05.00	Cooling Towers being supplied to site in assembled condition shall be subjected to run test at shop to measure FAD, Noise & Vibration. For Cooling Towers being supplied in knocked-down condition, these tests shall be done at site					
8.00.00	AIR FILTERS:					
	average synthetic dust v	tested for initial and final pre- veight arrestance as per the red ute) filters shall be tested as per	quirement of BS 654			
9.00.00	PIPES & FITTINGS:					
9.01.00	All pipes and fittings shal	l be tested as per applicable cod	les / standard.			
9.02.00	Site test- Pipes shall requirement	be tested at site hydraulically	//pneumatically as រុ	per application		
10.00.00	VALVES & SPECIALTIE	S				
10.01.00	Visual and dimensional of	check of valves as per relevant co	odes and approved d	rawing.		
10.02.0	All the water line valves shall be hydraulically tested for body, seat and back seat (wherever provided) as per the relevant standard to which these valves are supplied irrespective of the working pressure for which these valves are selected. Check valves shall also be tested for leak tightness test at 25% of the specified seat test pressure.					
10.03.0	Refrigerant line valves sh	nall be pneumatically tested for b	ody and seat leakage	e test.		
10.04.00	Valves shall be offered for	or hydro test and pneumatic test	in unpainted conditio	n.		
10.05.0	Functional check of the v	alves for smooth opening and cl	osing shall be done.			
10.06.0		ck pressure drop Vs flow shall b Balancing Valve'/Globe Valves v		e valve of each		
11.00.00	SPLIT, CASSETTE, W UNITS	INDOW, PRECISION/PACKAG	SED AC (PAC) &	CONDENSING		
11.01.00	Split/Cassette/ Window Guarantee and Warrante	AC/PAC will be accepted on the certificate.	ne basis of Manufac	turer Standard		
11.02.00	PAC/Condensing unit: I relevant standard.	Each Unit shall be subjected	to production routing	e Test as per		
11.03.00		d vibration of PAC/ Condensing unit of each type and rating.	unit shall be demor	nstrated as per		
12.00.00	Air Washer and Unitary	Air Filter (UAF)				
12.01.00	Random 10% DPT on we	eld joints shall be carried out.				
12.02.00		re parts at 1.5 times the designstruction at 1.5 times the designs and water fill test of tanks s		rking pressure		
12.03.00	Trial assembly of Air washer/UAF for one of each size shall be done in shop.					
12.04.00	Performance test to check pressure drop Vs flow shall be carried out for one Nozzle of each type, size and rating.					
	SIPAT SUPER THERMAL POWER PROJECT TECHNICAL SPECIFICATION SUB-SECTION-E-17					
	AGE-III (1X800 MW) EPC PACKAGE	SECTION-VI, PART-B BID DOC NO.:	AC AND VENTILATION SYSTEM(MECH)	Page 3 of 3		



1X800 MW SIPAT STPP (STAGE-III) AC & VENTILATION SYSTEM PROJECT SPECIFIC GENERAL REQUIREMENTS

SPECIFICATION No: PE-TS-520-553-002-A001				
SECTION: I				
SUB-SECTION :	: C 2B			
REV. 00 OCT 2025				

SECTION: I

SUB-SECTION: C 2
PART-B

CUSTOMER SPECIFICATION PROJECT SPECIFIC GENERAL REQUIREMENTS



PART - C

GENERAL TECHNICAL REQUIREMENTS

SIPAT SUPER THERMAL POWER PROJECT STAGE-III (1X800 MW) EPC PACKAGE TECHNICAL SPECIFICATION SECTION-VI, PART-C SEPARATOR BID DOC NO.

CLAUSE NO.	GENE	RAL TECHNICAL REQUIRE	MENTS	एनदीपीमी NTPC	
1.00.00	INTRODUCTION				
	Contract The follow specifications and	chnical requirements which wing provisions shall supplored requirements brought out a Technical Data Sheets.	ement all the detailed	l technical	
2.00.00	BRAND NAME				
	brand, manufacturer be indicative of the manufacturer's proc	I or article is specified or des or vendor, the specific item ne function and quality des ducts may be considered p the Employer to determine named.	mentioned shall be und sired, and not restrict provided sufficient info	derstood to tive; other rmation is	
3.00.00	NOT USED				
4.00.00	COMPLETENESS C	OF FACILITIES			
4.01.00	Bidders may note that this is a EPC Package contract. Each of the plant shall be engineered and designed in accordance with the specification requirement. All engineering and associated services are required to ensure a completely engineered plant shall be provided.				
4.02.00	All equipments furnished by the Contractor shall be complete in every respect, with all mountings, fittings, fixtures and standard accessories normally provided with such equipment and/or those needed for erection, completion and safe operation of the equipment and for the safety of the operating personnel, as required by applicable codes, though they may not have been specifically detailed in the respective specifications, unless included in the list of exclusions.				
	All same standard interchangeable with	components/ parts of sam one another.	e equipment provided	, shall be	
4.03.00	For the C&I systems, the Contractor shall be required to provide regular information about future upgrades and migration paths to the Employer.				
5.00.00	CODES & STANDARDS				
5.01.00	In addition to the codes and standards specifically mentioned in the relevant technical specifications for the equipment / plant / system, all equipment parts, systems and works covered under this specification shall comply with all currently applicable statutory regulations and safety codes of the Republic of India as well as of the locality where they will be installed, including the following:				
STAG	HERMAL POWER PROJECT E-III (1X800 MW) PC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 1 OF 119	

CLAUSE NO.		GENERAL TECHNICAL REQUIREMENTS					
	a)	Indian Electri	city Act				
	b)	Indian Electri	city Rules				
	c)	Indian Explos	sives Act				
	d)	Indian Factor	ies Act and State Factories Ac	et			
	e)	Indian Boiler Regulations (IBR)					
	f)	Regulations of	of the Central Pollution Contro	l Board, India			
	g)	Regulations of	Regulations of the Ministry of Environment & Forest (MoEF), Government of India				
	h)	Pollution Control Regulations of Department of Environment, Government of India					
	i)	State Pollution Control Board.					
	(j)	(j) Rules for Electrical installation by Tariff Advisory Committee (TAC).					
	(k) Building and other construction workers (Regulation of Employment and Conditions of services) Act, 1996				yment and		
	(I)	-	other construction workers services) Central Rules, 1998		yment and		
	(m)	Explosive Ru	les, 1983				
	(n)	Petroleum Ad	ot, 1984				
	(0)	Petroleum Ru	ules, 1976,				
	(p)	Gas Cylinder	Rules, 1981				
	(q)	Static and Mo	obile Pressure Vessels (Unifie	d) Rules, 1981			
	(r)	Workmen's C	Compensation Act, 1923				
	(s)	Workmen's C	Compensation Rules, 1924				
	(t)	NTPC Safety	Rules for Construction and E	rection			
	(u) NTPC Safety Policy						
STAG	HERMAL F E-III (1X80 PC PACK/	*	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 2 OF 119		

CLAUSE NO.		GENERAL TECHNICAL REQUIREMENTS				
	(v)	CERC (India	n Electricity Grid Code) Regula	ations, 2023		
	(w)	CEA (Flexibl Regulations,	e Operation of Coal Based ⁻ 2023	Thermal Power Genera	ting Units)	
	(x)	Any other statutory codes / standards / regulations, as may be applicable.				
5.02.00	the da	Unless covered otherwise in the specifications, the latest editions (as applicable the date fifteen (15) days prior to the date of bid submission), of the codes a standards given below shall also apply:				
	a)	Bureau of Ind	dian standards (BIS)			
	b)	Japanese Inc	lustrial Standards (JIS)			
	c)	American Na	tional Standards Institute (AN	SI)		
	d)	American So	ciety of Testing and Materials	(ASTM)		
	e)	American So	ciety of Mechanical Engineers	(ASME)		
	f)	American Pe	troleum Institute (API)			
	g)	Standards of	the Hydraulic Institute, U.S.A.			
	h)	International	Organization for Standardizati	on (ISO)		
	i)	Tubular Exch	anger Manufacturer's Associa	ition (TEMA)		
	j)	American We	elding Society (AWS)			
	k)	National Elec	trical Manufacturers Associati	on (NEMA)		
	l)	National Fire	Protection Association (NFPA	A)		
	m)	International	Electro-Technical Commission	n (IEC)/ European Norm	(EN)	
	n)	Expansion Jo	oint Manufacturers Association	ı (EJMA)		
	0)	Heat Exchan	ge Institute (HEI)			
	p)	IEEE standa	rd			
	q)	JEC standard	i			
STAG	HERMAL F E-III (1X80 PC PACK	•	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 3 OF 119	

CLAUSE NO.	GENE	RAL TECHNICAL REQUIRE	MENTS	एनरीपीमी NTPC		
5.03.00	Other International/ National standards such as DIN, VDI, BS, GOST etc. shall also be accepted for only material codes and manufacturing standards, subject to the Employer's approval, for which the Bidder shall furnish, adequate information to justify that these standards are equivalent or superior to the standards mentioned above. In all such cases the Bidder shall furnish specifically the variations and deviations from the standards mentioned elsewhere in the specification together with the complete word to word translation of the standard that is normally not published in English.					
5.04.00	National /Internation & VGB shall also be Testing of the respe covered by these	As regards highly standardized equipments such as Steam Turbine and Generator, National /International standards such as JIS, DIN, VDI, ISO, SEL, SEW, VDE, IEC & VGB shall also be considered as far as applicable for Design, Manufacturing and Testing of the respective equipment. However, for those of the above equipment not covered by these National / International standards, established and proven standards of manufacturers shall also be considered.				
5.05.00	above clauses and	In the event of any conflict between the codes and standards referred to in the above clauses and the requirement of this specification, the requirement of Technical Specification shall govern.				
5.06.00	Two (2) English language copies of all national and international codes and/or standards used in the design of the plant and equipment shall be provided by the Contractor to the Employer within two calendar months from the date of the Notification of Award.					
5.07.00	In case of any change in codes, standards & regulations between the date fifteen (15) days prior to the date of bid submission and the date when vendors proceed with fabrication and the date when vendors proceed with fabrication, the Employer shall have the option to incorporate the changed requirements or to retain the original standard. It shall be the responsibility of the Contractor to bring to the notice of the Employer such changes and advise Employer of the resulting effect.					
5.08.00	A detailed list of standards apart from those mentioned in the respective detailed specifications in other parts of Section-VI to which all equipment/systems/civil works should conform as indicated in this Part C and elsewhere in the specification.					
6.00.00	EQUIPMENT FUNCTIONAL GUARANTEE					
6.01.00	The functional guarantees of the equipment under the scope of the Contract is given in Section-VI Part - A & B of Technical Specifications. These guarantees shall supplement the general functional guarantee provisions covered under Defect liabilities Section-IV, General Conditions of Contract.					
6.02.00	Liquidated damages for shortfall in meeting functional guarantee(s) during the performance and guarantee tests shall be assessed and recovered from the Contractor as specified elsewhere in this specification.					
STAG	HERMAL POWER PROJECT E-III (1X800 MW) PC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 4 OF 119		

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS					
7.00.00	DESIGN OF FACILITIES/ MAINTENANCE & AVAILABILITY CONSIDERATIONS					
7.01.00	DESIGN OF FACILITIES					
	All the design procedures, systems and components proposed shall have already been adequately developed and shall have demonstrated good reliability under similar conditions elsewhere.					
	The Contractor shall be responsible for the selection and design of appropriate equipments to provide the best co-ordinated performance of the entire system. The basic requirements are detailed out in various clauses of the Technical Specifications. The design of various components, assemblies and subassemblies shall be done so that it facilitates easy field assembly and dismantling. All the rotating components shall be so selected that the natural frequency of the complete unit is not critical or close to the operating range of the unit.					
7.02.00	MAINTENANCE AND AVILABILITY CONSIDERATIONS					
	Equipment/works offered shall be designed for high availability, low maintenance and ease of maintenance. The Bidder shall specifically state the design features incorporated to achieve high degree of reliability/ availability and ease of maintenance. The Bidder shall also furnish details of availability records in the reference plants stated in his experience list.					
	Bidder shall state in his offer the various maintenance intervals, spare parts and man-hour requirement during such operation. The intervals for each type of maintenance namely inspection of the furnace, inspection of the entire hot gas path, turbine & equipments, inspection of the steam path and the minor and major overhauls shall be specified in terms of fired hours, clearly defining the spare parts and man-hour requirement for each stage.					
	Lifting devices i.e. hoists and chain pulley jacks, etc. shall be provided by the contractor for handling of any equipment or any of its part having weight in excess of 500 Kgs during erection and maintenance activities.					
	Lifting devices like lifting tackles, slings, etc. to be connected to hook of the hoist / crane shall be provided by the contractor for lifting the equipment and accessories covered under the specification.					
8.00.00	DOCUMENTS, DATA AND DRAWINGS TO BE FURNISHED BY CONTRACTOR					
STAG	ERMAL POWER PROJECT E-III (1X800 MW) C PACKAGE TECHNICAL SPECIFICATIONS SECTION VI, PART-C GENERAL TECHNICAL REQUIREMENTS 5 OF 119					

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS					
8.01.00	Bidders may note that this is an EPC Package contract . Each of the plant and equipment shall be fully integrated, engineered and designed to perform in accordance with the technical specification. All engineering and technical services required to ensure a completely engineered plant shall be provided in respect of mechanical, electrical and power systems, control & instrumentation, civil & structural works as per the scope.					
	assigned a unique accordance with KK	liary equipment/item of the pl tag number. The assignme S system. In all drawings/do nent/item/instrument etc. shal	ent of tag numbers s cuments/data sheet etc	hall be in		
		II furnish engineering data / ation as specified in Techn				
	•	ngineering and quality coordir bidder covering salient featur	•			
8.02.00	The number of copies/prints/CD-ROMs/manuals to be furnished for various types of document is given in Annexure-VI to this Part-C, Section-VI of the Technical Specification.					
8.03.00	The documentation that shall be provided by the Contractor is indicated in the various sections of specification. This documentation shall include but not be limited to the following:					
8.03.01	A) BASIC ENGI	NEERING DOCUMENTATIO	N			
	shall furnish	mencement of the detailed a Plant Definition Manual witl f Award. This manual shall co	nin 12 weeks from the	date of the		
	i) System description of all the mechanical, electrical, control & instrumentation & civil systems.					
	ii) Techn	ology scan for each system /	sub-system & equipmer	nt.		
	iii) Selection of appropriate technology / schemes for various systems/ subsystems including techno-economic studies between various options.					
	iv) Optimization studies including thermal cycle optimization.					
SIPAT SUPER THERMAL POWER PROJECT STAGE-III (1X800 MW) EPC PACKAGE TECHNICAL SPECIFICATIONS SECTION VI, PART-C GENERAL TECHNICAL REQUIREMENTS 6 OF 119						

CLAUSE NO.		GENE	RAL TECHNICAL REQUIRE	MENTS	एनहीपीमी NTPC	
	v)	struct	g criteria of all the syste ures/ equipment foundations a dentifying the sizing and the de	alongwith all calculation		
	vi)		mes and Process & Instruments and Process & Instruments and In	_	he various	
	vii)	Wate	Balance diagram.			
	viii)	•	ation Philosophy and the con ther plants.	itrol philosophy of the	Main Plant	
	ix)	Bidde also	ral Layout plan of the power soler's as well as those in the Ember form of the form of eering of areas not included in	ployer's scope. This dra CD-ROMs to the En	awing shall	
	x)	x) Basic layouts and cross sections of the main plant building (various floor elevations), boiler, fuel oil area, transformer yard, switchyard are other areas included in the scope of the bidder.				
	xi)		mentation in respect of Qualit here in this specification.	y Assurance System a	s listed out	
		date d Manu	successful bidder shall furnish of Notification of Award, a list al (PDMs) including techno-e utually discussed & finalised w	of contents of the Plan conomic studies, which	t Definition	
	B) DET	AILED E	NGINEERING DOCUMENTS			
	i)	Gene	ral layout plan of the station.			
	ii)	-	uts, general arrangements, ngs for all the equipment and t		ss-sections	
	iii)		diagram, Process and Instrum d system description.	entation diagrams alon	g with write	
	iv)	 iv) Start-up curves for boiler and both turbines and boiler combine together as a unit for various start-ups, viz. Cold, Warm and Hot sta up. 				
	v)	philos	g isometric, composite layout cophy & design parameter s ure drop calculation & flash ta	election for each pipir		
STAG	HERMAL POWER E-III (1X800 MW) PC PACKAGE	PROJECT	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 7 OF 119	

CLAUSE NO.	GEN	ERAL TECHNICAL REQUIRE	MENTS	एनरीपीसी NTPG
	wise sche fabri BON BON for p sam Syst inpu poin fabri	ng engineering diagrams, pipel or P&ID wise prepared pipe so adule, hanger and support so cation isometric drawings for p. 1, Painting schedule. Hanger / 1, Valve GA drawings, Layout on the project of the employer / project mem wise stress analysis / drawing with stress isometric diss. Also As-Built drawing for cation isometric drawing (ii) conger / Support arrangement drawing	chedule, valve schedule schedule and Piping i ipe size 65mm NB and support arrangement drawings for site routed with BOM (and submis lanager before start of lynamic analysis report lawing / sketch marked information & Records: omposite piping layout of schedules.	, insulation sometric / above with rawing with piping (i.e. sion of the work) and (including with node (i) Piping
	Con	nnical data sheets for all bou tractor shall use the Employe ement of orders on their sub ve	er's specifications as a	
	whe Mills	iled design calculations for of rever applicable including sizing , Fans, BFPs, CEPs, Hea densers, Vacuum pumps etc.	g calculations for all aux	iliaries like
	•	er pressure part schedule ormance data and boiler design	_	ns. Boiler
	whe	sient, hydraulic and thermal strever applicable & input and ou etrics showing nodes.		-
	-	mal cycle information (hormance calculations, condens and heat exchanger thermal cal		
	•	racteristic Curves/ Performanc hanical design calculations for		lydraulic &
	Émp	prehensive list of all Termi loyer's facilities, giving detail perature, fluid handled & end co	s of location, terminal	pressure,
		er supply single line diagram, rical schematics, etc.	block logics, control s	chematics,
	xv) Prot	ection system diagrams and rel	ay settings.	
STAG	HERMAL POWER PROJEC E-III (1X800 MW) PC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 8 OF 119

CLAUSE NO.		GENE	RAL TECHNICAL REQUIRE	MENTS	एनदीपीसी NTPC
	xvi)	Cable	es schedules and interconnecti	ion diagrams.	
	xvii)	Cable	e routing plan.		
	xviii)	wiring moun tubing loop a	ment schedule, measuring po g diagram, functional write-up ted instruments, logic diagran g diagrams of panels and er and close loop controls (both h alve schedule including type o	os, installation drawing ns, control schematics, nclosures etc. Drawing nardware and software).	s for field wiring and s for open
	xix)		n and annunciation/ Sequence et points.	of Event (SOE) list and	d alarms &
	xx)	Sequ	ence and protection interlock s	schemes.	
	xxi)	• •	test reports, insulation co-orm stability study report.	rdination study report a	and power
	xxii)		ol system configuration diagra enance details.	ams and card circuit dia	grams and
	xxiii)	Detail	led DDCMIS system manuals.		
	xxiv)	Detail	led flow chart for digital contro	l system.	
	xv)	Mimic	diagram layout, Assignment t	for other application eng	g.
	xxvi)	faciliti overg scope	and Structural works drawings les, architectural works, round works and super-stru e of the bidder civil calcul sis and design alongwith outpu	foundations undergro ctural works as includation sheets including	ound and ded in the
	xxvii)	Unde	rground facilities, levelling, sar	nitary, land scaping drav	vings.
	xxviii)		echnical investigation and scable).	site survey reports (if and as
	xxix)	Mode	l study reports wherever appli	cable.	
	xxx)	Funct	ional & guarantee test proced	ures and test reports.	
	xxxi)	Docu	mentation in respect of Commentation in respect of Commes specification.	-	
SIPAT SUPER THERMA STAGE-III (1) EPC PAC	X800 MW)	OJECT	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 9 OF 119

CLAUSE NO.		GENE	RAL TECHNICAL REQUIREM	MENTS	एनदीपीसी NTPC
	xxxii)	equip	documents such as P&IDs, ment's, performance curves, d r System etc.) shall be as per N	atasheet etc. (For CHP	
	xxxiii)	sche	er shall submit all tabulated dedule, valve schedule, etc.), in format to enable NTPC for fas	both EXCEL format as	
8.03.02	INSTRUCTIO	N MAI	NUALS		
	equipments of Letter of Aware erection, con manual shall of the Emploarment Annexure-IV.	overed ard. T nmissic be spe byer the The C ntil the	Il submit to the Employer, dra under the Contract by the end he Instruction manuals shall oning, operation and mainted ecifically compiled for this project he Instruction Manuals shall contract shall not be considere final Instructions manuals have uals shall comprise of the follow	d of one year from the contain full details renance of each equipeet. After finalisation and be submitted as ind to be completed for pere been supplied to the	date of the equired for ment. The dapproval dicated in ourposes of
	A) EREC	TION I	MANUALS		
	comm	encem	manuals shall be submitted at ent of erection activities of a ual should contain the followin	particular equipment/sy	
	a)	Erecti	on strategy.		
	b)	Sequ	ence of erection.		
	c)	Erecti	on instructions.		
	d)	Critica	al checks and permissible devi	ation/tolerances.	
	e)	List o	f tools, tackles, heavy equipme	ents like cranes, dozers	, etc.
	f)	Bill of	Materials		
	g)		edure for erection and General general general general general states and general states and general states and general states are states and general states and general states are states are states and general states are s	al Safety procedures t	to followed
	h)	Proce	edure for initial checking after e	rection.	
	i)	Proce	edure for testing and acceptance	ce norms.	
	j)	Proce	edure / Check list for pre-comm	issioning activities.	
SIPAT SUPER THERMAL POWER PROJECT STAGE-III (1X800 MW) EPC PACKAGE TECHNICAL SPECIFICATIONS SECTION VI, PART-C REQUIREMENTS				PAGE 10 OF 119	

CLAUSE NO.			GENE	RAL TECHNICAL REQUIRE	MENTS	एनदीपीमी NTPC
		k)	Proce	dure / Check list for commissi	oning of the system.	
		I)	Safet	y precautions to be followed during erection.	d in electrical supply	distribution
	В)	OPER	RATION	I & MAINTENANCE MANUAL	_S	
		a)	withs have than Nam the rholder	manual shall be a two rim P\stand constant usage or where locking steel pins, the size international size A3. The cove, Services covered and Volumanual shall be divided by a ser. The dividers shall clearly written instructions within the ufacturers shall be typewritten	e a thicker type is requor of the manual shall nower shall be printed with me / Book number Each stiff divider of the same state the section number manual not provide	ired it shall at be larger the Project in section of size as the er and title.
	b) The arrangement and contents of O & M manuals shall be as follows:					as follows:
	Chapter 1 - Plant Description: To contain the following sections specific to the equipment/system supplied				specific to	
		(a)		ription of operating principl natic drawing / layouts.	e of equipment / sy	stem with
		(b)		ional description of associate	ed accessories / contro	ols. Control
		(c)	(This	rated operation of the equipments to be given by the supplier of and the operating instruction given	the Main equipment by	taking into
	(d) Exploded view of the main equipment, associated accessories and auxiliaries with description. Schematic drawing of the equipment alongwith its accessories and auxiliaries.					
		(e)	Desig	n data against which the plant	t performance will be co	mpared.
		(f)		er list of equipments, Technic m and approved data sheets.	cal specification of the	equipment/
	(g) Identification system adopted for the various components, (it will be of a simple process linked tagging system).					
		(800 MW)	ROJECT	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 11 OF 119

CLAUSE NO.		GENE	RAL TECHNICAL REQUIRE	MENTS	एनदीपीमी NTPC
	(h)		er list of drawings (as built dra arate volume).	wing - Drawings to be e	enclosed in
	2) <u>Chapter</u>	<u> 2.0 - Pla</u>	ant Operation: To contain the equipment su	-	ecific to the
	(a)		ction logics provided for ophy behind the logic, Drawin		with brief
	(b)	Limitii	ng values of all protection setti	ngs.	
	(c)	Vario	us settings of annunciation/into	erlocks provided.	
	(d)		p and shut down procedu iated systems in step mode.	re for equipment alor	ngwith the
	(e)	Do's a	and Don'ts related to operation	of the equipment.	
	(f)	-	y precautions to be taken dur ction on total power failure co tions.	_	
	(g)	Parar	neters to be monitored with no	ormal value and limiting	values.
	(h)	Equip	ment isolating procedures.		
	(i)	Troub	le shooting with causes and re	emedial measures.	
	(j)		ne testing procedure to asc es alongwith schedule of testir		the safety
	(k)	Routii	ne Operational Checks, Recor	nmended Logs and Red	cords
	(1)		ge over schedule if more t se is given.	han one auxiliary for	the same
	(m)	Prese	rvation procedure on long shu	t down.	
	(n)	Syste	m/plant commissioning proced	dure.	
	3) <u>Char</u>	oter 3.0 -	<u>Plant Maintenance</u> - To conta the equip	in the following sections oment supplied.	specific to
STAG	HERMAL POWER I E-III (1X800 MW) PC PACKAGE	PROJECT	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 12 OF 119

CLAUSE NO.		GENE	RAL TECHNICAL REQUIRE	MENTS	एनदीपीसी NTPC
	(a)		ded view of each of the equipolate including name, code no.		gwith bill of
	(b)	dimer	ded view of the spare par nsional drawings (In case of E given) and spare parts catalog	lectronic cards, the circ	uit diagram
	(c)		of Special T/ P required fo ling special testing equipment		_
	(d)	tools	vise dismantling and assembl to be used, checks to be ma ance to be maintained etc.		
	(e)	Preve hours	entive Maintenance sche /calendar period alongwith che	edules linked with ecks to be carried out.	running
	(f)		nauling schedules linked wit with checks to be done.	h running hours/calen	dar period
	(g)	Long	term maintenance schedules		
	(h)	norma	umables list alongwith the eal running and during mainten Overhauling.		_
	(i)	includ replac longe	of lubricants with their Indian ling charts showing lubri cement procedure to be car r intervals to ensure trouble from mplete replacement.	ication checking, te ried daily, weekly, mo	sting and nthly & at
	(j)	Tolera	ance for fitment of various com	nponents.	
	(k)	Detail	s of sub vendors with their par	rt no. in case of bought	out items.
	(I)		f spare parts with their Part N ir interchangeability with alread		
	(m)	manu	of mandatory and recomr facturing drawings, material s ng consumable spares.	•	•
	(n)		time required for ordering ier, instructions for storage and		
	RMAL POWER P -III (1X800 MW) C PACKAGE	ROJECT	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 13 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			
	(o) General information on the equipment such as modification carried out in the equipment from its inception, equipment population in the country / foreign country and list of utilities where similar equipments have been supplied.			
8.03.03	After finalization and approval of the Employer, the O & M Manuals shall be submitted as indicated in Annexure-VI. The Contract shall not be considered to be completed for purposes of taking over until the final Instructions manuals (both erection and O & M manuals have been supplied to the Employer.			
	If after the commissioning and initial operation of the plant, the instruction manuals (Erection and /or O &M manuals) require modifications/additions/ changes, the same shall be incorporated and the updated final instruction manuals shall be submitted by the Contractor to the Employer for records and number of copies shall be as mentioned in Annexure-VI.			
8.03.03	PLANT HANDBOOK AND PROJECT COMPLETION REPORT			
8.03.03.01	PLANT HANDBOOK			
	The Contractor shall submit to the Employer a preliminary plant hand book preferably in A-4 size sheets which shall contain the design and performance data of various plants, equipments and systems covering the complete project including			
	i) Design and performance data.			
	ii) Process & Instrumentation diagrams.			
	iii) Single line diagrams.			
	iv) Sequence & Protection Interlock Schemes.			
	v) Alarm and trip values.			
	vi) Performance Curves.			
	vii) General layout plan and layout of main plant building and auxiliary buildings			
	viii) Important Do's & Don't's			
	The plant handbook shall be submitted within twelve (12) months from the date of award of contract. After the incorporation of Employer's comments, the final plant handbook complete in all respects shall be submitted three (3) months before start-up and commissioning activities.			
STAG	HERMAL POWER PROJECT TECHNICAL SPECIFICATIONS (E-III (1X800 MW) SECTION VI, PART-C REQUIREMENTS PAGE 14 OF 119			

	OMPLETION REPORT or shall submit a Project Completion Report at the time of handing over All the plant layouts shall be made in computerized 3D modelling system. The Employer reserves the right to review the 3D model addifferent stages during the progress of engineering. The layout drawings submitted for Employer's review shall be fully dimensione and extracted from 3D model after interference check.
he plant. DRAWINGS a) i)	All the plant layouts shall be made in computerized 3D modelling system. The Employer reserves the right to review the 3D model addifferent stages during the progress of engineering. The layout drawings submitted for Employer's review shall be fully dimensioned and extracted from 3D model after interference check.
a) i)	system. The Employer reserves the right to review the 3D model a different stages during the progress of engineering. The layou drawings submitted for Employer's review shall be fully dimensione and extracted from 3D model after interference check.
	system. The Employer reserves the right to review the 3D model a different stages during the progress of engineering. The layou drawings submitted for Employer's review shall be fully dimensione and extracted from 3D model after interference check.
ii)	All deguments submitted by the Contractor for Employer's review
	All documents submitted by the Contractor for Employer's review shall be in electronic form (soft copies) along with the desired number of hard copies as per Annexure-VI of Part-C. The soft copies shall be uploaded by the vendors in C-folders, a Web-based system of NTPC ERP, for which a username and password will be allotted to the new vendor by NTPC.
	Similarly, the vendor can download the drawings/documents approved/ commented by NTPC, through above site.
	The soft copies of identified drawings/documents shall be in po- format, whereas the attachments/reply to the submitted document(s can be in .doc, .xls, .pdf, .dwg or .std formats.
iii)	Final copies of the approved drawings along with requisite number of hard copies shall be submitted as per Annexure-VI of Part-C.
	Contractor shall prepare the model of all the facilities located within plant boundary covering facilities in Main Plant Block area and Balance of plant (BOP) area in an integrated & intelligent 3D softward solution. Main Plant Block area shall include Transformer Yard, To building (including all facilities), Boiler area, ESP area, chimney area FGD area and any other facility located in main plant block. BOP are shall include all facilities pertaining to AHP, CHP, LHP, GHP, DM Proplant, pipe & cable racks and any other facility located within plant boundary. All piping layouts, equipment layouts, floor plans, ducting layout (Air/flue gas, A/C, Ventilation etc.), General Arrangement drawing and RCC layout of major buildings and structural arrangement drawings shall necessarily be extracted from the aforesaid 3D mode and submitted for employer's review along with the 3D review model to enable NTPC to review and approve these drawings. Contractor shall prepare and provide 3D design review model (network).
RMAL POWER PI	ready, which shall include visual interference check, walk-throug ROJECT TECHNICAL SPECIFICATIONS SECTION VI, PART-C GENERAL TECHNICAL REQUIREMENTS PAGE 15 OF 119

CLAUSE NO.	GENE	RAL TECHNICAL REQUIRE	MENTS	एनशैपीशी NTPC
	remova intellig 3 mor	tion, video simulation for nal, visual effect, photo realisent 3D model and shall makenths from LOA to enable Nationary or as & when required be	m etc.), which is extra a presentation of the s ITPC to review the p	acted from same every
		rations of NTPC during the 3E ised editable model to be sub		
	future efficier with a models model comple range drawin also be with co	mplete 3D data (editable mo detailed engineering related ncy improvement of the projets built GADs, layout, isome for all disciplines, with any cand naming conventions were reference databases, compall be handed over to own gs like GADs, Isometrics etce submitted by the Contractor omplete Project databases satage and as final as-built. The figuration files, customization uses.	to maintenance, opera ct etc. Complete 3D metrics, reports extracted other document generate with as-built updates aponent catalogues for her. Apart from the 3D c. extracted from the nin Electronic form. 3D metall be submitted at each econtractor shall also	tion, R&M, nodel along and 3D along with all the size Model, all nodel shall nodel along ach model submit all
	CAES/ shall	ut files of software used for o AR2 files, input files for Presso be handed over to NTPC wer of Engineering Information	ure vessel design, datas as per NTPC specific	sheets etc.,
	Engine compa	r, two Licenses of the used eering View and One for Site value tible Hardware for possible resubmitted by the Bidder Time	View) shall be provided view and study of the I	along with
	of NC softwa have a	ftware and hardware shall be a DA. The 3D modelling software bidder will be using for plall editable features to edit the basis.	are shall preferably be reparation of 3D model	the same or it shall
	license contra release	ftware provided shall neces e(s) for use on all the maching (ct (AMC) which shall included by the software agency sty/guarantee period.	nes and an Annual me software upgrades a	aintenance as & when
SIPAT SUPER THERMAL STAGE-III (1X8 EPC PACK	00 MW)	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 16 OF 119

CLAUSE NO.	GEN	ERAL TECHNICAL REQUIRE	MENTS	एनहीपीमी NTPC
	data for h	over Plan: There shall be conting at various stages of the project andover of data to NTPC shall stage.	t including rules and trig	gger points
	Data NTP	pase backup shall be taken e C.	every month and hande	ed over to
	'	nts/text information shall be in la format as applicable.	atest version of MS Offic	e/MS
	time of bid weight of connection installation clearance a	s submitted by the Contractor shall be in sufficient detail indiceach component for packing fixing arrangement required and interconnections with conditional spaces required between the formation specifically requested.	cating the type, size, arring and shipment, the dimensions repther equipments and various portions of equi	rangement, e external quired for materials, pment and
	shall bear a the name o the specifion revisions. I shall be in	ng submitted by the Contracto a title block at the right hand be of the Employer, the system detailon number, the name of the standard catalogue pages and dicated therein. All titles, notinuall be in English. All the dimensi	ottom corner with clear esignation, the specificate Project, drawing nure submitted the applicate, markings and writir	mention of ations title, mber and able items
	Employer's own drawir available to drawing nu	gs submitted by the Contractor drawing number in addition to g number. Employer's drawing to the successful bidder to embers to the drawings to be subfithe Contract.	o contractor's (their sub numbering system sha nable him to assign l	o-vendor's) Il be made Employer's
	detailed er	Il the drawings/ documents sugineering stage shall be mar ION" prior to submission in line	ked "FOR APPROVAL	or "FOR
	Further, sp electronic s	ace shall be identified on eachignature.	drawing for Approval	stamp and
	shall be in these docu conformand	ing of detailed engineering dat accordance with the time sche ments/ data/ drawings by the e of the data/ drawings/ doc terfaces with the equipments	dule for the project. The Employer will cover or uments to the specifica	e review of ally general ations and
STAG	 	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 17 OF 119

CLAUSE NO.	GENE	ERAL TECHNICAL REQUIRE	MENTS	एनदीपीसी NTPG
	Employer sh quantities ar indicated or approval by	& dimensions which might afformation ould not be construed to be a not details of the equipments, the accuracy of the information the Employer/ Project Manage sponsibilities and liabilities und	thorough review of all d , materials, any device on submitted. The revie r shall not relieve the Co	imensions, s or items ew and/ or
	strict accord	proval of the drawings, further ance with these approved dr thout the written approval of the	awings and no deviatio	
	equipment / Contractor's design of the However, if equipment/s changes sha the reasons	turing, fabrication and execution system, prior to the approvarisk. The Contractor is expected equipment /system, once the some changes are necesystem at a later date, the Call promptly be brought to the for the change and get the mance to the provisions of the	I of the drawings, shall ed not to make any charge are approved by the essitated in the designation of the Employer evised drawing approve	be at the nges in the Employer. gn of the but such indicating
	Layout draw submitted fo pipes shall h authority/ rej indicated in Diagrams ar larger diame	vings for all piping of 65 m r review/ approval of Employe nowever be routed as per site presentative of Employer base approved/ finalised Flow Scl and/or the requirements cropp ter piping or otherwise after the the entire scope of work of this	m and larger diameter prior to erection. Small conditions in consultationed on requirements of speed on Process & Instruction of the condition	r shall be all diameter on with site such piping umentation venting of
	equipment s	& anticipating the requirements thall be done by the contractorogress of piping & equipment its effective draining & v	tor well in advance so ent erection, subseque	as not to
	j) As Built Drav	wings		
	Contractor w	cceptance of individual equipm vill update all original drawings o "as built" conditions and l.	and documents for the	equipment
	·	ust be checked by the Contra		•
STAG	I HERMAL POWER PROJECT EE-III (1X800 MW) PC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 18 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS	एनशैपीमी NTPC			
	submission to the Employer. In case drawings are found to without proper checking by the Contractor, the same shall not and returned to the Contractor for re-submission. The contractor a visit to site to see the existing facilities and understand completely and collect all necessary data/ drawings at site which as an input to the engineering. The contractor shall do the engineering including interfacing and integration of all his systems & facilities within his scope of work as well as interface & integration of systems, facilities, equipment & works under scope and submit all necessary drawings/ documents for the same	be reviewed or shall make of the layout he are needed the complete equipment, e engineering or Employer's			
	I) The Contractor shall submit adequate prints of drawing / data / per Annexure-VI. The Employer shall review the drawings an copy to the Contractor authorizing either to proceed with ma fabrication or marked to show changes desired. When changes drawings shall be re-submitted promptly, with revisions clearly final review. Any delays arising out of the failure of the submit/rectify and resubmit in time shall not be accepted as delay in the contract schedule.	d return soft anufacture or are required, marked, for Contractor to			
	m) All engineering data submitted by the Contractor after final process including review and approval by the Project Manager/ Employer shall form part of the contract documents and the entire works covered under these specification shall be performed in strict conformity with technical specifications unless otherwise expressly requested by the Project Manager in writing.				
8.03.05	e-Learning Package:				
	e-learning packages shall be supplied for the equipment / system for the following Steam Turbine Generator & auxiliaries and Steam Generator & auxiliaries along with associated electrical and C&I system.				
8.03.05.01	Steam Turbine Generator & Auxiliaries				
	Steam Turbine including stop valves, control valves, overload valves and cross over piping. Steam Turbine Auxiliary Systems including Quick Closing and Ordinary NRVs, Turbine gland sealing system, Lubricating oil system and its purification system, Centralized oil storage and its purification system, Control fluid and its purification system, governing and protection system, exhaust hood spray cooling system, drainage and vent system, turbine preservation system, HP/LP Bypass system.				
	Generator and Auxiliary System including Generator, complete hydrogen cooling, carbon dioxide and nitrogen gas systems as applicable, complete seal oil system, complete water cooling system where applicable and complete excitation system.				
	Condensing Plant including Condenser, Condenser air evacuation system and Condenser on load tube cleaning system as applicable etc.				
STAG	HERMAL POWER PROJECT TECHNICAL SPECIFICATIONS GE-III (1X800 MW) SECTION VI, PART-C REQUIREMENTS	PAGE 19 OF 119			

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS					
	Drip Pump along with all accessories as applicable, Condensate Extraction Pumps along with all accessories, Deaerator level Control Station, Feed Water Heating Plant including Drain Cooler, low pressure heaters, deaerator and feed storage tank, high pressure heaters and associated accessories, Boiler Feed Pumps along with all accessories, Drive Turbine for Boiler Feed Pump along with all accessories, Feed regulating station, Make up system to Condenser, Gland Steam Condenser Recirculation System, Turbine Hall EOT Cranes and EOT Crane for Boiler Feed Pump as applicable.					
8.03.05 .02	Steam Generator & Auxiliaries					
	Furnace/evaporator, separator & drain collection vessel, superheater, reheater, economiser, startup recirculation & drain system, desuperheating spray system, safety valves, soot blowing system, draft plant including FD & ID fans, PA fan, air preheaters, SCAPH, coal preparation and firing system including raw coal feeder and pulverisers, coal burners, fuel oil system and oil burners, Electrostatic precipitator, NOx control system and Flue gas desulphurisation system, Aux. PRDS system.					
8.03.05. 03	These packages shall be installed on the Learning Management Server (LMS) of Power Management Institute (PMI), NTPC located at Noida. The Project Manager / Engineer- In-Charge (EIC) for the e-learning modules shall be from PMI.					
	1. The objective of the e-Learning package consisting of courses for erection, commissioning, operation and maintenance of equipment / system as specified above is to facilitate the employees to have first hand information / requirement with respect to above activities for the supplied equipment / system.					
	2. The bidder shall submit e-learning courses each for erection, commissioning, operation and maintenance of each of the equipment / system supplied as above.					
	a. The erection course(s) should include instructions on pre-checks, prerequisites, erection strategy, erection procedure etc.					
	b. The commissioning course(s) should include instructions on precommissioning, commissioning, initial operation etc.					
	c. The operation course(s) should include instructions on the permissive, interlocks, physical check-ups, start-up, shutdown and protections etc.					
	d. The maintenance course(s) should include instructions on predictive, preventive, breakdown and overhauling.					
	Depth of coverage of above courses shall be as specified for "Instruction Manuals" in above clauses. A literature on caution / safety while handling equipment / system for the above modules shall follow the description of the said equipment /system.					
STAG	SIPAT SUPER THERMAL POWER PROJECT STAGE-III (1X800 MW) SECTION VI, PART-C GENERAL TECHNICAL PAGE 20 OF 119					

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS
	3. The e-Learning packages on equipment / system shall be installed by the vendor and shall be successfully test run in the presence of Project Manager EIC or representative before acceptance by NTPC. The vendor will also give the master copy in form of Flash Drive/CD/DVD. The respective module fo erection & commissioning shall be delivered and successfully test run at leas three months before the scheduled start of the corresponding activity at site.
	The respective module for operation & maintenance shall be delivered and successfully test run at least three months before scheduled firs synchronization of first unit.
	4. e-Learning course broad requirements:
	a. The courses shall be web based and mobile based Application type. It shall run on all possible versions of web browser like Internet Explorer, Google Chrome Firefox etc. on Laptop/Desktop and shall be Smartphone/Tablet/Mobile responsive. The Mobile responsive courses shall run on Android, Windows Mobile, Blackberry, iOS etc.
	b. The courses shall support liquid/fluid page layout so that the entire screen gets adjusted to PC, Laptop, Smartphone/Mobile, Tablet and any other display devices.
	c. Course content text shall be in English language and be associated with a voiceover in English language with Indian accent.
	d. Courses shall be SCORM (Sharable Content Object Reference Model compliant, version 1.2 which is compatible with LMS at PMI.
	e. Each course shall have every physical and functional detail of the equipment system supplied.
	f. Each of the e-Learning course shall be based on multiple web pages and mobile pages with multiple modules.
	g. There shall be option for self-assessment test after every course. In case the user doesn't opt for self-assessment test the user shall be able to go to the next course. There shall be no restriction in no. of times for repeating the assessments. All correct answers along with the answers marked by the user shall be displayed at the end of test/quiz.
	h. If Java and Flash, as applicable are not available in the system to run the package, then there shall be a prompt message for updation of the same.
	i. Each course shall have a self-running interactive content with navigation buttons containing forward, backward, pause, bookmark and menu options in the course window.
	j. The course shall contain chapter titled 'Introduction/overview' that explains the purpose of the course.

TECHNICAL SPECIFICATIONS

SECTION VI, PART-C

GENERAL TECHNICAL REQUIREMENTS

PAGE

21 OF 119

SIPAT SUPER THERMAL POWER PROJECT

STAGE-III (1X800 MW)

EPC PACKAGE

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS					
	k. The course content shall contain descriptive text shall be factual, specific, terse, clearly worded, and simply illustrative, so that the user can understand it.					
	I. The system shall provide the user with the ability to select the information with a Cursor.					
	m. The course menu should contain table of content linked to concerned pag The user shall be given the capability to access all of the functions available the system through a menu system. This shall consist of active buttons, wh shall control a hierarchy of pull down/pop-up menus. Menu shall appear quic and exist only while a selection is being made. The user shall be given capability to position the cursor or pointer on the menu item and use point device such as mouse to activate the function.					
	n. Every course shall contain the 3D design/drawing/exploded view/360° turn around view of the equipment/system, textual description of the equipment/system and its functionality with video (as applicable), animation and audio.					
	o. The users shall be able to control audio sound level associated with the courses.					
	p. Drawings / text in the courses shall be scalable (Zoom In/ Out).					
	q. The user shall have the capability to record a bookmark to mark displayed information for later recall, whenever he accesses the same course next time.					
	 e-learning Package of an equipment / system shall include e-learning courses for each of erection, commissioning, operation and maintenance of that equipment / system. e-learning courses on erection, commissioning, operation and maintenance of an equipment / system shall include e-learning lessons/chapters/modules (as required) for erection, commissioning, operation and maintenance respectively of that equipment / system. 					
	3. The vendor shall get the approval of one sample course from Project Manager / EIC before proceeding for further courses.					
8.04.00	Provision for Fail Safe operation of vital Equipments					
	All the Plant and equipments / Systems supplied under the contract shall be designed following "Fail Safe" concept. In case of failure of Power supply like Electric power, Hydraulic pressure, Pneumatic pressure, Vacuum etc. the system should be designed in such a way that the equipment/Valves/dampers etc. shall always move/remains (as applicable) to safest position as per system requirement to ensure safety of Man and Machinery.					
8.05.00	Engineering Co-ordination Procedure					
STAG	SIPAT SUPER THERMAL POWER PROJECT STAGE-III (1X800 MW) EPC PACKAGE TECHNICAL SPECIFICATIONS SECTION VI, PART-C GENERAL TECHNICAL REQUIREMENTS 22 OF 1'					

CLAUSE NO.	GENE	RAL TECHNICAL REQUIRE	MENTS	एनदीपीसी NTPC	
8.05.01	The following principal coordinators will be identified by respective organization after award of contract:				
	NTPC Engineering Coordinator (NTPC EC):				
	Name	:			
	Designation	:			
	Address	:			
	a) Postal	:			
	b) Telegraphic /	e-Mail :			
	c) FAX	: TELEPHONE :			
	Contractor's/ Vendo	r's Engineering Coordinator (V	ENDOR EC):		
	Name	:			
	Designation	:			
	Address	:			
	a) Postal	:			
	b) Telegraphic /	e-Mail :			
	c) FAX	: TELEPHONE :			
8.05.02	All engineering corr behalf of the respect	respondence shall be in the ive organizations.	name of above coord	linators on	
8.05.03	Contractor's/Vendor	s Drawing Submission and Ap	pproval Procedure:		
	documents/c	dor in the form of n for NTPC's information the general term "drawi	n/ interface		
	b) Not used				
	bottom corne Contractor sl	(including those of subvender the 'title plate' with all relevently all furnish this format to his sevendor's compliance.	vant information duly fill	ed in. The	
STAG	IPAT SUPER THERMAL POWER PROJECT STAGE-III (1X800 MW) EPC PACKAGE TECHNICAL SPECIFICATIONS SECTION VI, PART-C REQUIREMENTS 23 OF 119				

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS					
	d)	Not used				
	e)	understand the site which are the complete equipment, sengineering	ne layo e need e engi ystem & inte	all make a visit to site out completely and colle led as an input to the en neering including inters & facilities within his gration of systems, facilities and submit all necess	ect all necessary data / or agineering. The contract facing and integration scope of work as well a cilities, equipment & w	drawings at tor shall do of all his as interface orks under
	f)	completenes engineering drawings ar checking by	ss, c sche e fou y the	be checked by the lata adequacy and dule prior to submissed to be submitted we contractor, the same ontractor for re-submis	relevance with re sion to the Employer vithout proper endors ne shall not be revi	espect to In case ement for
	g)	The Contractor shall submit drawing / data / document for Employer's review and approval. The drawings submitted by the Contractor/vendor shall be reviewed by NTPC and their comments shall be forwarded within three (3) weeks of receipt of drawings. Upon review of each drawing, depending on the correctness and completeness of the drawing, the same will be categorized and approval accorded in one of the following categories:				or shall be n three (3) bending on the will be
		CATEGORY-	- I:	Approved		
		CATEGORY-	· II		to incorporation of ed. Resubmit revised ments.	
		CATEGORY	–III		mit revised drawings for nments/ modification as	
		CATEGORY	-IV	For information and re	cords.	
	h) After Rev 0 comments, the drawing will be locked in the system. Contractor will review the Rev 0 comments within 7 days & furnish the Comment Reply Sheet (CRS) to NTPC as an agenda point for TCM. TCM shall be conducted with Contractor on non-agreed comments of CRS. System will not allow Contractor to submit approval category drawings before the scheduled submission date. However, documents may be unlocked on case to case basis. Based on resolution of all comments and agreements, the document will be approved in TCM itself. The contractor will revise the document based on the resolutions and certify that all the resolutions has been taken care of.					
STAG	HERMAL F GE-III (1X80 PC PACKA	, i	TEC	CHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 24 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS				
	Based on this certification, the document will be opened and submitted by contractor in the system for approval as Rev 01 within 10 days of TCM.				
	i) In case, the Contractor/ Vendor does not agree with any specific comment, he shall furnish the explanation for the same to NTPC for consideration. In all such cases the Contractor shall necessarily enclose explanations along with the revised drawing (taking care of balance comments) to avoid any delay and/or duplication in review work.				
	j) It is responsibility of the Contractor/ Vendor to get all the drawings approved in the Category I & IV (as the case may be) and complete engineering activities within the agreed schedule. Any delay arising out of submission and modification of drawings shall not alter the contract completion schedule.				
	k) If Contractor/ Vendor fails to resubmit the drawings as per the schedule, construction work at site will not be held up and work will be carried out on the basis of comments furnished on previous issues of the drawing.				
	I) These comments will be taken care by the contractor while submitting the revised drawing.				
	The contractor shall use a single transmittal for drawings. Submission. This shall include transmittal numbers and date, number of copies being sent, names of the agencies to whom copies being sent, drawing number and titles, remarks or special notes if any etc.				
8.06.00	ENGINEERING PROGRESS AND EXCEPTION REPORT				
8.06.01	The Contractor shall submit every month an Engineering progress and Exception Report giving the status of each engineering information including				
	A list of drawings/engineering information which remains unapproved for more than four (4) weeks after the date of first submission				
	b) Drawings which were not submitted as per agreed schedule.				
8.06.02	The draft format for this report shall be furnished to the Employer within four (4) weeks of the award of the contract, which shall then be discussed and finalised with the Employer.				
9.00.00	TECHNICAL CO-ORDINATION MEETING				
9.01.00	The Contractor shall be called upon to organise and attend monthly Design/Technical Co-ordination Meetings (TCMs) with the Employer/Employer's representatives and other Contractors of the Employer during the period of contract. The Contractor shall attend such meetings at his own cost at NEW DELHI / NOIDA /				
SIPAT SUPER THERMAL POWER PROJECT STAGE-III (1X800 MW) EPC PACKAGE TECHNICAL SPECIFICATIONS SECTION VI, PART-C GENERAL TECHNICAL REQUIREMENTS 25 OF 11					

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS				
	HYDERABAD / PROJECT SITE or at mutually agreed venue as and when required and fully co-operate with such persons and agencies involved during the discussions.				
9.02.00	The Contractor should note that Time is the essence of the contract. In order to expedite the early completion of engineering activities, the comments of the Employer shall be discussed across the table during the above Technical Coordination Meeting (s) wherein best efforts shall be made by both sides to ensure the approval of the drawing.				
9.02.01	The Contractor shall ensure availability of the concerned experts / consultants/ personnel who are empowered to take necessary decisions during these meetings. The Contractor shall be equipped with necessary tools and facilities so that the drawings/documents can be resubmitted after incorporating necessary changes and approved during the meeting itself.				
9.02.02	Should any drawing remain unapproved for more than four (4) weeks after it's first submission, this shall be brought out in the monthly Engineering Progress and Exception Report with reasons thereof.				
9.03.0	Any delays arising out of failure by the Contractor to incorporate Employer's comments and resubmit the same during the TCM shall be considered as a default and in no case shall entitle the Contractor to alter the Contract completion date.				
10.00.00	DESIGN IMPROVEMENTS				
	The Employer or the Contractor may propose changes in the specification of the equipment or quality thereof and if the parties agree upon any such changes the specification shall be modified accordingly.				
	If any such agreed upon change is such that it affects the price and schedule of completion, the parties shall agree in writing as to the extent of any changing the price and/or schedule of completion before the Contractor proceeds with the change. Following such agreement, the provision thereof, shall be deemed to have been amended accordingly.				
11.00.00	EQUIPMENT BASE	s			
	A cast iron or welded steel base plate shall be provided for all rotating equipment which is to be installed on a concrete base, unless otherwise specifically agreed to by the Employer. Each base plate shall support the unit and its drive assembly, shall be of a neat design with pads for anchoring the units, shall have a raised lip all around, and shall have threaded drain connections.				
12.00.00	PROTECTIVE GUARDS				
STAGE-III (1X800 MW) SECTION VI. PART-C				PAGE 26 OF 119	

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS					
	_	all be provided for protection of personnel on all exposed rotating thine parts. All such guards shall be designed for easy installation aintenance purpose.				
13.00.00	LUBRICANTS, SER	VO FLUIDS AND CHEMICAL	_S			
13.01.00	oils, lubricants, serv Generator) etc. whic of specifications int completion of facili lubricants as availa	All the first fill and one year's topping requirement of consumables such as greases, oils, lubricants, servo fluids / control fluids, gases (excluding H_2 , CO_2 and N_2 for Generator) etc. which will be required to put the equipment covered under the scope of specifications into successful commissioning/initial operation and to establish completion of facilities shall be supplied by the contractor. Suitable standard lubricants as available in India are desired. Efforts should be made to limit the variety of lubricants to minimum.				
	· ·	nclude supply of H_2 , CO_2 and issioning of Generator.	N_2 as applicable for the	Generator		
	topping requirement lubricants, servo fluid	supply a quantity not less than 10% of the full charge or one (1) year irement mentioned above (Whichever is higher) of each variety of ervo fluids, gases etc. (as detailed above) used which is expected to be go the first year of operation. This additional quantity shall be supplied in tainers.				
13.02.00	The variety of lubrication for Main Turbine, Dr	far as possible lubricants marketed by the Indian Oil Corporation shall be used. The variety of lubricants shall be kept to a minimum possible. However, the lube oil Main Turbine, Drive Turbine, TDBFP and MDBFP shall be kept same in view of se of operation and maintenance.				
	fluids, chemicals el furnished. On comp their location and id	etailed specifications for the lubricating oil, grease, gases, servo fluids, control ids, chemicals etc. required for the complete plant covered herein shall be nished. On completion of erection, a complete list of bearings/ equipment giving peir location and identification marks shall be furnished to the Employer alongwith prication requirements.				
14.00.00	LUBRICATION					
14.01.00	Equipment shall be lubricated by systems designed for continuous operation. Lubricant level indicators shall be furnished and marked to indicate proper levels under both standstill and operating conditions.					
15.00.00	MATERIAL OF CONSTRUCTION					
15.01.00	All materials used for the construction of the equipment shall be new and shall be in accordance with the requirements of this specification. Materials utilised for various components shall be those which have established themselves for use in such applications.					
STAG	SIPAT SUPER THERMAL POWER PROJECT STAGE-III (1X800 MW) SECTION VI, PART-C GENERAL TECHNICAL REQUIREMENTS PAGE 27 OF 11S					

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS				
16.00.00	RATING PLATES, NAME PLATES & LABELS				
16.01.00	Each main and auxiliary item of plant shall have permanently attached to it in a conspicuous position, a rating plate of non-corrosive material upon which shall be engraved manufacturer's name, equipment, type or serial number together with details of the ratings, service conditions under which the item of plant in question has been designed to operate, and such diagram plates as may be required by the Employer.				
16.02.00	Each item of plant shall be provided with nameplate or label designating the service of the particular equipment. The inscriptions shall be approved by the Employer or as detailed in appropriate section of the technical specifications.				
16.03.00	Such nameplates or labels shall be of white non-hygroscopic material with engraved black lettering or alternately, in the case of indoor circuit breakers, starters, etc. of transparent plastic material with suitably coloured lettering engraved on the back.				
16.04.00	Items of plant such as valves, which are subject to handling, shall be provided with an engraved chromium plated nameplate or label with engraving filled with enamel. The name plates for valves shall be marked in accordance with MSS standard SP-25 and ANSI B 16.34 as a minimum.				
16.05.00	Hanger/ support numbers shall be marked on all pipe supports, anchors, hangers, snubbers and restraint assemblies. Each constant and variable spring support shall also have stamped upon it the designed hot and cold load which it is intended to support.				
16.06.00	Valves, steam traps and strainers shall be identified by Employer's tag number of a metal tap permanently attached to non-pressure parts such as the yoke by a stainless steel wire. The direction of flow shall also be marked on the body.				
16.07.00	Safety and relief valv	ves shall be provided with the	following:		
	a) Manufacturer	's identification.			
	b) Nominal inlet	and outlet sizes in mm.			
	c) Set pressure	in Kg/cm ² (abs).			
	d) Blowdown ar	nd accumulation as percentage	e of set pressure.		
	e) Certified capacity in Kg of saturated steam per hour or in case of liquid certified capacity in litres of water per minute.				
SIPAT SUPER THERMAL POWER PROJECT STAGE-III (1X800 MW) SECTION VI, PART-C GENERAL TECHNICAL REQUIREMENTS PAGE 28 OF 119					

CLAUSE NO.	GENE	RAL TECHNICAL REQUIRE	MENTS	एनदीपीमी NTPC	
16.08.00	All such plates, instruction plates, etc. shall be bilingual with Hindi inscription first, followed by English. Alternatively, two separate plates one with Hindi and the other with English inscriptions may be provided.				
16.09.00	All segregated phases of conductors or bus ducts, indoor or outdoor, shall be provided with coloured phase plates to clearly identify the phase of the system.				
17.00.00	TOOLS AND TACK	LES			
	and tackles and othe assembly, disassem systems (including s handling equipment, checking and meas	supply with the equipment or er instruments required and obly and proper maintenance oftware). These special tools jigs and fixtures for maintena surement aids etc. A list of der alongwith the offer.	other instruments for the of the plant and equips will also include specince and calibration / rea	e erection, pment and ial material adjustment,	
	price. These tools a Contractor shall also erection, commission	ol / tackle shall be deemed to and tackles shall be separate ensure that these tools and t ning and initial operation. For and tackles. All the tools and aployer.	ely packed and sent to ackles are not used by r this period the Contrac	site. The him during ctor should	
18.00.00	WELDING				
18.01.00	If the manufacturer has special requirements relating to the welding procedures for welds at the terminals of the equipments to be performed by others the requirements shall be submitted to the Employer in advance of commencement of erection work.				
19.00.00	COLOUR CODE FOR ALL EQUIPMENTS/ PIPINGS/ PIPE SERVICES				
19.01.00	All equipment/ piping/ pipe services are to be painted by the Contractor in accordance with Employer's standard colour coding scheme, which will be furnished to the Contractor during detailed engineering stage.				
20.00.00	PROTECTION AND	PRESERVATIVE SHOP CO	ATING		
20.01.00	PROTECTION				
	All coated surfaces shall be protected against abrasion, impact, discoloration and any other damages. All exposed threaded portions shall be suitably protected with either metallic or a non-metallic protection device. All ends of all valves and piping and conduit equipment connections shall be properly sealed with suitable devices to protect them from damage. All primers/paints/coatings shall take into account the hot humid, corrosive & alkaline, subsoil or over ground environment as the case may be.				
STAGE-III (1X800 MW) SECTION VI PART-C STAGE-III (1X800 MW)				PAGE 29 OF 119	

CLAUSE NO.	GENE	RAL TECHNICAL REQUIRE	MENTS	एनरीपीसी NTPC	
	-	r painting specification shall b chnical Specification.	pe complied with as deta	ailed out in	
20.02.00	PRESERVATIVE SHOP COATING				
	application of suitab the shop assembly, equipment. All surfa other coatings and p after installation or	c surfaces subject to corrostle coatings. All surfaces which shall be treated beforehand aces shall be thoroughly clea prepared in the shop. The surfaction require corrosion protection requirements covered in the	n will not be easily accer and protected for the ned of all mill scales, of faces that are to be find until installation, shal	ssible after life of the exides and ish-painted I be shop	
	one or more coats finished colors sha	her electrical equipments, if ir of primer and two coats of hi ll be as per manufacturer's ployer at a later date.	igh grade resistance er	namel. The	
20.03.00	Shop primer for all steel surfaces which will be exposed to operating temperature below 95 degrees Celsius shall be selected by the Contractor after obtaining specific approval of the Employer regarding the quality of primer proposed to be applied. Special high temperature primer shall be used on surfaces exposed to temperature higher than 95 degrees Celsius and such primer shall also be subject to the approval of the Employer.				
20.04.00	All other steel surfaces which are not to be painted shall be coated with suitable dust preventive compound subject to the approval of the Employer.				
20.05.00		All piping shall be cleaned after shop assembly by shot blasting or other means approved by the Employer. Lube oil piping or carbon steel shall be pickled.			
20.06.00	Painting for Civil structures and equipment/system covered under this package shall be done as specified under technical requirements on civil works in relevant part of this specifications.				
21.00.00	QUALITY ASSURA	NCE PROGRAMME			
21.01.00	To ensure that the equipment and services under the scope of contract whether manufactured or performed within the Contractor's works or at his sub-contractor's premises or at the Employer's site or at any other place of work are in accordance with the specifications, the Contractor shall adopt suitable quality assurance programme to control such activities at all points, as necessary. Such programmes shall be outlined by the Contractor and shall be finalized during detailed engineering with employer / authorized representative after discussion. The QA programme shall be generally in line with ISO-9001/IS-14001. A quality assurance programme of the				
STAG	HERMAL POWER PROJECT E-III (1X800 MW) PC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 30 OF 119	

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS				
	contractor shall ger	nerally cover the following:			
	l '	ation structure for the manage uality assurance programme	ement and implementa	tion of the	
	b) Quality Syst	em Manual			
	c) Design Con	trol System			
	d) Documentation Control System e) Qualification data for Bidder's key Personnel.				
	sub-contrac	ure for purchase of materials, p tor's services including vend w-material inspection, verification	dor analysis, source	inspection,	
	g) System for shop manufacturing and site erection control including proceedings and fabrication and assembly controls.				
	h) Control of n	on-conforming items and syster	m for corrective actions.		
	i) Inspection a	nd test procedure both for man	ufacture and field activi	ties.	
	j) Control of ca	alibration and testing of measur	ing testing equipments.		
	k) System for (Quality Audits.			
	I) System for i	ndication and appraisal of inspe	ection status.		
	m) System for a	authorising release of manufact	ured product to the Emp	oloyer.	
	n) System for I	nandling storage and delivery.			
	o) System for i	maintenance of records, and			
	p) Furnishing of quality plans for manufacturing and field activities detailing out the specific quality control procedure adopted for controlling the quality characteristics relevant to each item of equipment/component. Format for the same is attached as Annexure VIII.				
22.00.00	GENERAL REQUI	REMENTS - QUALITY ASSUR	ANCE		
22.01.00	All materials, components and equipment covered under this specification shall be procured, manufactured, erected, commissioned and tested at all the stages, as per a comprehensive Quality Assurance Programme. An indicative programme of				
STAG	HERMAL POWER PROJECT E-III (1X800 MW) PC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 31 OF 119	

CLAUSE NO.	GENE	RAL TECHNICAL REQUIRE	MENTS	एनदीपीसी NTPC
	given in the respective a comprehensive proimplement such properties of the properties of the submitted to Emplans shall be finalized.	re carried out by the contractive technical specification. This ogramme as it is the contractive gramme duly approved by the ring and field activities shall be apployer for approval. Scheduzed during detailed engineerid 1-QAI-P-1/F3. Monthly progress	s is, however, not intend tor's responsibility to dr the Employer. The detail the drawn up by the Bidd tule of finalization of su tng as per attached An	ded to form aw up and led Quality ler and will ich Quality nexure-VIII
22.02.00	various tests/inspection specification and state followed by Control Organisation, the relinspection document manufacture, assem	ity Plan will detail out for all ction, to be carried out as indards mentioned therein and tractor's/ Sub-contractor's/ levant reference documents and the raised etc., during all subly and final testing/performant ctronic media through C-folderapproval.	s per the requiremend quality practices and public sub-supplier's Quality and standards, acceptantages of materials pronce testing. The Quality	ts of this procedures y Control nce norms, ocurement, Plan shall
22.03.00	Field Quality Plans will detail out for all the equipment, the quality practices and procedures etc. to be followed by the Contractor's "Site Quality Control Organisation", during various stages of site activities starting from receipt of materials/equipment at site.			
22.04.00	The Bidder shall also furnish copies of the reference documents/plant standards/acceptance norms/tests and inspection procedure etc., as referred in Quality Plans along with Quality Plans. These Quality Plans and reference documents/standards etc. will be subject to Employer's approval without which manufacturer shall not proceed. These approved documents shall form a part of the contract. In these approved Quality Plans, Employer shall identify customer hold points (CHP), i.e. test/checks which shall be carried out in presence of the Employer's Project Manager or his authorised representative and beyond which the work will not proceed without consent of Employer in writing. All deviations to this specification, approved quality plans and applicable standards must be documented and referred to Employer along with technical justification for approval and dispositioning.			
22.05.00	The contractor shall submit to the Employer Field Welding Schedule for field welding activities in the format enclosed at Annexure-V. The field welding schedule shall be submitted to the Employer along with all supporting documents, like welding procedures, heat treatment procedures, NDT procedures etc. at least ninety days before schedule start of erection work at site.			
22.06.00	The contractor shall have suitable Field Quality Organization with adequate manpower at Employer's site, to effectively implement the Field Quality Plan (FQP) and Field Quality Management System for site activities. The contractor shall submit			
STAG	SIPAT SUPER THERMAL POWER PROJECT STAGE-III (1X800 MW) SECTION VI, PART-C GENERAL TECHNICAL PAGE REQUIREMENTS 32 OF 11			PAGE 32 OF 119

CLAUSE NO.	GENE	RAL TECHNICAL REQUIRE	MENTS	एनदीपीसी NTPC
		osed FQA setup (organizatio . The FQA setup shall be in p		• •
22.07.00	accepted by Empl	e despatched from the manufa oyer's Project Manager/Autl patch by issuance of Materia ance).	norised representative	and duly
22.08.00	be of tested quality conducted to determ heat treatment process.	equipment manufacture incluas per relevant codes/standanine the mechanical properties edure recommended and actuatemperature chart. Tests shand/or agreed details	rds. Details of results on s; chemical analysis and ally followed shall be re	of the tests d details of ecorded on
22.09.00	accordance with red	ing shall be carried out as pe quirements of ASME Section acceptable to the Employer.	•	•
		procedures shall be submitted to carrying out the welding/bra		authorized
22.10.00	All brazers, welders and welding operators employed on any part of the contract either in Contractor's/his sub-contractor's works or at site or elsewhere shall be qualified as per ASME Section-IX or BS-4871 or other equivalent International Standards acceptable to the Employer. All welding / brazing procedures qualified / used at shop, will be made available to NTPC during audit / inspection. Procedures to be qualified at site will be submitted to NTPC.			
22.11.00	Not Used.			
22.12.00	For all IBR pressure parts and high pressure piping welding, the latest applicable requirements of the IBR (Indian Boiler Regulations) shall also be essentially complied with. However, other piping shall be as per relevant code. Similarly, any other statutory requirements for the equipment/systems shall also be complied with. On all back-gauged welds MPI/LPI shall be carried before seal welding			
22.13.00	All the heat treatme	ent results shall be recorded nended regimes.	on time temperature	charts and
22.14.00	No welding shall be	carried out on cast iron compo	onents for repair.	
22.15.00	Unless otherwise proven and specifically agreed with the Employer, welding of dissimilar materials and high alloy materials shall be carried out at shop only.			
22.16.00	All non-destructive examination shall be performed in accordance with written procedures as per International Standards, The NDT operator shall be qualified as			
SIPAT SUPER THERMAL POWER PROJECT TECHNICAL SPECIFICATIONS STAGE-III (1X800 MW) SECTION VI. PART-C GENERAL TECHNICAL PAGE			PAGE 33 OF 119	

CLAUSE NO.	GENE	RAL TECHNICAL REQUIRE	MENTS	एनदीपीसी NTPC	
	be recorded in a re	ne American Society of non-deport, which includes details addata and identification of persport with the job.	of methods and equipr	ment used,	
	thickness equal to o specified in respect	of thickness greater than 40 r greater than 25mm shall be ive equipment specification. nan 40 mm shall be Ultrasonic	ultrasonically tested ot All bar stock/Forging o	herwise as	
22.17.00	l	all list out all major items/ se as well as procured from s		ents to be	
	All the sub-vendors proposed by the Main contractor for procurement of major bought out items including castings, forgings, semi-finished and finished components/equipment etc., list of which shall be drawn up by the Contractor and finalised with the Employer, shall be subject to Employer's approval on enclosed format as Annexure-III.				
		oved sub vendors against s Chapter E-60 Indicative sub-ve		ttached as	
	The contractor's proposal for any new sub vendor for any of the items identified in indicative sub-vendor list shall necessarily be furnished in the sub vendor questionnaire & main Contractor Evaluation report format attached as Annexure- VII with all relevant documents and main contractor's own physical assessment report assessed as per their quality management system for NTPC review and acceptance.				
	proposal is received Out Items/Start of M Main contractor shal Major checks and c assessed by main c same is not the part i. Duly Filled Ma ii. Duly Filled Sul	oposal will only be considered sufficiently in time: 90 days panufacturing so as not to imped I submit the documentation as quality requirements as ment contractor and complied with of their Quality management so in supplier Evaluation Report.	orior to ordering date of ede the progress of the of mentioned below: cioned below shall neco documentary support i	f a Bought- contract.	
	 iii. Factory Registration Certificate. iv. Overall Organization Chart with Manpower details (Design, Manufacturing, Quality etc.) v. Supply reference list of the Sub-Supplier indicating similar product supply order reference no., customer name, rating of product, date /year of supply, date / year of commissioning. 				
	 vi. List of Manufacturing Equipment available with sub vendor. vii. List of Testing Equipment available with sub vendor. viii. Manufacturing process execution plan with flow chart indicating various stages of manufacturing from raw material to finished product including outsourced process, if any. ix. Details of Outsourced Manufacturing Processes, if any. 				
SIPAT SUPER THERMAL POWER PROJECT STAGE-III (1X800 MW) SECTION VI, PART-C GENERAL TECHNICAL PAGE REQUIREMENTS PAGE 34 OF 11				PAGE 34 OF 119	

CLAUSE NO.	GENE	RAL TECHNICAL REQUIRE	MENTS	एनदीपीमी NTPC
		exercised during receipt, in-proc Statutory requirements (As appl		
	Incompleteness of the days to submit the co	n of proposal to NTPC, in proposal, The main contractor of the NTPC comment ontractor is not serious about pur	will be given a period of n ts. In case of noncomplian	naximum 07 ce, it will be
	i) Quality Mana traceability & c ii) Design Capab	ndor will be assessed broadly on gement System Compliance control over outsources process ilities (As applicable) , Testing & Storage Facility		
	v) Supply Experi	ence indicating similar product of product, date /year of supply, date		
	(Jointly with the main	ervations or non-compliance obs contractor) with respect to the sidered for acceptance and Main	submitted documents, pr	oposed sub
	preferably on enclose	orts on sub-vendor detail. Subr d format at Annexure-IV. Such ligation, duty or responsibility und	vendor approval shall not	
22.18.00	contract, after obta purchase specification the suppliers. The during the various supprocedures followed reference documentation raises finalised with the Empurchase order/cont weeks of the release /components, a copy purchase specification the Employer on the	uipment procured by the co- ining the written approval of ons and inquiries shall call for quality plans called for from tages of manufacture and inset d by the vendor's quality of ents/standards used, acce ed, etc. Such quality plans of apployer and such approved Quality plans of the purchase orders /co y of the same without price de ons, quality plans and deliver the monthly basis by the Con- ted so far for the contract.	of the Employer, the or quality plans to be sure the sub-contractor shadalation, the quality presontrol organisation, the eptance level, insport the successful vendo quality Plans shall form a and sub-contractor. With entracts for such bought etails but together with the conditions shall be furnished.	contractor's abmitted by all set out, actices and e relevant ection of rs shall be part of the hin two (2) t out items he detailed urnished to
22.19.00	systems and proce management and c	he right to carry out quality and edures of the Contractor's control activities. The control the Employer carry out such	or their sub-contracto actor shall provide all	or's quality
STAG	HERMAL POWER PROJECT E-III (1X800 MW) PC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 35 OF 119

CLAUSE NO.	GENE	RAL TECHNICAL REQUIRE	MENTS	एनरीपीमी NTPC	
22.20.00	The contractor shall carry out an inspection and testing programme during manufacture in his work and that of his subcontractor's and at site to ensure the mechanical accuracy of components, compliance with drawings, conformance to functional and performance requirements, identity and acceptability of all materials parts and equipment. Contractor shall carry out all tests/inspection required to establish that the items/equipment conform to requirements of the specification and the relevant codes/standards specified in the specification, in addition to carrying out tests as per the approved quality plan.				
22.21.00	Quality audit/surveillance/approval of the results of the tests and inspection will not, however, prejudice the right of the Employer to reject the equipment if it does not comply with the specification when erected or does not give complete satisfaction in service and the above shall in no way limit the liabilities and responsibilities of the Contractor in ensuring complete conformance of the materials/equipment supplied to relevant specification, standard, data sheets, drawings, etc.				
22.22.00	For all spares and replacement items, the quality requirements as agreed for the main equipment supply shall be applicable.				
22.23.00	I	Repair/rectification procedures to be adopted to make the job acceptable shall be subject to the approval of the Employer/ authorised representative.			
22.24.00	Environmental Stre	ess Screening			
	Environmental stress screening test process / procedure for eliminating infant mortile components for DDCMIS / PLC based system & for other systems having substantial electronics components (as determined by employer) like Electronic transmitter, CCTV components, PA systems etc. shall be furnished for NTPC acceptance				
22,25.00	The Contractor / Sub-contractor shall carry out routine test on 100% item at contractor / sub-contractor's works. The quantum of check / test for routine & acceptance test by employer shall be generally as per criteria / sampling plan defined in referred standards. Wherever standards have not been mentioned quantum of check / test for routine / acceptance test shall be as agreed during detailed engineering stage.				
22.26.00	Software Reliability	/ Quality Certification			
	Certification from OEM's authorized signatory that software offered with DDCMIS, PLC, CCTV, PA, Pyrometer, CEMS, AAQMS, EQMS, BHMS etc. declaring that the all the offered software(s) had gone through the established software quality test and offered software is not of β-version and offered software is also free from all known bugs as on date of approval of systems documents by NTPC as a part of quality documentation review and approval process during detail engineering.				
23.00.00	QUALITY ASSURANCE DOCUMENTS				
STAG	SIPAT SUPER THERMAL POWER PROJECT STAGE-III (1X800 MW) SECTION VI, PART-C GENERAL TECHNICAL PAGE SECTION VI, PART-C REQUIREMENTS 36 OF 119				

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS					
23.01.00	The Contractor shall be required to submit the QA Documentation in soft copies, as identified in respective quality plan with tick (\checkmark)mark.					
23.01.01	Each QA Documentation shall have a project specific Cover Sheet bearing name & identification number of equipment and including an index of its contents with page control on each document.					
	The QA Documentation file shall be progressively completed by the Supplier's subsupplier to allow regular reviews by all parties during the manufacturing.					
	The final quality document will be compiled and issued at the final assembly place of equipment before despatch. However, soft copies will be furnished not later than two (2) weeks.					
23.02.00	Typical contents of QA Documentation is as below:-					
	(a.) Quality Plan					
	(b.) Material mill test reports on components as specified by the specification and approved Quality Plans.					
	(c.) Manufacturer / works test reports/results for testing required as per applicable codes and standard referred in the specification and approved Quality Plans.					
	(d.) Non-destructive examination results /reports including radiography interpretation reports. Sketches/drawings used for indicating the method of traceability of the radiographs to the location on the equipment.					
	(e.) Heat Treatment Certificate/Record (Time- temperature Chart)					
	(f.) All the accepted Non-conformance Reports (Major/Minor)/deviation, including complete technical details / repair procedure).					
	(g.) CHP / Inspection reports duly signed by the Inspector of the Employer and Contractor for the agreed Customer Hold Points.					
	(h.) Certificate of Conformance (COC) wherever applicable.					
	(i.) MDCC					
23.03.00	Similarly, the contractor shall be required to submit soft copies containing QA Documentation pertaining to field activities as per Approved Field Quality Plans and other agreed manuals/ procedures, prior to commissioning of individual system.					
23.04.00	Before despatch / commissioning of any equipment, the Supplier shall make sure that the corresponding quality document or in the case of protracted phased deliveries, the applicable section of the quality document file is completed. The					
STAG	HERMAL POWER PROJECT E-III (1X800 MW) PC PACKAGE TECHNICAL SPECIFICATIONS SECTION VI, PART-C REQUIREMENTS PAGE 37 OF 119					

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS					
		supplier will then notify the Inspector regarding the readiness of the quadocument (or applicable section) for review.				
	· '	of the review carried out by nall stamp the quality docu		-		
	correct the in applicable se documents.	y document is unsatisfactory acompleteness, thus allowing tection) by time compatible with When it is done, the quality define the lospector.	to finalize the quality don the requirements as p	cument (or er contract		
	readily clear supplier shal the quality do the Inspecto outstanding document for submission of	is made for despatch, wherease of for the release of the quality immediately, upon shipment ocument Review Status signed and notify of the committed actions & submission. The lor applicable section when of QA documentation package the despatch of equipment.	nality document by that of the equipment, send by the Supplier Represed date for the completinspector shall stamp it is effectively comp	t time, the d a copy of sentative to etion of all the quality leted. The		
23.05.00	TRANSMISSION OI	F QA DOCUMENTATION				
		ocumentation by Inspector, or rate Quality Assurance Depar oyer.	•			
	For the particular case of phased deliveries, the complete quality document to the Employer shall be issued not later than two (2) weeks after the date of the last delivery of equipment.					
24.00.00	PROJECT MANAG	ER'S SUPERVISION				
24.01.00	To eliminate delays and avoid disputes and litigation, it is agreed between the parties to the Contract that all matters and questions shall be referred to the Project Manager and without prejudice to the provisions of 'Settlement of Disputes' clause in Section GCC, the Contractor shall proceed to comply with the Project Manager's decision.					
24.02.00	The work shall be performed under the supervision of the Project Manager.					
STAG	SUPER THERMAL POWER PROJECT TECHNICAL SPECIFICATIONS STAGE-III (1X800 MW) EPC PACKAGE TECHNICAL SPECIFICATIONS SECTION VI, PART-C REQUIREMENTS 38 OF 119					

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS				
	The scope of the duties of the Project Manager pursuant to the Contract, will include but not be limited to the following:				
	(a.) Interpretation of all the terms and conditions of these documents and specifications				
	(b.) Review and interpretation of all the Contractor's drawing, engineering data, etc.				
	(c.) Witness or his authorised representative to witness tests and trials either at the manufacturer's works or at site, or at any place where work is performed under the contract				
	(d.) Inspect, accept or reject any equipment, material and work under the contract				
	(e.) Issue certificate of acceptance and/or progressive payment and final payment certificates				
	(f.) Review and suggest modifications and improvement in completion schedules from time to time, and				
	(g.) Supervise Quality Assurance Programme implementation at all stages of the works.				
25.00.00	INSPECTION, TESTING AND INSPECTION CERTIFICATES				
25.01.00	The word 'Inspector' shall mean the Project Manager and/or his authorised representative and/or an outside inspection agency acting on behalf of the Employer to inspect and examine the materials and workmanship of the works during its manufacture or erection.				
25.02.00	The Project Manager or his duly authorised representative and/or an outside inspection agency acting on behalf of the Employer shall have access at all reasonable times to inspect and examine the materials and workmanship of the works during its manufacture or erection and if part of the works is being manufactured or assembled on other premises or works, the Contractor shall obtain for the Project Manager and for his duly authorised representative permission to inspect as if the works were manufactured or assembled on the Contractor's own premises or works.				
25.03.00	The Contractor shall give the Project Manager/Inspector fifteen (15) days written notice of any material being ready for testing. Such tests shall be to the Contractor's account except for the expenses of the Inspector's. The Project Manager/Inspector,				
STAG	HERMAL POWER PROJECT HERMAL POWER PROJECT SECTION VI, PART-C PC PACKAGE TECHNICAL SPECIFICATIONS GENERAL TECHNICAL REQUIREMENTS 39 OF 119				

CLAUSE NO.	GENE	RAL TECHNICAL REQUIRE	MENTS	एनरीपीसी NTPG
	attend such tests wind date on which the contractor made in the inspector	ng of the tests is virtually wa thin fifteen (15) days (for dom equipment is noticed as beir r may proceed with test whic or's presence and he shall fort st reports in two (2) copies.	estic) / 45 days (for foreing ready for test/inspections to shall be deemed to	eign) of the ction failing have been
25,04,00	days (for foreign) fro to the Contractor, o workmanship which Contractor shall giv modifications that m writing to the Project	er or Inspector shall within fifter the date of inspection as derived any objection to any drawing is in his opinion not in access due consideration to such any be necessary to meet the Manager/Inspector giving reamply with the contract.	efined herein give noticings and all or any equicordance with the contobjections and shall estaid objections or sha	e in writing pment and ract. The ither make
25.05.00	When the factory tests have been completed at the Contractor's or subcontractor's works, the Project Manager /Inspector shall issue a certificate to this effect fifteen (15) days after completion of tests but if the tests are not witnessed by the Project Manager /Inspectors, the certificate shall be issued within fifteen (15) days of the receipt of the Contractor's test certificate by the Project Manager /Inspector. Failure on the part of Project Manager /Inspector to issue such a certificate shall not prevent the Contractor from proceeding with the works. The completion of these tests or the issue of the certificates shall not bind the Employer to accept the equipment should it, on further tests after erection be found not to comply with the contract.			
25.06.00	In all cases where the contract provides for tests whether at the premises or works of the Contractor or any sub-contractor, the Contractor, except where otherwise specified shall provide free of charge such items as labour, material, electricity, fuel, water, stores, apparatus and instruments as may be reasonably demanded by the Project Manager /Inspector or his authorised representatives to carry out effectively such tests on the equipment in accordance with the Contractor and shall give facilities to the Project Manager/Inspector or to his authorised representative to accomplish testing.			
25.07.00	The inspection by Project Manager / Inspector and issue of Inspection Certificate thereon shall in no way limit the liabilities and responsibilities of the Contractor in respect of the agreed Quality Assurance Programme forming a part of the contract.			
25.08.00	To facilitate advance planning of inspection in addition to giving inspection notice as specified at clause no. 25.03.00 - of this chapter, the Contractor shall furnish quarterly inspection programme indicating schedule dates of inspection at Customer Hold Point and final inspection stages. Updated quarterly inspection plans will be made for each three consecutive months and shall be furnished before beginning of			
STAG	SIPAT SUPER THERMAL POWER PROJECT TECHNICAL SPECIFICATIONS STAGE-III (1X800 MW) EPC PACKAGE TECHNICAL SPECIFICATIONS SECTION VI, PART-C GENERAL TECHNICAL REQUIREMENTS 40 OF 119			

CLAUSE NO.	GENE	RAL TECHNICAL REQUIRE	MENTS	एनदीपीमी NTPC		
	each calendar month	٦.				
25.09.00	All inspection, measuring and test equipment used by contractor shall be calibrated periodically depending on its use and criticality of the test/measurement to be done. The Contractor shall maintain all the relevant records of periodic calibration and instrument identification, and shall produce the same for inspection by NTPC. Wherever asked specifically, the contractor shall re-calibrate the measuring/test equipment in the presence of Project Manager / Inspector.					
25.10.00	ASSOCIATED DOC	UMENT FOR QUALITY ASSI	JRANCE PROGRAMM	E		
25.10.01	List of items requiring QAI-P-01/F3-R0 (An	g quality plan and sub supplien nexure-III).	r approval. Format No.:	QS-01-		
25.10.02	Status of items requiat Annexure-IV.	Status of items requiring Quality Plan and sub supplier approval. Format enclosed at Annexure-IV.				
25.10.03	Field Welding Sched	lule Format enclosed at Anne :	xure-V.			
25.10.04	Main contractor eva at Annexure VII.	Main contractor evaluation report (MCER) and Sub vendor Questionnaire enclosed at Annexure VII.				
25.10.05	QA&I modalities and VIII.	d QA Co-ordination procedur	e (QACP) enclosed at	Annexure-		
25.11.00	TESTING OF MAJOR DESIGN FEATURES:					
	The major design features of the system shall be demonstrated by the Contractor at the Contractor's works, or any other place mutually agreed within Six months from the date of Sub-QR/Provenness approval. These are the system function tests, which have a major impact on the detailed system design & finalization of important engineering documents like configuration, functional grouping, BOM etc., but do not require a fully engineered system for conductance. Bidder shall identify these features & include detailed test procedures in the Sub-QR/Provenness proposal, which shall be finalized during discussions with the bidder. The developments and any augmentation of standard features undertaken by the Bidder to fulfill the various specification requirements, shall also be tested during these major design tests. This shall include but not be limited to the following.					
	a) System accu Part-B.	racy tests of DDCMIS for the	various type of inputs i	dentified in		
	b) Loop reaction	n time for sample loops/ logics				
	c) SOE function	nality tests.				
	d) Server changeover.					
STAGE-III (1X800 MW) SECTION VI. PART-C		PAGE 41 OF 119				