

TENDER SPECIFICATION

BHEL: PSSR: SCT: 1434

FOR

Handling at Site Stores / Storage yard, Transportation to Site of Work, Erection, Testing and Commissioning of Electrostatic Precipitator and ducts including Supply and Application of Final Painting for unit 2 of 1 X 600MW set

at

**Kakatiya Thermal Power Project, Stage-II
Chelpur Village, Warangal Dist,
Andhra Pradesh**

VOLUME –I BOOK - I

TECHNOCOMMERCIAL BID (Book I & II)

Book-I consists of

- o Notice Inviting Tender,
- o Volume-IA : Technical Conditions of Contract

Book-II consists of

- o Volume-IB : Special conditions of Contract,
- o Volume-IC : General conditions of Contract
- o Volume-ID : Forms & Procedures



BHARAT HEAVY ELECTRICALS LIMITED

(A Government of India Undertaking)

Power Sector – Southern Region

690, Anna Salai, Nandanam, Chennai – 600 035.

BHARAT HEAVY ELECTRICALS LIMITED
(A Government of India Undertaking)
Power Sector, Southern Region
690, Anna Salai, Nandanam, Chennai – 35

Tender Specification No. BHEL: PSSR: SCT: 1434

for

Handing at Site Stores / Storage yard, Transportation to Site of Work, Erection, Testing and Commissioning of Electrostatic Precipitator and its Auxiliaries including supply and application of final painting for unit -2 of 1x600MW set at Kakatiya TPP, Stage II, Chelpur Village, Warangal Dist, AP

One set of Tender documents consisting of

- 1) TECHNOCOMMERCIAL BID - 2 copies
- 2) PRICE BID - 2 copies

Book Sl no

Issued to
M/s

Refer NIT for Last date of submission

Please note this tender document is not transferable

For and on behalf of
BHARAT HEAVY ELECTRICALS LIMITED


ADDL GENERAL MANAGER / CONTRACTS

Place: Chennai -35
Date:

Rev 00
6th July
2010

NOTICE INVITING TENDER

Bharat Heavy Electricals Limited



NOTICE INVITING TENDER (NIT)

NOTE: BIDDER MAY DOWNLOAD FROM WEB SITES
OR
PURCHASE TENDERS FROM THIS OFFICE ALSO

=====

To

Dear Sir/Madam

Sub : NOTICE INVITING TENDER

Sealed offers in two part bid system are invited from reputed & experienced bidders (meeting [PRE QUALIFICATION CRITERIA](#) as mentioned in Annexure-I) for the subject job by the undersigned on the behalf of BHARAT HEAVY ELECTRICALS LIMITED as per the tender document. Following points relevant to the tender may please be noted and complied with.

1.0 Salient Features of NIT

Sl. No	ISSUE	DESCRIPTION	
i	TENDER NUMBER	BHEL PSSR SCT 1434	
ii	Broad Scope of job	Handing at Site Stores / Storage yard, Transportation to Site of Work, Erection, Testing and Commissioning of Electrostatic Precipitator and its Auxiliaries including supply and application of final painting for unit -2 of 1x600MW set at Kakatiya TPP, Stage II, Chelpur Village, Warangal Dist, AP	
iii	DETAILS OF TENDER DOCUMENT		
a	Volume-IA	<u>Technical</u> Conditions of Contract (TCC) consisting of Scope of work, Technical Specification, Drawings, Procedures, Bill of Quantities, Terms of payment, etc	Applicable
b	Volume-IB	Special Conditions of Contract (SCC)	Applicable
c	Volume-IC	General Conditions of Contract (GCC)	Applicable
d	Volume-ID	Forms and Procedures	Applicable
e	Volume-II	Price Schedule (Absolute value).	Applicable

iv	Issue of Tender Documents	<u>1. Sale from BHEL PSSR Regional office at :Chennai</u> Start : 06-01-2011 Closes: 25-01-2011 , Time :15.00 Hrs 2.From BHEL website (www.bhel.com) Tender documents can however be downloaded from website till due date of submission	Applicable
v	DUE DATE & TIME OF OFFER SUBMISSION	Date : 27 /01/ 2011 , Time :15.00Hrs Place : <u>BHEL PSSR :Chennai</u> Tenders can be submitted through representative / in person at SCT Dept, BHEL PSSR, Chennai.	Applicable
vi	OPENING OF TENDER	Date : 27 /01/ 2011, Time :15.30Hrs Notes: (1) In case the due date of opening of tender becomes a non-working day, tenders shall be opened on next working day at the same time. (2) Bidder may depute representative to witness the opening of tender	Applicable
vii	EMD AMOUNT	Rs 2,00,000/- (Rupees Two Lakhs Only)	Applicable
viii	COST OF TENDER	Rs 2,000/-.	Applicable
ix	LAST DATE FOR SEEKING CLARIFICATION	At least 7 days before the due date of offer submission or two days before the scheduled date of pre-bid meeting whichever is earlier Along with soft version also, addressing to undersigned & to others as per contact address given below	Applicable
x	Schedule of Pre Bid Discussion (PBD)	<u>Date: 20/01/2011, Time11.00AM</u> at BHEL:PSSR:Chennai-35	Applicable.

xi	INTEGRITY PACT & DETAILS OF INDEPENDENT EXTERNAL MONITOR (IEM)	Bidders shall enter into an Integrity Pact (IP) with BHEL as per format given at Volume 1D Formats of this tender. The bidders are required to return this Integrity Pact (IP) along with Techno Commercial Bid duly signed and stamped by the authorized signatory who signs the bid. It may be noted that only those bidders who have entered into such an IP with BHEL would be competent to participate against this tender .i.e. entering into this pact is a preliminary qualifications for the bidders. The Independent External Monitor against this NIT shall be Shri ...	<i>Not Applicable</i>
xii	Latest updates	Latest updates on the important dates, Amendments, Correspondences, Corrigenda, Clarifications, Changes, Errata, Modifications, Revisions, etc to Tender Specifications will be hosted in BHEL webpage (www.bhel.com --> Tender Notifications →View Corrigendums) and not in the newspapers. Bidders to keep themselves updated with all such information	

2.0 The offer shall be submitted as per the instructions of tender document and as detailed in this NIT. Bidders to note specifically that all pages of tender document, including these NIT pages of this particular tender together with subsequent correspondences shall be submitted by them, duly signed & stamped on each page, as part of offer. Rates/Price including discounts/rebates, if any, mentioned anywhere/in any form in the techno-commercial offer other than the Price Bid, shall not be entertained.

3.0 Unless specifically stated otherwise, bidder shall remit cost of tender and courier charges if applicable, in the form of Demand Draft drawn in favour of Bharat Heavy Electricals Ltd, payable at Power Sector Regional HQ at Chennai issuing the Tender, along with techno-commercial offer. Bidder may also choose to deposit the Tender document cost by cash at the Cash Office as stated above against sl no iv of 1, on any working day; and in such case copy of Cash receipt is to be enclosed with the Techno Commercial offer. Sale of tender Documents shall not take place on National Holidays, holidays declared by Central or State Governments and BHEL PS HQ at Chennai, Sundays and second/ last Saturdays

4.0 Unless specifically stated otherwise, bidder shall deposit EMD through Demand Draft/Pay Order in favour of Bharat Heavy Electricals Ltd, payable at Chennai. For other details and for 'One Time EMD' please refer General Conditions of Contract.

5.0 Procedure for Submission of Tenders: The Tenderers must submit their Tenders to Officer inviting Tender, as detailed below:

- PART-I consisting of 'PART-I A (Techno Commercial Bid)' & 'PART-I B (EMD/COST of TENDER)' in two separate sealed and superscribed envelopes (ENVELOPE-I & ENVELOPE-II)
- PART-II (Price Bid) – in sealed and superscribed envelope (ENVELOPE-III)
- One set of each document shall be retained by the bidder for their reference.

6.0 The contents for ENVELOPES and the superscription for each sealed cover / Envelope are as given below. (All pages to be signed and stamped)

Sl no	Description	Remarks
	Part-I A	
	<u>ENVELOPE – I superscribed as :</u> PART-I (TECHNO COMMERCIAL BID) TENDER NO : NAME OF WORK : PROJECT: DUE DATE OF SUBMISSION: CONTAINING THE FOLLOWING:-	
i.	Covering letter/Offer forwarding letter of Tenderer.	
ii.	Duly filled-in 'No Deviation Certificate' as per prescribed format to be placed after document under sl no (i) above. <u>Note:</u> a. In case of any deviation, the same should be submitted separately for technical & commercial parts, indicating respective clauses of tender against which deviation is taken by bidder. The list of such deviation shall be placed after document under sl no (i) above. It shall be specifically noted that deviation recorded elsewhere shall not be entertained.	

	b. BHEL reserves the right to accept/reject the deviations without assigning any reasons, and BHEL decision is final and binding. i). In case of acceptance of the deviations, appropriate loading shall be done by BHEL ii). In case of unacceptable deviations, BHEL reserves the right to reject the tender.	
iii.	Supporting documents/ annexure/ schedules/ drawing etc as required in line with Pre-Qualification criteria. It shall be specifically noted that all documents as per above shall be indexed properly and credential certificates issued by clients shall distinctly bear the name of organization, contact ph no, FAX no, etc.	
iv.	All Amendments / Correspondences / Corrigenda / Clarifications / Changes / Errata etc pertinent to this NIT.	
v.	Integrity Pact Agreement (Duly signed by the authorized signatory)	If applicable
vi.	Duly filled-in annexures, formats etc as required under this Tender Specification/NIT	
vii.	Notice inviting Tender (NIT)	
viii.	Volume – I A : <u>Technical</u> Conditions of Contract (TCC) consisting of Scope of work, Technical Specification, Drawings, Procedures, Bill of Quantities, Terms of payment, etc	
ix.	Volume – I B : Special Conditions of Contract (SCC)	
x.	Volume – I C : General Conditions of Contract (GCC)	
xi.	Volume – I D : Forms & Procedures	
xii.	Volume – II (UNPRICED – without disclosing rates/price, but mentioning only 'QUOTED' or 'UNQUOTED' against each item	
xiii.	Any other details preferred by bidder with proper indexing.	

	PART-I B	
	<u>ENVELOPE – II superscribed as:</u> PART-I (EMD/COST of TENDER) TENDER NO : NAME OF WORK : PROJECT: DUE DATE OF SUBMISSION: CONTAINING THE FOLLOWING:-	
i.	1. Earnest Money Deposit (EMD) in the form as indicated in this Tender	

	<u>OR</u>	
	Documentary evidence for 'One Time EMD' with BHEL PSSR Chennai	
	2. Cost of Tender (Demand Draft or copy of Cash Receipt as the case may be)	

	PART-II	
	PRICE BID consisting of the following shall be enclosed	
	<u>ENVELOPE-III</u> superscribed as: PART-II (PRICE BID) TENDER NO : NAME OF WORK : PROJECT: DUE DATE OF SUBMISSION: CONTAINING THE FOLLOWING	
i	Covering letter/Offer forwarding letter of Tenderer enclosed in Part-I	
ii	Volume II – PRICE BID (Duly Filled in Schedule of Rates – rate/price to be entered in words as well as figures)	
	OUTER COVER	
	ENVELOPE-IV (MAIN ENVELOPE / OUTER ENVELOPE) superscribed as: TECHNO-COMMERCIAL BID, PRICE BID & EMD TENDER NO: NAME OF WORK: PROJECT: DUE DATE OF SUBMISSION: CONTAINING THE FOLLOWING:	
i	o Envelopes I o Envelopes II o Envelopes III	

SPECIAL NOTE: All documents/ annexures submitted with the offer shall be properly annexed and placed in respective places of the offer as per enclosure list mentioned in the covering letter. BHEL shall not be responsible for any missing documents.

7.0 No Deviation with respect to tender clauses and no additional clauses/ suggestions/ in Techno-commercial bid/ Price bid shall normally be considered by BHEL. Bidders are requested to positively comply with the same.

8.0 BHEL reserves the right to accept or reject any or all Offers without assigning any reasons thereof. BHEL also reserves the right to cancel the Tender wholly or partly without assigning any reason thereof. Also BHEL shall not entertain any correspondence from bidders in this matter (except for the refund of EMD).

9.0 Assessment of Capacity of Bidders: (Shall be applicable for all Bid Evaluation from 1st APR 2011)

Bidders capacity for executing the job under tender shall be assessed as per the following:

I. Assigning Weightages (A) for Similar Jobs Under-Execution:

Weightages shall be worked out and assigned based on the average number of Similar Works under execution including works yet to be commenced by the agency, in the following manner:

i). Number of Similar Jobs

- a) No. of jobs in BHEL, PSER : Say 'J'
- b) No. of jobs in BHEL, PSSR : Say 'K'
- c) No. of jobs in BHEL, PSWR : Say 'L'
- d) No. of jobs in BHEL, PSNR : Say 'M'
- e) No. of jobs with other customers* : Say 'N' (*: Other than BHEL PSER, PSSR, PSWR & PSNR)
- f) Average No. of Jobs is 'P' = (J+K+L+M+N) divided by 5

ii) Weightage "A" assigned to bidders based on Average Number of jobs "P":

- a) If 'P' = 0-1, "A" will be equal to '3'
- b) If 'P' = 2-3, "A" will be equal to '2'
- c) If 'P' = 4-5, "A" will be equal to '1'
- d) If 'P' is Above 5, "A" will be equal to '0'

II. Weightage "B" for Quarterly Performance Reports of Vendors: This shall be based on the averages of the net weighted score obtained by the bidder for the jobs under execution (excluding works not commenced) for the quarter previous to the last quarter reckoned from the date of latest due date of submission, in all four Regions i.e BHEL PSER, PSSR, PSWR & PSNR, in the following manner.

i). Ratings by Power Sector Region:

a) PS ER's Rating 'Rer' = $(X_1 + X_2 + \dots + X_n)$

b) PS WR's Rating 'Rwr' = $(X_1 + X_2 + \dots + X_n)$

c) PS SR's Rating 'Rsr' = $(X_1 + X_2 + \dots + X_n)$

d) PS NR's Rating 'Rnr' = $(X_1 + X_2 + \dots + X_n)$

Over all Power Sector Region Rating ' R_{BHEL} ' = $(Rer + Rwr + Rsr + Rnr)$
divided by $(Ner + Nwr + Nsr + Nnr)$

(where " $X_1, X_2, X_3, \dots, X_n$ " is the net weighted score obtained by the bidder as per the "Evaluation of Contractor Performance (Quarterly)" against the various contracts 'N' under execution in the respective Region).

ii) Weightage "B" assigned to bidders based on Overall Power Sector Rating (R_{BHEL}):

a) If R_{BHEL} is 80% and above, "B" will be equal to '6'

b) If R_{BHEL} is $> 70\% < 80\%$, "B" will be equal to '5'

c) If R_{BHEL} is $> 60\% < 70\%$, "B" will be equal to '4'

d) If R_{BHEL} is $\leq 60\%$, "B" will be equal to '0'

III. Evaluation of Bidders capacity to execute the job under tender:

shall be based on the sum of scores obtained in 'A' and 'B', as below:

a) 6 or above : Considered 'Qualified' for the job under tender

b) Less than 6: Considered 'NOT Qualified' for the job under tender

IV. Explanatory note:

a) Similar work means Boiler or Turbine or Civil or Electrical or CI, etc as detailed in the scope irrespective of rating of Plant

b) Quarter shall be as per the quarter defined in the "Evaluation of Contractor performance (Quarterly)". For contracts where annexed Quarterly Evaluation performance was not part of the contract, 'Quarterly Performance Reports' previous to the last quarter reckoned from the date of latest due date of submission, given by the respective project site against the contract will be the basis for evaluation.

c) Vendors who are not executing any jobs presently in the Region and first timers to the Region, may be considered subject to satisfying all other tender conditions

- d) 'Under execution' shall mean works in progress upto Boiler Steam Blowing (for Boiler and Auxilliaries) or Synchronisation (for all other jobs including Civil) shall be considered.

- 10.0 Since the job shall be executed at site, bidders must visit site/ work area and study the job content, facilities available, availability of materials, prevailing site conditions including law & order situation etc before quoting for this tender. They may also consult this office before submitting their offers, for any clarifications regarding scope of work, facilities available at sites or on terms and conditions. No additional claim shall be entertained by BHEL in future, on account of non-acquaintance of above.
- 11.0 For any clarification on the tender document, the bidder may seek the same in writing or through e-mail, as per specified format, within the scheduled date for seeking clarification, from the office of the undersigned. BHEL shall not be responsible for receipt of queries after due date of seeking clarification due to postal delay or any other delays. Any clarification / query received after last date for seeking clarification may not be normally entertained by BHEL and no time extension will be given.
- 12.0 BHEL may decide holding pre-bid discussion [PBD] with all intending bidders as per date indicated in the NIT. The bidder shall ensure participation for the same at the appointed time, date and place as may be decided by BHEL. Bidders shall plan their visit accordingly. The outcome of pre-bid discussion (PBD) shall also form part of tender.
- 13.0 In the event of any conflict between requirement of any clause of this specification/ documents/ drawings/data sheets etc or requirements of different codes/standards specified, the same to be brought to the knowledge of BHEL in writing for clarification before due date of seeking clarification (whichever is applicable), otherwise, interpretation by BHEL shall prevail. Any typing error/missing pages/ other clerical errors in the tender documents, noticed must be pointed out before pre-bid meeting/submission of offer, else BHEL's interpretation shall prevail.
- 14.0 Unless specifically mentioned otherwise, bidder's quoted price shall deemed to be in compliance with tender including PBD.
- 15.0 Bidders shall submit Integrity Pact Agreement (Duly signed by authorized signatory who signs in the offer), if applicable, along with techno-commercial bid. This pact shall be considered as a preliminary qualification for further participation. The names and other details of Independent External Monitor (IEM) for the subject tender is as given at point (xi) of 1 above.

- 16.0 The Bidder has to satisfy the Pre Qualifying Requirements stipulated for this Tender in order to be qualified. The Price Bids of only those bidders will be opened who will be qualified for the subject job on the basis of pre-qualification evaluation/ techno-commercial bids, approval/ acceptance of customer (as applicable), etc. and date of opening of price bids shall be intimated to only such bidders.
- 17.0 In case BHEL decides on a 'Public Opening', the date & time of opening of the sealed PRICE BID shall be intimated to the qualified bidders and in such a case, bidder may depute one authorised representative to witness the price bid opening. BHEL reserves the right to open 'in-camera' the 'PRICE BID' of any or all Unsuccessful / Disqualified bidders under intimation to the respective bidders.
- 18.0 Validity of the offer shall be for six months from the latest due date of offer submission (including extension, if any) or specified otherwise in SCC of tender.
- 19.0 BHEL reserves the right to decide the successful bidder on the basis of Reverse Auction process. In such case all qualified bidders will be intimated regarding procedure/ modality for Reverse Auction process prior to Reverse Auction and price will be decided as per the rules for Reverse Auction. .
- However, if reverse auction process is unsuccessful as defined in the RA rules/procedures, or for whatsoever reason, then the sealed 'PRICE BIDS' will be opened for deciding the successful bidder. BHEL's decision in this regard will be final and binding on bidder.
- 20.0 On submission of offer, further consideration will be subject to compliance to tender & qualifying requirement and customer's acceptance, as applicable.
- 21.0 In case the bidder is an "Indian Agent of Foreign Principals", 'Agency agreement has to be submitted along with Bid, detailing the role of the agent along with the terms of payment for agency commission in INR, along with supporting documents.
- 22.0 The bidders shall not enter into any undisclosed M.O.U. or any understanding amongst themselves with respect to tender.
- 23.0 In case Consortium Bidding is allowed as per Pre Qualifying Requirement, then Prime Bidder and Consortium Partner shall enter into Consortium Agreement. Validity period of Consortium Agreement shall be 6 months after which the same can be re validated.

'Stand alone' bidder cannot become a 'prime bidder' or a 'consortium bidder' in a consortium bidding. Prime bidder shall neither be a consortium partner to other prime bidder nor take any other consortium partners. However, consortium partner may enter into consortium agreement with other prime bidders. In case of non compliance, consortium bids of such Prime bidders will be rejected. .

- 24.0 The bidder shall submit documents in support of possession of 'Qualifying Requirements" duly self certified and stamped by the authorized signatory, indexed and properly linked in the format for PQR. In case BHEL requires any other documents/proofs, these shall be submitted immediately.
- 25.0 The bidder may have to produce original document for verification if so decided by BHEL.
- 26.0 Order of Precedence
In the event of any ambiguity or conflict between the Tender Documents, the order of precedence shall be in the order below:
- a. Amendments/Clarifications/Corrigenda/Errata etc issued in respect of the tender documents by BHEL
 - b. Notice Inviting Tender (NIT)
 - c. Price Bid
 - d. Technical Conditions of Contract (TCC)—Volume-1A
 - e. Special Conditions of Contract (SCC) —Volume-1B
 - f. General Conditions of Contract (GCC) —Volume-1C
 - g. Forms and Procedures —Volume-1D

For BHARAT HEAVY ELECTRICALS LTD

AGM /SCT

Enclosure

- 01. Annexure-1: Pre Qualifying criteria.
- 02. Annexure-2: Check List.
- 03 Other Tender documents as per this NIT.

ANNEXURE - 1**PRE QUALIFYING CRITERIA**

JOB	Handing at Site Stores / Storage yard, Transportation to Site of Work, Erection, Testing and Commissioning of Electrostatic Precipitator and its Auxiliaries including supply and application of final painting for unit -2 of 1x600MW set at Kakatiya TPP, Stage II, Chelpur Village, Warangal Dist,AP
TENDER NO	BHEL PSSR SCT 1434

Sl. No	PRE QUALIFICATION CRITERIA	Bidders claim in respect of fulfilling the PQR Criteria	
		Name and Description of qualifying criteria	Page no of supporting document
A	Submission of Integrity Pact duly signed (if applicable)	Not applicable	
B	Assessment of Capacity of Bidder to execute the work as per sl no 9 of NIT (if applicable)	<u>Shall be applicable for Bid Evaluation from 1st APR 2011</u>	
C	<u>Technical</u> a) The bidder should have executed erection and commissioning of at least one unit of 190MW or above capacity Boiler or ESP works in a Thermal Power plant the last seven years. Note: The term “executed “means the unit was synchronized.		
D 1	<u>Financial</u> TURNOVER Bidders must have achieved an average annual financial turnover (audited) of Rs 2.40Crores or more over last three financial years i.e., 2007-08, 2008-09 & 2009-10		

2	NETWORTH Net worth of the bidder based on the latest audited accounts as furnished for 'D1' above should be positive.		
3	PROFIT Bidders must have earned cash profit in any one of the three financial years in the last three years defined in 'D1' above		
E	Approval of Customer (if applicable) Note: Names of bidders who stand qualified after compliance of criteria A to D shall be forwarded to customer for their approval. Price bid of only those bidders shall be opened who are approved by customer.	Not Applicable	
F	Consortium criteria (if applicable)	Not applicable	
	Explanatory Notes for QR 'A' 1.The word 'executed' means the bidder should have achieved the criteria specified in the QR even if the total contract has not been completed or closed 2.Bidder to submit Audited Balance Sheet and Profit and Loss Account for the respective years as given above along with all annexures		

BIDDER SHALL SUBMIT ABOVE PRE-QUALIFICATION CRITERIA FORMAT, DULY FILLED-IN, SPECIFYING RESPECTIVE ANNEXURE NUMBER AGAINST EACH CRITERIA AND FURNISH RELEVANT DOCUMENT IN THE RESPECTIVE ANNEXURES IN THEIR OFFER INCLUDING THE AUDITED BALANCE SHEET WITH PROFIT AND LOSS ACCOUNT DETAILS FOR THE THREE YEARS PERIOD SPECIFIED ABOVE.

ANNEXURE - 2

CHECK LIST

NOTE: - Tenderers are required to either fill in or submit separately the following details

1	Name and Address of the Tenderer		
2	Details about type of the Firm / Company		
3	Details of Contact person for this Tender Name : Mr/Ms Designation: Telephone No: Mobile No: email id: Fax No:	Details of alternate Contact person for this Tender Name : Mr/Ms Designation: Telephone No: Mobile No: email id: Fax No:	
4	EMD DETAILS	DD No: Date : Bank : Amount: <u>Please tick (√) whichever applicable:-</u> ONE TIME EMD / ONLY FOR THIS TENDER	
5	Validity of offer	To be valid for six months from due date	
		APPLICABILITY	BIDDER REPLY
6	Whether the format for compliance with PRE QUALIFICATION CRITERIA (ANNEXURE-I) is understood and filled with proper supporting documents referenced in the specified format	Applicable / Not applicable	YES / NO
7	Audited profit and Loss Account for the last three years submitted	Applicable / Not applicable	YES/NO
8	Copy of PAN Card submitted	Applicable / Not applicable	YES/NO
9	Whether all pages of the Tender documents including annexures, appendices etc are read understood and signed	Applicable / Not applicable	YES/NO
10	Integrity Pact	Applicable / Not applicable	YES/NO
11	Declaration by Authorised Signatory	Applicable / Not applicable	YES/NO
12	No Deviation Certificate	Applicable / Not applicable	YES/NO

13	Declaration confirming knowledge about Site Conditions	Applicable / Not applicable	YES/NO
14	Declaration for relation in BHEL	Applicable / Not applicable	YES/NO
15	Non Disclosure Certificate	Applicable / Not applicable	YES/NO
16	Bank Account Details for E-Payment	Applicable / Not applicable	YES/NO
16	Capacity Evaluation of Bidder for current Tender	Applicable / Not applicable	YES/NO
17	Tie Ups/Consortium Agreement are submitted as per format	Applicable / Not applicable	YES/NO
18	Power of Attorney for Submission of Tender/Signing Contract Agreement	Applicable / Not applicable	YES/NO
19	Analysis of Unit rates	Applicable / Not applicable	YES/NO
20	Unquoted price bid submitted or not	Applicable / Not applicable	YES/NO

NOTE: STRIKE OFF 'YES' OR 'NO', AS APPLICABLE

DATE:


AUTHORISED SIGNATORY
(With Name, Designation and Company seal)

Rev 00
6th July
2010

VOLUME – IA Part I & II TECHNICAL CONDITIONS OF CONTRACT (TCC)

(Document No PS:MSX:TCC)

BHARAT HEAVY ELECTRICALS LIMITED



TECHNICAL CONDITIONS OF CONTRACT (TCC)

CONTENTS

SI no	DESCRIPTION	Chapter	No. of Pages
Vol I A	Part-I: Contract specific details		
1	Project Information	Chapter-I	01
2	Scope of works	Chapter-II	01
3	Facilities in the scope of Contractor / BHEL (Scope Matrix)	Chapter-III	05
4	T&Ps and MMEs to be deployed by Contractor	Chapter-IV	01
5	T&Ps and MMEs to be deployed by BHEL on sharing basis	Chapter-V	02
6	Time Schedule	Chapter-VI	02
7	Terms of Payment	Chapter-VII	02
8	Taxes and other Duties	Chapter-VIII	02
9	Weight schedule	Chapter-IX	04
10	General	Chapter-X	03
11	Foundation & Grouting	Chapter-XI	02
12	Material Handling & storage	Chapter-XII	01
13	Erection	Chapter-XIII	06
14	Progress of work	Chapter-XIV	02
15	Welding	Chapter-XV	01
16	Testing & Commissioning	Chapter-XVI	04
17	Painting	Chapter-XVII	03
Vol IA	Part-II: Technical specifications		
1	Reverse auction procedure	Chapter-1	02
2	Painting scheme	Chapter-2	05
3			
4			
5			
6			
7			
8			
9			
10			
11			

TECHNICAL CONDITIONS OF CONTRACT (TCC)

PART – I CHAPTER – I PROJECT INFORMATION

1	Name of the Project	Kakatiya Thermal Power Project
2	Station Capacity	1 x 600 MW (Coal based)
3	Owner	Andhra Pradesh Power Generation Corporation Limited (APGENCO)
4	Consultant	M/s DESEIN
5	Site Location	Chelpur Village, Ghanur Mandal, Warangal District (½ Km from State High way) and 10 Km from Bhoopalapally
6	Latitude	18 23" N
7	Longitude	79 51"E
8	MSL	180 M
9	Nearest Highway	SH-7 (Connecting Parkal with Mahadevpur)
10	Nearest Town / City	Warangal 65 Kms South East
11	Nearest Railway Station	1. Uppal Railway station on SCR & 45 Kms from site 2. Warangal Railway station of SCR 65 Kms from Site
12	Nearest Air port	240 Kms (Hyderabad)
13	Metrological Data	
	A) Temperature	
	i. Average Max Temperature	34.5 Deg C
	ii. Average Min Temperature	22.3 Deg C
	iii. Highest Max Temperature	45.7 Deg C
	iv. Lowest Minimum Temperature	9.0 Deg C
	v. Temperature to be considered for design of Electrical Equipments / Devices	50 Deg C
	B) Relative Humidity average	55%
	C) Rainfall (Average Annual)	1005 mm
	D) Wind Data / Basic Speed	47 M / Sec
	E) Seismic Data	Zone II

TECHNICAL CONDITIONS OF CONTRACT (TCC)

14	Languages spoken in the region	English, Telugu
15	Language for communication with Sub-Contractor / Vendors	English
16	Tropicalisation	All Equipments supplied against this specification shall be given tropical and fungicidal treatment in view of climatic conditions prevailing at site
17	Supply Voltage	240 V AC for Lighting

TECHNICAL CONDITIONS OF CONTRACT (TCC)

PART – I CHAPTER – II SCOPE OF WORKS

- 1.2.1 The scope of work includes Handling at Site Stores / Storage yard, Transportation to Site of Work, Erection, Testing and Commissioning of Electrostatic Precipitator and its Auxiliaries including supply and application of final painting for unit -2 of 1x600MW set at Kakatiya TPP, Stage II, Chelpur Village, Warangal Dist,AP

The scope of the work will comprise of but not limited to the following:

- 1.2.1.1 Receipt of materials / component to be erected by the contractor, loading and transportation from the storage yard to the project site, stacking, storage and preservation.
- 1.2.1.2 Preassembly, Erection, Testing, Commissioning, Trial operation and reliability operation of equipment.
- 1.2.1.3 Final painting including supply of paints.

1.2.2 INSULATION:

With respect to insulation, it shall be limited to only the application of insulation for the inner roof of ESP including fixing components. The insulation materials will be supplied by BHEL.

1.2.3 PAINTING

The scope of work shall include supply and application of final painting for all the components under the scope of work.

Note:

FOR FURTHER DETAILED SCOPE OF WORKS REFER
RELEVANT CHAPTERS IN THIS BOOK

TECHNICAL CONDITIONS OF CONTRACT (TCC)

PART – I CHAPTER – III FACILITIES IN THE SCOPE OF CONTRACTOR / BHEL (SCOPE MATRIX)

Sl.No	Description	Scope to be taken care by		Remarks
		BHEL	Bidder	
1.3.1.1.0	ESTABLISHMENT			
1.3.1.1.1	FOR CONSTRUCTION PURPOSE:			
A	Open space for office	Yes		
B	Open space for storage	Yes		
C	Construction of bidder's office, canteen and storage building including supply of materials and other services		Yes	
D	Bidder's all office equipments, office / store / canteen consumables		Yes	
E	Canteen facilities for the bidder's staff, supervisors and engineers etc		Yes	
F	Fire fighting equipments like buckets, extinguishers etc		Yes	
G	Fencing of storage area, office, canteen etc of the bidder		Yes	
1.3.1.1.2	FOR LIVING PURPOSES OF THE BIDDER			
A	Open space		Yes	
B	Living accommodation		Yes	
1.3.1.2.0	ELECTRICITY			
1.3.1.2.1	Electricity For construction purposes (to be specified whether chargeable or free)			Free of charges
1.3.1.2.1.1	Single point source	Yes		
1.3.1.2.1.2	Further distribution for the work to be done which include supply of materials and execution		Yes	

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Sl.No	Description	Scope to be taken care by		Remarks
		BHEL	Bidder	
	PART I			
1.3.1.2.2	Electricity for the office, stores, canteen etc of the bidder which include:		Yes	
1.3.1.2.2.1	Distribution from single point including supply of materials and service		Yes	
1.3.1.2.2.2	Supply, installation and connection of material of energy meter including operation and maintenance		Yes	
1.3.1.2.2.3	Duties and deposits including statutory clearances for the above		Yes	
1.3.1.2.2.4	Living facilities for office use including charges		Yes	
1.3.1.2.2.5	Demobilization of the facilities after completion of works		Yes	
1.3.1.2.3	Electricity for living accommodation of the bidder's staff, engineers, supervisors etc on the above lines.(in case BHEL provides this facility, the scope should be given without ambiguity)		Yes	
1.3.1.3.0	WATER SUPPLY			Free of charges
1.3.1.3.1	For construction purposes:			
1.3.1.3.1.1	Making the water available at single point	Yes		
1.3.1.3.1.2	Further distribution as per the requirement of work including supply of materials and execution		Yes	
1.3.1.3.2	Water supply for bidder's office, stores, canteen etc			
1.3.1.3.2.1	Making the water available at single point		Yes	

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Sl.No	Description	Scope to be taken care by		Remarks
		BHEL	Bidder	
	PART I			
1.3.1.3.2.2	Further distribution as per the requirement of work including supply of materials and execution		Yes	
1.3.1.4.0	LIGHTING			
1.3.1.4.1	For construction work (supply of all the necessary materials) At office storage area At the preassembly area At the construction site /area		Yes	
1.3.1.4.2	For construction work (Execution of the lighting work / arrangements) At office storage area At the preassembly area At the construction site /area		Yes	
1.3.1.5.0	COMMUNICATION FACILITIES for site operations of the bidder	-		
1.3.1.5.1	Telephone, Fax, internet, intranet, email etc		Yes	
1.3.1.6.0	COMPRESSED AIR SUPPLY			
1.3.1.6.1	Supply of Compressor and all other equipments required for compressor & compressed air system including pipes, valves, storage systems etc	-	YES	
1.3.1.6.2	Installation of above system and operation & maintenance of the same	-	YES	
1.3.1.6.3	Supply of the all the consumables for the above system during the contract period		YES	

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Sl.No	Description	Scope to be taken care by		Remarks
		BHEL	Bidder	
	PART II			
	ERECTION FACILITIES			
1.3.2.1.0	Engineering works for construction			
1.3.2.1.1	Providing the erection drawings for all the equipments covered under this scope	Yes		
1.3.2.1.2	Drawings for construction methods		Yes	In consultation with BHEL
1.3.2.1.3	As-built drawings – wherever deviations observed and executed and also based on the decisions taken at site- example – routing of small bore pipes	Yes	Yes	”
1.3.2.1.4	Shipping lists etc for reference and planning the activities	Yes	Yes	”
1.3.2.1.5	Preparation of site erection schedules and other input requirements		Yes	”
1.3.2.1.6	Review of performance and revision of site erection schedules in order to achieve the end dates and other commitments		Yes	
1.3.2.1.7	Weekly erection schedules based on SI No 2.1.5		Yes	
1.3.2.1.8	Daily erection / work plan based on SI No 2.1.7		Yes	For daily monitoring meeting at site
1.3.2.1.9	Periodic visit of the senior official of the bidder to site to review the progress so that works are completed as per schedule. It is suggested this review by the senior official of the bidder should be done		Yes	

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Sl.No	Description	Scope to be taken care by		Remarks
		BHEL	Bidder	
	PART II			
	once in every two months.			
1.3.2.1.10	Preparation of preassembly bay		Yes	
1.3.2.1.11	Laying of racks for gantry crane if provided by BHEL or brought by the contractor/bidder himself			

1.3.3 OPEN SPACE:

Open space for building of temporary office shed, contractor's stores shed(s) will be provided free of hire charges. Contractor has to make his own arrangements for labour colony.

1.3.4 ELECTRICITY:

1.3.4.1 Electricity will be provided on free of charges at one single point. Further distribution is to be arranged by the bidder at his cost.

1.3.4.2 Any duty, deposit involved in getting the Electricity shall be borne by the bidder. As regards contractor's office shed also all such expenditure shall be borne by the contractor.

1.3.4.3 Provision of distribution of electrical power from the given single central common point to the required places with proper distribution boards, approved cables and cable laying including supply of all materials like cables, switch boards, pipes etc., observing the safety rules laid down by electrical authority of the State / BHEL / their customer with appropriate statutory requirements shall be the responsibility of the tenderer / contractor.

1.3.4.4 BHEL is not responsible for any loss or damage to the contractor's equipment as a result of variations in voltage / frequency or interruptions in power supply.

1.3.5 WATER:

1.3.5.1 Water for construction will be provided by BHEL free of charges at single point. Further distribution is to be arranged by the bidder at his cost.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

PART – I CHAPTER – IV

T&PS and MMEs TO BE DEPLOYED BY CONTRACTOR

The following minimum Tools & Plants shall be deployed by the contractor:

S no	Description	Capacity	Minimum quantity	Remarks
1	Mobile crane	8 T	01	
2	Crawler crane	18 T	01	
3	Crawler crane	75 T	01	

NOTE:

1. As there are bound to be interruptions in regular power supply, power cut/ load shedding in any construction site due to inherent power shortage in state; it shall be the responsibility of the contractor to have minimum numbers of diesel operated welding generator sets to get urgent and important work to go on without interruptions. The consumables required to operate the generators are to be provided by the bidders at their cost. No separate payment shall be made for this contingency.
2. Depending upon the nature of work and availability of facilities locally, contractor may have to arrange for a temporary workshop for facilitating uninterrupted progress of work
3. All the T&Ps required for this scope of work, except the T&Ps provided by BHEL are to be arranged by the contractor within the quoted rates.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

PART – I CHAPTER - V

T&Ps AND MMEs TO BE DEPLOYED BY BHEL ON SHARING BASIS

List of T&Ps to be made available by BHEL to contractor free of hire charges on sharable basis.

Sl. No	Description	Qty
1	Suitable higher capacity crane (above 75T capacity on need basis)	1 No.
2	Huck bolting Machine	2 Nos
3	Air blowers for Gas Tightness test (ESP and Duct)	2 Nos

Note:

1. BHEL Crane will be available to contractor only after the contractor deploys all of the minimum T & Ps mentioned in sl no 1 to 3 of the table in chapter IV.
2. BHEL may provide either BHEL owned cranes or hired cranes at the discretion of BHEL. BHEL will provide crane operators for the cranes in BHEL's scope.

In the event of providing BHEL Cranes:

Fuel has to be arranged by the bidder.

In the event of providing hired cranes:

The fuel charges shall be recovered as given below:

For 75 T crane: Rs. 120/hr

For 100T to 150 T crane: Rs 200 /hr

For Heavy duty crane (above 150T): Rs 250 /hr

3. Besides the T & P mentioned above, which is being made available to the contractor on free of hire charges, any additional crane and other T & P which may be required for successful and timely execution of the work covered within the scope of this tender shall be arranged and provided at site by the contractor at his cost.
4. All the distribution boards, connecting cables, hoses etc., and temporary connection work including electrical connections shall have to be arranged by the contractor at his cost.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

5. Cranes are only for erection purpose and shall not be available for material handling or transportation purpose. Contractor shall make their own arrangements for material transportation to erection site.
6. The contractor at his cost shall arrange for grouting of anchor points of T & Ps issued to him. Necessary grout materials are to be arranged by the contractor at his cost.
7. For the movement of cranes, it may become necessary to lay sleeper bed for obtaining safe approach for usage of equipment. It shall be the contractor's responsibility to lay necessary sleepers. Necessary sleepers shall be arranged by the contractor at his cost.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

PART – I CHAPTER-VI TIME SCHEDULE

1.6.1 TIME SCHEDULE

1.6.1.1 The entire work of Erection, Testing and Commissioning of Electrostatic Precipitator and its Auxiliaries including supply and application of final painting for unit -2 of 1x600MW set at Kakatiya TPP, Stage II, Chelpur Village, Warangal Dist, AP as detailed in the Tender Specification shall be completed within 30 (thirty) months from the date of commencement of work at site

1.6.1.2 During the total period of contract, the contractor has to carryout the activities in a phased manner as required by BHEL and the program of milestone events.

1.6.1.3 The erection work shall be commenced as may be stipulated in the letter of intent and shall be deemed as completed in all respect only when the unit is in operation. The decision of BHEL in this regard shall be final and binding of the contractor.

1.6.2 INITIAL MOBILISATION

Contractor shall mobilize necessary resources as per fax letter of Intent or as per directive of Construction manager.

1.6.3 COMMENCEMENT OF CONTRACT PERIOD

The date of start of work will be indicated in the “Letter of Intent” or “request letter for mobilization” by the BHEL engineer, which shall be recognized as “start of contract period”.

1.6.4 MOBILISATION FOR ERECTION, TESTING, ASSISTANCE FOR COMMISSIONING ETC.,

The activities for erection, testing etc shall be started as per directions of Construction manager of BHEL.

The contractor has to subsequently augment his resources in such a manner that following major milestones of erection & commission are achieved on specified schedules:

TECHNICAL CONDITIONS OF CONTRACT (TCC)

ESP ERECTION START : FEB'2011 (Expected)

ESP for KAKATIYA 1x600MW MILESTONES		
S No	Milestone activity	COMPLETION
1	Gas Distribution Test	23 rd month from date of commencement
2	Synchronization (with oil)	28 th month from date of commencement
3	Trial Operation Completion	30 th month from date of commencement

NOTE:

1.6.5 In order to meet above schedule in general, and any other intermediate targets set, to meet customer / project schedule requirements, contractor shall arrange & augment all necessary resources from time to time on the instructions of BHEL.

1.6.6 In case the project is to be advanced, the erection works in the scope of the contractor is to be advanced to meet the project requirement. No extra payment whatsoever shall be paid on this account.

1.6.5 CONTRACT PERIOD

The contract period for completion of entire work under scope shall be 30 (thirty) months from the "START OF CONTRACT PERIOD" as specified earlier.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

PART – I CHAPTER-VII TERMS OF PAYMENT

1.7 Terms of payment :

1.7.1 Progressive Payment against monthly running bills will be made upto 85 % of the value of the erected tonnage Pro rata as per CI no 1.7.1.1 to 1.7.1.8 of the following table.

1.7.2 Further 15 % payment on pro-rata basis common to all PG shall be released on achievement of the following stage / milestones events (as per CI no1.7. 2.1 to1.7.2.11 of the following table) for the tonnage erected.

CI No:	Description	ESP (rate schedule ID- 1A)	Non Pressure Parts (rate schedule ID -1B)
	PRO RATA PAYMENTS (85%)	%	%
1.7.1.1	ON PRE-ASSEMBLY WHEREVER APPLICABLE (IF NOT APPLICABLE, THIS PORTION SHALL BE CLUBBED WITH PLACEMENT IN POSITION)	15	15
1.7.1.2	PLACEMENT IN POSITION	20	10
1.7.1.3	ALIGNMENT	15	15
1.7.1.4	WELDING/BOLTING/FIXING	20	30
1.7.1.5	HANGERS & SUPPORTS ETC WHEREVER NECESSARY AS PER DRG	--	15
1.7.1.6	COMPLETION OF HOPPERS ALONG WITH ALL DOORS, HEATING ELEMENTS, POKING DOORS, ETC	5	--
1.7.1.7	COMPLETION OF INNER, OUTER ROOF INSULATOR HOUSING, RECTIFIER TRANSFORMERS, PENT HOUSE MONO RAILS, HOISTS ETC	5	--
1.7.1.8	ERECTION OF EMITTING AND COLLECTING RAPPING SYSTEM WITH ALL DRIVES	5	--
	TOTAL FOR PRO RATA PAYMENTS (TOTAL 85%)	85	85
	STAGE/MILESTONE PAYMENTS (15%)		

TECHNICAL CONDITIONS OF CONTRACT (TCC)

1.7.2.1	AIR & GAS TIGHTNESS TEST	1	5
1.7.2.2	GAS DISTRIBUTION TEST	1	--
1.7.2.3	CHARGING OF ESP FIELDS	4	--
1.7.2.4	Alkali Boil Out	--	1
1.7.2.5	Coal Firing	2	2
1.7.2.6	Trial Operation of Unit	1	2
1.7.2.7	Painting	2	1
1.7.2.8	Area cleaning, temporary structures cutting/removal and return of scrap	1	1
1.7.2.9	Punch List points/pending points liquidation	1	1
1.7.2.10	Material Reconciliation	1	1
1.7.2.11	Completion of Contractual Obligation	1	1
	TOTAL FOR STAGE / MILESTONE PAYMENTS (15%)	15	15
	TOTAL I + II	100	100

Note:

1. Recovery of Retention amount as per Cl. 2.22 of GCC.
2. RA bill payments as per Chapter-X of SCC
3. Payment for the first running bill will be released only on production of the following.
 - i. PF Regn. No.
 - ii. Labour License No.
 - iii. Workmen Insurance Policy No.
 - iv. Unqualified Acceptance for Detailed L.O.I.
 - v. Initial 50% Security Deposit.
 - vi. Rs 100 /- Stamp Paper for Preparation of Contract agreement.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

PART – I CHAPTER VIII TAXES AND OTHER DUTIES

1.8.0 TAXES

1.8.1 Value Added Tax (VAT) for the works

- 1.8.1.1 Price quoted shall be inclusive of VAT except service tax.
- 1.8.1.2 Notwithstanding the fact that this is only an erection service contract not involving any transfer of materials whatsoever and not attracting VAT liability, being labour oriented job work, for the purpose of VAT the contractor has to maintain the complete data relating to the expenditure incurred towards wages etc. in respect of the staff/workers employed for this work as also details of purchase of materials like consumables, spares etc., inter alia indicating the name of the supplier, address and VAT Registration No. and VAT paid for the purchases, etc
- 1.8.1.3 The bidder shall get registered with State VAT authorities and the registration certificate shall be forwarded to BHEL immediately after commencement of work. In case the bidder had already registered under respective State VAT, they must quote their registration Number and forward copy of Registration Certificate while submitting this tender.
- 1.8.1.4 The monthly/quarterly VAT return, duly incorporating the erection income from BHEL as turnover, should be submitted to BHEL at regular intervals with all annexure and details of payment of VAT (WCT).
- 1.8.1.5 You have to obtain VAT Clearance Certificate from the on concerned authorities as per the provisions of local VAT act, on completion of the project and submit along with the final bill.
- 1.8.1.6 The bidder shall quote very competitive price after taking into consideration of above points.

1.8.2.0 Service Tax

- 1.8.2.1. Price quoted shall be exclusive of Service Tax. The service tax as statutorily leviable and payable by the bidder under the provisions of service tax Law / Act shall be paid by BHEL as per bidder claim through various running bills. The bidder shall furnish proof of service tax registration with Central Excise Department specifying the name of services covered under this contract. Registration Certificate should also bear the endorsement for the premises from where the billing shall be done by the bidder on BHEL for this project. The bidder shall obtain prior consent of BHEL before billing the service tax amount.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

1.8.3.0 Other Taxes & Levies

1.8.3.1 Any other taxes and duties (except VAT & Service Tax) if any, as applicable, viz. Entry Tax, Octroi, Licenses, Deposits, Royalty, Stamp Duty, other charges / levies, etc. prevailing / applicable on the date of opening of technical bids and any variation thereof during the tenure of the contract are in the scope of bidder. In case BHEL is forced to pay any such taxes, BHEL shall have the right to recover the same from the bidder either from running bills or otherwise as deemed fit.

1.8.4.0 New Levies / Taxes

1.8.4.1 In case Government imposes any new levy / tax after award of the work during the tenure of the contract, BHEL shall reimburse the same at actual on submission of documentary proof of payment subject to the satisfaction of BHEL that such new levy / tax is applicable to this contract..

1.8.5.0 Statutory variations

1.8.5.1 Statutory variations are applicable only in the cases of Value Added Tax and Service Tax. The changes implemented by the Central / State Government in the VAT Act / Service Tax during the tenure of the contract viz. increase / decrease in the rate of taxes, applicability, etc. and its impact on upward revision / downward revision are to be suitably paid/ adjusted from the date of respective variation. The bidder shall give the benefit of downward revision in favour of BHEL. No other variations shall be allowed during the tenure of the contract.

1.8.6.0 Direct Tax

1.8.6.1 BHEL shall not be liable towards Income Tax of whatever nature including variations thereof arising out of this contract as well as tax liability of the bidder and their personnel. Deduction of tax at source at the prevailing rates shall be effected by BHEL before release of payment as a statutory obligation, unless exemption certificate is produced by the bidder. TDS certificate will be issued by BHEL as per the provisions of Income Tax Act.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

PART – I CHAPTER - IX WEIGHT SCHEDULE

1.9.1 WEIGHT SCHEDULE SUMMARY:-

KTPP STAGE -II 1 X 600 MW UNIT				
ESP WEIGHT SCHEDULE				
PG WISE				
SLNO.	PG	DESCRIPTION	WEIGHT IN MT	Rate schedule Id
1	39	EXTERNAL STRUCTURES	1466.00	1B
2	48	DUCTS (ESP)	1513.70	1B
3	57	DAMPERS & ACTUATORS	316.20	1B
4	79	ESP	5605.95	1A
5	89	ESP GALLERIES & ESP ROOF	120.74	1B
TOTAL WEIGHT (MT)			9022.59	

DETAIL WEIGHT SCHEDULE

<u>PGMA WISE WEIGHT SCHEDULE -KAKATIYA 1 x 600 MW</u>		
ESP		
PGMA	PGMA DESCRIPTION	Estimated Weight in Kgs
39-012	Foundation Materials I.D.Duct Supports	26100
39-101	Columns Frames Before ESP- Left	130500
39-102	Columns Frames Before ESP -Right	313200
39-141	Cols Frames Near ID Fan - Left	168300
39-142	Cols Frames Near ID Fan - Right	339300
39-150	Col Frames Betn I.D.Fan And Chimney	65200
39-300	Platforms - External Structure	208800
39-301	Struc and Platform For Fans	8500
39-302	Struc for Motor Hood Covering	8500
39-306	Fan Handling Structure For ID Fan	65200
39-700	HSFG Fasteners For PG 39	1400
39-810	Floor Grill	65200
39-820	Stairs	28100
39-850	Hand Rail and Hand Rail Posts	37700
TOTAL WEIGHT OF PG 39		1466000

TECHNICAL CONDITIONS OF CONTRACT (TCC)

48-462	Rect Duct Boiler Outlet To Elec Precp	359200
48-464	Expn Piecesboiler Outlet To Elec Precp	25400
48-465	Bof To Ep Ducting Supports	6000
48-468	Sq Duct,Blr Outlet F	173500
48-482	Rect Ducts-Elec Prptr/M.S To Inddraftf	120500
48-484	Expn Pieceselec Prptr/M.S To Inddraftf	25400
48-485	Supportsetcelec Prptr/M.S To Inddraftf	41600
48-486	Ep Spool Duct	173600
48-489	Sq Duct,Ep Interconn	82300
48-492	Rect Duct Ind Draft Fan To Chimney	413400
48-494	Expn Piecesind Draft Fan To Chimney	7600
48-495	I.D.System Duct Supports	85200
TOTAL WEIGHT OF PG 48		1513700
57460	GUILLOTENE GATE EP INL	57200
57466	PLATFORMS AND LADDERS	40000
57470	EP OUTLET GATE	57200
57480	ID FAN INLET GATE	76000
57490	GUILLOTENE GATE ID FAN	80000
57491	BLOWER WITH MOTOR	3800
57497	KNIFE GATE VALVE	2000
TOTAL WEIGHT OF PG 57		316200
79101	ROLL/SLIDE SUPPORTS	25908
79105	ESP-SUB-DELIVERY COMPO	520.844
79106	INSULATOR HOUSING AS	48978.66
79108	GAS DIST. ASSY	79898.804
79109	GD-RAPPING MECHANISM	15270.024
79110	GD_DRIVE ARRANGEMENT	858.216
79111	GAS SCREEN-EP	8336.6
79113	EMIT SYST SUSPENSION	17604.496
79114	SUPPORT INSULATORS	7680
79115	EMITTING ELECTRODES	24033.2
79116	EMIT ELECT RAPP MECH	39869.952
79117	DRIVE ARGT. FOR EMIT.	33319.44
79119	COL ELEC SUSPENSION	116976.176
79120	COLLECTING ELECTRODE	549984.156
79121	EMIT SYS FRAME-TOP	160677.946
79122	EMIT SYS FRAME BOTOM	167564.298
79123	INSPECTION DOORS	15123.644
79124	SHOCK BARS	96872.105
79125	COLL ELECT RAPP MECH	104811.712
79126	COLL ELEC RAPP DRIVE	6865.728
79128	ESP ROOF PANELS	151615.616

TECHNICAL CONDITIONS OF CONTRACT (TCC)

79131	GEARED MOTORS FOR RAPP	25000
79132	EMIT SYS FRAME-MIDDLE	163221.796
79142	OUTER ROOF-EP	256594.112
79143	HOPPER RIDGES	68879.692
79144	HOPPER UPPER PART	330000
79145	HOP MLD&LOWER PART	310000
79146	INSULATOR SUPP PANEL	110716.744
79147	ROOF PANEL ASSY	112572.316
79148	CASING STRUCTURE	318829.164
79149	CASING SHELL/PANEL	399553.644
79150	INLET-OUTLET FUNNEL	171782.12
79155	PENT HOUSE FOR E P	60000
79157	SPLITTER&GUIDE VANES	29202.592
79159	CONTROL ROOM-INSERTS	40000
79161	EP PERF TEST EQUIPT	1000
79163	ASH LEVEL INDICATOR	3500
79165	APP PLATFORM-HOPPER	173118.344
79166	WATER WASHING SYSTEM	6000
79172	INTERLOCKS-EP	2500
79173	ELECTRICALLY OPERTD HO	7000
79180	FOUNDATION MATLS FOR E	17387.978
79181	SUPPOTING STRUCTURES F	476966.868
79190	HEATING ELEMENTS	3940
79220	COLLECTING ELECTRODE	545019.2
79996	TOOLS & TACKLES	400
79-xxx	ESP HV RECTIFIER TRANSFORMER (APPROX WT)	300000
TOTAL WEIGHT OF PG 79		5605954.187
89610	EP GALLERIES & STAIRS	112225.746
89611	ESP ROOF HANDRAILS	8513.07
TOTAL WEIGHT OF PG 89		120738.816
TOTAL WEIGHT OF PGs 39,48,57,79 & 89		9022593.003
TOTAL WEIGHT OF ESP: 9023 MT		

NOTE FOR WEIGHT SCHEDULE:

1. The weights given are only approximate and for general guidance and they are subject to variation as per design consideration.
2. The information furnished is only a description regarding the items to be erected by the contractor. BHEL reserves the right to add or exclude any components / items / system according to the site requirements / customer requirements to complete the systems in all respects.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

3. Any other systems / Components which are integral to ESP & auxiliaries, supplied by BHEL manufacturing units are also to be erected and commissioned by the contractor within the quoted / accepted tonnage rate / lump sum value.
4. Erection & dismantling of air blowers and connecting pipes & ducts, providing blanks/ dummies at the required locations and conducting gas-tightness test is in the scope contract and shall be carried out with in the quoted price.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

PART –I CHAPTER -X GENERAL

The scope of the work will comprise of but not limited to the following:

- 1.10.1 All the works such as cleaning, leveling, aligning, trial assembly, dismantling of certain components for checking and cleaning, surface preparation, fabrication of sheets, tubes and pipes as per general engineering practice and as per BHEL Engineer's instructions at site, cutting, weld depositing, grinding, straightening, chamfering, filing, chipping, drilling, reaming, scrapping, lapping, fitting-up etc., as may be applicable in such erection works and are necessary to complete the work satisfactorily, shall be carried out by the contractor as part of the work with in the quoted rate. Major machining work, which is only to be carried out in workshops, will be arranged by BHEL.
- 1.10.2 The work shall conform to dimensions and tolerances given in various drawings and quality manuals provided by BHEL. If any portion of work is found to be defective in workmanship not conforming to drawings or other stipulations, the contractor shall dismantle and redo the work duly replacing the defective materials at his cost, failing which the job will be carried out by BHEL by engaging other agencies and recoveries will be effected from contractor's bill towards expenditure incurred including BHEL's overhead charges.
- 1.10.3 Contractor shall execute the work as per sequence and procedure prescribed by BHEL at site. The applicable erection manuals which are available with BHEL site office are to be referred for compliance and guidance before taking up the work. Any rework on this failure to comply with will be to account contractor only. BHEL engineer, depending upon the availability of materials, fronts etc, will decide the sequence of erection and methodology. No claims for extra payment from the contractor will be entertained on the grounds of deviation from the method of erection adopted in erection of similar jobs or for any reason whatsoever.
- 1.10.4 Contractor has to work in close co-ordination with other erection agency at site. BHEL engineer will co-ordinate area clearance. In a project of such magnitude, it is possible that the area clearance may be less/more at a particular given time. Activities and erection program have to be planned in such a way that the milestones are achieved as per schedule/ plans. Contractor shall arrange & augment the resources accordingly.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

- 1.10.5 The contractor is strictly prohibited from using BHEL's regular components like angles, channels, beams, plates, pipe/tubes, and handrails etc for any temporary supporting or scaffolding works. Contractor shall arrange himself all such materials. In case of such misuse of BHEL materials, a sum as determined by BHEL engineer will be recovered from the contractor's bill. The decision of BHEL engineer is final and binding on the contractor.
- 1.10.6 The contractor will be responsible for the safe custody and proper accounting of all materials in connection with the work. If the contractor has drawn materials in excess of design requirements, recoveries will be effected for such excess draws at the rate prescribed by manufacturing units.
- 1.10.7 No member of the already erected structure/ platform, pipes, grills, platform, other component and auxiliaries should be cut without specific approval of BHEL engineer.
- 1.10.8 Contractors shall ensure that all their Staff/Employees are exposed to periodical training programme conducted by qualified agencies/ personnel on ISO 9001 – 2000 Standards.
- 1.10.9 For other agencies, such as piping, cabling, instrumentation, insulation etc., to commence their work from/on the equipments coming under this scope, Contractor has to clear the front, expeditiously and promptly as instructed by BHEL Engineer. Some time it may be required to re-schedule the activities to enable other agencies to commence/continue the work so as to keep the over all project schedule.
- 1.10.10 The terminal points decided by BHEL are final and binding on the contractor for deciding the scope of work and effecting the payment for the work done up to the terminals.
- 1.10.11 For the purpose of planning, contractor shall furnish the estimated requirement of power (month wise) for execution of work in terms of maximum KW demand.
- 1.10.12 On Completion of work, all the temporary buildings, structures, pipe lines, cable etc. shall be dismantled and leveled and debris shall be removed as per instruction of BHEL by the contractor at his cost. In the event of his failure to do so, the expenditure towards clearance of the same will be recovered from the contractor. The decision of BHEL Engineer in this regard is final.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

- 1.10.13 All the necessary certificates and licenses required to carry out this scope of work are to be arranged by the contractor then and there at no extra cost.
- 1.10.14 For the movement of cranes it may become necessary to lay sleeper bed for obtaining safe approach for usage of equipment. It shall be the contractor's responsibility to lay necessary sleepers. Necessary sleepers shall be arranged by the contractor at his cost.
- 1.10.15 The contractor must obtain the signature and permission of the security personnel of the customer for bringing any of their materials inside the sit premises. Without the Entry Gate Pass these materials will not be allowed to be taken outside.

1.10.16 SITE INSPECTION

The owner/employer or his authorized agents may inspect various stages of work during the currency of the contract awarded to him. The contractor shall make necessary arrangements for such inspection and carry out the rectification pointed out by the owner/employer without any extra cost to the owner / employer. No cost whatsoever such duplication of inspection of work be entertained.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

PART –I CHAPTER -XI

FOUNDATIONS AND GROUTING

The scope of the work will comprise of but not limited to the following:

- 1.11.1 Foundation for the equipments to be erected shall be provided by BHEL/ clients of BHEL. The dimension of the foundation and anchor bolt pits shall be checked by the contractor for their correctness as per drawings. Further, top elevation of foundations shall be checked with respect to bench mark etc. All adjustments of foundations surfaces, enlarging the pockets in foundations etc. as may be required for the erection of equipments plants shall be carried out by the contractor.
- 1.11.2 Cleaning of foundation surfaces, pocket holes and anchor bolt pits etc., de-watering, making them free of oil, grease, sand and other foreign materials by soda wash, water wash, compressed air or any other approved methods etc., form/shuttering work are within the scope this work.
- 1.11.3 It shall be contractor's responsibility to check the various equipment foundations for their correctness with respect to level, orientation, dimensions etc., and ascertained dimensions shall be measured and submitted to BHEL for approval before erection. Also minor chipping, dressing of foundations up to 30 mm for obtaining proper face for packer plates/shims, and may be required for the erection of the equipment/plants will have to be carried out by the contractor without extra cost.
- 1.11.4 The surface of foundations shall be dressed to bring the surface of the foundations to the required level and smoothness prior to placement of equipments
- 1.11.5 Foundation pockets are to be cleaned thoroughly before placing the columns / equipments. Verticality of foundation bolts to be checked along with correctness of the threads and freeness of the nuts movement. If required cleaning of the threads to be done with proper dies.
- 1.11.6 The concrete foundation, surfaces shall be properly prepared by chipping, as required to bring the top of such foundation to the required level to provide the necessary roughness for bondage and to ensure enough bearing strength. All laitance and surface film shall be removed and cleaned and the packers placed with suitable mortar prior to

TECHNICAL CONDITIONS OF CONTRACT (TCC)

erection of the equipment. Packer plates should not only be blue matched with foundation but also inter-packer contact surfaces between the packers and foundation frame etc., shall also be blue matched by Prussian Blue match checks and required percentage contact shall be achieved by chipping and scrapping as per BHEL Engineers instructions.

- 1.11.7 The certificates of the grout is to be submitted to BHEL. If necessary test cubes are to be made and tested at site to ensure the quality of the grout as per relevant IS standards. In case grouting with Portland cement is approved, necessary cement, sand etc to be arranged by the contractor including the fine aggregates.
- 1.11.8 All the materials required for grouting including free flow special cements like Conbextra GPI,GP2, ACC- Shrinkkomb-N20, Sika Ankor, NSG/ NSG -1, CICO Excem GP, or its equivalent as approved by BHEL and other materials like Portland cement, sand etc., are to be arranged by the contractor at his cost. It shall be the responsibility of the contractor to obtain prior approval of BHEL, regarding suppliers, type of grouting cements before procurement of grouting cements.
- 1.11.9 Certain packer plates and shims over and above the quantity received as part of supplies from manufacturing units of BHEL will have to be cut out from steel plates/sheets at site by the contractor to meet site requirement. However machining of the packers, wherever necessary, will be arranged by BHEL at free of cost.
- 1.11.10 PROCEDURE FOR GROUTING :

Contractor has to carryout the grouting as per the work instructions for grouting available at site.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

PART –I CHAPTER -XII MATERIAL HANDLING AND SITE STORAGE

The scope of the work will comprise of but not limited to the following:

- 1.12.1 Loading at BHEL/Customer stores and storage yard, transport to site, unloading at site/working area of equipment placement on respective foundation/location, fabrication yard, pre-assembly bay or at working area are in the scope of work. The scope includes taking materials / Equipments from customer stores / storage yard also. Contractors Quoted / Accepted rate shall be inclusive of the same. Required cranes, tractors, trailer or trucks / slings / tools and tackles / labour including operators Fuel lubricants etc for loading & unloading of materials will be in the scope of contractor.
- 1.12.2 The equipments / materials from the storage yard shall be moved in sequence to the actual site of erection /location at the appropriate time as per the direction of BHEL Engineer so as to avoid damage/loss of such equipment at site.
- 1.12.3 Sometimes it may become necessary for the contractor to handle certain unrequired components in order to take out the required materials. The contractor has to take this contingency also into account. No extra payment is payable for such contingencies.
- 1.12.4 Materials shall be stacked neatly, preserved and stored in the contractor's shed/work area in an orderly manner. In case it is necessary to shift and re-stack the materials kept at work area/site to enable other agencies to carry out their work, same shall be done by the contractor at no extra cost.
- 1.12.5 All pipe and tube ends shall be covered with plastic caps or will be closed with wooden plugs as the case may be.
- 1.12.6 The contractor shall provide any fixtures, concrete blocks & wooden sleepers, which are required for temporary supporting of the components at site.
- 1.12.7 Contractor has to arrange required fire proof tarpaulins to protect the machined components / assembled parts drawn from BHEL before and after erection at their cost.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

PART – I CHAPTER- XIII ERECTION

The scope of the work will comprise of but not limited to the following:

- 1.13.1 Ducts / expansion pieces are dispatched to site in loose walls / plates and these are to be assembled at site before erection.
- 1.13.2 All the dampers, valves, lifting equipments, power cylinders, etc., shall be serviced and lubricated to the satisfaction of BHEL engineer before erecting the same and also during pre commissioning. The bearings of dampers shall be properly cleaned, serviced and lubricated before commissioning at no extra cost. Even after commissioning in the equipments, if there are problems in the operation they have to be attended by the contractor during the tenure of the contract.
- 1.13.3 In the case of structural members / ducts in certain cases, the raw material will be supplied in random lengths and the contractor will have to make up the length / prepare the edges to suit the matching profiles, weld / bolt connect the joints at no extra cost.
- 1.13.4 Any other systems / Components which are integral to ESP & auxiliaries, supplied by BHEL manufacturing units are also to be erected and commissioned by the contractor within the quoted / accepted tonnage rate / lump sum value.
- 1.13.5 Insulation: With respect to insulation, it shall be limited to only the application of insulation for the inner roof of ESP including fixing components.
- 1.13.6 The Erection & Alignment of HV rectifier transformer is in the scope of contractor. However, dry out, testing and commissioning is not in the scope of this contract.
- 1.13.7 Erection & dismantling of air blowers and connecting pipes & ducts, providing blanks/ dummies at the required locations and conducting gas-tightness test is in the scope contract and shall be carried out with in the quoted rate.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

- 1.13.8 Fine fittings and other small bore piping have to be routed according to site conditions and hence shall be done only in position as per the site requirement. Necessary sketch for routing these lines should be got approved from BHEL by the contractor. There is a possibility of slight change in routing the above pipelines when after completion, to suit the site conditions. The contractor should absorb this cost in his quoted rate.
- 1.13.9 All welded joints should be painted with anti corrosive paint, once NDE works are over.
- 1.13.10 It shall be the responsibility of the contractor to provide ladders on column for initial works till such time stairways are completed. For this the ladder should not be welded on the column and should be pre-fabricated clamping type ladders. No temporary welding on any structural member is permitted except under special circumstances with the approval of BHEL.
- 1.13.11 Work such as minor rectification of foundation bolts, reaming of holes, drilling of dowels, matching of bolts and nuts, making new dowel pin, etc. are covered in the scope of work.
- 1.13.12 Certain extra lengths of various tubes/pipes and fabricated ducts are provided as erection allowance and the same have to be cut/adjusted to suit the site conditions and layouts or certain small lengths may have to be added for adjustments to suit the site conditions. For any mismatch while matching the joints in tubes, the cutting, adjusting, re welding, addition spool pieces should be done by the contractor to match site conditions without any extra payment.
- 1.13.13 All hangers, supports and anchors (including concreting or welding) shall be installed as per drawing to obtain are reliable and complete installation as per instructions of BHEL Engineer. Normally supports are issued in running meters. Any additional supports as called for by BHEL Engineer shall be fabricated by the contractor and provided at no extra cost. However, the raw material required for fabrication of such supports shall be supplied by BHEL free of cost. (Any machining or threading is involved will only be done by BHEL).

TECHNICAL CONDITIONS OF CONTRACT (TCC)

- 1.13.14 HSFG Bolts are to be tightened by turn of nut method/Torque Wrench, as per the instruction of BHEL Engineer. The bolted joints shall be jointly checked by BHEL/Customer and contractors personnel for the required tightness and retightened wherever necessary. The tightened bolts shall be identified by color paints. Facility for random checking with calibrated Torque Wrench shall also be provided by contractor.
- 1.13.15 All Rotating machineries and equipment shall be cleaned, lubricated, checked for their smooth rotation, if necessary dismantling and refitting before erection. If in the opinion of BHEL Engineer, the equipment is to be checked for clearance, tolerance at any stage of work or during commissioning period, all such works are to be carried out by contractor at his cost.
- 1.13.16 D.S.L / equivalent system for hoisting equipments are also to be erected and commissioned including load testing by the contractor within the quoted rates. Required manpower including electricians are to be arranged by the contractor for carrying out commissioning of electrical hoist and load testing of the above electrical hoist. Required loads will be provided by BHEL free of cost.
- 1.13.17 The temporary structures/items welded to permanent members/pipes are to be cut and removed without any damage. Any damage so to be made good by the contractor at his cost.
- 1.13.18 Before lifting the heavy components, soft materials like gunny bags to be used while lashing the rope to avoid dents, rubbing marks etc. The capacity, number of sheave pulleys, size of the rope, guide pulley locations are to be decided at site with respect to the capacity and positioning of the winch. The end caps provided at shop for various stubs are to be removed during final fit up only.
- 1.13.19 Prior to erection of any components inspection to be done for any foreign materials and damages and they are to be removed / attended as per BHEL engineer. Fixing, welding of necessary instrumentation tapping points, to be provided on auxiliaries covered within the scope of this specification will also be the responsibility of the contractor and will be done as per the instructions of BHEL Engineer. The fixing / welding of all the above items will be contractor's responsibility even if the
- i) Product groups under which these items are not specifically indicated in the Tender Specification.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

ii) Items are supplied by an agency other than BHEL

- 1.13.20 For skid mounted equipment, the checking and re-alignment required at site is in the scope of work.
- 1.13.21 All the shafts of rotating equipment shall have to be properly aligned to those of matching equipment to perfection, accuracy as required and the equipment shall be free from excessive vibration so as to avoid overheating of bearings or other conditions which may tend to shorten the life of the equipment.
- 1.13.22 All the equipments /material to be taken inside the plant building shall be cleaned thoroughly before taking them inside and erect. The contractor shall clean, wherever necessary and paint inside surfaces of the equipments like coolers, oil tanks, Rubber expansion joints assemble and other components as per instruction of BHEL Engineer during erection at the quoted rate.
- 1.13.23 Wherever equipments are supplied in pre-fabricated assembled packages, there may be necessity to make minor changes, including strengthening by additional welds. This shall be treated as part of the contractor's scope.
- 1.13.24 All the bearings, Gearboxes etc., of the equipment and electrical motors to be erected are provided with protective greases only. Contractor shall arrange as and when required by the engineer for cleaning the bearing/gear boxes etc., with kerosene or some other agent if necessary by dismantling some of the parts of the equipment during erection and shall arrange for re-greasing/lubricating them with recommended lubricants and assembling back.
- 1.13.25 Certain instruments like pressure switches, gauges, air sets, regulators, filters, junction boxes, power cylinders, dial gauges, thermometers, flow meters, valve actuators, flow indicators etc., are received in assembled conditions as integral part of equipments. Contractor shall dismantle such instruments and re-erect whenever required prior to commissioning. Some time this may have to be handed over to store or instrumentation contractor.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

- 1.13.26 Attachment, welding of necessary instrumentation tapping points, both for regular measurements and performance testing to be provided on E.S.P / its auxiliaries or pipelines covered within the scope of this tender will also be the responsibility of the contractor and the same will be done as per the instruction of BHEL Engineer.
- 1.13.27 All the motors/pumps shall be stripped opened, thoroughly serviced with proper care and re-assembled properly before erection by the contractor. During servicing, pre-commissioning & commissioning, if any deficiency is observed the same should be taken up with BHEL Engineer at site and rectified at site without any delay.
- 1.13.28 All site-fabricated pipes will be issued in running metres as straight. These are to be cut and edge prepared at site to required length to suit layout as given in the erection drawing. All the attachments like lugs, stoppers, cleats etc., will be supplied as loose items and to be cut and welded to the pipes at site as per erection drawing necessary drilling of holes on main pipe for welding stubs shall also be done at site by the contractor. Fittings like bends, tees, elbow, mitre bends, reducers, flanges etc., will be supplied as loose items.
- 1.13.29 ESP collecting Electrodes may require straightening and repair due to minor transport damages before erection and spot heating in position to get correct alignment which shall be done by contractor with in the quoted price.
- 1.13.30 Additional platforms of permanent nature for approaching different equipments, as per site requirement which may not be indicated in drawings shall be fabricated and installed by the contractor. However the contractor will be paid for this work on accepted tonnage rate for erection. The material required for platform will be supplied by BHEL free of cost.
- 1.13.31 One layer of insulation mattress on roof top of E.S.P roof (inner) shall be applied before outer roof is placed. The scope shall also include the above work even though the materials are supplied under some other product group and the erected materials shall be paid at the accepted tonnage rate for ESP.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

- 1.13.32 Pipes above 2" diameter have to be cleaned by means of wire brush as per the instruction of BHEL Engineer and subsequently flushed with air before lifting them into position. For pipes below 2" diameter, shall be sponge cleaned with air flushing.
- 1.13.33 Incase of piping connected to equipment, matching of flanges for achieving the parallelism and alignment at equipment end by suitably resorting to heat correction or other method as instructed by BHEL Engineer is within scope of work.
- 1.13.34 All piping items including pipes, valves, flanges, fittings etc. shall be supplied as commercially available. Hence Fit-ups, edge preparation including welding of stubs, shall be included in the contractor's scope.
- 1.13.35 Wherever elbows of 45 deg or any other angle are required, the same shall be cut from 90 deg. elbow supplied and used. No extra cost shall be paid.
- 1.13.36 Erection of flow switches, filters, flow meters, other metering elements, flow orifices, flow indicators, control valves supplied either by BHEL or customer forming part of the system is in the scope of work. This will include collecting from BHEL/Customer stores, transport to site, suitably cutting the erected piping, cleaning, erection, welding, radiography and stress relieving and commissioning.
- 1.13.37 Contractor shall also weld small length of piping with root valve to the pressure, flow and level tapping points on piping or flow nozzles/orifices/ metering elements fixed on piping as per the instructions of BHEL Engineer.
- 1.13.38 Welding of all thermo wells, draft, pressure and temperature instrumentation points and all other instrumentation points on piping and auxiliaries and welding of thermocouple pads for permanent system as well as for performance guarantee test is in the scope of work.
- 1.13.39 Plate / Pipe shoes for piping supports shall be fabricated at site by the contractor at no extra cost. Other supports namely Hangers, U-clamps etc., shall be supplied by BHEL duly bent and threaded. Assembly and necessary cutting work etc., shall be carried out at site by contractor within the quoted rate.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

- 1.13.40 Wherever hanger and support materials are not received from manufacturing unit in time to suit the erection schedule, contractor shall erect the system on temporary supports to ensure the progress of work. The required structural steel materials will be issued on free of charges by BHEL, either from scrap/spare materials. The same shall be removed and returned to BHEL store after erection of permanent supports.
- 1.13.41 No separate payment will be made for the edge preparation of pipes, Standard fittings such as bends, Tees etc.,
- 1.13.42 Contractors has to carryout fabrication works such as welding of stubs / nipples, attachments etc., preparation of surface for rust preventive coating and application of rust preventive is within the quoted / accepted rate.
- 1.13.43 Adjustments like removal of ovalities in pipes and opening or closing the fabricated bends piping to suit the layout shall be considered part of work and the contractor is required to carry out such work free of cost, as per instructions of BHEL.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

PART – I CHAPTER - XIV

PROGRESS OF WORK

The scope of the work will comprise of but not limited to the following:

- 1.14.1. Refer forms F -14 to F-18 of volume I D of volume -I book-II. Plan and review will be done as per the formats.
- 1.14.2. Contractor is required to draw mutually agreed monthly erection programs in consultation with BHEL well in advance. Contractor shall ensure achievement of agreed program and shall also timely arrange additional resources considered necessary at no extra cost to BHEL.
- 1.14.3. Progress review meetings will be held at site during which actual progress during the week vis-a-vis scheduled program shall be discussed for actions to be taken for achieving targets. Contractor shall also present the program for subsequent week. The contractor shall constantly update / revise his work program to meet the overall requirement. All quality problems shall also be discussed during above review meetings. Necessary preventive and corrective action shall be discussed and decided upon in such review meetings and shall be implemented by the contractor in time bound manner so as to eliminate the cause of nonconformities.
- 1.14.4. The contractor shall submit daily, weekly and monthly progress reports, manpower reports, materials reports, consumables (gases / electrodes) report, cranes availability report and other reports as per Performa considered necessary by the Engineer as per the format enclosed with this tender document.
- 1.14.5. The contractor shall submit weekly / fortnightly / monthly statement report regarding consumption of all consumables for cost analysis purposes.
- 1.14.6. The monthly report ending on 24th of every month shall be submitted as a booklet and shall contain the following details :-
 - a) Colour Progress photographs to accompany the report should be submitted.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

- b) Erection progress in terms of tonnage, welding joints, radiography, stress relieving, etc., completed as relevant to the respective work areas against planned.
 - c) Site Organization chart of engineers & supervisors as on 24th of the month with further mobilization plan
 - d) Category- wise man hours engaged during the previous month under the categories of fitters, welders, riggers, khalasis, grinder-men, gas-cutters, electricians, crane operations and helpers. Data will be spilt up under the work area of Boiler
 - e) Consumables report giving consumption of all types of gases and electrodes during the previous month.
 - f) Availability report of cranes
 - g) Safety implementation report in the format
 - h) Pending material and any other inputs required from BHEL for activities planned during the subsequent month.
- 1.14.7. The manpower reports shall clearly indicate the manpower deployed, category wise specifying also the activities in which they are engaged.
- 1.14.8. During the course of erection, if the progress is found unsatisfactory, or if the target dates fixed from time to time for every milestone are to be advanced, or in the opinion of BHEL, if it is found that the skilled workmen like fitters, operators, technicians employed are not sufficient BHEL will induct required additional workmen to improve the progress and recover all charges incurred on this account including all expenses together with BHEL overheads from contractor's bills.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

PART – I CHAPTER - XV WELDING

The scope of the work will comprise of but not limited to the following:

- 1.15.1 All welders including tack welders, structural and high pressure welder shall be tested and approved by BHEL Engineer before they are actually engaged on work even though they may possess a valid certificate. BHEL reserves the right to reject any welder if the welder's performance is not found to be satisfactory. The contractor shall maintain the records of qualification and performance of welders. BHEL Engineer will issue all the welders qualified for the work, an identity card. The welder will keep the same with him at work place at all times. He may be stopped from work if he is not found in possession of the same.
- 1.15.2 Engineer may stop any welder from the work if his performance is unsatisfactory for any technical reason or if there is a high percentage of rejection in the joints welded by him. The welders having passed qualification tests does not absolve the contractor of contractual obligation to continuously check the welder's performance.
- 1.15.3 Faulty welds caused by the poor workmanship shall be cut and re-welded at the contractor's expense. The Engineer prior to any repair being made shall approve the procedure for the repair of defective welds. After the repair has been carried out, the compliance shall be submitted to the quality engineer.
- 1.15.4 All expenses for testing of contractor's welders including destructive and Non- destructive tests conducted by BHEL at site or at laboratory shall have to be borne by the contractor only. Limited quantity of tube and pipe material required for making test pieces will be supplied by BHEL free of cost.
- 1.15.5 Only BHEL approved electrodes and filler wire will be used. All electrodes shall be baked and dried in the electric electrode-drying oven to the required temperature for the period specified by the Engineer before these are used in erection work. All welders shall have electrodes drying portable oven at the work spot.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

- 1.15.6 The contractor shall also be equipped for carrying out other NDT like LPI /MPI / Hardness test etc. as required as per welding schedules / drawings within the finally accepted price / rates.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

PART - I CHAPTER- XVI TESTING AND COMMISSIONING

The scope of the work will comprise of but not limited to the following:

1.16 TESTING , PRE – COMMISSIONING & COMMISSIONING AND POST COMMISSIONING

(All the works mentioned hereunder shall be carried out within the quoted and accepted rate)

- 1.16.1 Contractor to provide necessary commissioning assistance from pre-commissioning state onwards and up to continuous operation of the unit & handing over to customer.
- 1.16.2 The contractor shall carry out all the required tests on the equipments erected such as gas tightness test for ducts, kerosene leak test, air flow test, etc., using contractor's own consumables, labour and scaffoldings.
- 1.16.3 It is the responsibility of the contractor to provide necessary manpower, tools, tackles and consumable within the quoted price to carryout the Gas Distribution test of ESP.
- 1.16.4 All required tests (Mechanical and electrical) indicated by BHEL and their clients for successful commissioning are included in the scope of these specifications. These tests / activities may not have been listed in these specifications. All the tests should be repeated till all the equipments satisfy the requirement / obligation of BHEL to their customer. All the repairs (shop welded or site welded) arising out of the failures during testing shall be done by the contractor as part of the work.
- 1.16.5 For conducting gas tightness test, it may be required to erect the blowers and connecting ducts and commission the same for tightness test. It is the responsibility of the contractor to erect the blowers & dismantle once the test is over. Contractor shall carry out the work with in the quoted rate and BHEL will provide only the required materials, like Blowers and dummies free of hire charges for conducting the test.
- 1.16.6 Fixing dummy plates at required locations for conducting tightness test and normalising after the test is over, is also covered in the scope of contract and shall be carried out with in the quoted rate. BHEL will provide raw materials for the dummy plates.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

- 1.16.7 The contractor shall carryout any other test as desired by BHEL Engineer on erected equipment covered under the scope of this contract during testing, pre-commissioning, commissioning, and operation, to demonstrate the completion of any part or whole work performed by the contractor.
- 1.16.8 The ESP rectifier transformers are to be only erected by the contractor. Testing, commissioning and oil filtering is not in the scope of this contract.
- 1.16.9 In case, any rework is required because of contractor's faulty erection, which is noticed during pre-commissioning and commissioning, the same has to be rectified by the contractor at his cost. If any equipment / part is required to be inspected during pre-commissioning and commissioning, the contractor will dismantle / open up the equipment / part and reassemble / redo the work without any extra claim.
- 1.16.10 During commissioning, opening / closing of valves, changing of gaskets, Re-alignment of rotating and other equipment, attending to leakage and adjustments of erected equipment may arise. The finally accepted price /rates shall also include all such work.
- 1.16.11 Commissioning of the equipments will involve, trial runs of all the equipments erected, blowing through the lines, flushing of all the lines by air, oil or steam as the case may be, trial run of the equipment and any other works incidental to commissioning.
- 1.16.12 The valves will have to be checked, cleaned or overhauled in full or in part before erection, after acid cleaning, steam blowing and during commissioning as may be necessary.
- 1.16.13 In case any erection defect is detected during various tests / operations trial runs such as loose components undue noises or vibration strain on connected equipment steam or oil or water leakage etc. the contractor shall immediately attend these defects and take necessary corrective measures. If any readjustment and realignments are necessary the same shall be done as per BHEL Engineer's instructions. If any part needs repairs rectification and replacement the same shall be done by the contractor at no extra cost. The parts to be replaced shall be provided by BHEL free of cost If insulation is to be removed to attend any of the defects the cost of removal and reapplication of insulation should be borne by the contractor.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

- 1.16.14 The contractor shall carry out cleaning and servicing of valves and dampers / gates actuators prior to pre-commissioning tests and / or trial operations of the plant. A system for recording of such servicing operations shall be developed and maintained in a manner acceptable to BHEL Engineer to ensure that no valves and actuators are left un-serviced.
- 1.16.15 Replacing / Cleaning and servicing of all the filters of the erected equipments during pre-commissioning / commissioning stage shall be done by the contractor within the accepted price..
- 1.16.16 Contractor may have to replace old / damaged gaskets / packing etc. in the erected equipments and the same shall be carried out by contractor as per requirement. Materials will be given by BHEL.
- 1.16.17 In case any erection defect is detected during various tests / operations trial runs, such as loose components undue noises or vibration strain on connected equipment steam or oil or water leakage etc. the contractor shall immediately attend these defects and take necessary corrective measures. The parts to be replaced shall be provided by BHEL free of cost. If the insulation is to be removed to attend any of the defects the cost of removal and reapplication of insulation should be borne by the contractor.
- 1.16.18 Contractor shall cut / open works if needed, as per BHEL engineer's instructions during commissioning for inspection, checking and make good the works after inspection is over. This contingency shall be included within the quoted value. During commissioning opening of valves, changing of gaskets, attending to leakages, minor modification / rectification works may arise. The contractor has to carry out these works at his cost by providing required manpower in all the three shifts. In case any rework is required because of contractor's faulty erection and which is noticed during commissioning the same has to be rectified by the contractor at his cost.
- 1.16.19 After synchronization, the commissioning activities will continue. It shall be the responsibility of the contractor to provide manpower including necessary consumables, hand tools and supervision as part commissioning assistance.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

- 1.16.20 It shall be the responsibility of the contractor to provide various categories of workers in sufficient numbers along with Supervisors during pre commissioning, commissioning and post commissioning of equipment and attending any problem in the equipment erected by the contractor till handing over. The contractor will provide necessary consumables, T&Ps, IMTEs etc., and any other assistance required during this period. Association of BHEL's / Client's staff during above period will not absolve contractor from above responsibilities.
- 1.16.21 It shall be specifically noted that the contractor and employees of the contractor may have to work round the clock during the pre-commissioning, commissioning and post-commissioning period along with BHEL Engineers / customer officials. Hence contractor's quoted rate shall take into consideration of all expenses that will be incurred for such arrangement of personnel including engineers/supervisors.
- 1.16.22 During commissioning any improvement / repair / rework / rectification / fabrication / modification due to design improvement / requirement is involved, the same shall be carried out by the contractor promptly and expeditiously.
- 1.16.23 Contractor shall lay all necessary electric cables and switches etc. required for the tests and maintain the system till the tests are completed satisfactorily.
- 1.16.24 Transportation of oil drums from customer's / BHEL's stores. Filling of lubricants and filling of oil for flushing and first filling and subsequent topping up during commissioning and post commissioning is included in the scope of this contract. The contractor shall have to return all the empty drums to the customer/BHEL stores. Similarly transport of chemicals for various pre-commissioning, commissioning activities and related processes and returning of remaining and/or the empty containers of the chemicals to customer/BHEL stores is the responsibility of the contractor.
- 1.16.25 The contractor shall carry out the trial run of motors including checking the direction of rotation in the uncoupled condition checking aligning and coupling the motor to the respective driven equipment. Before starting the motor, IR values of insulation shall be recorded and if found necessary the contractor shall dry out to improve the IR value at no extra cost.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

- 1.16.26 Necessary scaffolding and approaches for conducting the above shall also be within the scope of the contract.
- 1.16.27 Assistance for calibrating / testing the power cylinders / actuators / valves, gauges, instruments, etc. and setting to actuators shall be provided by contractor within the quoted rates.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

PART- I CHAPTER-XVII PAINTING

The scope of the work will comprise of but not limited to the following:

1.17.0 FINAL PAINTING

- 1.17.1 The scope of work shall also include supply and application of final painting of all the erected equipments as required and specified for the components of boiler and its auxiliaries.
- 1.17.2 In the case of steel fabricated items, raw steel after fabrication has to be cleaned and subsequent painting to be carried out.
- 1.17.3 All the exposed metal parts of the equipments including piping, structures, hangers etc., wherever applicable after installation unless otherwise specified the surface protected, are to be first painted with at least one coat of suitable primer and required number of finish coats as indicated in the Painting Specification in TCC which matches the shop primer paint used, after thoroughly cleaning the dust, rust, scales, grease oil, and other foreign materials by wire brushing scrapping and chemical cleaning and the same being inspected and approved by BHEL engineers for painting. Afterwards the above parts shall be finished with as per the instructions of BHEL/Customer official.
- 1.17.4 Paint shall be applied by brushing or by spray painting as per the instruction of BHEL Engineer. Spray painting gun and compressed air arrangement has to be made by the contractor himself. It shall be ensured that brush marks are minimum.
- 1.17.5 Before applying the subsequent coats the thickness of each coat shall be measured and recorded with BHEL / Customer.
- 1.17.6 Paint used shall be stirred frequently to keep the pigment in suspension. Paint shall be of the ready mix type in original sealed containers as packed by the paint manufacturer. No thinners shall be permitted. Paint manufacturers instructions shall be followed in method of application, handling, drying time etc.,
- 1.17.7 The scope of painting includes application of colour bands, lettering the names of the systems equipments; tag Nos of valves, marking the directions of flow and other data required by BHEL within the quoted rate.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

- 1.17.8 All surfaces shall be thoroughly cleaned, free from scales, dirt and other foreign matter. Each coat shall be applied in an even & uniform film free from lumps, streaks, runs, sags and uncoated spots. Each coat (Primer, intermediate, finish) shall have a minimum thickness of dry film thickness (DFT) in microns and the DFT of finish paint shall not be less than the specified. Necessary instrument for measuring the thickness of paint applied is to be arranged by the contractor.
- 1.17.9 Finish coat paint, No of coat and DFT shall be as indicated in the painting specification enclosed in this tender / relevant BHEL document/ customer's approved specifications. The painting specification which is forming part of this tender as in TCC shall be used as guidelines to be followed.
- 1.17.10 The actual colour to be applied shall be approved by the customer before starting of actual painting work.
- 1.17.11 Primer & finish paint shall be of reputed paint supplier approved by BHEL / Customer. Contractor has to procure paints from the BHEL / Customer approved agencies only, and the paints should be as per the customer painting specification. The quality of the finish paint shall be as per the standards of IS or equivalent as approved by BHEL / Customer. Before procurement of paint the contractor has to obtain the clearance from BHEL authorities.
- 1.17.12 No paint shall be applied when the surface temp is above 55 deg. Centigrade or below 10 deg. Centigrade, and when the humidity is greater than 90% to cause condensation on the surface or frost / foggy weather.
- 1.17.13 If needed and insisted either by BHEL / Customer in certain cases, spray painting has to be carried out within the Quoted rates.
- 1.17.14 Before commencement of final painting, contractor has to obtain written clearance from BHEL / Customer for effective completion of surface preparation.
- 1.17.15 Before applying the subsequent coats, the thickness of each coat shall be measured and recorded with BHEL/ Customer.
- 1.17.16 **PRESERVATION / TOUCH UP PAINTING**
- 1.17.16.1 Contractor shall carryout cleaning and preservation / touch up painting for the materials / equipments under this tender specification right from pre- assembly stage to till the equipment is cleared for final painting.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

- 1.17.16.2 The contractor shall effectively protect the finished work from action of weather and from damage or defacement and shall cover the finished parts, then and there, for their protection.
- 1.17.16.3 Any equipment which has been given the shop coat of primer shall be carefully examined after its erection in the field and shall be treated with touch up coat of red oxide primer wherever the shop coat has been abraded, removed or damaged during transit / erection, or defaced during welding.
- 1.17.16.4 Mostly the equipment / items/ components will be supplied with one coat of primer paint and one coat of finish paint. However during storage and handling, the same may get peeled off / deteriorate. All such surfaces are to be thoroughly cleaned and to be touch up painted with suitable approved primer and finish paint matching with shop paint / approved final colour.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

PART – II CHAPTER - 1 REVERSE AUCTION PROCEDURE

GENERAL TERMS AND CONDITIONS OF REVERSE AUCTION

Against this NIT for the subject work, tender shall be processed through “REVERSE AUCTION PROCEDURE” i.e. ON LINE BIDDING on INTERNET.

1. For the proposed reverse auction, technically and commercially acceptable bidders only shall be eligible to participate.
2. BHEL will engage the services of a service provider who will provide all necessary training and assistance before commencement of on line bidding on Internet.
3. BHEL will inform the vendor in writing in case reverse auction, the details of service provider to enable them to contact and get trained.
4. Business rules like event date, time, start price, bid decrement, extensions, etc. also will be communicated through service provider for compliance.
5. Vendors have to fax the compliance form in the prescribed (provided by service provider) before start of Reverse auction. Without this the vendor will not be eligible to participate in the event.
6. BHEL will provide the calculation sheet (e.g.: EXCEL sheet) which will help to arrive at “Total Cost to BHEL”.
7. Reverse auction will be conducted on schedule date & time.
8. At the end of reverse auction event, the lowest bidder value will be known on the network.
9. The lowest bidder has to fax the duly signed filled-in prescribed format as provided on case-to-case basis to BHEL through service provider within 24 hours of action without fail.
10. During Reverse Auction, the process of reverse auction is unsuccessful then BHEL at its discretion may decide to call the L1 bidder of reverse auction for further negotiation.
11. Sealed bid reverse auction: The opening bid (in the initial auction) of the bidders shall be same as that quoted in their final sealed price submitted to BHEL. The bidder shall confirm in writing to BHEL that their opening bid in both cases shall be same as that quoted in their final sealed price bids submitted to BHEL against this NIT along with Technical bid.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

12. BHEL reserves the right to cancel Reverse Auction (RA) without assigning any reasons and resort to considering the sealed bids submitted by vendor for processing and finalizing the tender.
13. Any variation between the on-line bid value and signed document will be considered as sabotaging the tender process and will invite disqualification of vendor to conduct business with BHEL as per prevailing procedure.
14. In case BHEL decides not to go for Reverse auction procedure for this tender enquiry, the price bids and price impacts, if any already submitted and available with BHEL shall be opened as per BHEL standard practice.
15. Bids given by the bidders during the reverse auction process will be taken as an offer to execute the work. Bids once made by the bidder, cannot be cancelled/withdrawn and bidders shall be bound to execute the work as mentioned above at the final bid price. BHEL shall take appropriate action as the lowest bidder do not execute the contract as per the rates quoted by him.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

PART II CHAPTER 2 PAINTING SCHEME

		MANUFACTURER'S NAME & ADDRESS M/S BHEL: BAP: RANIPET TAMIL NADU-632 406		MANUFACTURING QUALITY PLAN Item/subsystem: Emitting Electrode Of ESP			Project : KAKATTIYA THERMAL POWER PROJECT - II (1 X 600 MW), CHELUPUR VILLAGE GHANAPURAM (MANDAL), WARANGAL DIST (A.P) Cust Name: M/S ANDHRAPRADESH POWER GENERATION CORPORATION LIMITED Cust No : R607 Contractor: M / s BHEL - Ranipet-6		
Sl No	Component & operation	Characteristics	Type of Check	Quantum of Check	Reference Documents	Acceptance Norms	Format Of Records	Agency	Remarks
1	2	3	4	5	6	7	8	9	10
1.0	Raw Material								
1.1	Wire:	Chemical	Analysis	Each Heat	Respective Material Spec.		TC	P	V
		Ultimate Tensile Strength	Tensile Test	Each Heat	-do-		TC	P	V
2.0	In-process Control								
2.1	Dimension	No of turns & End Construction	Measurement and checking with template	Random	Drawing		R	P	W
2.2	Spring back retention Force, initial Tension	Spring back Test, retention Force, initial Tension test	Measurement	One electrode Per heat	Drawing & BHEL specification		R	P	W
LEGENDS: M - MANUFACTURER / SUBCONTRACTOR B - BHEL / AUTHORISED INSPECTION AGENCY. P - PERFORM ED, V - VERIFICATION, W - WITNESS R - REPORT TC - TEST CERTIFICATE C - CUSTOMER									
K.V.S.						P. Lakshmi			
PREPARED BY						REVIEWED and APPROVED BY			

CHIEF ENGINEER
Thermal Projects Constrn.
GENCO, Vidyut Soudha,
HYDERABAD - 500 082.

		MANUFACTURER'S NAME & ADDRESS M/S BHEL: BAP: RANIPET TAMIL NADU-632 406		MANUFACTURING QUALITY PLAN Item/subsystem: Emitting Electrode Of ESP				Project : KAKATIYA THERMAL POWER PROJECT - II (1 X 600 MW),CHELPUR VILLAGE GHANAPURAM (MANDAL), WARANGAL DIST (A.P) Cust Name: M/S ANDHRAPRADESH POWER GENERATION CORPORATION LIMITED Cust No : R607 Contractor: M / s BHEL - Ranipet-6			
Sl no 1		Component & operation 2	Characteristics 3	Type of Check 5	Quantum of Check 6	Reference Documents 7	Acceptance Norms 8	Format Of Records 9	Agency M B C 10		Remarks 11
3.0 Final inspection of above		Cleanliness, painting,preservation, identification & verification completeness	Visual	100%	Refer Note-2-2	-	P	W	-	-	

Note 1: All other items of ESP, like, Columns, Bracings, Roof Beams, Panels, Casing Shells, Hoppers, collecting electrode, Funnels and etc., which are of general fabricated items from rolled sections, plates & sheets, which are not covered under QAP will be manufactured, inspected by BHEL / BHEL Authorized Inspection Agency as per the relevant drawings, AWS D1.1 and BHEL standards and dispatched.

Painting Scheme for ESP Components:

1. Surface Preparation: Power Tool Cleaning to St3

a) Surface exposed to Atmosphere :

- Primer: Two coats of Red Oxide Zinc phosphate primer to IS: 12744 to a DFT of 40µm.(min)
- Finish: Two coats of Synthetic Enamel to IS: 2932 smoke grey (shade no 692 of IS 5) to a DFT of 2x 20=40 µm.(min) Total DFT : 80µm.(min)

b) Other surfaces (Insulated & Flue gas path)


- Primer: Two coats of Red Oxide zinc phosphate primer to IS 12744 to a DFT of 2x30 =60µm.(min)
- 2. Emitting Electrode hook, machined components and foundation bolts are applied with rust preventive fluid and min DFT = 20 µm
- 3. Collecting Electrodes are dipped in Rust Preventive fluid and min DFT = 20 µm
- 4. Stainless steel, Aluminum and Galvanized items are not painted.

CHIEF ENGINEER
Thermal Projects Constrn.-I
ADGENCO, Vidyut Soudha,
HYDRABAD - 500 082.

		MANUFACTURER'S NAME & ADDRESS		MANUFACTURING QUALITY PLAN		Project		KAKATIYA THERMAL POWER PROJECT II,									
		M/S BHEL: BAP: RANIPET TAMIL NADU- 632 406		Item/subsystem: Gates and Damper		Q.P. No: KAKA 401 Rev. No: 01 Date: 28 10 09 Page: 1 of 2		Customer No Contractor									
SL NO		COMPONENT & OPERATION		CHARACTERISTICS		TYPE OF CHECK		QUANTUM OF CHECK		REFERENCE DOCUMENTS		ACCEPTANCE CRITERIA		FORMAT OF RECORD		REMARKS	
1		2		3		4		5		6		7		8		9	
1		2		3		4		5		6		7		8		9	

1.0	Materials Seals	Chemical and Mechanical Properties	Chemical and Tensile Test	Each Heat	As per Respective material spec.	TC	P	V	-	*CHP Random
2.0	In process Inspection	Soundness	LP1/MP1	Note -1	ASME Sec V & Company standard	NDT Report	P	W	V	
2.1	Weld Quality	Over all Dimension/ Match mark	Measurement	100%	Relevant Drawing	DR	P	W	W	
2.2	Frame dimension	Free movement	Open and Close	100%	Free operation	DR	P	W	W	
2.3	a) Trial Operation of gates	Seal Tightness	Check by Feeler Gauge	100%	Relevant drawing	DR	P	W	W	
	b) Trial operation of Dampers	Leak tightness test	Verification	(**)	Company standard	Test report	P	V	V	
3.0	Final inspection	Cleanliness Painting and preservation & Identification, Verification of Completeness.	Visual	100%	Refer Note -2	--	P	V	V	

(*)CHP-Random means- 100% Witness by BHEL Inspection. One Gate and One Damper will be offered to Customer

LEGENDS: M - MANUFACTURER / SUBCONTRACTOR, B - BHEL / BHEL Authorized Inspection Agency, C - CUSTOMER, P - PERFORM, V - VERIFICATION of reports, W - WITNESS, T C - TEST CERTIFICATE, DR - DIMENSIONAL REPORT, CHP-Customer hold point.	Prepared by. 	Reviewed by. 	Approved by. 
--	--	--	--

CHIEF ENGINEER
 Thermal Projects Constr.-1
 APGENCO, Vidyut Soudha,
 HYDERABAD - 500 082.

 Ranipet		MANUFACTURER'S NAME & ADDRESS M/S BHEL: BAP: RANIPET TAMIL NADU- 632 406		MANUFACTURING QUALITY PLAN				Project KAKATTIYA THERMAL POWER PROJECT II, 1X600 MW	
		Item/subsystem: Gates and Damper		QP: No: KAKA 401 Rev: No: 01 Date: 28 10 09 Page: 2 of 2		Customer APGENCO			
		CHARACTERISTICS 3		TYPE OF CHECK 4		QUANTUM OF CHECK 5		Contractor BHEL	
COMPONENT & OPERATION 2						REFERENCE DOCUMENTS 6		ACCEPTANCE NORMS 7	
						FORMAT OF RECORD 8		Agency 9	
SL NO 1								REMARKS 10	

(**) Earlier test reports for these A) Air Heater Out let damper, B) ESP Inlet Gate, C) Eco out let gate, D) ID Fan out let gate will be offered for customer verification and records.

Note: 1- Dampers: 100% LPI / MPI on Blade block, Mounting bracket & Stud welding with gland plate and splice joints of Blade & Frame
Gates: 100% MPI/LPI on mounting bracket welds bar welding of gate plate collar welding on shaft blower, air-mounting brackets and Splice joints of blades and Frame.

Note 2-

Surface preparation: Power tool cleaning

Painting:

(a) Surfaces exposed to Atmosphere


- Primer coat: Two coats of Red oxide zinc phosphate primer to IS 12744 to a DFT of 40 µm(min).
- Finish Coat: Two coats of Synthetic enamel to IS 2932 smoke grey shade no 692 of IS 5 to a DFT of 40 µm. Total DFT 80 µm.(min)

(b) Surfaces Under insulation and Flue Gas path (including gate frames)

- Two coats of Red oxide zinc phosphate primer to IS 12744 to a DFT of 60 µm.(min)

(c) Machined components & Gate blade are protected with Temporary Rust preventive application.

Record of revision	Rev 00 DT 23 02 09	Original Issue
	Rev 01 DTD 28 10 09	Revised vide Customer LTR reference . Lr. No. CPP/711/KTPP-II/RANIPET/QUALITYPLAN/ D.NO.234/2009 DTD 07 10 2009

LEGENDS: M – MANUFACTURER / SUBCONTRACTOR, B – BHEL /BHEL Authorized Inspection Agency, C –CUSTOMER, P – PERFORM, V – VERIFICATION of reports, W – WITNESS, T C – TEST CERTIFICATE, DR – DIMENSIONAL REPORT, CHP-Customer hold point.	 Prepared by.	 Reviewed by	 Approved by.
--	--	---	--

CHIEF ENGINEER
 Thermal Projects Constrn.
 BHEL, Vidyut Soudha,
 HYDERABAD - 500 082.