

ANNEXURE-1

Detailed scope of work

Description of Work: Rubber lining for SAC, SBA&MB Vessels of 23 Sq. meters inside surface area.

Scope of work:

Supply of 5mm thickness Natural rubber and required chemical solutions for SAC, SBA & MB vessels of total surface area of 23 sq. mtrs as per Specifications and Standards IS 4682 PART-I

Labour Work involves-

Removing of Existing Rubber Lining and Providing New Natural Rubber Lining (5mm thickness) to SAC, SBA & MB Vessels.

After completion of rubber lining work, spark test to be conducted for any leaks. Spark test equipment to be arranged by vendor only.

Note: - Exhaust fan, Consumables and required tools are to be arranged by vendor only.

Vendor may visit BHEL/R.C.Puram site for study of scope of work before quotation submitted.

Vendor has to quote Lump sum amount for the total scope of work.

Signature
12/07/19
ओडेला राजेंद्र
Odela Rajendar
उप प्रबंधक(बी.ओ.ई.) / बॉयलर हाऊस (एम & एस)
Dy. Manager (B.O.E) / Boiler House (M&S)
बी.एच.ई.एल. हैदराबाद, BHEL.HYD-32