

TENDER

TENDER NOTIFICATION NO. - FCX/22231007

FOR

**Name of work : Repair and maintenance of RCC drain work
at south side of block-4 and other area inside factory area.**

PRICE BID



FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION

BHARAT HEAVY ELECTRICALS LIMITED

**(A Government of India Undertaking)
BHOPAL – 462 022 (M.P)**

PREAMBLE OF PRICE BID

1.0 This Price Bid consists of Three Schedule:

1.1 Schedule A

Schedule A consists of **Two** Annexure:

The evaluation currency for this tender shall be INR. Total price of the package combining **Annexure I & Annexure II** to be quoted by the bidders which shall form the basis for comparison for deciding lowest bid. For further processing and award, total quoted amount by the L1 (lowest) bidder for the package shall be used for deriving individual item rate by BHEL based on % (percentage) weightage specified at Annexure I & Annexure II of Price Schedule.

1.2 Schedule B

It consists of details of free issue materials by BHEL.

1.3 Schedule C

It consists of details of tools & tackles provided by BHEL either on higher basis or on free of cost basis which are mentioned in price bid.

2.0 The work to be carried out under the contract shall, except as otherwise provided in tender conditions, include all labour, materials, tools, plant, equipment, and transport which may be required in preparation of and for full & entire execution and completion of the Works. The descriptions given in the Schedule of Quantities shall, unless otherwise stated, be held to include waste on materials, carriage and cartage, carrying in return of empties, hoisting, setting, fitting and fixing in position and all other labours necessary in and for the full and entire execution and completion as aforesaid in accordance with good practice and recognized principles as laid down in Technical Specification & elsewhere in Tender Specification.

3.0 The price bid should not contain any condition. Conditional price Bids shall be summarily rejected.

4.0 The bidder should not leave any column blank in Price Schedules.

5.0 Price Quoted shall include all taxes, & duties except **GST**.

6.0 Unless otherwise specified in the items involving cement, reinforcement steel or structural steel, these items shall be issued free of cost by BHEL.

FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION**Price Schedule**

Name of work : Repair and maintenance of RCC drain work at south side of block-4 and other area inside factory area.

SUMMARY

	Details ANNEXURE	Total Amount (Rs.)
	Total price of the package combining of Annexure-I & Annexure-II.	

Amount in words: Rs.

.....

.....

NOTE:

- 1** The evaluation currency for this tender shall be INR. Total price of the package combining of **Annexure-I & Annexure-II** to be quoted by the bidders which shall form the basis of comparison for deciding lowest bid.
For further processing & award total quoted Amount for the package by the L1 (lowest) bidder shall be used for deriving Individual item rate by BHEL based on % (percentage) weightage specified at **Annexure-I & Annexure-II** of Price Schedule.
- 2** In case of "discrepancy in words and figures", the same shall be adjusted in accordance with following rule:
 - (a)** If, in the price structure quoted for the required goods/ services/ works, there is discrepancy between the unit price and the total price (which is obtained by multiplying the unit price by the quantity), the unit price shall prevail and the total price corrected accordingly, unless in the opinion of the purchaser there is an obvious misplacement of the decimal point in the unit price, in which case the total price as quoted shall govern and the unit price corrected accordingly.
 - (b)** If there is an error in a total corresponding to the addition or subtraction of subtotals, the subtotals shall prevail and the total shall be corrected.
 - (c)** If there is a discrepancy between words and figures, the amount in words shall prevail, unless the amount expressed in words is related to an arithmetic error, in which case the amount in figures shall prevail subject of (a) and (b) above.
 - (d)** If there is such discrepancy in an offer, the same shall be conveyed to the bidder with target date upto which the bidder has to send his acceptance on the above lines and if the bidder does not agree to the decision of the purchaser, the bid is liable to be ignored.

FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION**Price Schedule : Anneuxre - I**

Name of work:- Repair and maintenance of RCC drain work at south side of block-4 and other area inside factory area.

Sr. No.	Based on DSR' 2012	Item Description	Qty.	Unit	% Weightage of item amount against total amount
1		Carriage of material up to 1 km lead by Mechanical transport including, loading, unloading & stacking -			
	1.1.1	a) Lime, Moorum, Building rubbish	5.00	cum	0.1112
	1.1.2	b) Earth	100.00	cum	2.7795
2	2.6	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m; disposed earth to be levelled and neatly dressed.			
	2.6.1	All kinds of soil.	166.00	cum	7.2097
3	2.25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations, etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5m	67.00	cum	1.8852
4	**	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:(Cement free issue by the Deptt.)			
	4.1.3	a) 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	10.00	cum	8.6508
	4.1.6	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size).	8.00	cum	6.805
5	**	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level.(Cement free issue by the Deptt.)			
	5.1.2	1 : 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size).	16.00	cum	14.4846

FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION**Price Schedule : Anneuxre - I**

Name of work:- Repair and maintenance of RCC drain work at south side of block-4 and other area inside factory area.

Sr. No.	Based on DSR' 2012	Item Description	Qty.	Unit	% Weightage of item amount against total amount
6	**	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : (Cement free issue by BHEL)			
	5.2.2	1 : 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size).	28.00	cum	31.3736
7	Ana. 5.22.6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level : (Reinforcement bars will be supplied free of cost from BHEL store).			
	5.22A.6	Thermo-Mechanically Treated bars.	2800.00	Kg	6.9572
8		Centering and shuttering including strutting, propping, etc. and removal of form for:			
	5.9.1	Foundations, footings, bases of columns, etc. for mass concrete.	220.00	sqm	11.4867
9	**	Coursed rubble masonry (second sort) with hard stone in foundation & plinth with (Excluding the cost cement and which shall be supplied free of cost by BHEL):-			
	7.7.1	Cement mortar 1:6 (1 cement : 6 coarse sand).	2.00	cum	1.8498
10	Ana. 10.2	Structural steel work in built up sections, trusses and framed work i/c cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. In tees, R.S. joists, angles, flats, channels and Rail (Structural steel, primer free issue from BHEL stores).	100.00	Kg	0.4298

FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION**Price Schedule : Anneuxre - I**

Name of work:- Repair and maintenance of RCC drain work at south side of block-4 and other area inside factory area.

Sr. No.	Based on DSR' 2012	Item Description	Qty.	Unit	% Weightage of item amount against total amount
11	**	Pointing on stone work with cement mortar 1 : 3 (1 cement : 3 fine sand):(excluding cost of cement which shall be supplied free of cost by BHEL)			
	13.33.2	Raised and cut pointing.	20.00	sqm	1.2628
12		12 mm cement plaster of mix:(Cement free issue by the Deptt.)			
	13.4.2	1 : 6 (1 cement : 6 coarse sand) .	20.00	sqm	0.6661
13	15.3	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.	1.00	cum	0.3287
14		Dismantling steel work in single sections including dismembering and stacking within 50 metres lead in:			
	15.17.2	Channels, angles, tees, flats & rails	100.00	kg	0.0218
15	15.25	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	75.00	sqm	1.856
Total : Annexure I				= Rs.	98.1585

FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION**Price Schedule : Anneuxre - II**

Name of work:- Repair and maintenance of RCC drain work at south side of block-4 and other area inside factory area.

Sr. No.	Item Description	Qty.	Unit	% Weightage of item amount against total amount
1	40 mm thick fine dressed stone flooring over 20 mm (average) thick moorum base with joints finished flush in cement mortar 1:5 (1 cement : 5 coarse sand).(excluding cost of cement and sand stone which shall be supplied free of cost by BHEL)			
	Red sand stone.	50.00	sqm	1.8415
	Total : Annexure II			1.8415
	Total : Annexure I + Annexure II			100.0000

FACTORY CIVIL CONSTRUCTION & MAINTENANCE DIVISION

Price Schedule : B

Name of work:- Repair and maintenance of RCC drain work at south side of block-4 and other area inside factory area.

The following material free issue from BHEL stores.

- 1 Cement
- 2 Reinforcement steel
- 3 Str. Steel
- 4 Red oxide primer

Price Schedule : C

Name of work:- Repair and maintenance of RCC drain work at south side of block-4 and other area inside factory area.

SCHEDULE-C

Name of work:- Repair and maintenance of RCC drain work at south side of block-4 and other area inside factory area.

- 1 Electricity charges at Rs.66.00/- per M.T. of fabrication of structural steel

Hire charges.

- | | |
|-------------------------------------|-----------------------------|
| i) Drill machine @ 252.00/- per day | } (Subject to availability) |
| ii) Jack Hammer @108.00/- per day | |

Drill machine/jack hammer rod Rs. 100.00 per rod