

3X660 MW NORTH KARANPURA STPP											
AUXILIARY SERVICE TRANSFORMERS (OIL FILLED) For NON ACC Application											
PRICE SCHEDULE											
S. No.	Item code	Item Description	Unit	Quantity	Unit Ex-Works Price (INR)	Total Ex-Works Price (INR)	ED Nil against PAC	CST/VAT @.....% of EX-Works (INR)	Service Tax @ (INR)	Freight Including Service Tax @.....% of EX-Works (INR)	Total FOR Site Price (INR)
1.0	302-11007-A	1000kVA, 11kV/0.433kV, 3 phase, 2 winding, outdoor, ONAN, Z=6.25%, Dyn1, OFF Circuit taps ±5% in steps of 2.5% (with cable box type HV, with bus-duct type LV and with solidly grounded LVN termination)	NO.	2							
2.0	302-11008-A	1600kVA, 11kV/0.433kV, 3 phase, 2 winding, outdoor, ONAN, Z=8.0%, Dyn1, OFF Circuit taps ±5% in steps of 2.5% (with cable box type HV, with bus-duct type LV and with solidly grounded LVN termination)	NO.	2							
3.0	302-11009-A	2000kVA, 11kV/0.433kV, 3 phase, 2 winding, outdoor, ONAN, Z=10.0%, Dyn1, OFF Circuit taps ±5% in steps of 2.5% (with cable box type HV, with bus-duct type LV and with solidly grounded LVN termination)	NO.	30							
4.0	302-11030-A	1000kVA, 3.3kV/0.433kV, 3 phase, 2 winding, outdoor, ONAN, Z=6.25%, Dyn1, OFF Circuit taps ±5% in steps of 2.5% (with cable box type HV, LV and with solidly grounded LVN termination)	NO.	2							
5.0	302-11060-A	5000kVA, 33kV/11.5kV, 3 phase, 2 winding, outdoor, ONAN, Z=8%, Dyn11, OFF Circuit taps ±5% in steps of 2.5% (with cable box type HV, LV and with solidly grounded LVN termination)	NO.	2							
6.0	302-11061-A	2000kVA, 33kV/3.45kV, 3 phase, 2 winding, outdoor, ONAN, Z=6%, Dyn11, OFF Circuit taps ±5% in steps of 2.5% (with cable box type HV, LV and LVN termination)	NO.	2							
7.0	302-11062-A	7500kVA, 33kV/3.45kV, 3 phase, 2 winding, outdoor, ONAN, Z=7%, Dyn11, OFF Circuit taps ±5% in steps of 2.5% (with cable box type HV, LV and LVN termination)	NO.	2							
8.0	302-11013-A	5000kVA, 11kV/3.45kV, 3 phase, 2 winding, outdoor, ONAN, Z=7%, Dyn1, OFF Circuit taps ±5% in steps of 2.5% (with cable box type HV, with bus-duct type LV and with cable box type LVN termination)	NO.	2							

AUXILIARY SERVICE TRANSFORMERS (OIL FILLED) For NON ACC Application

NOTES:-

1. BIDDER TO NOTE THAT THE COST OF TRANSFORMER SHALL INCLUDE THE COST OF ROUTINE TESTS AND SHALL BE CHARGED OUT ON ALL TRANSFORMERS WITHIN ANY ADDITIONAL COST BIDDER SHALL QUOTE ACCORDINGLY

2 BIDDER SHALL SUPPLY 10% EXTRA OIL AS PER THE QUOTED PRICE QUANTITY OF EXTRA OIL SHALL BE SUBJECT TO APPROVAL DURING DETAIL ENGINEERING

3. **CHARGES FOR CARRYING OUT SHORT CIRCUIT TEST SHALL BE PAYABLE BASED ON ACTUAL INVOICE FROM DESIGNATED LABORATORIES (CPRI BHOPAL / CPRI

4 IN CASE TYPE TESTS ARE WAIVED, THE TYPE TEST CHARGES SHALL NOT BE PAYABLE TO THE BIDDER.

5. CHARGES FOR ALL TYPE TESTS EXCEPT SHORT CIRCUIT TEST SHALL BE CONSIDERED FOR PRICE COMPARISONS PURPOSE.

DELIVERY IMPLICATION TO BHEL.

3X660 MW NORTH KARANPURA STPP									
AUXILIARY SERVICE TRANSFORMERS (OIL FILLED) - NON-ACC Application									
PRICE SCHEDULE (MANDATORY SPARES)									
S. No.	Item Description	Unit	Quantity	Unit Ex-Works (INR) Price (INR)	Total Ex- Works (INR) Price (INR)	ED	CST/VAT @.....% of EX-Works (INR)	Freight Including Service Tax @.....% of EX- Works (INR)	Total FOR Site Price (INR)
1.0	HV bushing with metal parts & gaskets	NO. EACH TYPE							
a	11.0/0.433kV, 1000KVA	NO.	3						
b	11.0/0.433kV, 1600KVA	NO.	3						
c	11.0/0.433kV, 2000KVA	NO.	3						
d	3.3/0.433kV, 1000KVA	NO.	3						
e	33.0/11.5kV, 5000KVA	NO.	3						
f	33.0/3.45kV, 2000KVA	NO.	3						
g	33.0/3.45kV, 7500KVA	NO.	3						
h	11.0/3.45kV, 5000KVA	NO.	3						
i	11.0/3.45kV, 10000KVA	NO.	3						
2.0	LV bushing with metal parts & gaskets	NO. EACH TYPE							
a	11.0/0.433kV, 1000KVA	NO.	3						
b	11.0/0.433kV, 1600KVA	NO.	3						
c	11.0/0.433kV, 2000KVA	NO.	3						
d	3.3/0.433kV, 1000KVA	NO.	3						
e	33.0/11.5kV, 5000KVA	NO.	3						
f	33.0/3.45kV, 2000KVA	NO.	3						
g	33.0/3.45kV, 7500KVA	NO.	3						
h	11.0/3.45kV, 5000KVA	NO.	3						
i	11.0/3.45kV, 10000KVA	NO.	3						
3.0	LV Neutral bushing with metal parts & gaskets	NO. EACH TYPE							

3X660 MW NORTH KARANPURA STPP									
AUXILIARY SERVICE TRANSFORMERS (OIL FILLED) - NON-ACC Application									
PRICE SCHEDULE (MANDATORY SPARES)									
S. No.	Item Description	Unit	Quantity	Unit Ex-Works (INR) Price (INR)	Total Ex- Works (INR) Price (INR)	ED	CST/VAT @.....% of EX-Works (INR)	Freight Including Service Tax @.....% of EX- Works (INR)	Total FOR Site Price (INR)
a	11.0/0.433kV, 1000KVA	NO.	1						
b	11.0/0.433kV, 1600KVA	NO.	1						
c	11.0/0.433kV, 2000KVA	NO.	1						
d	3.3/0.433kV, 1000KVA	NO.	1						
e	33.0/11.5kV, 5000KVA	NO.	1						
f	33.0/3.45kV, 2000KVA	NO.	1						
g	33.0/3.45kV, 7500KVA	NO.	1						
h	11.0/3.45kV, 5000KVA	NO.	1						
i	11.0/3.45kV, 10000KVA	NO.	1						
4.0	WTI with contacts	NO EACH TYPE							
a	11.0/0.433kV, 1000KVA	NO.	1			Nil against PAC			
b	11.0/0.433kV, 1600KVA	NO.	1						
c	11.0/0.433kV, 2000KVA	NO.	1						
d	3.3/0.433kV, 1000KVA	NO.	1						
e	33.0/11.5kV, 5000KVA	NO.	1						
f	33.0/3.45kV, 2000KVA	NO.	1						
g	33.0/3.45kV, 7500KVA	NO.	1						
h	11.0/3.45kV, 5000KVA	NO.	1						
i	11.0/3.45kV, 10000KVA	NO.	1						
5.0	OTTI with contacts	NO EACH TYPE							
a	11.0/0.433kV, 1000KVA	NO.	1						
b	11.0/0.433kV, 1600KVA	NO.	1						

3X660 MW NORTH KARANPURA STPP									
AUXILIARY SERVICE TRANSFORMERS (OIL FILLED) - NON-ACC Application									
PRICE SCHEDULE (MANDATORY SPARES)									
S. No.	Item Description	Unit	Quantity	Unit Ex-Works (INR) Price (INR)	Total Ex- Works (INR) Price (INR)	ED	CST/VAT @.....% of EX-Works (INR)	Freight Including Service Tax @.....% of EX- Works (INR)	Total FOR Site Price (INR)
c	11.0/0.433kV, 2000KVA	NO.	1						
d	3.3/0.433kV, 1000KVA	NO.	1						
e	33.0/11.5kV, 5000KVA	NO.	1						
f	33.0/3.45kV, 2000KVA	NO.	1						
g	33.0/3.45kV, 7500KVA	NO.	1						
h	11.0/3.45kV, 5000KVA	NO.	1						
i	11.0/3.45kV, 10000KVA	NO.	1						
6.0	Pressure relief Device	NO. EACH TYPE	1						
7.0	MOG	NO. EACH TYPE	1						
8.0	Buchholz relay complete	NO. EACH TYPE	1						
9.0	Set of gaskets	SET							
a	11.0/0.433kV, 1000KVA	SET	1						
b	11.0/0.433kV, 1600KVA	SET	1						
c	11.0/0.433kV, 2000KVA	SET	1						
d	3.3/0.433kV, 1000KVA	SET	1						
e	33.0/11.5kV, 5000KVA	SET	1						
f	33.0/3.45kV, 2000KVA	SET	1						
g	33.0/3.45kV, 7500KVA	SET	1						
h	11.0/3.45kV, 5000KVA	SET	1						
i	11.0/3.45kV, 10000KVA	SET	1						

3X660 MW NORTH KARANPURA STPP									
AUXILIARY SERVICE TRANSFORMERS (OIL FILLED) - NON-ACC Application									
PRICE SCHEDULE (EXTRA OIL)									
S. No.	Item Description	Unit	Quantity	Unit Ex-Works Price (INR)	Total Ex-Works Price (INR)	ED Nil against PAC	CST/VAT @.....% of EX-Works (INR)	Freight Including Service Tax @.....% of EX-Works (INR)	Total FOR Site Price (INR)
	EXTRA OIL (10%) IN SEALED NON RETURNABLE STANDARD DRUMS (Type & no. of Transformers, as below)								
1.0	1000kVA, 11kV/0.433kV, 3 phase, 2 winding, outdoor, ONAN, Z=6.25%, Dyn1, OFF Circuit taps $\pm 5\%$ in steps of 2.5% (with cable box type HV, with bus-duct type LV and with solidly grounded LVN termination)	NOS.	2						
2.0	1600kVA, 11kV/0.433kV, 3 phase, 2 winding, outdoor, ONAN, Z=8.0%, Dyn1, OFF Circuit taps $\pm 5\%$ in steps of 2.5% (with cable box type HV, with bus-duct type LV and with solidly grounded LVN termination)	NOS.	2						
3.0	2000kVA, 11kV/0.433kV, 3 phase, 2 winding, outdoor, ONAN, Z=10.0%, Dyn1, OFF Circuit taps $\pm 5\%$ in steps of 2.5% (with cable box type HV, with bus-duct type LV and with solidly grounded LVN termination)	NOS.	30						
4.0	1000kVA, 3.3kV/0.433kV, 3 phase, 2 winding, outdoor, ONAN, Z=6.25%, Dyn1, OFF Circuit taps $\pm 5\%$ in steps of 2.5% (with cable box type HV, LV and with solidly grounded LVN termination)	NOS.	2						
5.0	5000kVA, 33kV/11.5kV, 3 phase, 2 winding, outdoor, ONAN, Z=8%, Dyn11, OFF Circuit taps $\pm 5\%$ in steps of 2.5% (with cable box type HV, LV and with solidly grounded LVN termination)	NOS.	2						

3X660 MW NORTH KARANPURA STPP							
AUXILIARY SERVICE TRANSFORMERS (OIL FILLED) - NON-ACC Application							
PRICE SCHEDULE (TYPE TEST)							
S. No.	Description of Type Test	Unit	Quantity	Unit Prices (INR)	Total Prices (INR)	Service Tax (INR)	Total Prices Including Service Tax (INR)
1.0	1600kVA, 11kV/0.433kV, 3 phase, 2 winding, outdoor, ONAN, Z=6.25%, Dyn11, OLF Circuit taps $\pm 5\%$ in steps of 2.5% (with cable box type HV, with bus duct type LV and with solidly grounded LVN termination)	NO.					
1.a	TANK PRESSURE TEST	NO.	1				
1.b	TANK VACUUM TEST	NO.	1				
1.c	MEASUREMENT OF ACOUSTIC NOISE LEVEL AS PER NEMA TR-1	NO.	1				
1.d	TEMPERATURE RISE TEST AT A TAP CORRESPONDING TO MAXIMUM LOSSES. (Gas Chromatography shall be conducted on oil sample taken before & immediately after temp. rise test. Gas analysis shall be as per IS: 9434 (based on IEC: 60567), results will be interpreted as per IS: 10593 (based on IEC: 60599). Result shall be recorded for future reference).	NO.	1				
1.e	LIGHTNING IMPULSE(FULL & CHOPPED WAVE) TEST ON WINDINGS (AS PER IEC 60076-3)	NO.	1				
1.f	SHORT CIRCUIT TEST (SPECIAL TEST) AS PER IEC 60076-5**	NO.	1	AS PER NOTE 1			
2.0	1600kVA, 11kV/0.433kV, 3 phase, 2 winding, outdoor, ONAN, Z=8.0%, Dyn11, OLF Circuit taps $\pm 5\%$ in steps of 2.5% (with cable box type HV, with bus duct type LV and with solidly grounded LVN termination)	NO.					

3X660 MW NORTH KARANPURA STPP							
AUXILIARY SERVICE TRANSFORMERS (OIL FILLED) - NON-ACC Application							
PRICE SCHEDULE (TYPE TEST)							
S. No.	Description of Type Test	Unit	Quantity	Unit Prices (INR)	Total Prices (INR)	Service Tax (INR)	Total Prices Including Service Tax (INR)
2 a	TANK PRESSURE TEST	NO.	1				
2 b	TANK VACUUM TEST	NO.	1				
2 c	MEASUREMENT OF ACOUSTIC NOISE LEVEL AS PER NEMA TR-1	NO.	1				
2 d	TEMPERATURE RISE TEST AT A TAP CORRESPONDING TO MAXIMUM LOSSES. (Gas Chromatography shall be conducted on oil sample taken before & immediately after temp. rise test. Gas analysis shall be as per IS: 9434 (based on IEC: 60567), results will be interpreted as per IS: 10593 (based on IEC: 60599). Result shall be recorded for future reference).	NO.	1				
2 e	LIGHTNING IMPULSE(FULL & CHOPPED WAVE) TEST ON WINDINGS (AS PER IEC 60076-3)	NO.	1				
2 f	SHORT CIRCUIT TEST (SPECIAL TEST) AS PER IEC 60076-5**	NO.	1	AS PER NOTE 1			
3 d	2000kVA, 11kV/0.433kV, 3 phase, 2 winding, outdoor, ONAN, Z=10.0%, Dyn110BF (Circuit taps=5% at steps of 2.5% (with cable box type HV, with bus-duct type LV and with solidly grounded LVN termination)	NO.					
3 a	TANK PRESSURE TEST	NO.	1				
3 b	TANK VACUUM TEST	NO.	1				
3 c	MEASUREMENT OF ACOUSTIC NOISE LEVEL AS PER NEMA TR-1	NO.	1				

3X660 MW NORTH KARANPURA STPP						
AUXILIARY SERVICE TRANSFORMERS (OIL FILLED) - NON-ACC Application						
PRICE SCHEDULE (TYPE TEST)						
S. No.	Description of Type Test	Unit	Quantity	Unit Prices (INR)	Total Prices (INR)	Total Prices Including Service Tax (INR)
3 d	TEMPERATURE RISE TEST AT A TAP CORRESPONDING TO MAXIMUM LOSSES. (Gas Chromatography shall be conducted on oil sample taken before & immediately after temp. rise test. Gas analysis shall be as per IS: 9434 (based on IEC: 60567), results will be interpreted as per IS: 10593 (based on IEC: 60599). Result shall be recorded for future reference).	NO.	1			
3 e	LIGHTNING IMPULSE(FULL & CHOPPED WAVE) TEST ON WINDINGS (AS PER IEC 60076-3)	NO.	1			
3 f	SHORT CIRCUIT TEST (SPECIAL TEST) AS PER IEC 60076-5**	NO.	1	AS PER NOTE 1		
4 d	1000kVA, 3.3KV/0.433KV, 3 phase, 2 winding, outdoor ONAN, Z=6.25%, Dyn11, OLF, Circuit taps $\pm 5\%$ in steps of 2.5% (with cable box type HV, 11kV and with solidly grounded LVN termination)	NO.				
4 a	TANK PRESSURE TEST	NO.	1			
4 b	TANK VACUUM TEST	NO.	1			
4 c	MEASUREMENT OF ACOUSTIC NOISE LEVEL AS PER NEMA TR-1	NO.	1			

3X660 MW NORTH KARANPURA STPP							
AUXILIARY SERVICE TRANSFORMERS (OIL FILLED) - NON-ACC Application							
PRICE SCHEDULE (TYPE TEST)							
S. No.	Description of Type Test	Unit	Quantity	Unit Prices (INR)	Total Prices (INR)	Service Tax (INR)	Total Prices Including Service Tax (INR)
4 d	TEMPERATURE RISE TEST AT A TAP CORRESPONDING TO MAXIMUM LOSSES. (Gas Chromatography shall be conducted on oil sample taken before & immediately after temp. rise test. Gas analysis shall be as per IS: 9434 (based on IEC: 60567), results will be interpreted as per IS: 10593 (based on IEC: 60599). Result shall be recorded for future reference).	NO.	1				
4 e	LIGHTNING IMPULSE(FULL & CHOPPED WAVE) TEST ON WINDINGS (AS PER IEC 60076-3)	NO.	1				
4 f	SHORT CIRCUIT TEST (SPECIAL TEST) AS PER IEC 60076-5**	NO.	1	AS PER NOTE 1			
5 d	5000kVA, 33kV/HI-5kV, 3 phase, 2 winding, outdoor ONAN, Z=8%, Dyn11, OEF Circuit taps ±5% in steps of 2.5% (with cable-box type HV-LV and with solidly grounded LVN termination)	NO.					
5 a	TANK PRESSURE TEST	NO.	1				
5 b	TANK VACUUM TEST	NO.	1				
5 c	MEASUREMENT OF ACOUSTIC NOISE LEVEL AS PER NEMA TR-1	NO.	1				

3X660 MW NORTH KARANPURA STPP							
AUXILIARY SERVICE TRANSFORMERS (OIL FILLED) - NON-ACC Application							
PRICE SCHEDULE (TYPE TEST)							
S. No.	Description of Type Test	Unit	Quantity	Unit Prices (INR)	Total Prices (INR)	Service Tax (INR)	Total Prices Including Service Tax (INR)
5 d	TEMPERATURE RISE TEST AT A TAP CORRESPONDING TO MAXIMUM LOSSES. (Gas Chromatography shall be conducted on oil sample taken before & immediately after temp. rise test. Gas analysis shall be as per IS: 9434 (based on IEC: 60567), results will be interpreted as per IS: 10593 (based on IEC: 60599). Result shall be recorded for future reference).	NO.	1				
5 e	LIGHTNING IMPULSE(FULL & CHOPPED WAVE) TEST ON WINDINGS (AS PER IEC 60076-3)	NO.	1				
5 f	SHORT CIRCUIT TEST (SPECIAL TEST) AS PER IEC 60076-5**	NO.	1	AS PER NOTE 1			
6.0	2000kVA, 33kV/3.45kV, 3 phase, 2 winding, outdoor ONAN, Z=6%, Dyn11, OBF (Circuit taps ±5% in steps of 2.5% (with cable box type HV, LV and LVN termination)	NO.					
6.a	TANK PRESSURE TEST	NO.	1				
6 b	TANK VACUUM TEST	NO.	1				
6 c	MEASUREMENT OF ACOUSTIC NOISE LEVEL AS PER NEMA TR-1	NO.	1				

3X660 MW NORTH KARANPURA STPP							
AUXILIARY SERVICE TRANSFORMERS (OIL FILLED) - NON-ACC Application							
PRICE SCHEDULE (TYPE TEST)							
S. No.	Description of Type Test	Unit	Quantity	Unit Prices (INR)	Total Prices (INR)	Service Tax (INR)	Total Prices Including Service Tax (INR)
7 d	TEMPERATURE RISE TEST AT A TAP CORRESPONDING TO MAXIMUM LOSSES. (Gas Chromatography shall be conducted on oil sample taken before & immediately after temp. rise test. Gas analysis shall be as per IS: 9434 (based on IEC: 60567), results will be interpreted as per IS: 10593 (based on IEC: 60599). Result shall be recorded for future reference).	NO.	1				
7 e	LIGHTNING IMPULSE(FULL & CHOPPED WAVE) TEST ON WINDINGS (AS PER IEC 60076-3)	NO.	1				
7 f	LIGHTNING IMPULSE ON NEUTRAL (For transformer neutral earthed through NGR)	NO.	1				
7 g	SHORT CIRCUIT TEST (SPECIAL TEST) AS PER IEC 60076-5**	NO.	1	AS PER NOTE 1			
8.0	5000kVA, 11kV/3.45kV, 3 phase, 2 winding, outdoor, ONAN, Z=7%, Dyn11, ONP (Circuit taps = 9% in steps of 2.5% (with cable box type IEC, with bus duct, typically and with cable box type LVN termination))	NO.					
8.a	TANK PRESSURE TEST	NO.	1				
8 b	TANK VACUUM TEST	NO.	1				
8 c	MEASUREMENT OF ACOUSTIC NOISE LEVEL AS PER NEMA TR-1	NO.	1				

3X660 MW NORTH KARANPURA STPP							
AUXILIARY SERVICE TRANSFORMERS (OIL FILLED) - NON-ACC Application							
PRICE SCHEDULE (TYPE TEST)							
S. No.	Description of Type Test	Unit	Quantity	Unit Prices (INR)	Total Prices (INR)	Service Tax (INR)	Total Prices Including Service Tax (INR)
8 d	TEMPERATURE RISE TEST AT A TAP CORRESPONDING TO MAXIMUM LOSSES. (Gas Chromatography shall be conducted on oil sample taken before & immediately after temp. rise test. Gas analysis shall be as per IS: 9434 (based on IEC: 60567), results will be interpreted as per IS: 10593 (based on IEC: 60599). Result shall be recorded for future reference).	NO.	1				
8 e	LIGHTNING IMPULSE(FULL & CHOPPED WAVE) TEST ON WINDINGS (AS PER IEC 60076-3)	NO.	1				
8 f	LIGHTNING IMPULSE ON NEUTRAL (For transformer neutral earthed through NGR)	NO.	1				
8 g	SHORT CIRCUIT TEST (SPECIAL TEST) AS PER IEC 60076-5**	NO.	1	AS PER NOTE 1			
9 d	10000kVA, 11kV/3145kV, 3 phase, 2 winding, outdoor ONAN/ Z=9%, DV=1.00%, ONP, CH termination, 5% in steps of 2.5% (with cable box type LV with busbar type LV and with cable box type LVN termination)	NO.					
9.a	TANK PRESSURE TEST	NO.	1				
9 b	TANK VACUUM TEST	NO.	1				
9 c	MEASUREMENT OF ACOUSTIC NOISE LEVEL AS PER NEMA TR-1	NO.	1				

ANNEXURE-CIF 3X660 MW NORTH KARANPURA STPP, STAGE-I AUXILIARY SERVICE TRANSFORMERS (OIL FILLED) For Non- ACC Application						
Sl. No.	Description of items to be imported.	Unit of Measure	Qty.	Currency	Unit rate in foreign currency	Total CIF Contents
GRAND TOTAL						