

SCOPE OF WORK

The scope of work shall be as follows:

- 1) Demolishing of 2 nos. RCC beams and RCC flooring for foundation, manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 meters lead.
- 2) Earth work in excavation for foundation to get the desired depth and disposal of excavated earth lead up to 50 m and lift up to 1.5 m.
- 3) Dismantling C.I. or asbestos rain water pipe with fittings and clamps including stacking the material within 50 meters lead and refitting after completion of work.
- 4) Providing & laying in position cement concrete of grade 1:4:8 excluding the cost of centering and shuttering - All work up to plinth level.
- 5) Providing and fixing of Carbon Steel galvanized (min 5 micron) dash fastener (min 5 micron) of 12 mm dia double threaded 6.8 grade counter sunk head screw comprising of 12 mm dia polyamide PA 6 grade sleeve in column. Size 12mm x 160 mm.
- 6) Steel reinforcement for R.C.C. work of foundation, column and beams of +4.0 & +7.0 Mtr (approximate) including straightening, cutting, bending, placing in position and binding all complete.
- 7) Centering and shuttering including strutting, propping etc. and removal of form work for foundations, footings, bases for columns, columns, piers, abutments, pillars, posts and struts.
- 8) Providing & laying in position cement concrete of grade 1:1.5:3 for Raft, Column, floor and beams of level +4.0 & +7.0 Mtr (approximate).
- 9) Filling available excavated earth in sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.
- 10) Casting of concrete floor (200mm thick) and finishing the top surface with ironite mix.
- 11) Carriage of Materials by Mechanical Transport including loading, unloading and stacking of Building Rubbish.
- 12) Miscellaneous works which are not included in the scope to complete the above work.