

BOQ cum Price Distribution Sheet**Name of Work: Repair of the cracked beams (2 nos.) of B1 column in OPS**

S. No.	Description	Unit	Qty	Activity wise percentage against total cost (without GST)	GST tariff to be quoted by bidder in %
1.1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead.	Cum	3.756	9.94%	-
1.2	Extra for cutting reinforcement bars manually/ by mechanical means in R.C.C. or R.B. work (Payment shall be made on the cross sectional area of R.C.C. or R.B. work).	Sqm	2.66	1.49%	-
1.3	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 Sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m. All kind of Soil	Cum	1.064	0.15%	-
1.4	Dismantling C.I. or asbestos rain water pipe with fittings and clamps including stacking the material within 50 metres lead	Metre	10.00	0.59%	-
2	Providing & laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level. PCC (1:4:8)	Cum	0.204	0.77%	-
3	Carbon Steel galvanised (min 5 micron) dash fastner (min 5 micron) of 12 mm dia double threaded 6.8 grade counter sunk head screw comprising of 12 mm dia polyamide PA 6 grade sleeve. Size 12mm x 160 mm	10 Nos.	40	2.00%	-
4.1	Providing & laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level. RCC (1:1.5:3)	Cum	5.542	25.36%	-
4.2	Extra for concrete work in superstructure above floor V level for each four floors or part thereof.	Cum	3.66	2.80%	-
5.1	Centering and shuttering including strutting, propping etc. and removal of form work for Foundations, footings, bases for columns	Sqm	2.08	0.39%	-
5.2	Centering and shuttering including strutting, propping etc. and removal of form work for Columns, piers, abutments, pillars, posts and struts	Sqm	32.40	16.20%	-
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level TMT bars of grade Fe-500D or more	Kg	554.2	30.97%	-
7	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Cum	1.324	0.21%	-
8	Carriage of Materials by Mechanical Transport including loading,unloading and stacking. Building Rubbish	Cum	3.496	0.31%	-
9	Miscellaneous Items (i.e. PVC pipe 200mm dia, bends, clamps etc.)	Lot	1	8.82%	-
	TOTAL			100.00%	

Note: 1). Total amount quoted by the bidder in Price Bid shall be distributed & allocated to the individual activity as per above percentage. Basic rate (without GST) for individual line item shall be worked out as per respective amount for all activities.

2). Payment shall be made on actual GST rate or quoted rate, whichever is lower, on actual consumption.

3). The correctness of GST tariff and its payment to government shall be the sole responsibility of supplier. Accordingly, supplier has to ensure the tariff of GST quoted for the above activities.

4) The actual quantity used in the final work may vary upto $\pm 10\%$ for individual activities vis-à-vis the quantity mentioned above.

5) L-1 shall be decided on overall cost basis.