

A. Bill of Quantity: -

Sl.no.	DESCRIPTION	QTY	Unit
1.	As per scope of work PFR(Pre-dispatch inspection) of IPBD, SPBD & NSPBD inside BHEL, CFP, Rudrapur Plant on rate of Rs./Duct	2800	nos

(B) SCHEDULE OF START AND COMPETION OF WORK:-

Contract Period will 12 months from the date of work order.

SL. NO.	ACTIVITY	DATE OF COMPLETION
1	Mobilization of requisite manpower.	Within 10 days of receipt of W.O.
2	PFR(Pre-dispatch inspection) of IPBD, SPBD & NSPBD	As per clause B(i) of Annexure-C
3	Demobilization of manpower deployed	Within one week of completion of W.O. after obtaining no objection certificate from PDN department.

(C) PROCEDURE & SCOPE OF WORK FOR WINDOW ASSEMBLY & PFR CLEARANCE

V)	PROCEDURE & SCOPE OF WORK FOR WINDOW ASSEMBLY
1.1	Sifting of ducts & raw material gasket, fasteners for window assembly.
1.2	Cutting & pasting of gasket as per drawing.
1.3	Fitting of window by tightening of fasteners.
1.4	Cleaning of duct after window assembly.
1.5	Sifting of rubber scrap to scrap yard.
VI)	PFR ACITIVITY OF IPBD, SPBD & NSPBD
1.1	Repainting of IPBD & SPBD by single coat.
1.2	Touch up work IPBD & SPBD where it's required.
1.3	Cleaning of ducts by cloth or washing.
1.4	Dent removal from enclosure & conductor.
1.5	Sticker pasting on enclosure.
1.6	Other points clearance marked by quality department for PFR clearance.
1.7	Sifting of ducts by hydra.(hydra & operator provide by BHEL)

PREPARED BY:

APPROVED BY: