

A. Bill of Quantity as per following

Bill of quantity for PPC Items :-			
Sl. No.	Work Description	Unit	Quantity in Kgs.
1	Plain Makeup pieces/ 1/3 channel Rings /Rain Hood/Shunt Plate/Packers/Backing Tube	Kg.	25000
2	Fabrication of : Window Makeup Pieces with window as per drawing no. 2100100248	Kg.	20000
3	Fabrication of : Shorting Bar /Wallfarme	Kg.	8000
4	Fabrication of : Window Makeup Pieces with window as per drawing no. 3537111093	Kg.	7000
Total qty. in Kgs.			60000

(B) SCHEDULE OF START AND COMPETION OF WORK:

Duration of this contract will be 12 months from the date of work order/LOI.

Sl. No.	ACTIVITY	DATE OF COMPLETION
1	Mobilization of requisite manpower.	Within one week of receipt of W.O.
2	Fabrication of PPC items	- Work order quantity in 12 months progressively. Monthly annexure will be provided to contractor for work loading. - Time of work completion shall be as per schedule given at Sl. No.9 of (Liquidated damage) of SCC as per Annexure-C.
3	Demobilization of manpower deployed	Within one week of completion of W.O. after obtaining no objection certificate from PDN department.

PREPARED BY:

[Signature]
19.12.2020

APPROVED BY:


[Signature]
19.12.2020

Page /3


(C) FEBRICATION PROCDURE & SCOPE OF WORK

FABRICATION PROCDURE	
1.0	FABRICATION OF PLAIN/WINDOW MAKE UP PICES :
1.1	Shifting of raw material from BHEL stores to fabrication station.
1.2	Cutting/Shearing of sheet as per requirement of fabrication.
1.3	Rolling of sheet as par dia given in drawing
1.4	Offer for in process inspection (DP & Dimension) by BHEL/Qty
1.5	Dressing & roughing of makeup pieces.
1.6	Punching of Project name & Dia by hard punch on makeup pieces.
1.7	Offering for final inspection and clearance from BHEL/QLY through Route Card for each job separately. Route Card to be filled by shop supervisor of contractor
1.8	Offer for in process inspection (DP & Dimension) by BHEL/Qty
1.9	Dressing & roughing
1.10	Offering for final inspection and clearance from BHEL/QLY through Route Card for each job separately. Route Card to be filled by shop supervisor of contractor.
2.0	FABRICATION OF SHORTING BAR/WALL FARMER/ RAIN HOOD :
2.1	Shifting of raw material from BHEL stores to fabrication station.
2.2	Cutting/Shearing of sheet as per requirement of fabrication.
2.3	Rolling/bending of sheet/flat as per drawing
2.4	Welding/Drilling/ Slotting as per drawing
2.5	Punching of Project name & BOM No. by hard punch
2.6	Offer for in process inspection (DP & Dimension) by BHEL/Qty.
2.7	Dressing & roughing
2.8	Offering for final inspection and clearance from BHEL/QLY through Route Card for each job separately. Route Card to be filled by shop supervisor of contractor.
1.0	FABRICATION OF WINDOW MAKE UP PICES drg. No. 21001000248 :
1.1	Shifting of raw material from BHEL stores to fabrication station.
1.2	Marking/Cutting/welding of Al. Flat for Window cover as per requirement of fabrication.
1.3	Marking/Cutting of sheet for Window cover as per requirement of fabrication.
1.4	Marking/Cutting/welding of unequal angle as per requirement of fabrication.
1.5	Cutting/Shearing of sheet as per requirement of fabrication.
1.6	Rolling of sheet as par dia given in drawing
1.7	Tagging/Welding of Window frame with make up pieces
1.6	Offer for in pprocess inspection (DP & Dimension) by BHEL/Qty

PREPARED BY:


 19.12.2020

APPROVED BY:



 19-12-2020

Page /3

Annexure-E**BOQ , SCHEDULE OF WORK & FABRICATION
PROCEDURE**


1.5	Dressing & roughing of makeup pieces.
1.6	Punching of Project name & Dia by hard punch on makeup pieces.
1.7	Offering for final inspection and clearance from BHEL/QLY through Route Card for each job separately. Route Card to be filled by shop supervisor of contractor
1.8	Offer for in process inspection (DP & Dimension) by BHEL/QLY
1.9	Dressing & roughing
1.10	Offering for final inspection and clearance from BHEL/QLY through Route Card for each job separately. Route Card to be filled by shop supervisor of contractor.

PREPARED BY:


19/12/2020

APPROVED BY:

Page /3


19/12/2020

Annexure-H1

PRICE BID


(Tender Enquiry No.: ----- Dt: -----)

Sl. No.	Work Description	Unit	Quantity in Kgs.	Unit Rate per kg. in Rs.	Total value in Rs.
1	Plain Makeup pieces/ 1/3 channel Rings /Rain Hood/Shunt Plate/Packers/Backing Tube	Kg.	25000		
2	Fabrication of : Window Makeup Pieces with window as per drawing no. 2100100248	Kg.	20000		
3	Fabrication of : Shorting Bar /Wallfarme	Kg.	8000		
4	Fabrication of : Window Makeup Pieces with window as per drawing no. 3537111093	Kg.	7000		
Sub-Total value in Rs.					
SGST @ 6%					
CGST @ 6%					


- We confirm that all the terms & conditions of this tender enquiry are acceptable to us & we have quoted the rates accordingly.
- We confirm that we are aware of the site & the working environment.

(Signature & stamp of bidder)

PREPARED BY:


 15.12.2020

APPROVED BY:


 19-12-2020

Page 1/2

Annexure-H2

UN-PRICE BID


(Tender Enquiry No.: ----- Dt: -----)

Sl. No.	Work Description	Unit	Quantity in Kgs.	Unit Rate per kg. in Rs.	Total value in Rs.
1	Plain Makeup pieces/ 1/3 channel Rings /Rain Hood/Shunt Plate/Packers/Backing Tube	Kg.	25000		
2	Fabrication of : Window Makeup Pieces with window as per drawing no. 2100100248	Kg.	20000		
3	Fabrication of : Shorting Bar /Wallfarme	Kg.	8000		
4	Fabrication of : Window Makeup Pieces with window as per drawing no. 3537111093	Kg.	7000		
Sub-Total value in Rs.					
SGST @ 6%					
CGST @ 6%					

- We confirm that all the terms & conditions of this tender enquiry are acceptable to us & we have quoted the rates accordingly.
- We confirm that we are aware of the site & the working environment.

(Signature & stamp of bidder)

PREPARED BY:


 19.12.2020

APPROVED BY:


 19.12.2020