

CORRIGENDUM:

RFQ NO: BKC0000007

"HT Tender, Technical Spec: PS-439-1121:

A) Page 6 of 52, Cl. 4.0 Vendor Scope (deliverables):

(i) Sl. No. 1: Item description revised to 'Concrete pedestal 250X250X160mm(h) @ 1:2:4 ratio + 15mm coping'.

(ii) Sl. No. 2: Qty for NITO bond revised to '400 Liters'.

C) Page 13 of 52: Clause 8.6: Installation of String inverters, Sl. No. (2) shall be replaced with:

Vendor shall install the inverters using two-column structure with two independent pedestals of size minimum 250x 250 x 160 (h) mm + 15mm coping @ 1:2:4 ratio. The structure shall be made of GI ISA / cold-formed angles of minimum 3mm thick as per IS: 2062, IS: 811, IS: 808 as applicable.

D) Annexure A1 , Annexure A2 stands revised accordingly.

TECHNICAL BID ENCLOSURE FOR COMPLIANCE OF QUOTE : UNPRICED BID (Indigenous vendors)										
RFQ No. BKC0000007 Dtd.21.02.2017 Due Date (Tech Bid):01.03.2017										
Sl No.	Material Code	DESCRIPTION	ADDITIONAL DESCRIPTION	QTY	UNIT	TAXES				REMARKS
						ED %	CST %	VAT %	S. TAX%	
1	PS0679069321	Concrete pedestal 250X250X160mm(h) @ 1:2:4 ratio+15 mm coping.	As per spec:PS-439-1121	11580	Nos	NA			NA	TAXES INCLUDED
2	PS0679069330	NITO Bond Epoxy Bonding agent	As per spec:PS-439-1121	400	Ltr	NA			NA	TAXES INCLUDED
3	PS0679069348	4 sq.mm Cu, XLPO, FRLS, unarmoured DC Cable	As per spec:PS-439-1121	14500	Mtrs	NA			NA	TAXES INCLUDED
4	PS0679069356	3CX 35sqmm Al, XLPE, armoured cable	As per spec:PS-439-1121	1600	Mtrs	NA			NA	TAXES INCLUDED
5	PS0679069364	1.1kV, 3CX185 sq.mm Al, XLPE armoured cable	As per spec:PS-439-1121	80	Mtrs	NA			NA	TAXES INCLUDED
6	PS0679069380	1.1kV, 3CX300 sq.mm Al, XLPE armoured cable	As per spec:PS-439-1121	60	Mtrs	NA			NA	TAXES INCLUDED
7	PS0679069399	1.1kV, 3CX400 sq.mm Al, XLPE armoured cable	As per spec:PS-439-1121	850	Mtrs	NA			NA	TAXES INCLUDED
8	PS0679069402	1.1kV, 3CX500 sq.mm Al, XLPE armoured cable	As per spec:PS-439-1121	160	Mtrs	NA			NA	TAXES INCLUDED
9	PS0679069410	11KV 3Cx185Sqmm Al, XLPE (E) armoured cable	As per spec:PS-439-1121	60	Mtrs	NA			NA	TAXES INCLUDED
10	PS0679069690	ACCB 4 In 1 Out	As per spec:PS-439-1121	1	Nos	NA			NA	TAXES INCLUDED
11	PS0679069429	ACCB 5 In 1 Out	As per spec:PS-439-1121	1	Nos	NA			NA	TAXES INCLUDED
12	PS0679069437	ACCB 7 In 1 Out	As per spec:PS-439-1121	4	Nos	NA			NA	TAXES INCLUDED
13	PS0679069445	LTPDB 3IN 1Out with MFM	As per spec:PS-439-1121	2	Nos	NA			NA	TAXES INCLUDED
14	PS0679069453	Transformer 700KVA ONAN 11KV/415V Dyn11	As per spec:PS-439-1121	1	Nos	NA			NA	TAXES INCLUDED
15	PS0679069461	Transformer 1100KVA ONAN 11KV/415V Dyn11	As per spec:PS-439-1121	1	Nos	NA			NA	TAXES INCLUDED
16	PS0679069470	HT panel 11KV, 1In 1 Out, outdoor, VCB 630A, 25KA/1sec, MFM: 0.5s class	As per spec:PS-439-1121	2	Nos	NA			NA	TAXES INCLUDED
17	PS0679069488	Weather proof Male & Female Snap-on (MC4 type) Connectors for 4 sq.mm	As per spec:PS-439-1121	650	Set	NA			NA	TAXES INCLUDED
18	PS0679069496	Cable tray 100mm(W)X50mm(H)X2mm(T)	As per spec:PS-439-1121	2800	Mtrs	NA			NA	TAXES INCLUDED
19	PS0679069500	Copper globe type 1A	As per spec:PS-439-1121	18	Nos	NA			NA	TAXES INCLUDED
20	PS0679069518	Chemical earthing Material	As per spec:PS-439-1121	1	Set	NA			NA	TAXES INCLUDED
21	PS0679069658	Switchyard Fence & Lighting	As per spec:PS-439-1121	2	Set	NA			NA	TAXES INCLUDED
22	PS0679069534	25X3 mm GI strip for structure earthing	As per spec:PS-439-1121	3650	Mtrs	NA			NA	TAXES INCLUDED
23	PS0679069542	25 X 6 mm GI strip for Equip earthing	As per spec:PS-439-1121	1600	Mtrs	NA			NA	TAXES INCLUDED
24	PS0679069550	50 X 6 mm GI strip for Switchyard Equip earthing	As per spec:PS-439-1121	200	Mtrs	NA			NA	TAXES INCLUDED
25	PS0679069569	Tools & Equipments	As per spec:PS-439-1121	2	Set	NA			NA	TAXES INCLUDED
26	PS0679069666	Data & Communication Accessories	As per spec:PS-439-1121	1	Set	NA			NA	TAXES INCLUDED
27	PS0679069585	Fire Fighting anc Safety Equipment	As per spec:PS-439-1121	1	Set	NA			NA	TAXES INCLUDED
28	PS0679069674	Module Cleaning System	As per spec:PS-439-1121	1	Set	NA			NA	TAXES INCLUDED
29	PS0679069607	Weather Monitoring Station (WMS)	As per spec:PS-439-1121	1	Set	NA			NA	TAXES INCLUDED
30	PS0679069615	Data Management and Monitoring Devices	As per spec:PS-439-1121	1	Set	NA			NA	TAXES INCLUDED
31	PS0679069682	Miscellaneous Supply items	As per spec:PS-439-1121	1	Set	NA			NA	TAXES INCLUDED
32	PS0679069704	Spares	As per spec:PS-439-1121	1	Set	NA			NA	TAXES INCLUDED
33	PS0679069623	Unloading, storing, shifting, I&C of 940KW SPV power plant	As per spec:PS-439-1121	1	AU	NA	NA	NA		TAXES INCLUDED
34	PS0679069631	Unloading, storing, shifting, I&C of 650KW SPV power plant	As per spec:PS-439-1121	1	AU	NA	NA	NA		TAXES INCLUDED
35	PS0679069640	AMC for 10 Years of 940KW & 650KW SPV Power Plants	As per spec:PS-439-1121	120	AU	NA	NA	NA		TAXES INCLUDED
36	Freight Charge including Service Tax on Freight: Included in Quoted rates									

Note:1. The quoted prices shall be on "FOR" basis to project site: SURAT,GUJARAT.

2. The quoted prices shall be inclusive of all Taxes & Duties, Packing & Forwarding charges and Freight.

3. However, the percentage of taxes considered against each item shall be indicated in the column for Taxes for the purpose of availing Tax Credit.

4. **ED shall not be considered as the project is under MNRE approval. Hence all inclusive rate for Supply is to be quoted without ED for Supply. However, the prevailing rate of ED shall be indicated in SCC (Annexure B). In case any item is rejected by MNRE, ED shall be reimbursed for that item at actuals.

5. The above format only shall be used for compliance. (reproducing on your letter head is acceptable).

6. Insurance will be in BHTEL scope.

AUTHORISED SIGNATORY WITH SEAL

PRICED BID (Indigenous Vendors)											
RFQ No. BKC0000007 Dtd.21.02.2017 Due Date (Tech Bid): 01.03.2017											
SI No.	Material Code	DESCRIPTION	QTY	UNIT	Unit Rate (Rs.)	Total Value (Rs.) (Rate X Qty)	TAXES				Remarks
							ED %	CST%	VAT %	S TAX%	
1	PS0679069321	Concrete pedestal 250X250X160mm(h) @1:2:4 ratio+15 mm coping.	11580	Nos			NA			NA	TAXES INCLUDED
	Unit rate in words:										
2	PS0679069330	NITO Bond Epoxy Bonding agent	400	Ltr			NA			NA	TAXES INCLUDED
	Unit rate in words:										
3	PS0679069348	4 sq.mm Cu, XLPO, FRLS, unarmoured DC Cable	14500	Mtrs			NA			NA	TAXES INCLUDED
	Unit rate in words:										
4	PS0679069356	3C X 35sqmm Al, XLPE, armoured cable	1600	Mtrs			NA			NA	TAXES INCLUDED
	Unit rate in words:										
5	PS0679069364	1.1kV, 3CX185 sq.mm Al, XLPE armoured cable	80	Mtrs			NA			NA	TAXES INCLUDED
	Unit rate in words:										
6	PS0679069380	1.1kV, 3CX300 sq.mm Al, XLPE armoured cable	60	Mtrs			NA			NA	TAXES INCLUDED
	Unit rate in words:										
7	PS0679069399	1.1kV, 3CX400 sq.mm Al, XLPE armoured cable	850	Mtrs			NA			NA	TAXES INCLUDED
	Unit rate in words:										
8	PS0679069402	1.1kV, 3CX500 sq.mm Al, XLPE armoured cable	160	Mtrs			NA			NA	TAXES INCLUDED
	Unit rate in words:										
9	PS0679069410	11KV 3Cx185Sqmm Al, XLPE (E) armoured cable	60	Mtrs			NA			NA	TAXES INCLUDED
	Unit rate in words:										
10	PS0679069690	ACCB 4 In 1 Out	1	Nos			NA			NA	TAXES INCLUDED
	Unit rate in words:										
11	PS0679069429	ACCB 5 In 1 Out	1	Nos			NA			NA	TAXES INCLUDED
	Unit rate in words:										
12	PS0679069437	ACCB 7 In 1 Out	4	Nos			NA			NA	TAXES INCLUDED
	Unit rate in words:										
13	PS0679069445	LTPDB 3IN 1Out with MFM	2	Nos			NA			NA	TAXES INCLUDED
	Unit rate in words:										
14	PS0679069453	Transformer 700KVA ONAN 11KV/415V Dyn11	1	Nos			NA			NA	TAXES INCLUDED
	Unit rate in words:										
15	PS0679069461	Transformer 1100KVA ONAN 11KV/415V Dyn11	1	Nos			NA			NA	TAXES INCLUDED
	Unit rate in words:										
16	PS0679069470	HT panel 11KV, 1In 1 Out, outdoor, VCB 630A, 25KA/1sec, MFM: 0.5s class	2	Nos			NA			NA	TAXES INCLUDED
	Unit rate in words:										
17	PS0679069488	Weather proof Male & Female Snap-on (MC4 type) Connectors for 4 sq.mm	650	Set			NA			NA	TAXES INCLUDED
	Unit rate in words:										
18	PS0679069496	Cable tray 100mm(W)X50mm(H)X2mm(T) Perforated type GI with coupler plate, H/W and cover of 2 mm Thk	2800	Mtrs			NA			NA	TAXES INCLUDED
	Unit rate in words:										
19	PS0679069500	Copper globe type LA	18	Nos			NA			NA	TAXES INCLUDED
	Unit rate in words:										
20	PS0679069518	Chemical earthing Material Electrodes, backfill compound etc.	1	Set			NA			NA	TAXES INCLUDED
	Unit rate in words:										
21	PS0679069658	Switchoyard Fence & Lighting	2	Set			NA			NA	TAXES INCLUDED
	Unit rate in words:										
22	PS0679069534	25X3 mm GI strip for structure earthing	3650	Mtrs			NA			NA	TAXES INCLUDED
	Unit rate in words:										
23	PS0679069542	25 X 6 mm GI strip for Equip earthing	1600	Mtrs			NA			NA	TAXES INCLUDED
	Unit rate in words:										
24	PS0679069550	50 X 6 mm GI strip for Switchoyard Equip earthing	200	Mtrs			NA			NA	TAXES INCLUDED
	Unit rate in words:										
25	PS0679069569	Tools & Equipments	2	Set			NA			NA	TAXES INCLUDED
	Unit rate in words:										
26	PS0679069666	Data & Communication Accessories	1	Set			NA			NA	TAXES INCLUDED
	Unit rate in words:										
27	PS0679069585	Fire Fighting anc Safety Equipment	1	Set			NA			NA	TAXES INCLUDED
	Unit rate in words:										
28	PS0679069674	Module Cleaning System	1	Set			NA			NA	TAXES INCLUDED
	Unit rate in words:										
29	PS0679069607	Weather Monitoring Station (WMS)	1	Set			NA			NA	TAXES INCLUDED
	Unit rate in words:										
30	PS0679069615	Data Management and Monitoring Devices	1	Set			NA			NA	TAXES INCLUDED
	Unit rate in words:										

31	PS0679069682	Miscellaneous Supply items	1	Set			NA			NA	TAXES INCLUDED
	Unit rate in words:										
32	PS0679069704	Spares	1	Set			NA			NA	TAXES INCLUDED
	Unit rate in words:										
33	PS0679069623	Unloading, storing, shifting, I&C of 940KW SPV power plant	1	AU			NA	NA	NA		TAXES INCLUDED
	Unit rate in words:										
34	PS0679069631	Unloading, storing, shifting, I&C of 650KW SPV power plant	1	AU			NA	NA	NA		TAXES INCLUDED
	Unit rate in words:										
35	PS0679069640	AMC for 10 Years of 940KW & 650KW SPV Power Plants	120	AU			NA	NA	NA		TAXES INCLUDED
	Unit rate in words:										
36	Freight Charge including Service Tax on Freight		Lumpsum								

Note: 1. The quoted prices shall be on "FOR" basis to project site: SURAT, GUJARAT.
2. The quoted prices shall be inclusive of all Taxes & Duties, Packing & Forwarding charges and Freight.
3. However, the percentage of taxes considered against each item shall be indicated in the column for Taxes for the purpose of availing Tax Credit.
4. **ED shall not be considered as the project is under MNRE approval. Hence all inclusive rate for Supply is to be quoted without ED for Supply. However, the prevailing rate of ED shall be indicated in SCC (Annexure B). In case any item is rejected by MNRE, ED shall be reimbursed for that item at actuals.
5. The above format only shall be used for compliance. (reproducing on your letter head is acceptable).
6. Insurance will be in BHEL scope.

AUTHORISED SIGNATORY WITH SEAL