

BHARAT HEAVY ELECTRICAL LIMITED , JHANSI						
FACTORY CIVIL DEPARTMENT						
Blank PRICE BID						
Name of work:- Energy conservation by enhancing the natural illumination in sheds of factory area.						
Tender Enq No-FCX/TW/21/20/R						
Sl. No.	Description of Work	% Allocation (Item-wise)	Unit	Quantity	Rate per Unit (in Rs.)	Amount (in Rs.)
1	Providing and fixing fire retardant and U.V. resistant profiled and solid transparent embossed polycarbonate sheet of minimum 3 mm thick of matching profile at the roof top of manufacturing blocks including: • Removal of existing old GS Sheet/ Galvalume Sheet including removal of ridges, hips valley, gutters etc. and stacking the material with 50 meters lead. To avoid breakage of sheets, adjacent sheets may also be required to be removed /loosened and then fixed accordingly. • Rates shall be inclusive of GI hooks, self-tapping screws or any other material required for fixing. For measurement, overlap between new and existing sheet will not be deducted and would be considered during calculation of area. Whereas, the overlap arising between new sheets would be deducted during calculation of area. During dismantling, if adjacent AC sheet gets broken, it shall be provided free of cost from BHEL and the fixing & installation shall be done by contractor at his own cost. The above item comprises of all the activities required to replace the existing sheet with Polycarbonate Sheet.	68.7418397626	Sqm	165.00	-	0

2	Providing and fixing fiberglass reinforced plastic sheet 2 mm thick corrugated of matching profile at the roof top of manufacturing blocks including: • Removal of existing old GS Sheet/ AC sheet including removal of ridges, hips valley, gutters etc. and stacking the material with 50 meters lead. To avoid breakage of sheets, adjacent sheets may also be required to be removed /loosened and then fixed accordingly. • Rates shall be inclusive of GI hooks, self-tapping screws or any other material required for fixing. For measurement, overlap between new and existing sheet will not be deducted and would be considered during calculation of area. Whereas, the overlap arising between new sheets would be deducted during calculation of area. During dismantling, if adjacent AC sheet gets broken, it shall be provided free of cost from BHEL and the fixing & installation shall be done by contractor at his own cost. The above item comprises of all the activities required to replace the existing sheet with FRP Sheet.	31.2581602374	sqm	115.00	-	0
	Total	100.0000%				
	IN WORDS	0				

Note -GST extra as applicable

1. **Bidder has to quote in above unlocked cell (G-09) only.** Item rate shall be calculated automatically. Calculated item rates upto four decimal points may be adjusted w.r.t. gross total amount and it shall be the itemwise final rate for execution of contract and all other purposes.
2. Quoted gross total amount should be considered only if quoted in this excel sheet and print out of this should only be considered for evaluation. If Price is quoted in any other format other than the Excel Sheet enclosed to the NIT , the offer of the bidder will be rejected
3. During the execution , the quantity of various items may vary to any extent depending on requirement of work/site and as per discretion of BHEL.

(Signature and Seal of Contractor)