



BHARAT HEAVY ELECTRICALS LIMITED
PROJECT ENGINEERING MANAGEMENT, NOIDA

Date-21-Jan-26

CORRIGENDUM- 01

PROJECT	:	2 X 660 MW CSPGCL Korba West TPP - EPC
PACKAGE	:	Water Treatment Package
ENQUIRY NO	:	77/25/6254/AMI dated 06.01.2026
SUBJECT	:	Technical amendment to Technical Specification

Type of Corrigendum			
Technical Corrigendum -	<input checked="" type="checkbox"/>	Commercial Corrigendum -	<input type="checkbox"/>

Bidders are requested to note the following:

Technical amendment to Technical Specification for subject tender in enclosed.

All other terms and conditions of the tender enquiry remain unchanged. All the bidders are requested to quote accordingly.

Yours faithfully,

For and on behalf of BHEL

Amit Kumar
Manager/BOP



**AMENDMENT TO TECHNICAL SPECIFICATION FOR
WATER TREATMENT PACKAGES
2 X 660 MW SUPER CRITICAL THERMAL POWER PROJECT, HTPS, KORBA WEST
(PE-TS-530-404-W001)**

BHEL DOCUMENTS NO.:

TECHNICAL AMENDMENT NO # 2

REV. NO. 00

DATE: 21.01.2026

Page 1 of 1

The following modifications with respect to Technical Specification for Water Treatment Packages. BHEL's Technical specification no PE-TS-530-404-W001 shall apply.

Bidder to note that existing clauses/ details as appearing in the specification stands deleted and clauses/details as mentioned in "Modified to or Read as" column shall be applicable and complied by the bidder as listed below in **SCHEDULE A**.

SCHEDULE-A

MODIFIED CLAUSES/ PAGE NUMBERS:

SL NO.	SECTION	SUB-SECTION/ DESCRIPTION	CLAUSE NO	PAGE NO	EXISTING	ADDITION/ MODIFICATION
1.	-	INTENT OF SPECIFICATION	2b.	22 OF 3511	Island-2: DM tanks & PH, Control/ RIO Room, MCC (MV/LV as applicable), Sewage Collection Sumps, battery room, Sewage networking, transformers, Analyzer room, Roads, drains (process drains & storm water drains), Paving, Misc. foundations for equipment & piping, Cable Rack, Cable vault, HVAC & its building (if applicable), toilet blocks, associated material handling e.g. Cranes, electric hoists & Chain pulley block etc.	To be read as- Island-2: CST tanks & PH , Control/ RIO Room, MCC (MV/LV as applicable), Sewage Collection Sumps, battery room, Sewage networking, transformers, Analyzer room, Roads, drains (process drains & storm water drains), Paving, Misc. foundations for equipment & piping, Cable Rack, Cable vault, HVAC & its building (if applicable), toilet blocks, associated material handling e.g. Cranes, electric hoists & Chain pulley block etc.
2.	SECTION – I	ANNEXURE XII: DRAWINGS / P&I DIAGRAM FOR PRE-TREATMENT PLANT (SHEET 1 OF 2)	-	744 OF 3511	-	One (1) nos. TDS analyser shall be provided by bidder at common discharge header of DM Plant Feed Pumps.