

NIT number 34337
Corrigendum 01 dated 12-Sep-2017

Ref: TENDER NOTICE NO.: CL/04/17-18 **DATED:** 30/08/2017

Laying of Main water line from Municipal Main Line to Shopping complex in BHEL R&D Township

Sir,

In the above cited NIT number in schedule A, at item No.15 the Quantity, was mentioned as 2.0 Sq.m instead of 2 Each. The amendment is reproduced below;

Item No.	Description of item of work	Quantity - existing	Quantity – Read As
15.	Constructing masonry Chamber 90x90x100 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for sluice valve, with C.I. surface box 100 mm top diameter, 160 mm bottom diameter and 180 mm deep (inside) with chained lid and RCC top slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), i/c necessary excavation, foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick, finished with a floating coat of neat cement complete as per standard design : With common burnt clay F.P.S.(non modular) bricks of class designation 7.5 without cost of cement. CEMENT will be issued Free of cost.	2.0 Sq.m	2 Each

Accordingly, please submit your quotation, taking into above corrigendum /change into consideration.

With rgds
Nalini Thilak /AGM-CWC
Bharat Heavy Electricals Limited,
Corporate Research and Development
Vikasnagar, Hyderabad-500 093, India
Ph: +91 40 2388 2454;
