पावर सेक्टर- पश्चिमी क्षेत्र Power Sector-Western Region श्रीमोहिनी काम्पलेक्स, 345 किंग्सवे, नागपुर Shreemohini complex, 345 Kingsway Nagpur - 440 001 फोन / Phone 0712- 3048600, फैक्स FAX: 0712- 3048699 www.bhelpswr.co.in

Ref: BHE/PW/PUR/2101094/Corg-01	Page 1 of 2	Date: 30/08/2021
To	rage 1 01 Z	
ALL BIDDERS,		

Sub: Corrigendum-01: Amendment to Tender specification document & due date extension

Reference:

- 1. E-Tender specification No: 2101094
- 2. **Scope of work:** Detailed drawing preparation based on Input design drawings provided by BHEL-Engineering Centers for Flue Gas Desulphurization (FGD) Package as specified in scope and getting approval from BHEL- Engineering Centers/ NTPC. Fabrication and supply of finished product (procurement of raw structural steel will be in the scope of bidder) i.e. structures of FGD as per BOM/Drawings at 2X500 MW NTPC Mauda, Stage-I, TPP-FGD, Maharashtra.

Bidders to kindly take note of the following:

AA) Amendment to tender condition:

GA Drawings attached with this Corrigendum (for tendering purpose only) shall form the integral part of the tender Document (Vol-IA-Technical Conditions of contract).

BB) Amendment to tender condition:

S.	Cl. Of Tender	Description	Existing Provision	Amended as
No.	Specification			
1	Vol-IA-TCC- Chapter-II, Sl. No. 2 (b), Page 29 of 72	Scope of work	A list of structural steel sections requirement- (TENTATIVE as per initial stage of engineering) for the scope of work is attached as Appendix-1. This list is not exhaustive and is only for general purpose and may vary during the detailed engineering	This clause stands deleted.
2	Vol-IA-TCC- Chapter-VI (Time Schedule), Sl. No. 6.1.2 (12), Page 41 of 72	Activity	Supply of Shop Fabrication Material to Site as per scope of Work	Completion of Supply of Shop Fabrication Material to Site as per scope of Work.

पावर सेक्टर- पश्चिमी क्षेत्र Power Sector-Western Region श्रीमोहिनी काम्पलेक्स, 345 किंग्सवे, नागपुर Shreemohini complex, 345 Kingsway Nagpur - 440 001 फोन / Phone 0712- 3048600. फैक्स FAX: 0712- 3048699 www.bhelpswr.co.in

Ref: BHE/PW/PUR/2101094/Corg-01 Date: 30/08/2021 ------Page 2 of 2------

CC) Tender Due date extension:

Due date of offer submission has been extended till 02/09/2021, 15.00 Hrs., Technical bid shall be opened on 02/09/2021, 17.00 Hrs.


All other Terms and conditions of the Tender Specification shall remain unaltered unless expressly amended by BHEL in writing. Bidders are requested to submit as a part of their offer, a copy of this corrigendum duly Digitally countersigned by the authorized signatory as a token of Bidder's unqualified acceptance of this corrigendum.


BIDDERS MAY PLEASE NOTE THAT SUBJECT TENDER IS E-TENDER AND THE OFFER IS TO BE SUBMITTED ONLY IN E-PROCUREMENT PORTAL Https://eprocurebhel.co.in


BIDDERS WHO HAVE ALREADY SUBMITTED THEIR OFFERS PRIOR TO ISSUANCE OF THIS CORRIGENDUM IN E-TENDER PORTAL ARE REQUIRED TO RE-SUBMIT THEIR OFFER AFTER TAKING COGNIZANCE OF THIS CORRIGENDUM.


Thanking you, Yours faithfully,


GM (Purchase)
































COMPLIANCE REPORT

	2 X 500 MW MAUDA STPP-FGD PACKAGE			
DWG / DOC NO AND TITLE : 9561-109-ISG-PVC-B-445 - CONVEYOR LBC-1AB-GA OF GALLERY & TRESTLES R0				
SL NO	NTPC COMMENTS	BHEL REPLY		
1	Hold	Staad file has been revised and errors resolved		
2	PTFE bearing shall be provided for slinding support	Accepted. PTFE indicated in elevation view.		
3	COMPLY TO COMMENTS MARKED DESIGN DOCUMENT	Complied		
4	DESIGN/DRAWING TO CONFORM TO LATEST MECHANICAL/ELECTRICAL GADRG.	Accepted. Trestle Tr-2A introduced for structural requirement, after discussion with mechanical. The same will be updated in Mech GA dwg.		
5	ALL FURTHER CHANGES TO BE INCORPORATED IF ANY.	Noted.		
6	ALL PREVIOUS COMMENTS, IF ANY, ARE DEEMED TO HAVE BEEN INCORPORATED.	Agreed.		
7	Vendor to recheck before taking up construction-Approval does not absolve the turnkey contractor from ensuring structural safety and functional adequacy of the structure.	Accepted.		
8	Design and Detailing of connections shall be done as per section 10 and section 12 of IS 800:2007.	Ok. The same has been incorporated in Notes		









COMPLIANCE SHEET		
2 X 500 MW MAUDA FGD PACKAGE		
NTPC DWG / DOC NO AND TITLE : 9561-109-ISG-PVC-B-448 - (Limestone Silos-R1)		
SL NO	NTPC COMMENTS	BHEL'S REPLY
1	Compliance of observation marked in the design document required	Incorporated comments in the latest revision of drawings.


Signature North Verified


SAMIANTA Date: 2021.01.27 19:36:19 IST Reason: CAT II


location: NTPCEOC













































COMPLIANCE REPORT

	2 X 500 MW MAUDA STPP-FGD PACKAGE		
DWG / DOC NO AND TITLE : 9561-109-ISG-PVC-B-456 - STRUCTURAL DESIGN CALCULATION FOR GBC-1AB GALLERY & TRESTLES-R0			
SL NO	NTPC COMMENTS	BHEL REPLY	
1	DESIGN/DRAWING TO CONFORM TO LATEST MECHANICAL/ELECTRICAL GA DRG.	Accepted. Trestle Tr-1A has been introduced as per structural requirement. The same has been informed to mechanical after discussion.	
2	ALL FURTHER CHANGES TO BE INCORPORATED IF ANY.	Agreed.	
3	ALL PREVIOUS COMMENTS, IF ANY, ARE DEEMED TO HAVE BEEN INCORPORATED.	Noted.	
4	Vendor to recheck before taking up construction-Approval does not absolve the turnkey contractor from ensuring structural safety and functional adequacy of the structure.	Accepted.	
	utilization ratio is high and some of the members are failing please check and provide next higher section	Members revised in staad and drawings	
6	incorporate comment marked in structural document	Incorporated	
7	incorporate comments marked in structural drawing	Incorporated	














	2 X 500 MW MAUDA -STPP PACKAGE			
CI NO	NTPC DWG / DOC NO AND TITLE : 9561-109-ISG-PVC-B-457 - (Gypsum Shed Unit-R1)			
SL NO	NTPC COMMENTS	BHEL REPLY		
1	Remove it as it shall cause hinderance in loading of trucks	As per the approved mech GA, gypsum is stored inside the shed by the tripper / conveyor only. Trucks are not envisaged to load gypsum at EL(+)7.10M. Hence, door for maintenance platform will not pose any threat to service requirements.		
2	these bracings not allowed. This shall create hinderance in truck movement for loading purpose.	As per the approved mech GA, gypsum is stored inside the shed by the tripper / conveyor only. Trucks are not envisaged to load gypsum at EL(+)7.10M. Hence, the side bracings will not hamper service requirements.		
3	please keep design same as mech GA.	Total dimension of the shed is inline with that of the approved mech GA. However, due to introduction of expansion gap in the RCC structure below as per design requirements, grid to grid dimensions at ends of expansion joint are suitably modified.		
4	check the ladder support location. This must be for access to hoist maintenance platform. The location to be revised as per mech GA.	These ladder supports are meant to access door maintenance platform. Ladder for Hoist maintenance platform are shown separately in the revised dwgs.		
5	DE system foundation to be as per approved GA of equipment. Further, this is at EL (+) 7.10 M.	As it is a structural dwg, location & detail of DE system foundations are shown for indicative purpose only. For details of the same, kindly refer the relevant civil dwgs.		



















FOR 9561-109-PEM-PVC-B-077 R0 NTPC COMMENTS RECEIVED VIDE LETTER Reference: CC:PE:9561:109:39665 DATED 02.12.2019

SL NO	NTPC COMMENT	BHEL REPLY
1	Load calculation & Analysis of Ball Mill	Load calculation & Analysis of Ball
	Building is yet to be submitted for	Mill Building revised and submitted
	NTPC approval. This document	separately.
	document can be reviewed after	Kindly refer doc. No. 9561-109-
	approval of Load calculation &	PEM-PVC-U-176-00.
	Analysis of Ball Mill Building and	
	Design of Foundation.	




FOR 9561-109-PEM-PVC-B-077 R2 NTPC COMMENTS RECEIVED VIDE LETTER Reference: CC:PE:9561:109:40506 DATED 11.01.2021

SL NO	NTPC COMMENT	BHEL REPLY
1	Review in line with the comments	Drawing reviewed and found in
	marked on design document.	order.




FOR 9561-109-PEM-PVC-B-078 R1


SL NO	NTPC COMMENT	BHEL REPLY	
1	No comment.	Drawing has been revised due to change in ball mill	
		building layout as per site observations.	





FOR 9561-109-PEM-PVC-B-079 R1

SL NO	NTPC COMMENT	BHEL REPLY	
1	No comment.	Drawing has been revised due to change in ball mill	
		building layout as per site observations.	









FOR 9561-109-PEM-PVC-B-102- R1 NTPC COMMENTS RECEIVED VIDE LETTER Reference: CC:PE: 9561:109:39703 DATED 09.12.2019

SL NO	NTPC COMMENT	BHEL REPLY
1	Monorail beam to be shown in both plan and elevation and fixing detail of same also to be shown.	
2	Structure for hoist maintenance platform and access provision to the platform also to be shown.	Incorporated.

