

Project Engineering
Management

Bharat Heavy Electricals Limited
(A Govt. Of India Undertaking)



Ref No. : PE/PG/KG1/E-4766/2015

Date: 15.05.2015

CORRIGENDA / ADDENDA-2

Tender Enquiry no.: PE/PG/KG1/E-4766/2015

Date: 15.04.2015


PROJECT : 1x800 MW TSGENCO KOTHAGUDAM TPP

PACKAGE: GAS CHLORINATION PLANT

DUE DATE
28-MAY-2015
03:30 PM

This corrigendum is being issued due to Amendment in Technical specification. Amendment Details are enclosed herewith.

All other terms & conditions shall remain unchanged.

With Regards,
For & on behalf of BHEL

Naina Singh
Dy. Manager/PG-II-2

Please reply to:
Naina Singh/ PG-II-2
Power Project Engineering Institute Building
HRD & ESI Complex Plot No. 25, Sector -16 A,
BHEL-PEM,Noida-201301 (U.P.)
Tel No. 0120-4368762



**AMENDMENT ON TECHNICAL SPECIFICATION FOR CHLORINATION PLANT
1X800 MW TSGENCO KOTHAGUDEM TPS, STAGE –VII, PALONCHA.**

SPECIFICATION NO.: PE-TS-410-174-A001

AMENDMENT NO # 1

REV. NO. 00

DATE: 13/05/2015

Page 1 of 1

The following modifications with respect to Technical Specification for Chlorination Plant BHEL's Technical specification no PE-TS-410-174-A001 shall apply.

Bidder to note that existing clauses/details as appearing in the specification stands deleted and clauses/details as mentioned in "Modified to or Read as" column shall be applicable and complied by the bidder.

MODIFIED CLAUSES/PAGE NUMBERS.

SI no.	Vol. No.	Section/ Description	Clause no	Page no	Existing clause/details	Modified to or Read as
1.	IIB	SECTION– C1	PE-DG-410-174-A001 (P&ID)	55 of 240	8 numbers CW Chlorination booster pumps indicated.	One number booster pump in each stream shall be provided (Total number of booster pump shall be as per Section-C1, Clause no-2, Point number-13, pager number 8 of 240).
2.	IIB	SECTION– C1	PE-DG-410-174-A001 (P&ID)	55 of 240	CW chlorinator Capacity 180 Kg/Hr (each) indicated.	The CW Chlorinator capacity shall be 160 kg/Hr (each) as indicated in Section-C1, Clause no-2, Point number-6, pager number 8 of 240.
3.	IIB	SECTION– C1	PE-DG-410-174-A001 (P&ID)	55 of 240	RW chlorinator Capacity 15 Kg/Hr (each) indicated.	The RW Chlorinator capacity shall be 25 kg/Hr (each) as indicated in Section-C1, Clause no-2, Point number-7, pager number 8 of 240.
4.	IIB	SECTION – D3	2.03.03	185 of 240	DDCMIS Back-up Panel (referred as Unit Control Panel-UCP) shall also mount annunciation fascia (minimum 500 nos.) and the flame monitoring cameras along with other hardwired devices as decided during detail engineering stage by Owner. Color coding shall also subject to Owner's approval.	Clause deleted.
5.	IIB	SECTION – D3	2.05.01 (WORK STATION FURNITURE)	188 of 240	Modular work station furniture, suitable for mounting servers & historians, Programmer stations, PC based systems, printers (A4/A3 color LaserJet) etc. shall be provided.	Modular work station furniture, suitable for mounting servers & historians, Programmer stations, PC based systems, printers (A3 color LaserJet) etc. shall be provided.