

Ref. No. PE/PG/TAN/E-5435/2016-01
Enquiry No.: PE/PG/TAN/E-5435/2016
Date: 01/02/2017

1X800MW TANGEDCO NORTH CHENNAI STAGE-III BTG
DOUBLE GIRDER EOT CRANE ABOVE 200T TO 250T

CORRIGENDA / ADDENDA-1

Dear Sirs,

Please find enclosed pre-bid clarifications. All bidders are requested to quote accordingly.

With Regards,
For & on behalf of BHEL

Rohit Juneja
SR. ENGINEER/PG-II-1

ROHIT JUNEJA
SR. ENGINEER/PG-II-1,
BHEL/PS-PEM
POWER PROJECT ENGINEERING INSTITUTE,
PLOT NO. 25, SECTOR - 16A, NOIDA (UP)
(OFF) 0120-4368848.#

Regd. Office:
BHEL House
Siri Fort
New Delhi-110049



TITLE
1X800 MW NORTH CHENNAI TPP STAGE III
DOUBLE GIRDER EOT CRANES ABOVE 200T
UPTO 250T
PRE BID CLARIFICATION SCHEDULE

SPECIFICATION NO. PE-TS-423-501-A301

REV 00

Section III

Page 1 of 2

PRE-BID CLARIFICATION REPLY

S. No.	Section/Clause/Page No.	Statement of the referred clause	Clarification Required	BHEL Reply
1.	Clause no. 3.7.0(h) pg. no. 226	This clause of technical data sheet of technical specification PE-TS-423-501-A301 no. of LT wheel has been mentioned as 8 nos. where as in CCD drg. No. PE-DG-423-501-A301 shown as 16 nos.	This clause of technical data sheet of technical specification PE-TS-423-501-A301 no. of LT wheel has been mentioned as 8 nos. where as in CCD drg. No. PE-DG-423-501-A301 shown as 16 nos. Please clarify.	16 no. LT wheels per crane as per Crane Clearance diagram attached in tender technical specification shall be considered.
2.		We refer to SCOPE OF SUPPLY under sr. no. 1.1.3, wherein under sr. no. "q" we have to arrange for slings & cradle for load testing at site on returnable basis. Further, as per sr. no. "r", we have to supply Lifting Beam along with required slings.	However, we are not able to understand what type of Slings are required as mentioned in sr. no. 4.0 (H) Annexure II- Mandatory Spares. Pls inform per return enable us to submit our offer by due date.	Please note that 'sling & cradle for load testing on returnable basis' required against S. no. 1.1.3 q) of section IA shall be solely for the purpose of load/overload testing of the crane & lifting beam at site whereas slings along with lifting beam (mentioned against S. no. 1.1.3 r) shall be used for stator handling at site. Further, the sling required as mandatory spares shall be suitable for Auxiliary Hoist capacity i.e. 50T. Bidder has to quote for all the items i.e. items mentioned against S. no. 1.1.3.q) & 1.1.3.r) of section IA and 4.0 h) of mandatory spares list.



TITLE
1X800 MW NORTH CHENNAI TPP STAGE III
DOUBLE GIRDER EOT CRANES ABOVE 200T
UPTO 250T
PRE BID CLARIFICATION SCHEDULE

SPECIFICATION NO. PE-TS-423-501-A301

REV 00

Section III

Page 2 of 2

3.		Kindly inform us whether Lifting Beam is to be load tested at our works. If so, 100% or 125% load.	Kindly inform us whether Lifting Beam is to be load tested at our works. If so, 100% or 125% load.	Pl refer S. no. 5 of Manufacturing Quality Plan of lifting beam (Page 87) attached in tender technical specification.
----	--	--	--	---