

	PPX-BOI DEPARTMENT BHARAT HEAVY ELECTRICALS LIMITED HEEP: HARDWAR-249 403 (Uttarakhand) FAX: +91 1334 226084/226462 TEL: +91 1334 28 5773	ENQUIRY NO. B/4222/2017/2028V/1 PACKAGE: AIR COOLED CONDENSER PACKAGE PROJECT: 3X800 MW PATRATU PROJECT
---	--	--

Date: 01/09/2018

**CORRIGENDUM FOR TENDER ENQUIRY NO.
B/4222/2017/2028V/1 FOR AIR COOLED CONDENSER
PACKAGE of Patratu Project.**

Corrigendum is being issued for revision in Document No. HXE/SK/90345/3 and HE57070, through amendment No. 09 dated 01/09/2018.

Amendment No. 09 dated 01/09/2018 is enclosed.

Air Cooled Condenser Package for 3X800MW NTPC Patratu

Amendment No. 9

Date:01 September, 2018

Sl. No.	Reference	Instead Of	Read As
01	HXE/SK/90345/3, Tube Bundle Manufacturing Facility & other sub-vendor items.		Document revised and attached with this amendment.
02	HXE/SK/90345/3, Annexure-2 and sl. No 25 of Amendment-02		Annexure-2 revised and attached with this amendment.
03	HE57070, CI No. VI.4.1 Page 78 of 121		New Clause Added Bidder to provide the supporting documents describing the standard philosophy of various instrumentations provided in ACC system; example, for Fan vibration measurement, for oil pressure and temperature measurement in gear box etc.
04	HE57070, CI No. VI.7.4 Page 91 of 121	v) Vibration Switch - 10% of each type vi) Temperature Switch - 10% of each type vii) Pressure/ DP Switch - 10% of each type	Clause deleted.
05	HE57070, CI No. IV.4.3.6.1, Page 27 of 121		New Clause Added: Drain pump piping system should be able to handle flow corresponding to all pumps (including stand-by) simultaneously in operation.
06	HE57070, CI No. IV.4.3.6.2, Page 27 of 121		New Clause Added: Flow through control valve shall be controlled through feed back mechanism received from flowmeter.

Handwritten signature
01/09/2018

Handwritten signature
01/09/2018