

BHARAT HEAVY ELECTRICALS LTD
HEAVY PLATES & VESSELS PLANT
VISAKHAPATNAM-12
OUTSOURCING DEPARTMENT

Dated: 14.09.2017

CORRIGENDUM 01


Sub: Repair Works of Township boundary wall facing Hyundai show room near Autonagar Road at M/s. BHEL
– HPVP, Visakhapatnam - Reg.

Tender Enquiry No: OPS/OS/WC/2017-18/49/056, Dated: 01.09.2017

The following changes are effected in the above refereed NIT instead of existing clauses.

Sl. No.	Description	Existing	Read As
1	Part II (Price Bid)	As per Annexure – VII	As per Annexure – VII(A) as enclosed.
2	Last Date for Offer Submission & Opening of Bids	14.09.2017.	14:00 Hrs. on 19.09.2017

Bidders are requested to note the above changes and submit your offer accordingly.


14/09/2017
Sr. Manager (Outsourcing)

PART – II

(PRICE BID)

**BHARAT HEAVY ELECTRICALS LIMITED
HEAVY PLATES & VESSELS PLANT
VISAKHAPATNAM – 530 012**

NAME OF WORK: Repair Works of Township boundary wall facing Hyundai show room near Autonagar Road at M/s. BHEL – HPVP, Visakhapatnam – Reg.

Tender Enquiry No: OPS/OS/WC/2017-18/49/056, Date: 01.09.2017

- 1) Tenderers are requested to visit the site before submitting their tenders and go through the site conditions, nature and quantum of the job to be done and in general shall themselves obtain all necessary information as to risks, safety precautions, contingencies and other circumstances. A tenderer shall be deemed to have full knowledge of the site, whether he inspects it or not, no claim shall be allowed.
- 2) Contractor shall pay the minimum wages to the contract labour as per circulars issued by HR dept. of BHEL – HPVP, Visakhapatnam from time to time.

In addition to the above the contractor has to comply with all the statutory requirement such as PF, ESI, Bonus, Leave wages, Retrenchment compensation etc.
- 3) The quantities provided in the schedule are only provisional & may vary according to exigency of the work and no extra claim can be entertained on this score.
- 4) The supply of the cement is in the contractor's scope. The cement used should be of the Grade – 43 /53 OPC conforming the IS 8112/1269 cement consumption should strictly be as per CPWD Specification.
- 5) The supply of Reinforcement Steel is also in the scope of contractor. The mild steel reinforcement bar should conform to IS 432 Gr. I and high yield deformed reinforcement bar to conform to IS 1786 or IS 1139.
- 6) In General all the materials are in the scope of contractor. Only water and power will be provided at a point free of charge and subsequent lines will be drawn by contractors at their own cost.
- 7) Before procurement of the materials, approval of the Engineer-in-charge regarding required quality and make/brand should be obtained.
- 8) Tenderers should have accidental insurance in favour of their work man.
- 9) All rates should be inclusive of scaffolding/staging or the full height of building so as to carry out the complete work. No additional payment will be made for the scaffolding work.
- 10) **The quoted prices shall be inclusive of all applicable taxes & duties as applicable as on date of tender submission except GST.** However, GST as applicable shall be payable by the contractor and same will be reimbursed by BHEL on submission of proof of payment.
- 11) **The quoted rate shall be fixed & firm throughout the contract period. No cost escalation will be paid on any account throughout the contract period for any item.**
- 12) **L1 shall be evaluated based on quoted total price.**
- 13) **Offered discount / Increase will be considered for calculation of unit rate & total amount for each item.**

SIGNATURE OF THE TENDERER WITH SEAL

BHARAT HEAVY ELECTRICALS LIMITED
HEAVY PLATES & VESSELS PLANT
VISAKHAPATNAM – 530 012

NAME OF WORK: Repair Works of Township boundary wall facing Hyundai show room near Autonagar Road at M/s. BHEL – HPVP, Visakhapatnam – Reg.

Tender Enquiry No: OPS/OS/WC/2017-18/49/056, Date: 01.09.2017

SCHEDULE OF QUANTITY FOR THE WORK

ITEM NO.	DESCRIPTION OF ITEM	UNIT	QTY	Unit Rate (in ₹)	Amount (in ₹)
1	Removal of the fallen rubble masonry manually including stacking of serviceable material and disposal of unserviceable material within 50 meters lead as per direction of Engineer-in-Charge.	Cu.m.	15	502.85	7,542.75
2	Dismantling of rubble masonry manually including stacking of serviceable material and disposal of unserviceable material within 50 meters lead as per direction of Engineer-in-Charge.	Cu.m.	15	1005.70	15,085.50
3	Earthwork in excavation in foundation up to 1.5 m	Cu.m.	5	125.75	628.75
4	Providing and laying cement concrete 1:4:8(1 Cement: 4 Coarse sand: 8 Graded hard granite stone aggregate 40 mm nominal size)	Cu.m.	2.5	4,478.15	11,195.38
5	Supply of the stone for random rubble masonry.	Cu.m.	15	865.00	12,975.00
6	Laying of Random rubble masonry with hard stone in foundation and superstructure above plinth Random rubble masonry with hard stone in superstructure above plinth, including leveling up with cement concrete 1:6:12 (1 Cement: 6 Coarse sand: 12 Graded stone aggregate 20 mm with cement mortar 1:6) (Excluding supply of stone)	Cu.m.	30	3,515.50	1,05,465.00
7	Providing and laying 20 mm thick plastering with 1:6 cement mortar (Top of wall)	Sq.m	15	220.60	3,309.00
8	Pointing on stone work with cement mortar 1:3 (1 cement: 3 fine sand Flush/ Ruled Pointing)	Sq.m	120	168.45	20,214.00
	Total amount (in ₹)				1,76,415.40
	Discount / increase offered by Bidder on above total amount in %				
	Total Offered amount after Discount / increase (in ₹)				

TOTAL AMOUNT IN WORDS:

SIGNATURE OF THE TENDERER WITH SEAL