

CORRIGENDUM TO REPLIES TO PRE BID QUERIES DTD .08.07.2017

PROJECT: 4 x 270 MW Kothagudem

PACKAGE: Supply and Supervision of E&C for Inert Gas Extinguishing system

ENQUIRY NO. : T7B1Q93772

Corrigendum - BHEL replies to Pre bid queries under sl. No.6 issued on dtd 08.07.2017 shall be replaced by "BHEL Replies dtd 12.08.2017".

Sl. No.	Cl. No. of Tender Specification (PY51233, Rev 00)	Description	Bidder Queries	BHEL Replies dtd 08.07.2017.	BHEL Replies dtd 12.08.2017.
6	9.1.4, iv		Installation nor civil is in vendor's scope. This Clause is not relevant. The cabling from FDA panel to gas release panel is not in scope as distance/location of FDA panle from Clean Agent Panel is not given.Please Confirm.	Noted. Please note that installation or civil works is in the scope of the bidder. Bidder may however, note that supervision of Erection & commissioning is in their scope. Bidder to note that the cabling from Gas release panel to all inert gas components/equipment like abort switches, manual release buttons, pre-discharge indicators and discharge indicators is in their scope. Bidder to also note that the cable between Fire Alarm panel and Gas Release panel is in bidder's scope. Bidder to also note that the location of Fire Aalrm panel is already indicated in drg. no: PE-DG-411-145-I401 (Refer sl.no. 6 of Common control room). In any case, for estimation purpose the cable distance between Fire Alarm panel and Gas Release panel to be considered as 100 mtrs.	Noted. Please note that installation or civil works is not in the scope of the bidder. Bidder may however, note that supervision of Erection & commissioning is in their scope. Bidder to note that the cabling from Gas release panel to all inert gas components/equipment like abort switches, manual release buttons, pre-discharge indicators and discharge indicators is in their scope. Bidder to also note that the cable between Fire Alarm panel and Gas Release panel is in bidder's scope. Bidder to also note that the location of Fire Aalrm panel is already indicated in drg. no: PE-DG-411-145-I401 (Refer sl.no. 6 of Common control room). In any case, for estimation purpose the cable distance between Fire Alarm panel and Gas Release panel to be considered as 100 mtrs.