

BHEL PAN: AAACB4146P

Ref: BHE/PW/PUR/NTPRT-STR ERE PKG-A/2117/Pkg-B/2118/Corr-02

Date: 08/07/2019

Page 1 of 2

To

ALL BIDDERS,

**Sub: Corrigendum-02: Issue of Clarification and Extension in due date of offer submission**

**Job: Package-A:** Erection, Alignment, Bolting/Welding, Roofing & Cladding Work of Power House Building (including control room of Unit#01) (Power House Unit#01 {Grid-1 to Grid13a} + Power House Unit#03 {Grid-28a to Grid-39}), Pipe/cable rack along C row for Unit#01 & Unit#03, Misc. structural work in T/ O yard area of Unit#01 & Unit#03, FGD System structural work (including ball mill, gypsum dewatering, oxidation pump house), Structural works of Misc. BOP Building, Ammonia storage shed and Handling of Materials at BHEL / Client's Stores / Storage yard and transportation to site at 3X800 MW PVUNL PATRATU, Jharkhand.

AND

**Package-B:** Erection, Alignment, Bolting/Welding, Roofing & Cladding Work of Power house building (Grid 13a to Grid-28a) including CCR (i.e. common control room of Unit#02 & Unit#03), Pipe/cable rack along C row for Unit#02, Misc. structural work in T/ O yard area of Unit-2, BOP Pipe Rack & Cable Rack, Compressor Building, Service Building etc and Handling of Materials at BHEL / Client's Stores / Storage yard and transportation to site at 3X800 MW PVUNL PATRATU, Jharkhand.

S. No.	Package	E- TENDER SPECIFICATION NUMBER
01	Package-A	BHE/PW/PUR/NTPRT-STR ERE PKG-A/2117
02	Package-B	BHE/PW/PUR/NTPRT-STR ERE PKG-B/2118

Bidders to kindly take note of the following:

**AA) ISSUE OF CLARIFICATIONS:**

Sl. No.	Reference clause of Tender doc	Existing provision	Bidder's query	BHEL's Clarification
1.	Chapter- XVII of Vol-IA TCC (BILL OF QUANTITIES AND % WEIGHTAGE OF INDIVIDUAL ITEMS) ST NO G2301	Providing welded splices for joining pre-fabricated structural parts (Beams, columns, roof trusses, struts, ties, bracings etc.) supplied by BHEL including welding of main structural members as per drawing, ,cutting if required, grinding, machining, preparing smooth surface for splicing, welding splice over welded structural member etc complete as per fabrication drawing , electrodes and other consumables for welding, alignment, manual/blast cleaning, providing and application of primer, paint etc. all complete. Weight of splice plates along with weight of structural members on either side of joint to maximum extent of 3 meters length or actual length (if lesser than 3 m ) shall be payable. Manual/blast cleaning of steel surface , application of primer and paint including supply shall be paid separately as per Item No.A2303/A2302, A2304, B2304 & C2304.	Please clarify providing of splice plate are in vender/agency scope.	Supply of splice plate is not in the bidders scope only erection is in bidders scope.

Sl. No.	Reference clause of Tender doc	Existing provision	Bidder's query	BHEL's Clarification
2.			Please share the detailed drawings of this project	All available drawings have already been issued with tender documents. Detailed erection drawings shall be issued progressively during execution of work .

**BB) Extension of Due Date of offer Submission:** The last date for submission of Tender has been re-scheduled to **15/07/2019, 15.00 hrs.**

Technical Bid shall be opened on **15/07/2019 at 16.00 hrs.**

=====

All other Terms and conditions of the Tender Specification shall remain unaltered unless expressly amended by BHEL in writing. Bidders are requested to submit as a part of their offer, a copy of this corrigendum duly Digitally countersigned by the authorized signatory as a token of Bidder's unqualified acceptance of this corrigendum.

BIDDERS MAY PLEASE NOTE THAT SUBJECT TENDER IS E-TENDER AND THE OFFER IS TO BE SUBMITTED ONLY IN E-PROCUREMENT PORTAL → [www.bhel.abcprocure.com](http://www.bhel.abcprocure.com)

BIDDERS WHO HAVE ALREADY SUBMITTED THEIR OFFERS PRIOR TO ISSUANCE OF THIS CORRIGENDUM IN E-TENDER PORTAL ARE REQUIRED TO RE-SUBMIT THEIR OFFER AFTER TAKING COGNIZANCE OF THIS CORRIGENDUM.

Thanking you,

Yours faithfully,

AGM (Purchase)