

**CORRIGENDUM-I**

Date: 15.12.2017

NIT No. AA: GAX:17: Paver Block:001

Dated: 14.12.2017

**Due Date & Time: 21.12.2017 by 14:30 Hrs**

**PART 'B' – REVISED PRICE BID**

**NAME OF WORK: PROVIDING & LAYING OF CEMENT CONCRETE PAVER BLOCK IN PARKING AREA AND APPROACH ROADS AT BHEL HOUSE, SIRI FORT, NEW DELHI**

Sl. No	Description of Item	Unit	Qty	Rate	Amount
1	Providing and laying factory made coloured chamfered edge Cement Concrete paver blocks in footpath, park & lawn, driveway or light traffic parking etc of required strength, thickness & size/shape, made by table vibratory method using PU mould, laid in required color & pattern over 50 mm thick compacted bed of coarse sand, compacting & proper embedding/laying of interlocking paver block into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand all complete as per manufacturer specification & direction of engineer in-charge. 60 mm thick cement concrete paver block of M-35 grade with approved colour, design & pattern.	SQM	4600	638	2934800
2	<b>Total Estimated Amount (excluding GST) in Rs.</b>				<b>2934800</b>
3	Percentage Above(+)/ Below(-) at par with S. No. 2				
4	<b>Total Quoted Amount after applying percentage (S. No. 2) (excluding of GST) in Rs.</b>				
5	GST @ _____ % of Total				
6	Total Amount inclusive of GST (in Rs.)				

(Signature & seal of the contractor)