Corrigendum - 1 dated 02/09/2024 to CPC Tender No. BHEL/CPC/LRA/ESP-FGD/25/030 for the work of "Erection, commissioning & Trial Operation including application of lining, Insulation, supply & touch-up painting as and where required including Handling of materials at BHEL / Client's Stores / Storage Yard and transportation to site, and handing over of Electrostatic Precipitator (ESP) and its auxiliaries along with Ducting complete with all accessories, lining and insulation from ESP outlet to Chimney Inlet including supply & installation of items as per BOQ and FGD system and related auxiliaries along with the common system of Gypsum Dewatering System. E & C of Ducts of absorber, Absorber tower along with oxidation blowers, Lime Stone Handling System, including supply & installation of items as per BOQ of Unit#3 and Unit#4 of Stage#2 of 2X800 MW NTPC LARA Stage II Project, Dist. Raigarh, CG".

A) Time Extension: Clause No. 1.0 Salient Features of NIT in NOTICE INVITING TENDER is revised as below:

Sl. No.	Clause No.	Existing in Tender	Revised As
1	SI. No. v) DUE DATE & TIME OF OFFER SUBMISSION.	Date: 02/09/2024, Time: 10:00 Hrs	Date: 09/09/2024, Time: 10:00 Hrs
2	Sl. No. vi) OPENING OF TENDER	Date: 02/09/2024, Time: 16:30 Hrs	Date: 09/09/2024, Time: 16:30 Hrs

B) Some of the Bidders sought clarifications in regard to the published tender specification. The clarifications/modifications issued by BHEL are as below;

Sl.	Reference	Clause	Existing provision	Bidder's query	BHEL's clarification
No	clause of	No.			
	Tender				
	Document				
1	TCC	3.11.7	Contractor to arrange DG Set till construction power is made available by BHEL (approx first 3 months)	We will deploy DG Set of appropriate capacity to provide back-up power essential to continue essential activities from technical and HSE viewpoints. Please	Tender Conditions shall prevail.

Sl. No	Reference clause of Tender Document	Clause No.	Existing provision	Bidder's query	BHEL's clarification
				provide Construction Power from the beginning.	
2	TCC	4.1	Major T&P (150 MT Crawler Crane) - included in Contractor's scope	Please include in BHEL scope	Tender Conditions shall prevail.
3	TCC	4.1 (Note - 2)	Contractor to remobilize major T&P as per BHEL instruction without any extra cost to BHEL	We will mobilise/demobilize the T&P once as per jointly agreed schedule. However, cost of remobilization may please be reimbursed because it involves substantial additional expenses.	Tender Conditions shall prevail.
4	TCC	4.2 (SN-4)	Trailer with prime mover (20 MT) - 2 nos in Contractor's scope	In our estimation 1 such trailer is necessary for the scope of work, please amend the condition.	TCC Clause no. 4.2 (SN-4) Modified as: - Sl No 4 Trailer with Prime Mover (20 MT)- 1 no. in Contractor Scope
5	TCC	4.2 (SN-6)	Low Bed Trailer 70-100 ft span (60 MT) APR is in Contractor's scope	In our estimation that trailer is not required for the current job, request to exclude from the list.	Tender Condition shall prevail. Further refer Clause no. 4.3.1 for clarity.
6	TCC	4.2 (SN-8)	Man-Lifter (minimum 40 m height capacity) APR is in Contractor's scope	Man-lifter of required capacity will be deployed as per site requirement, please exclude the capacity.	Tender Condition shall prevail. Further refer Clause no. 4.3.1 for clarity.
7	TCC	5.1 (SN - 4)	Consumables for Huck Bolting machine are in Contractor's scope	Request for clarity about the scope of routine spare parts of	Refer Clause no 5.1 Table Serial No 4 Remarks "Only machine will

Sl. No	Reference clause of Tender Document	Clause No.	Existing provision	Bidder's query	BHEL's clarification
	TCC	5.7	BHEL shall supply spare parts free of charges for normal wear & tear	Huck Bolting machine that need periodical replacement (like Jaws, Ejector, Follower, Release kit etc), in earlier projects they are provided by BHEL free of cost.	be provided by BHEL, the consumables required for the machine shall be arranged by bidder".
8	TCC	7 (Non- pressure Parts - 1C)	Payment Terms: some of the assigned percentages are: 7.1.1 Preassembly - 20%, 7.1.4 Welding, Bolting - 20%, 7.1.9 Attachment/Fin welding & Supports - 5%, 7.1.13 Hangers & Supports - 5%	Pre-assembly of NPP involves substantial expenses, assigned percentage (20%) is not commensurate. Same percentage is assigned for insitu welding where the expenses would be lesser than Pre-assembly. SN. 7.1.9 and 7.1.13 - both are for the same activity namely Supports. We request for the following percentages: 7.1.1 - 30% 7.1.4 - 15% 7.1.9 - 0% 7.1.13 - 5%	Tender Conditions shall prevail.
9	TCC	9	Note to Weight Schedule SN-8: Providing Blanks/Dummies is in scope of the Contractor	Please exclude supply of Blanks/Dummies from Contractor's scope	BHEL will provide materials for the dummies free of cost for conducting the Gas Tightness Test, Fabrication & Erection of

Sl. No	Reference clause of Tender Document	Clause No.	Existing provision	Bidder's query	BHEL's clarification
					the dummies in the scope of vendor.
10	TCC	12.13	Supply of Special cement for grouting	Request to provide the estimated quantity	Shall be assessed from the Number of Rotating Components in the BOQ of Chapter-IX and drawings.
11	TCC	14.3.5	Supply of Self drilling cum tapping screws and Fixing Clamps for Floor Grills is in Contractor's scope	Please exclude from Contractor's scope.	Tender Conditions shall prevail.
12	TCC	19.5 & 19.6	Supply of Aluminium Paint for Retainer and Bitumen Sealing Compound for sheet joints is Contractor's scope	Please exclude from Contractor's scope.	Tender Conditions shall prevail.
13	TCC	19.4	Supply of Black Bitumen Paint for internal surface of Aluminium Cladding and Bitumen Sealing Compound for joint sealing is in Contractor's scope	Please exclude from Contractor's scope.	Tender Conditions shall prevail.
14	TCC		Welding Process for C-276 and Ti	 Please specify the processes (e.g. GTAW, SMAW, SAW etc). Whether all the required Filler Wire & Welding Electrodes are supplied by BHEL free of cost. 	1) C276 Welding involves SMAW (99%) and GTAW (1%) Titanium Welding Involves GTAW (100%) 2) Refer Chapter-IX of TCC for Special Electrodes. Those covered under the BOQ shall be provided by BHEL Free of Cost. Any Electrode not covered under the

Sl. No	Reference clause of Tender Document	Clause No.	Existing provision	Bidder's query	BHEL's clarification
					BOQ shall be arranged by bidder at its own cost.
15	TCC		Cutting & Edge Preparation of C-276 & Ti	Please confirm if any cutting/trimming/edge preparation of C-276 and Ti material is required at the site. If yes, please specify the approximate quantum of work and if any special equipment/tools are required and scope thereof.	No cutting/trimming/edge preparation at site, But in any cases of rework minor cuttings to be done, Cutting to be done either by Hand Plasma Cutting machine or grinding cutting wheels, Hand tools like Grinding wheels, Brushes, holding tools and other tools required for Site Welding of C276 equipment & Titanium Equipment should be restricted to use on the one material only. Wire brushes should be stainless steel or C276 composition similar to the steel being cleaned, and should not have been previously used on other materials. Abrasive disks or wheels that have never been used on iron or steel shall only be used for C-276 material.
16	TCC	2.9.12	Sealing compounds and GI wires for insulation mattress binding and Self drilling screws / Self taping screws for sheeting works shall be provided by the agency within the quoted price/rates.	Kindly provide as free of cost	Tender Conditions shall prevail.

Sl. No	Reference clause of Tender Document	Clause No.	Existing provision	Bidder's query	BHEL's clarification
17	TCC	3.9.3	Land for labour colony shall be arranged by Contractor at their own cost as per availability outside project area preferably within 5Km, Necessary levelling/dressing of land shall be done by the contractor. All arrangement for electricity and drinking/service water to be arranged by the contractor within his quoted price. All expenses towards installation of transformer, depositing requisite fees etc if required shall be borne by vendor.	Land for labour colony-kindly provide by BHEL as free of Cost.	Tender Conditions shall prevail.
18	TCC	2.5.14	Medical/First aid centre/medicine purchased for emergency/Doctor purpose along with ambulance services with fuel and operator (round the clock) shall be arranged by BHEL for handling medical emergencies. Cost against these facilities shall be distributed / shared among the vendors working in Lara Project site proportionately based on contract value.	of the contract value that should be recovered	Tender Conditions shall prevail. Further for clarity, refer Clause no 2.5.14.

Sl. No	Reference clause of Tender Document	Clause No.	Existing provision	Bidder's query	BHEL's clarification
19	TCC	2.8.12	Painting: Touch-up Painting: All structures/ components shall be supplied from BHEL units/ workshops with finish coats of paint. Therefore, final painting is not applicable in the scope of contractor for Unit supplied items (until specifically mentioned in the tender). However, touch up painting (wherever required), incidental to the work, shall be in the scope of the contactor, including supply of the required paints and primers and associated consumables. Special Requirement of Lifeline/scaffolding/ special safety requirement shall be paid on manhour rate as per GCC.	Payment" of the TCC, 1% of the CV is allocated to the ESP, Structure, and Piping head. However, final painting is excluded from the vendor's scope of work, with only touch-up painting included. Could you please define the	Tender condition shall prevail. Further, Touch Up Painting on all erected structure shall be in agency scope invariably.
20	TCC	2.8.15	2.8.15 Manpower required exclusively for BHEL Menial and Secretarial Services: SN Description of Work/Item BOQ (Man Months) Pkg-A Pkg-B	We understand that BHEL will utilize this manpower for the work related to the ESP and FGD packages awarded to the vendor	The manpower required shall be used for the BHEL Menial and Secretarial Services and the payment shall be regulated as per the terms of payment mentioned under Chapter-VII.

Sl. No	Reference clause of Tender Document	Clause No.	Existing provision	Bidder's query	BHEL's clarification
21	TCC	2.8.28	Adequate lighting facilities such as hand lamps and area lighting shall be arranged by the contractor at the site of construction, preassembly yard and contractor's material storage area etc. at his cost.	We understand that the vendor is responsible only for job site illumination, while the rest of the area lighting is under the scope of M/s	Tender Conditions shall Prevail.
22	TCC	3.11.10	The bidder will have to Procure & install General mobile illumination system during construction right from start of his work. This system will include temporary pole lighting, within the quoted price. The illumination should be such that minimum illumination requirement as specified by Indian standards for general illumination is maintained.	BHEL.	
23	TCC	2.9.12	Sealing compounds and GI wires for insulation mattress binding and Self drilling screws / Self taping screws for sheeting works shall be provided by the agency within the quoted price/rates.	According to BHEL's standard practice, sealing compounds, GI wires for insulation mattress binding, and self-drilling/self-tapping screws for sheeting work are to be provided by BHEL. We request that BHEL continue to supply these items as per previous practices.	Tender Conditions shall Prevail.
24	TCC	2.10	BHEL is entitled to engage a separate Contractor for NDT & PWHT / SR for the welding works executed in this contract, without assigning any reason to the	Please confirm if BHEL will arrange for its own agency to conduct NDT services. If so, will the charges for these	Tender condition shall prevail. Further refer Clause no 2.10 where it is mentioned that in case BHEL engages a separate

Sl.	Reference	Clause	Existing provision	Bidder's query	BHEL's clarification
No	clause of	No.			
	Tender Document				
	Document		contractor. In this regard, Contractor shall	services be deducted from the	contractor for NDT & PWHT /
			not be entitled for corresponding payment	vendor's bill? Alternatively,	SR for the welding works
			against as mentioned in Terms of payment	does this imply that the	executed in this contract
			Chapter VII of TCC. However, Contractor	percentage specified under	"Contractor shall not be entitled
			has to provide all possible support to NDT &	'7.1.5.1 Completion of non-	for corresponding payment
			PWHT / SR agency such as Scaffolding, area	destructive examination – as	against as mentioned in Terms of
			illumination, approach, wrench/sky climber	per approved FQP/EWS (if	payment Chapter VII of TCC".
			with operator etc. Item no. 7.1.5.2 of Terms	not applicable, then this	Relevant Clauses in Chapter-VII
			of payment Chapter VII of TCC shall be payable for such support.	portion to be paid along with S1.No. 7.1.4)' will not be	shall be referred in this regard.
			payable for such support. In case, any defect is identified, repair work	payable to the vendor?	
			shall be done by contractor at no extra cost to	payable to the vehicor:	
			BHEL. Extra NDT & PWHT / SR arise due		
			to defect, shall be debited to contractor at		
			prevailing rate with 5% overhead.		
			Engagement of NDT & PWHT / SR agency		
			by BHEL, shall not vacate contractor from		
			their responsibility of workmanship till trial		
			run/PG Test/warrantee period. Repair in		
			weld joints, as and when required, shall be		
25		2.8.11	attended by the contractor." The storage yard is located within the plant	If the material yard is located	Tender Conditions shall Prevail.
23		2.0.11	boundary in multiple locations. All other	more than 3 km from the site,	Tender Conditions sharr revair.
			materials have to be transported from storage	M/s BHEL will be required to	
			yard to construction area by the contractor at	pay additional transportation	
			his own cost, using own Pick & Carry Crane	charges per kilometer per	
			(Farrana), crane and trailer.	metric ton for the extra	

Sl.	Reference	Clause	Existing provision	Bidder's query	BHEL's clarification
No	clause of	No.	J •	1	
	Tender				
	Document				
			13.2 The storage yard is located within the	distance beyond 3 km from	
			Main Plant Boundary.	the BHEL storage yard to the	
				project premises.	
26	TCC	3.2.2	Chargeable at a Single point source	Pl provided the Unit Charge	Refer the latest DISCOM rates of
		Electricity	(Chargeable) prevailing tariff on project site	and demand charges for the	the state for reference purpose
		for office,	at one or two points near the site at a distance	office, stores, canteen etc.	only.
		stores,	of approx.500 meter.		
		canteen			
		etc. of the bidder			
		(Chargeabl e) within			
		project			
		project			
27	TCC	3.9.2	In case labour hutment is not completed as	What happens if the vendor	Tender Conditions shall Prevail.
	100	0.7.2	per the drawings and specification and any	arranges rented	201001 00101120110 011011 110 10111
			penalty is imposed by Customer, same shall	accommodation for their	
			be recovered from contract's RA Bill.	workers in a nearby area close	
			Rectification and Corrections in labour	to the site? Is this permitted	
			hutment as pointed out by BHEL/Customer	by BHEL?	
			shall be bidder's responsibility and any cost		
			incurred by BHEL to complete the works, in		
			case of noncompliance of the instructions,		
			same shall be recovered from his RA Bills		
			along with 5% overheads		

Sl. No	Reference clause of Tender Document	Clause No.	Existing provision	Bidder's query	BHEL's clarification
28	TCC	3.11.7	Contractor to note that till construction power is made available by BHEL (approx. within 3 months from start of work); contractor shall make his own arrangement like DG set etc. The contractor shall also take the approval/ permission of statutory authorities for his DG set installation. The Contractor has to make his own arrangement for the same as required to carry out the job under the scope of work within the quoted rate. Nothing extra shall be paid on this account of DG set up and running for construction and office maintenance etc. Fuel (HSD) shall be paid at actuals till construction power is made available by BHEL during initial days. For outages of more than 2 hours (15 minutes tolerance) fuel shall be reimbursed by BHEL at actuals for running of DG set exclusively for construction purpose only.	construction power is provided by BHEL (approximately within 3 months from the start of work), BHEL will reimburse the actual fuel costs for running the DG set, which is used exclusively for construction purposes. Pl	Tender Conditions shall Prevail.
29	TCC	4.1 Major T&P:	1.Crawler Crane 150 MT -01 No. 2.Crawler Crane 75 MT -01 No.	*Pl provided the deployment period of each crane. 1.Crawler Crane 150 MT -01 No.: We request that M/s BHEL take responsibility for managing this crane. Is this	1. Tender Conditions shall Prevail

Sl. No	Reference clause of Tender Document	Clause No.	Exis	ting pr	ovisio	n	Bidder's query	BHEL's clarification
	Document		4.2 Other T&Ps: The following Other execution of work as per Technical Condition				crane meant for ESP	
			SN DESCRIPTION OF OTHER T&Ps	CAPACITY (MINIMUM)	MINIMUM QUANTITY	REMARKS	Package?	
			1 Tyre mounted mobile crane	35 MT	As per requirement	As per requirement	2. Crawler Crane 75 MT -01	2. Tender Conditions shall
			2 Tyre mounted mobile crane	18 MT	As per requirement	As per requirement	No.: This will be deployed till	Prevail
			3 Tyre mounted mobile crane	10 MT	As per requirement	As per requirement	completion of Preassembly of	
			4 Trailer with prime mover 5 Trailer with prime mover	20 MT 40 MT	2 Nos 1 Nos	As per requirement As per requirement	outlets Ducts.	2 T 1 G 12
			6 Low bed trailer Low bed trailer with min 70-100 feet span	60 MT	As per requirement	As per requirement	3.A 35 MT Tyre Mounted	3. Tender Conditions shall
			7 Backhoe Loader/JCB	NA min. 40mtr	NA As per		Mobile Crane will be	Prevail
			8 Man lifter Calibrated Power driven HSFG	height capacity As per	requirement As per	As per requirement	deployed for the pre-assembly	
			bolt tightening machines	Requirment	requirement	As per requirement	of the inlet and outlet funnels	
							and will be released shortly	
							after the pre-assembly is completed.	
							4. We request that M/s BHEL	4. Tender Conditions shall
							consider using a 15 MT	Prevail
							Farana pick-and-carry crane	Tievan
							instead of the 18 MT and 10	
							MT cranes. And also quantify	
							the qty of its deployment and	
							duration.	
							5.Based on our past	5. TCC Clause no. 4.2 (SN-4)
							experience, a single 20 MT &	Modified as:-
							40 MT trailer is sufficient for	Sl No 4 Trailer with Prime Mover
							single ESP & FGD.	(20 MT)- 1 nos in Contractor
								Scope.
							6.Since the man lifter is not	6. Refer Clause 4.14 Penalty due
							heavily utilized in the ESP	to non-availability of T&Ps.

Sl. No	Reference clause of Tender Document	Clause No.	Existing provision	Bidder's query	BHEL's clarification
				and FGD areas, does its non-deployment attract a penalty? *.In the event of an overstay of these Cranes & Trailers beyond the original contract period, the monthly hiring charges shall be paid by M/s BHEL at the prevailing market rate on a monthly basis until the equipment is demobilized from the site.	Refer GCC Clause no 2.12 OVERRUN COMPENSATION for the package,
30	TCC	4.1 Major T&P:	21. Air compressor/blower (electric/diesel operated) 210 CFM, 7KG/CM2 -01 no.	As per BHEL's standard practice Air Blower with damper for flow control/valve for ATT along its all electrical accessories including Power Cable shall be supplied by M/s BHEL.	Tender Conditions shall Prevail.
31	TCC	4.3.2	Heavy Equipment (cranes, winch etc.) manufactured less than 15 Yrs. from the current Year shall be only allowed to be used at project Site.	Instead of stating that the crane's lifespan is less than 15	Tender Conditions shall Prevail.

Sl. No	Reference clause of	Clause No.			Existi	ng pro	vision	Bidder's query	BHEL's clarification
	Tender Document								
32	TCC	5.1 LIST OF T&P	5.1 LIST OF T&P TO BE PROVIDED BY BHEL FREE OF HIRE CHARGES ON SHARING BASIS:		1. In which area and for what purpose does M/s BHEL	1) Tower Crane Shall be Used in ESP and FGD Area.			
		TO BE PROVIDE	SL NO	DESCRIPTION & CAPACITY OF T&P	QUANTITY Pkg-A	QUANTITY Pkg-B	REMARKS	intend to install the tower crane?	Specifications shall be decided in consultation with Project Director
		D BY BHEL	1	Tower Cranes	1 Nos	1 Nos	For ESP and FGD erection. Assistance to be provided by Bidder for Erection, dismantling of the Tower Crane.	Pl specify specification and configuration of Tower Crane.	depending upon site conditions. However, the crane shall be
		FREE OF HIRE CHARGE	2	Crane	Ai1	A	Any other crane required from the Cranes Mentioned in clause 4.1 of Chapter-IV and Tower Crane, if required to complete the package shall be provided by BHEL. The Capacity of Crane, Quantity and duration of		adequate to cater to the erection needs of ESP and FGD.
		S ON SHARING BASIS:			As required	As required	deployment shall be drawn mutually during the review meeting held at site. BHEL decision on deployment of crane other than mentioned in Chapter-IV and Tower Crane shall be final.	2.Min one 250 MT crane is required in FGD & ESP area.	2) Refer 5.1 list of T&P to be provided by BHEL free of hire charges on SHARING BASIS
			3	Venturimeter	As required	As required	Tower craite shall be final.		table Serial no 2 REMARKS.
			4	Huck Bolting Machine	As required	As required	Only machine will be provided by BHEL, the consumables required for the machine shall be arranged by bidder.		
33	TCC	4.2 Other T&Ps:			_		with forged clamps etc works (As per	This quantity is excessive; approximately 5,000 pipes	Modified as 46. Scaffolding materials with forged clamps for
			Rec	quirement tching cl	it) M	_	_	with matching clamps should be sufficient to complete the work.	insulation, painting etc works (As per Requirement) Min 5,000 pipes and matching clamps
34	TCC		Air ope			/blower 1, 7 KC	(electric/diesel G/CM2-01 no.	As per BHEL's standard practice Air Blower with damper for flow control/	Tender Conditions shall prevail.
								valve for ATT along its all electrical accessories	

Sl. No	Reference clause of Tender Document	Clause No.	Existing provision	Bidder's query	BHEL's clarification
				including Power Cable shall be supplied by M/s BHEL.	
35	TCC		Sufficient quantity of steel ladders for approach up to the top of each erected column to be required during erection of columns.	Based on our previous experience using the ladder supplied by BHEL for column erection, we request that M/s BHEL permit the use of the ladder provided in PGMA-79-921,922 & 932	Tender Conditions shall prevail.
36	TCC		Suspended working platform Size :7mX1mX0.5m, Rated load 800 kg to 1000 Kg, -01 Nos. (Prior to start of Cladding works.)	For Insulation and cladding we used to erect scaffolding for application of fixing component, insulation and cladding. Could you please clarify the purpose of deploying the suspended working platform in what context?	Modified as SN DESCRIPTION OF OTHER T&PS (MINIMUM) QUANTITY Suspended working platform Size As per 2:7mX1mX0.5m,Ra ted load 800 kg to 1000 Kg, MINIMUM QUANTITY REMAKRS Prior to start of Requirment Requirment Requirment Works.
37			MIG welding Machine (For welding of ESP Inner Roof and Outer Roof alone for Sheet Thickness of upto 5 mm.)	If M/s BHEL permits we may use in Preassembly of Funnels Plates as well as in Casing wall.	MIG welding can be used for preassembly of funnel walls only and not for casing walls. However, MIG welding should not be used for in-situ for erection welding of ESP funnels.

Sl. No	Reference clause of Tender Document	Clause No.	Existing provision	Bidder's query	BHEL's clarification
38	TCC	5.1 list of T&P to be provided by BHEL free of hire charges on sharing basis:	For ESP and FGD erection. Assistance to be provided by Bidder for Erection, dismantling of the Tower Crane.	Is M/s BHEL will provide the required capacity of crane for Erection, dismantling of the Tower Crane.	The required assistance for the Erection and Dismantling of Tower Cranes shall be in the scope of bidder.
39	TCC		Venturi meter	This also falls under the category of "T&P deployed by the vendor". Please clarify whether M/s BHEL will provide it or not.	Tender Conditions shall prevail.
40	TCC		Huck Bolting (As required Machine) Only machine will be provided by BHEL, the consumables required for the machine shall be arranged by bidder.	We request M/s BHEL to provide a new Huck Bolting Machine. If an older, functioning machine is supplied, M/s BHEL must also provide consumables for six months from the date of issue.	Tender Conditions shall prevail.
41	TCC	SECURED RECOVER- ABLE ADVANCES	 a) For Package – A 1. For Mobilization of 01 no. of Crane of 150 MT capacity, 1 no. of 75 MT Mobile crane - 2.0% of Contract value of Package-A. 2. For Posting of Site Manager and team consisting of Construction/Erection 	We request M/s BHEL to assign a weightage percentage for crane deployment, which should be paid on a monthly basis.	SECURED RECOVERABLE ADVANCES Modified as: Interest Free Secured Mobilization Advance as per GCC Clause No. 2.13.1 will be payable under exceptional circumstances on certification of

Sl. No	Reference clause of Tender Document	Clause No.	Existing provision	Bidder's query	BHEL's clarification
	Document		Engineers, Quality Engineer, Safety Engineer etc. in Site Office - 1.5% of Contract value of Package-A. 3.For Mobilization of required T & Ps to start the work, skilled manpower like fitters, Riggers, Gas-cutter, Grinders & other skilled manpower - 1.5% of Contract value of Package-A.		BHEL Construction Manager at Site. Interest Free Mobilization Advance shall be disbursed in specifically mentioned stages of major respective resource mobilization for both packages as specified hereunder: a) For Package – A 1) For Posting of Site Manager and team consisting of Construction/Erection Engineers, Quality Engineer, Safety Engineer etc. in Site Office and 1 nos of 75 MT Crane - 2% of Contract value of Package-A. 2) For Mobilization of required T & Ps to start the work, skilled manpower like fitters, Riggers, Gas-cutter, Grinders & other
					skilled manpower - 1.5% of Contract value of Package-A. 3) For Mobilization of 01 no. of Crane of 150 MT capacity

Sl. No	Reference clause of Tender Document	Clause No.	Existing provision	Bidder's query	BHEL's clarification
	Bocument				crane – 1.5% of Contract value of Package-A.
					b) For Package – B
					1) For Posting of Site Manager and team consisting of Construction/Erection Engineers, Quality Engineer, Safety Engineer etc. in Site Office and 1 nos of 75 MT Crane - 2% of Contract value of Package-B.
					2) For Mobilization of required T & Ps to start the work, skilled manpower like fitters, Riggers, Gas-cutter, Grinders & other skilled manpower - 1.5% of Contract value of Package-B.
					3) For Mobilization of 01 no. of Crane of 150 MT capacity crane – 1.5% of Contract value of Package-B.
					Note:

Sl. No	Reference clause of Tender	Clause No.	Existing provision	Bidder's query	BHEL's clarification
	Document				
					1. BHEL Site-CM shall be the deciding authority for assessing the admissibility of advance payment to contractor.
					2. In case contractor do not fulfil the agreed conditions of payment of earlier mobilization advance, BHEL Construction Manager will have the authority to not allow the subsequent mobilization advance to contractor.
42	TCC	10.1 Brief feature of Electrostat ic Precipitato r (ESP) & Auxiliaries for each Unit	6) Ash hoppers complete with curved panel heating elements, matching with curved surfaces of conical hopper, level monitors and indicators, outlet flanges, jointing material, poke holes, access doors and walkways beneath the hoppers.	1	Refer attached Field Quality Plan.
43	TCC	10.2 Brief feature of Flue Gas Desulfuriz ation (FGD) and	VIII. One number of Passengers cum Goods Elevator of adequate capacity shall be provided with adequate landings for absorber. The erection and commissioning of the Elevator is in Elevator Vendor Scope.	We presume that Passengers cum Goods Elevator shall be provided by M/s BHEL. However, its erection and commissioning of the Elevator is in Elevator Vendor	Refer Point no VIII. Under Serial No 1 of ABSORBER SYSTEM- It is mentioned that Only the structure is in the vendor scope for the Passengers cum Goods Elevator by BHEL. Payment of

Sl.	Reference	Clause	Existing provision	Bidder's query	BHEL's clarification
No	clause of	No.	<u> </u>		
	Tender				
	Document				
		Auxiliaries	Lift Structure and other supporting structure	Scope. Pl specify under which	structure shall be made under
		for each	is included in the scope of this contract.	head of the Terms of	relevant clauses as mentioned in
		Unit		Payment, it will be claimed by the Vendor.	Chapter-VII.
44	TCC	LIMESTONE GRINDING	Limestone Storage Silos- Fabrication and erection of Limestone Storage Silos	Will these silos be supplied in preassembled condition? If	The Silos are supplied in Segments Namely: -
		SYSTEM	complete with Supporting Steel structure,	yes, please also provide the	segments runnery.
			platforms, Staircase, air canons, power	number of segments for each	1) Cylinder of Silo- Maximum 3
			operated gates, gravimeter feeders etc.	shell	rings of average 5 nos. of
					segments in each ring.
					2) Ring Beam- Maximum 6
					segments.
					3) Hopper- Average 26 segments.
					Including Cone.
					The above requirements are
					provided to bidder to have a rough
					idea of the package; however, the
					actual segments may vary on
					approval of the design drawings.
					Reference drawing is attached,
					however the same shall not be
					taken as reference for the LARA Project Drawings for LAPA
					Project. Drawings for LARA project shall be issued
					subsequently.
					subsequently.

Sl.	Reference	Clause	Existing provision	Bidder's query	BHEL's clarification
No	clause of	No.			
	Tender				
	Document				
45	TCC	FGD	FRP Piping- The Erection Testing and Commissioning of FRP piping in the FGD area is also included in the scope of the contractor, all necessary arrangements required for the completion of the piping including consumables, special tools and tackles are to be arranged by vendor within the quoted rates.	experience M/s BHEL will arrange a separate agency for FRP piping. We request M/s BHEL to exclude it from	Tender Conditions shall prevail.
46	TCC	14.2.6	14.2.6 Erection & dismantling of air blowers and connecting pipes & ducts, providing blanks/ dummies at the required locations and conducting gas-tightness test is in the scope of contract and shall be carried out within the quoted rate.	Blanks/ Dummies Plates (Materials required) shall be provided by M/s BHEL Free	BHEL will provide materials for the dummies free of cost for conducting the Gas Tightness Test. Fabrication & Erection of the dummies in the scope of vendor.
47	TCC	14.3.5	14.3.5 Fixing of floor grills shall be done by self-tapping screws and not by weldable studs. Special purpose electrically operated hand tools are available in the market for this, which drills, taps and fixes the screws in a single operation. Supply of necessary self-drilling-cum-tapping screws and fixing clips are in contractor scope. Contractor shall deploy the drilling cum fixing machine required for this purpose as a regular scope of work. i) Agency shall supply self tapping screw for entire scope of work of different sizes as required at site.	Supply of necessary self-drilling-cum-tapping screws and fixing clips shall be supply M/s BHEL.	Tender Conditions shall prevail.

Sl. No	Reference clause of Tender Document	Clause No.	Existing provision	Bidder's query	BHEL's clarification
48	GCC	2.12 OVERRU N COMPEN SATION	2.12.3.1 For initial period of twelve months of extended period, ORC rate applicable over executed value shall be 5%. For every subsequent period of twelve months, ORC rate shall be further increased by 5% over the previous rate. For example, ORC rates applicable for initial period of 12 months and subsequent period of 12 months are given below. This process of increasing ORC rate for each subsequent period of 12 months shall continue till applicability of ORC. SI. Extended Period for the reasons ORC rate applicable over executed value 1 First 12 months 5% 2 13th 24th month and so on 10.25% [[(1.05 x 1.05)-1] x 100]	allocated in this tender document is set at 5%, which is insufficient to cover both the monthly rental charges and the site setup costs. For Heavy T&P items, the fixed monthly rental charges should be paid as per current market	Tender Conditions shall prevail.

Sl. No	Reference clause of Tender Document	Clause No.	Existing provision	Bidder's query	BHEL's clarification
49	GCC	2.12.3.5	2.12.3.5 The maximum amount of ORC payable for the month shall be limited to Rs. 10,00,000/- (Rupees Ten Lakhs). 2.12.3.6 In case, there is no shortfall attributable to contractor for the month and also contractor has deployed the resources as agreed in Form-14 but ORC amount payable for the month worked out as per procedure mentioned in clause 2.12.3.3, 2.12.3.4 and 2.12.3.5, is less than Rs.1,00,000/-, then ORC amount payable for the month shall be Rs.1,00,000/- otherwise ORC amount payable for the month shall remain same	increase the minimum and maximum values of the payable ORC amount, as the current amount is insufficient to cover the monthly site expenses and the vendor's	Tender Conditions shall prevail.
50	GCC	2.12.4	2.12.4 Applicability of ORC: ORC shall not be applicable for following activities. i). Area cleaning, removal of temporary structures and return of scrap.ii). Punch list points / pending points liquidation pending due to reasons attributable to contractoriii). Submission of "As built Drawing"iv). Material Reconciliationv). Completion of Contract Closure formalities like HR Clearance/ No dues from various dept./ Statutory Authorities etc.	ORC should be paid for all activities, as delays are generally not caused by the vendor.	Tender Conditions shall prevail.

Sl. No	Reference clause of Tender Document	Clause No.	Existing provision		Bidder's	query	BHEL's clarification
51	General		ESIC		Is ESIC applicab project? Please c		Refer GCC clause no. 2.8.3.
52	TCC	3.2.2	Electricity for office, stores, canteen etc (Chargeable) with in project premises	of the bidder	Kindly Provide the e cost for office store a rest room		Tender Conditions Shall Prevail
53	TCC	3.9.1	Labour Colony is to be developed by bid labours required to be deployed for the labour colony set-up is to be developed a drawing and in compliance of statutory	the works. All as per attached	We may provide the accommodation on i		Tender Conditions Shall Prevail
54	TCC	3.9.3	Land for labour colony shall be arranged at their own cost as per availability of area preferably within 5 kms levelling/dressing of land shall be contractor.	outside project s. Necessary	Kindly provide the la colony free of cost w		Tender Conditions Shall Prevail
55	TCC	3.9.3	For Non-Pressure Part Payment term Sub Packages On pre-assembly wherever applicable (if not applicable, this portion shall be clubbed with placement in position) Placement in position Alignment Welding/bolting/fixing/Torque check/tightness check of bolts	Non- Pressure Parts 20% 20% 20% 20%	We are request that the payment terms f parts as following: - Sub-Packages On pre-assembly wherever applicable (if not applicable, this portion shall be clubbed with placement in position) Placement in position Alignment		Tender Conditions Shall Prevail

Sl. No	Reference clause of Tender Document	Clause No.	Existing provision		Bidder's	query	BHEL's clarification
			Completion of non-destructive examination —as per approved FQP/EWS (if not applicable, then this portion to be paid along with S.No. 7.1.4)	5%	Welding/bolting /fixing/Torque check/tightness check of bolts Completion of	10%	
			Completion of attachment welding, fin welding, supports in individual area of work	5%	non-destructive examination –as per approved FQP/EWS (if not	5%	
			Hangers & supports etc wherever necessary as per drg	5%	applicable, then this portion to be paid along with S.No. 7.1.4)		
					Completion of attachment welding, fin welding, supports in individual area of work	5%	
					Hangers & supports etc wherever necessary as per drg	5%	

Note:

- 1) All other terms and conditions against this NIT shall remain unchanged.
- 2) This corrigendum is to be submitted duly signed and stamped along with the Techno-commercial bid (Part- I).

for BHARAT HEAVY ELECTRICALS LTD Sr. Manager/ SCT



एन टी पी सी लिमिटेड (भारत सरकार का उद्यम) NTPC Limited (A Govt. of India Enterprise) (Formerly National Thermal Power Corporation Ltd.) (केंद्रीय कार्यालय नोएडा) Corporate Center NOIDA

Reference: CC-ENGG-9587-001-104-QVM-Q-091 **Date**: 19/08/2024

From: RAMESH CHANDRA SHIAL

ENGINEER

To: BHARAT HEAVY ELECTRICALS LTD

NEW DELHI 110049 IN

Cc: sudipt@bhel.in

dipakbag@bhel.in

Subject: EPC Package

Please find enclosed following drawings/ documents for necessary action at your end.

Vendor Drg. No.: PP-QBE-2401-HD-QA-204 **Orgn. Drg. No.**: 9587-001-104-QVM-Q-091

Revision No. : 00

Comments


Drg. Title : Filed Quality Plan FOR ESP MECHANICAL ERECTION

App. Category : CAT-III

Release Date : 19/08/2024

Cat III. Please submit the copy of ESP erection manual for review of this doc.







FIELD QUALITY PLAN FOR ELECTRO STATIC PRECIPITATOR (MECH)



एनटीपीसी - लारा सुपर थर्मल पावर प्रोजेक्ट चरण-II (2x800 MW)

NTPC-LARA SUPER THERMAL POWER PROJECT STAGE-II (2x800 MW)

एनटीपीसी दस्तावेज़ संख्या / NTPC DOC. NO. : 9587-001-104-QVM-Q-091 संशोधन संख्या / REV. №: 00



भारत हेवी इलेक्ट्रिक ल्स लिमिटेड पावर सेक्टर - पूर्वी क्षेत्र, कोलकाता – 700091

BHARAT HEAVY ELECTRICALS LIMITED

POWER SECTOR - EASTERN REGION, KOLKATA - 700091

दस्तावेज़ संख्या / BHEL DOC. NO.: PP-QBE-2401-HD-QA-204

संशोधन संख्या / REV. №: 00





FIELD QUALITY PLAN FOR **ELECTRO STATIC PRECIPITATOR (MECH)**

एनटीपीसी दस्तावेज़ संख्या / NTPC DOC. NO. : **9587-001-104-QVM-Q-091** संशोधन संख्या / REVISION NO.: 00


द्वारा तैयार PREPARED BY	Digitally signed by ARUP RATAN PAUL DN: c-IN, o-BHARAT HEAVY ELECTRICALS LIMITED, our-GOVERNMENT, 25.42 - b-053550-604-20 addbotd:dbi-feadis c91a7:d353fa88668996h74b6536-9655939 postalCode-700091; s-WEST BENGAL serialNumber=12BC38448BF87320F7DE8 F8872DAD92476JADAG-6669098A67-03 3A8F0AE_cn=ARUP RATAN PAUL Date: 2024.08.09 17:54:54 +0530'	APPROVED BY	SNEHASIS Objective power by SNEHASE ANNOCA. SNEHASIS ON CHI. Co-The collegate theory described unitreed. On Co-The Collegate theory described unitreed. On Co-The Collegate theory of the Collegate theory of the Collegate theory. On Collegate theory of the Collegate theory of the Collegate theory of the Collegate theory. On Collegate theory of the Collegate theory
एफक्यूपी संख्य	T / FQP NO.	PP-QBE-240	1-HD-QA-204
जारी करने की ISSUE	मूल तिथि / DATE OF FIRST	06/08/2024	
संशोधन संख्या	और तारीख / REV. № & DATE	Rev. Nº : 00 ,	Date : 06/08/2024
कॉपी नंबर / CC	OPY NO.	01	
को जारी / ISSU	ED TO		
जारी करने की	तिथि / DATE OF ISSUE		
उद्देश्य / PUR	POSE		
द्वारा जारी (हस्ताध ISSUED BY (SI	क्षर और पदनाम) IGNATURE & DESIGNATION)		



भारत हेवी इलेक्ट्रिक ल्स लिमिटेड पावर सेक्टर - पूर्वी क्षेत्र, कोलकाता – 700091

BHARAT HEAVY ELECTRICALS LIMITED

POWER SECTOR - EASTERN REGION, KOLKATA - 700091





FIELD QUALITY PLAN FOR ELECTRO STATIC PRECIPITATOR (MECH)

एफक्यूपी संख्या / FQP NO: **PP-QBE-2401-HD-QA-204**

संशोधन संख्या / REV. №: 00


शीट / SHEET : 01 / 01



Scan QR code for checking the latest revision

विषय-सूची / CONTENTS

क्रम संख्या <u>S. No.</u>	<u>विवरण</u> <u>Description</u>	<u>शीट की संख्या</u> No. of Sheets
1.0	संशोधन स्थिति Status of Revisions	01
2.0	जाँच और नॉनकन्फ़र्मिटि समाधान के लिए प्राधिकार Authorization for checks and nonconformity disposition	01
3.0	जाँच का विवरण Statement of Checks	07
4.0	गुणवत्ता योजना में संदर्भित दस्तावेज Documents referred in QP	01
5.0	लॉग शीट्स Log Sheets (L-00 to L-04)	07
6.0	प्रोटोकॉल प्रारूप Protocol Format	01





FIELD QUALITY PLAN FOR ELECTRO STATIC PRECIPITATOR (MECH)

एफक्यूपी संख्या / FQP NO: **PP-QBE-2401-HD-QA-204**

संशोधन संख्या / REV. №: 00


शीट / SHEET : 01 / 01



Scan QR code for checking the latest revision

संशोधन स्थिति / STATUS OF REVISIONS

क्रम संख्या	संशोधित शीट का संदर्भ	संशोधन संख्या और तारीख	टिप्पणियाँ
SL. NO.	REFERENCE OF SHEETS REVISED	REVISION NO. & DATE	REMARKS
01	All	00, 06/08/2024	Document prepared in line with NTPC Technical Specifications.





FIELD QUALITY PLAN FOR ELECTRO STATIC PRECIPITATOR (MECH)

एफक्यूपी संख्या / FQP NO: **PP-QBE-2401-HD-QA-204**

संशोधन संख्या / REV. №: 00

शीट / SHEET : 01 / 01



Scan QR code for checking the latest revision

जाँच और नॉनकन्फ़र्मिटि समाधान के लिए प्राधिकार AUTHORISATION FOR DIFFERENT CATEGORIES OF CHECKS & NONCONFORMITY DISPOSITION

जाँच की श्रेणी Category of Check	निरीक्षण प्राधिकारी Inspection Authority	साक्षी तथा स्वीकृति प्राधिकारी Witness & Accepting Authority	एनटीपीसी द्वारा निगरानी Surveillance by NTPC
'A' (CHP)	BHEL FQA Engineer in association with Executing Engineer.	NTPC FQA Engineer in association with Executing Engineer.	Head FQA/ NTPC
'B' (CHP)	BHEL Executing Engineer.	NTPC Executing Engineer.	FQA Engineer
'C'	BHEL Executing Engineer.	NTPC Executing Engineer.	Another Engineer authorised by Head (Executing Department)


लेख / Legend:

Class A: Critical, Class B: Major, Class C: Minor.

SR - Site Register, TR- Test Report, LB-Log Book, IR - Inspection Report, MTC - Manufacturer's Test Certificate.

टिप्पणियाँ / Notes:

- 1. गुणवत्ता योजना में किसी भी गैर-अनुरूपता/विचलन को एनटीपीसी के ध्यान में लाया जाना चाहिए। एनटीपीसी एफएक्यू सिस्टम मैनुअल के अनुसार निपटान प्राधिकारी एनटीपीसी का अधिकृत प्रतिनिधि होगा।
 - Any non-conformity/ deviation to the Quality plan must be brought to notice of NTPC/Owner. Dispositioning authority shall be the authorised representative of NTPC/Owner as per NTPC FQA system manual.
- 2. सभी विशेषताओं के लिए जाँच की मात्रा 100% होगी जब तक कि निर्माण क्षेत्र गुणवत्ता योजना/ संदर्भ दस्तावेजों में अन्यथा उल्लेख न किया गया हो।
 - Quantum of check shall be 100% for all characteristics unless otherwise mentioned in Field Quality Plan/ reference documents.
- 3. ग्राहक अपने निर्णय से किसी भी 'सी' श्रेणी की जाँच में निगरानी करने के लिए भी अधिकृत है। Customer is also authorized to carry out surveillance in any of 'C' category of checks at his discretion.
- 4. सुरक्षित पहुंच सुनिश्चित की जाएगी और केवल उचित सुरक्षा गियर वाले अधिकृत व्यक्ति को ही निर्माण क्षेत्र में प्रवेश करने की अनुमति दी जाएगी।
 - Safe access shall be ensured and only the authorized persons with proper safety gears to be allowed in construction area.





FIELD QUALITY PLAN FOR ELECTRO STATIC PRECIPITATOR (MECH)

एफक्यूपी संख्या / FQP NO: **PP-QBE-2401-HD-QA-204**

संशोधन संख्या / REV. №: 00

शीट / SHEET : 01 / 06



Scan QR code for checking the latest

जाँच का विवरण / STATEMENT OF CHECKS

क्षमता / प्रकार Capacity / Type	: 800MW
सिस्टम System	: Steam Generator & Auxiliaries
सब-सिस्टम Sub-system	: Electro Static Precipitator
क्षेत्र Area	: Mechanical Erection

इस्तेमाल किए गए संक्षिप्ताक्षर / ABBREVIATIONS USED:

R – रिकॉर्ड सत्यापन / Record Verification, V – विस्अत जांच / Visual Check, P – फ़िसीकाल जांच / Physical Check, M – माप / Measurement, T – परीक्षण / Test, MTC – निर्माता परीक्षण प्रमाणपत्र / Manufacturers Test Certificate, SR – साइट रजिस्टर / Site Register, MDR – सामग्री असंगति रिपोर्ट / Material Discrepancy Report

टिप्पणियाँ / NOTES:

1. कार्य को संतोषजनक ढंग से करने के प्रमाण के रूप में, सभी जांचों के लिए एक सामान्य प्रयोजन लॉग शीट, L-00 बनाए रखा जाएगा।

As an evidence of having carried out the work satisfactorily, a general-purpose log sheet, L-00 shall be maintained for all the checks.

2. गैर-अनुरूपता के मामले में, स्वीकार करने वाला प्राधिकारी स्वीकृति से पहले गैर-अनुरूपता का निपटान सुनिश्चित करेगा, और निपटान लॉग-शीट/प्रोटोकॉल में प्रतिबिंबित किया जाएगा।

In case of nonconformity, accepting authority shall ensure the disposition of the nonconformity before acceptance and disposition shall be reflected in the log-sheets/ protocols.

- 3. मानकों, विशिष्टता और ड्राइंग का नवीनतम संशोधन लागू होगा। Latest revision of Standards, Specification & Drawings shall apply.
- 4. माप के लिए केवल एनटीपीसी-स्वीकृत और एनएबीएल मान्यता प्राप्त प्रयोगशाला से वैध अंशांकन प्रमाणपत्र वाले गेज और माप उपकरणों का उपयोग किया जाएगा।
 - Only the Gauges and Measuring Instruments having valid calibration from a NTPC-accepted and NABL accredited laboratory shall be used.
- 5. कॉलम संख्या 'D*' में "टिक" (√) चिह्न के साथ पहचाने गए रिकॉर्ड का प्रारूप अनिवार्य रूप से क्यूए दस्तावेजीकरण में शामिल किया जाएगा।

Format of record identified with "tick" ($\sqrt{\ }$) mark in column no. 'D*' shall be essentially included in QA documentation.

			III FIEI	FIELD QUALITY PLAN	PLAN					Skowesh
	SUPPLIERS NAME AND ADDRESS	SYSTEM : St	SYSTEM : Steam Generator & Auxiliaries	QP NO : PP-QBE	QP NO.: PP-QBE-2401-UHN-QA-104	PROJECT:	NTPC -LARA stage-II 2x800 MW	2x800 MW		/
1 5 111 11		CI ID. CVCTEM	CIB. CVCTEM · Electro Ctatic Drocinitator	REV. №: 00		PACKAGE:	EPC			
HH	पावर सेक्टर - पूर्वी क्षेत्र, कोलकाता ВНАВАТ НЕЛХУ EI ECTBICAI S I IMITED	30B-31EIM	. Electro Static Frecipitator	DATE: 06/08/2024	4	CONTRACT NO.	CS-9587-001R-2-SC-NOA-7333, DATE-29.08.2023	OA-7333, DATE	29.08	:023
	PS:ER, KOLKATA AREA : Mechanical Erection	AREA : Mecha	nical Erection	PAGE :2 of 13		MAIN CONTRACTOR	MAIN CONTRACTOR BHEL, PS:ER, KOLKATA	TA.		
SI. No	Activity and operation	Type of Check	Characteristics / instruments	Class of check	Quantum of check	Reference Document	Acceptance Norms	Format of Record	cord	Remark
1	2	3	4	5	9	7	8	6	ν,	
4	GENERAL REQUIREMENTS									
1.01	Ensure availability of requisite equipment in good working condition well before commencement of concerned activity. NOTE: Functioning of MMEs in proper working condition to be verified on monthly basis.	ი ფ ন	Wherever practical, a label shall be affixed on the Instrument, indicating the validity of Calibration	٧	All MMEs in the field shall be calibrated before start of work and thereof yearly OR immediately after repair	Technical Specifications & Drawing	The calibration certificate shall specify the fitness of the MMEs within the limit of tolerance for use.	List of equipment / Calibration certificate	7	Calibration shall be done by NABL accredited & NTPC-approved lab and the report shall be submitted to NTPC
1.02	Ensure availability of approved drawings & procedures, as applicable	ч	-	В	100% for each structure before start of activity	List of Latest Revision of Approved Drawings and Owner's Technical Specifications		ı		
2	FOUNDATION CHECKS									
2.01	Location of foundation pedestals of ESP with reference axes to boiler.	Σ	Measuring Tape	В	100%	Drawing / Ere	Drawing / Erection Manual	L-01	>	
2.02	Top elevation of foundation pedestals to be ensured as per drawing.	M	Water Level / Dumpy Level / Scale	В	100%	Drawing / Ere	Drawing / Erection Manual	L-01	>	
2.03	Spacing between foundation pedestals and its diagonals.	Σ	Measuring Tape	Ф	100%	Drawing / Er	Drawing / Erection Manual	L-01	>	
2.04	Bott pitches and its diagonals of individual pedestals. (7X-X80 Foundation Bott)	Σ	Measuring Tape	В	100%	Drawing / Ere	Drawing / Erection Manual	L-01	>	
3	STRUCTURE									
3.01	Check Camber and sweep in column pieces before erection.	≥	Piano wire / Tape	В	100%	Drawing & Er	Drawing & Erection Manual	SR	>	
3.02	Check BOB level, orientation, spacing between columns and its diagonals.	M	Measuring Tape / Water Level	В	100%	Drawing & Er	Drawing & Erection Manual	L-01	<u>ъ с</u>	BOB shall be ensured using shim plates as per drawing.
3.03	Verticality of X81 columns both in X & Y directions.	M \	Electronic theodolite / Measuring Tape	В	100%	Drawing & Er	Drawing & Erection Manual	L-02	7	
3.04	Ensure completion of bolt tightening of horizontal and diagonal bracings & supporting structures before erecting casing columns.	M	Bolt tension calibrator, Torque wrench	В	Random 10% or 2 no, bolt assy., which ever is larger, in each joint	Drawing	Drawing, IS 4000	Joint Protocol	>	
3.05	Verification of test certificates of grout material and grouting of column bases.	^		В	100%	Drawing & Gro	Drawing & Grouting Procedure	SR	0 1	Cube test of Grout by FQA
3.06	Ensure proper sequence of welding, as applicable	>	,	O	100%	Drawings & WPS	Drawings & WPS	SR		



			FIE	FIELD QUALITY PLAN	LAN					Kamesh
	SUPPLIERS NAME AND ADDRESS	SYSTEM : Ste	SYSTEM: Steam Generator & Auxiliaries	QP NO.: PP-QBE-2401-UHN-QA-104	2401-UHN-QA-104	PROJECT:	NTPC -LARA stage-II 2x800 MW	3x800 MW		/
\$ na lin		NETSYSTEM .	SIB-SYSTEM · Flactro Static Dracinitator	REV. №: 00		PACKAGE:	EPC			
HH	पावर सेक्टर - पूर्वी क्षेत्र, कोलकाता स	305-315 EMI.	Electio Static Frecipitatol	DATE: 06/08/2024		CONTRACT NO.	CS-9587-001R-2-SC-NOA-7333, DATE-29.08.2023	OA-7333, DATE	29 08	1023
11	PS:ER, KOLKATA AREA: Mechanical Erection	AREA: Mechar	lical Erection	PAGE :3 of 13		MAIN CONTRACTOR	MAIN CONTRACTOR BHEL, PS:ER, KOLKATA	TA		
SI. No	Activity and operation	Type of Check	Characteristics / instruments	Class of check	Quantum of check	Reference Document	Acceptance Norms	Format of Record		Remarks
1	2	3	4	5	9	7	8	6	D *	
4	7X-X01 SLIDE SUPPORT BEARINGS									
4.01	Ensure location and orientation of sliding supports w.r.t. fixed foot. NOTE: Ensure that support bearings are erected in locked condition and to be released before admitting flue gas into ESP.	Σ	Таре	ď	100%	Drawing & Err	Drawing & Erection Manual	L-03	7	
4.02	Ensure type (biaxial / mono axial) and capacity (vertical load / horizontal load) of bearing as per drawing.	>		В	100%	Drawing & Err	Drawing & Erection Manual	Log Book		
4.03	Check Top level of support (slide supports and fixed foot).	M	Water Level /Scale	А	100%	Drawing & Er	Drawing & Erection Manual	L-03	^	
4.04	Check Horizontality of slide supports.	Σ	Water Level / Scale	۲	100%	Drawing & Er	Drawing & Erection Manual			
4.05	Ensure welding of top and bottom plates at all locations.	^		А	100%	Drawing, Technical Directive: 016 & Erection Manual	Directive: 016 & Erection Manual	SR		
2	7X-X48 CASING STRUCTURE									
5.01	Check Column overall height as per drawing before erection	M	Tape	В	100%	Drawing & Er	Drawing & Erection Manual	SR		
5.02	Check Diagonals of inlet, outlet and intermediate frames (pre-assembly).	M	Таре	В	100%	Drawing & Er	Drawing & Erection Manual	L-04	>	
5.03	Check Verticality of all columns of inlet, outlet and intermediate frames in both X & Y directions.	M	Plumb bob / Tape	В	100%	Drawing & En	Drawing & Erection Manual	L-02	>	
5.04	Check Verticality of inlet, outlet and intermediate frames after erection.	M	- op -	В	100%	Drawing & Er	Drawing & Erection Manual	L-02	^	
5.05	Ensure the center line matching of X81 columns, X01 bearings and X48 columns before erection of casing assembly (maximum permissible deviation: 5 mm) Transfer the foundation center line to base plate center line. From the base plate, transfer the center line to bearing bottom plate. From the bearing bottom plate.	> 8	Tape	ω	100%	Drawing & Err	Drawing & Erection Manual	S		
5.06	Ensure welding of horizontal and diagonal bracings to the gusset provided in the column as per assembly drawing.	>		В	100%	Drawing, Technical Directive: 017 & Erection Manual	Directive: 017 & Erection Manual	SR		
5.07	Ensure completion of welding of casing structure with horizontal and diagonal bracings before erecting further and load the same.	>		В	100%	Drawing, Technical Dir Mar	Drawing, Technical Directive: 017 & Erection Manual	SR		
5.08	Close the welding openings outside of gas path.	>		O	100%	Drawing & Er	Drawing & Erection Manual	SR		

			먪	FIELD QUALITY PLAN	LAN					Mamosh
	SUPPLIERS NAME AND ADDRESS	SYSTEM : St	SYSTEM : Steam Generator & Auxiliaries	QP NO.: PP-QBE-2401-UHN-QA-104	2401-UHN-QA-104	PROJECT:	NTPC -LARA stage-II 2x800 MW	2x800 MW		/
S. D.A. IB	भारत हेवी इलेक्ट्रिक्त्स लिमि <u>ो</u> ड		SI IB-SYSTEM · Flortro Static Dracinitator	REV. №: 00		PACKAGE:	EPC			
HH			. Electro Static Frecipitator	DATE: 06/08/2024		CONTRACT NO.	CS-9587-001R-2-SC-NOA-7333, DATE-29.08.2023	OA-7333, DATE	29 08 2	023
	PS:ER, KOLKATA AREA: Mechanical Erection	AREA: Mecha	nical Erection	PAGE :4 of 13		MAIN CONTRACTOR	MAIN CONTRACTOR BHEL, PS:ER, KOLKATA	TA		
SI. No	Activity and operation	Type of Check	Characteristics / instruments	Class of check	Quantum of check	Reference Document	Acceptance Norms	Format of Record		Remarks
1	2	3	4	5	6	7	8	6	D*	
9	CASING SHELL									
6.01	Straightness and diagonals of wall panel assembly before erection.	M	Tape / Piano wire	0	100%	Drawing & En	Drawing & Erection Manual	Log Book		
6.02	Ensure that Panels are temporarily stiffened during lifting. NOTE: Wall panels should be welded with respective columns before erecting next panel.	۸	-	S	100%	Drawing & Err	Drawing & Erection Manual	SR		
6.03	Check Verticality of walls.	M	Plumb bob / Tape	В	100%	Drawing & Er	Drawing & Erection Manual	Joint Protocol	^	
6.04	Check Distance between the walls.	Μ	Tape	၁	100%	Drawing & Er	Drawing & Erection Manual	SR		
6.05	Check Straightness of wall along the gas flow.	Μ	Piano wire / Tape	O	100%	Drawing & Er	Drawing & Erection Manual	SR		
90'9	Check Diagonals of wall panel assembly after erection.	M	Tape	А	100%	Drawing & Er	Drawing & Erection Manual	F-05	^	
6.07	Ensure welding between primary stiffeners in casing wall with horizontal bracings in X48 PGMA.	۸		В	100%	Drawing, Technical Directive: 034 & Erection Manual	ective: 034 & Erection nual	SR	<u>> ŪÑ</u>	Welding & NDT check as per SI. No. 20
6.08	Ensure completeness of welding at all locations. (Fasteners are provided for locating purpose only).	۸		В	100%	Drawing & En	Drawing & Erection Manual	SR	<u>> ʊ ʎ</u>	Welding & NDT check as per SI. No. 20
60.9	Weld continuous fillet in the inner side (gas path) of the walls.	۸		В	100%	Drawing & Er	Drawing & Erection Manual	SR	<u>> ʊ ʎ</u>	Welding & NDT check as per SI. No. 20
6.10	Weld fillet size and length of weld to be ensured at all locations.	۸		O	100%	Drawing & Er	Drawing & Erection Manual	SR	<u>> 0 Ñ</u>	Welding & NDT check as per SI. No. 20
6.11	Ensure proper erection of deflection plates to avoid sneakage.	^		A	100%	Drawing, Technical Directive: 026 & Erection Manual	ective: 026 & Erection nual	SR		
2	ROOF BEAMS									
7.01	Camber and sweep of roof beams in pre-assembly condition before erection.	Μ	Piano wire/ Tape/ Water Level	В	100%	Drawing & Er	Drawing & Erection Manual	Log Book		
7.02	Length, out of squareness of roof beams before erection.	Σ	Tape / Plumb bob	В	100%	Drawing & Err	Drawing & Erection Manual	Log Book		
7.03	Centre line to be marked on both side of the flanges.	۸		o	100%	Drawing & Eท	Drawing & Erection Manual	Log Book		
7.04	Welding of Roof Beams NOTE: 1. Before placing the splice plate each layer of weld shall undergo LPI 2. LR beam butt welding to be inspected with RT/ PAUT after completion of all welding.	>		а	100%	Drawing & Erection Manual	ection Manual	Log Book	> Ü N	Welding & NDT check as per SI, No. 20

			FIEI	FIELD QUALITY PLAN	-LAN					Kamesh
	SUPPLIERS NAME AND ADDRESS	SYSTEM : Ste	SYSTEM : Steam Generator & Auxiliaries	QP NO.: PP-QBE-2401-UHN-QA-104	2401-UHN-QA-104	PROJECT:	NTPC -LARA stage-II 2x800 MW	2x800 MW		/
S DIA IN			SI IB-SYSTEM · Flortro Static Dracinitator	REV. №: 00		PACKAGE:	EPC			
HA	पावर सेक्टर - पूर्वी क्षेत्र, कोलकाता Выхрат нелуу हा हत्मधारता हु । IMITED		Electio Static Frecipitator	DATE: 06/08/2024		CONTRACT NO.	CS-9587-001R-2-SC-NOA-7333, DATE-29.08.2023	OA-7333, DATE	= 29 08	2023
	PS:ER, KOLKATA AREA : Mechanical Erection	AREA: Mechar	nical Erection	PAGE :5 of 13		MAIN CONTRACTOR	MAIN CONTRACTOR BHEL, PS:ER, KOLKATA	ΤA		
SI. No	Activity and operation	Type of Check	Characteristics / instruments	Class of check	Quantum of check	Reference Document	Acceptance Norms	Format of Record	cord	Remarks
1	2	3	4	5	9	7	8	6	ν,	時が百
7.05	Level of bottom flange of roof beams.	M	Water Level / Scale	А	%001	Drawing & Er	Drawing & Erection Manual	T-05	٨	
90'.2	Spacing of roof beams.	M	Таре	В	%001	Drawing & Er	Drawing & Erection Manual	F-05	٨	
70.7	Marking of gas path center line (GPCL) on roof beams on top and bottom flange.	Σ	Plumb bob / Tape	٨	100%	Drawing & Er	Drawing & Erection Manual	F-05	>	
7.08	Alignment of insulator support panel w.r.t. GPCL - spacing and diagonals.	M	Piano wire / Tape	A	%001	Drawing & Er	Drawing & Erection Manual	90-7	٨	
7.09	Ensure TR beam CL coincide with top panel vertical stiffener web bottom line.	M&V	Tape	O	100%	Drawing & Er	Drawing & Erection Manual			
7.10	Ensure welding of stiffeners in LR beams at casing column locations.	۸		O	%001	Drawing & Er	Drawing & Erection Manual			Welding & NDT check as per SI. No. 20
7.11	Ensure welding of stiffeners in TR beams at primary channel locations in side wall top panel.	۸		O	%001	Drawing & Er	Drawing & Erection Manual			Welding & NDT check as per SI. No. 20
7.12	Ensure completeness of welding at all locations. (Fasteners are provided for locating purpose only).	۸		В	%001	Drawing & Er	Drawing & Erection Manual			Welding & NDT check as per SI. No. 20
8	COLLECTING ELECTRODE SUSPENSION									
8.01	Check for straightness and dimensional tolerance (at ground before erection).	M	Tape	2	%001	Drawing & Er	Drawing & Erection Manual			
8.02	Diagonal variation of individual frame between corner hooks.	M	Tape	В	4001	Drawing & Er	Drawing & Erection Manual	L-07	٨	
8.03	Individual and cumulative pitch of support angles.	Σ	Таре	ပ	100%	Drawing & Er	Drawing & Erection Manual	L-07	>	
8.04	Check Straightness of frame.	M	Piano wire / Tape	В	100%	Drawing & Er	Drawing & Erection Manual	Log Book		
8.05	Ensure Alignment of frame w.r.t. GPCL.	ν	Tape	¥	%001	Drawing & Er	Drawing & Erection Manual	RO-7	٨	
8.06	Disposition of adjacent suspension frame, cumulative measurement from GPCL to the middle angle of individual suspension frames.	V	Таре	Ą	100%	Drawing & Er	Drawing & Erection Manual	R-08	>	
8.07	Hooks in angles at rapping side are in one-line perpendicular to GPCL.	Μ	Piano wire / Tape	В	100%	Drawing & Er	Drawing & Erection Manual			
8.08	Distance between center of emitting system suspension point to first hook with collecting electrodes frames.	M	Таре	A C	100%	Drawing & Er	Drawing & Erection Manual	L-08	>	
8.09	Gap between guide ends and casing walls.	M	Таре	၁	100%	Drawing & Er	Drawing & Erection Manual	L-08	^	
8.10	Level of suspension frames at bottom of end hooks in each field.	M	Water Level / Scale	В	100%	Drawing & Er	Drawing & Erection Manual	SR		



				FIELD QUALITY PLAN	LAN					Mamosh
	SUPPLIERS NAME AND ADDRESS	SYSTEM : Ste	SYSTEM: Steam Generator & Auxiliaries	QP NO.: PP-QBE-2401-UHN-QA-104	401-UHN-QA-104	PROJECT:	NTPC -LARA stage-II 2x800 MW	2x800 MW		/
S na In		SIIB_SYSTEM .	SIB-SYSTEM · Flortro Static Dracinitator	REV. №: 00		PACKAGE:	EPC			
HHH	पावर सेक्टर - पूर्वी क्षेत्र, कोलकाता ' हाउन्हर्म महत्र हा हत्मग्रह्म हा । MITED		Electio Static Frecipitator	DATE: 06/08/2024		CONTRACT NO.	CS-9587-001R-2-SC-NOA-7333, DATE-29.08.2023	OA-7333, DATE	29 08	:023
	BITAINA I REAVE LINIOALS LIMITED PS:ER, KOLKATA AREA: Mechanical Erection	AREA: Mechan	ical Erection	PAGE :6 of 13		MAIN CONTRACTOR	MAIN CONTRACTOR BHEL, PS:ER, KOLKATA	ТА		
SI. No	Activity and operation	Type of Check	Characteristics / instruments	Class of check	Quantum of check	Reference Document	Acceptance Norms	Format of Record		Remarks
1	2	3	4	5	9	7	8	6	D *	
8.11	Completion of welding. NOTE: 1. Welding of locking plate shall be on one side of roof beam only. 2. Do not weld suspension arrangement and attachment to roof beams. 3. Ensure welding of support angle with support beam.	>	•	۵	100%	Drawing & Er	Drawing & Erection Manual	L-11	> 0 ((Welding & NDT check as per Sl. No. 20
6	EMITTING ELECTRODE SUSPENSION:	†							+	
9.01	Diagonal variation of individual frames between corner holders.	M	Tape	В	100%	Drawing & Er	Drawing & Erection Manual	F-09	^	
9.02	Individual and cumulative pitch between rows.	Σ	Таре	В	100%	Drawing & Er	Drawing & Erection Manual	F-09	>	
9.03	Straightness of support beams, vertical beams and shock beams.	W	Piano wire / Tape	В	100%	Drawing & Er	Drawing & Erection Manual	Joint Protocol	>	
9.04	Straightness of vertical stays. (if applicable)	>	•	O	100%	Drawing & Er	Drawing & Erection Manual			
9.05	Alignment of support beam with frame part top.	W	Water level / Tape	4	100%	Drawing & Er	Drawing & Erection Manual	L-10	>	
90.6	Alignment of frame part top w.r.t. GPCL.	Σ	Таре	∢	100%	Drawing & Er	Drawing & Erection Manual	Log Book		
9.07	Cumulative pitches and diagonals of the holders of frame part top.	M	Таре	o	100%	Drawing & Er	Drawing & Erection Manual	Log Book		
90.6	End side emitting frame middle to be positioned before erecting the frame bottom.	^		O	100%	Drawing & Er	Drawing & Erection Manual			
60.6	During alignment of middle and bottom frames, the water level of shock angle of the middle frame shall be maintained uniform throughout the width of ESP.	^		В	100%	Drawing & Er	Drawing & Erection Manual			
9.10	Holders are in one line for top, middle and bottom frame part.	Μ	Plumb bob / Tape	В	100%	Drawing & Er	Drawing & Erection Manual	Log Book		
9.11	Verticality and diagonals of emitting frame work assembly for frame part middle and bottom.	Μ	Plumb bob / Tape	٨	100%	Drawing & Er	Drawing & Erection Manual	L-10	>	
9.12	Alignment of holders top to bottom in both directions – measure at four extreme corner holders.	M	Plumb bob / Tape	o	100%	Drawing & Er	Drawing & Erection Manual	Log Book		
9.13	The gap between emitting frame of two bus sections shall be maintained at prescribed levels at all places. Excess projection of EE frame towards casing wall shall be cut & maintained to 50mm at all levels after completion of alignment.	>		∢	100%	Drawing, Technical Dii Mai	Drawing, Technical Directive: 027 & Erection Manual			
9.14	Ensure welding of supporting beam with frame part top and welding of supporting beam with vertical beam.	>		O	100%	Drawing & Er	Drawing & Erection Manual			

			먪	FIELD QUALITY PLAN	LAN					Mamesh
	SUPPLIERS NAME AND ADDRESS	SYSTEM : Ste	SYSTEM : Steam Generator & Auxiliaries	QP NO.: PP-QBE-2401-UHN-QA-104	2401-UHN-QA-104	PROJECT:	NTPC -LARA stage-II 2x800 MW	2x800 MW		/
ह तात है	भारत हेवी इलेक्ट्रिक्त्स लिमिोड		SIIB-SYSTEM · Flactro Static Precinitator	REV. №: 00		PACKAGE:	EPC			
HAI			. Fiedio Static Fredibitator	DATE: 06/08/2024		CONTRACT NO.	CS-9587-001R-2-SC-NOA-7333, DATE-29.08.2023	OA-7333, DATE	E-29.08.	:023
	PS:ER, KOLKATA AREA : Mechanical Erection	AREA : Mechai	nical Erection	PAGE :7 of 13		MAIN CONTRACTOR	MAIN CONTRACTOR BHEL, PS:ER, KOLKATA	ТА		
SI. No	Activity and operation	Type of Check	Characteristics / instruments	Class of check	Quantum of check	Reference Document	Acceptance Norms	Format of Record		Remarks
1	2	3	4	5	9	7	8	6	<i>D</i> *	
9.15	Ensure welding of stair beam with vertical beam and vertical beam with middle & bottom frames.	^		၁	100%	Drawing & Erection Manual	ection Manual			
9.16	Ensure welding of vertical stay with emitting frames and diagonal stay with vertical beam.	۸		O	100%	Drawing & Ere	Drawing & Erection Manual			
9.17	Avoid falling of weld splatter on support insulator i.e. complete all the welding in support insulator area before placement of support insulator	^		O	100%	Drawing & Ere	Drawing & Erection Manual			
9.18	Ensure critical dimensions in insulator housing (HT connection clearance with support insulator heater/thermostat)	۸		В	100%	Drawing & Erection Manua	ection Manual	Log Book	j	(dimension is to be indicated)
10	COLLECTING SYSTEM:									
10.01	Straightness of collecting electrodes before erection.	۸	Fixture	В	100%	Drawing & Erection Manual	ection Manual			
10.02	Welding of "U" guides in collecting electrodes. Use low current only to avoid damage to CE. (Refer to BAP-Ranipet for WPS no.)	>		В	100%	Drawing & Ere	Drawing & Erection Manual			
10.03	Ensure correct orientation of collecting electrodes (orientation in 1st field is different from other fields).	>		٧	100%	Drawing, Technical Directive: 033 & Erection Manual	ective: 033 & Erection nual			
10.04	Ensure that each collecting electrode rests on both hooks.	۸		٧	100%	Drawing & Ere	Drawing & Erection Manual			
10.05	Distance between collecting electrodes to vertical beam (on front $\&$ rear).	M	Tape	∢	100%	Drawing & Erection Manual	ection Manual	L-11	>	
10.06	Gap at bottom of gas distributor screen assembly (Minimum 100 mm to be maintained).	M	Tape	В	100%	Drawing & Erection Manua	ection Manual	L-11	7	
10.07	Clearance between shock bar edge to ridge cap.	M	Tape	٧	100%	Drawing & Ere	Drawing & Erection Manual	L-11	>	
10.08	Clearance between shock bar edge to shock bar guide (40 mm).	M	Таре	∢	100%	Drawing, Technical Directive: 007 & Erection Manual	ective: 007 & Erection nual	L-11	>	
10.09	Shock pads of all shock bars are in one line.	Σ	Piano wire /Tape	В	100%	Drawing & Ere	Drawing & Erection Manual	L-11	>	
10.10	Clearance between collecting electrodes and hopper (vertical) deflection plate in the vertical plane.	M	Tape	В	100%	Drawing & Erection Manual	ection Manual	L-11	>	
10.11	Clearance between shock bar to hopper ridge plate (40 mm min).	M	Tape	٧	100%	Drawing & Ere	Drawing & Erection Manual	L-11	7	
10.12	Straightness of shock bars and guides.	Σ	Piano wire	В	100%	Drawing & Ere	Drawing & Erection Manual			
10.13	Lock bolting of electrodes to be done after ensuring straightness of the collecting electrodes.	^		၁	100%	Drawing & Erection Manual	ection Manual			
10.14	Ensuring removal of temp locking (if any) between shock bar & guide during alignment. Ensure free movement of shock bars. Refer TD No-46.	>		Ф	100%	Drawing, Technical Directive: 046 & Erection Manual	Directive: 046 & Erection Manual	Log Book		

				FIELD QUALITY PLAN	LAN					Samesh
	SUPPLIERS NAME AND ADDRESS	SYSTEM : Ste	SYSTEM : Steam Generator & Auxiliaries	QP NO.: PP-QBE-2401-UHN-QA-104	2401-UHN-QA-104	PROJECT:	NTPC -LARA stage-II 2x800 MW	2x800 MW		1
वी एप इ	भारत हेवी इलेक्ट्रिकल्स लिमिोड	SUB-SYSTEM:	SUB-SYSTEM : Electro Static Precipitator	REV. №: 00		PACKAGE:	EPC			
BH			<u>-</u>	DATE: 06/08/2024		CONTRACT NO.	CS-9587-001R-2-SC-NOA-7333, DATE-29.08.2023	10A-7333, DATE	=-29.08	.2023
	PS:ER, KOLKATA AREA : Mechanical Erection	AREA: Mechar	lical Erection	PAGE :8 of 13		MAIN CONTRACTOR	MAIN CONTRACTOR BHEL, PS:ER, KOLKATA	ιΤΑ		
SI. No	Activity and operation	Type of Check	Characteristics / instruments	Class of check	Quantum of check	Reference Document	Acceptance Norms	Format of Record		Remarks
1	2	3	4	5	9		8	6	,Q	克拉罗 国
11	EMITTING SYSTEM:									
11.01	Record sweep / camber for vertical beam, vertical stay and supporting beam.	M	Tape	O	100%	Drawing & Er	Drawing & Erection Manual	Log Book		
11.02	Distance between transverse roof beam bottom to emitting frame supporting beam top.	M	Таре	А	100%	Drawing & Er	Drawing & Erection Manual	L-11	٨	
11.03	Concentricity of suspension rod to screen tube.	M	Tape	В	100%	Drawing & Er	Drawing & Erection Manual	L-11	٨	
11.04	Distance between emitting suspension screen tube edge and deflection plate (shield).	M	Таре	В	100%	Drawing & Er	Drawing & Erection Manual	L-11	^	
11.05	Distance between emitting rapping shaft screen tube edge and deflection plate.	M	Таре	В	100%	Drawing & Er	Drawing & Erection Manual	L-11	^	
11.06	Pin wheel clearance.	Σ	Таре	В	100%	Drawing & Er	Drawing & Erection Manual	L-11	7	
11.07	Spring back of emitting electrode.	Σ	Таре	Ą	Random	Drawing & Er	Drawing & Erection Manual	L-11	>	
11.08	Stretching of emitting electrodes (by stretching tool only).	^		0	100%	Drawing & Er	Drawing & Erection Manual			
11.09	The emitting electrode shall be stretched only up to hook level to avoid overstretching.	^		O	100%	Drawing & En	Drawing & Erection Manual			
11.10	Earthing device shall be located on the frame near the inspection door.	^		В	100%	Drawing & Er	Drawing & Erection Manual			
11.11	Insulators – cleanliness, glossiness and no cracks.	>		В	100%	Drawing & Er	Drawing & Erection Manual			
11.12	Supporting flange below the support insulators shall be fully welded as per drawing.	^		А	100%	Drawing, Technical Directive: 005 & Erection Manual	Directive: 005 & Erection Manual			
11.13	Clearance between the emitting frame and collecting electrode.	Μ	Tape /Go-gauge	A	100%	Drawing & En	Drawing & Erection Manual	L-11	>	
12	COLLECTING RAPPING SYSTEM:									
12.01	Clearance between shaft axis to gable wall - front / rear	M	Таре	В	100%	Drawing & Ere	Erection Manual	L-11	>	
12.02	Distance between the roof beams and Centre line of 1st and last collecting electrodes in all the fields located in each row adjacent to ESP walls to be marked and plumbed on ESP wall.	M	Таре	В	100%	Drawing & Err	Drawing & Erection Manual			
12.03	Ensure lube oil as per the grade specified in drawing/datasheet.De-coupling and direction of rotation check	^		В	100%	Drawing & Er	Drawing & Erection Manual			
12.04	Distance between Centre line of rapping shaft to Centre of shock bar (310 mm).	Δ	Таре	В	100%	Drawing & En	Drawing & Erection Manual	L-11	>	



				EIEI D OI IAI ITY BI AN	NA		0	·		Samesh	
	SEGULA CINA MAIN SOEL IGGILS	CYCTEM . C+0	All I	OB NO : BB OBE	2464 HUNDA 464	TOT.	YII COOPE AGA I DOTIN	AIM OOO			
	SUPPLIERS NAME AND ADDRESS	SYSIEM :	Steam Generator & Auxiliaries	QP NO.: PP-QBE-	۵۲ NO. : ۲۲-۵BE-2401-0HN-QA-104	PROJECT:	N I P.CLARA Stage-II 2X800 MW	ZX800 MW			
al vu s	भारत हेवी इलीक्ट्रक्त्स लिमि े ड		SI IB-SYSTEM · Flectro Static Precipitator	REV. №: 00		PACKAGE:	EPC				
HHH			Fiedro Static Freeipitator	DATE: 06/08/2024		CONTRACT NO.	CS-9587-001R-2-SC-NOA-7333, DATE-29.08.2023	OA-7333, DATE	E-29.08.	2023	
	BITAINA I BELEVINICALS LIMITED PS:ER, KOLKATA AREA : Mechanical Erection	AREA: Mechar	nical Erection	PAGE :9 of 13		MAIN CONTRACTOR	MAIN CONTRACTOR BHEL, PS:ER, KOLKATA	ΤA		多製画	388
SI. No	Activity and operation	Type of Check	Characteristics / instruments	Class of check	Quantum of check	Reference Document	Acceptance Norms	Format of Record	ecord	Remark	
1	2	3	4	5	9	7	8	6	D*		,
12.05	Distance between support insulator center and roof beams. (Clarity required)	Σ	Tape	В	100%	Drawing & En	Drawing & Erection Manual	Log Book			
12.06	Ensure motor base plate center line is in same vertical plane with center line of rapping shaft.	۸	Water Level/Tape	В	%001	Drawing & En	Drawing & Erection Manual				
12.07	Ensure indicator correctness as per direction of rotation marked in drawing.	۸		В	%001	Drawing & En	Drawing & Erection Manual				
12.08	Shock pad face and shaft axis to be in the same vertical plane to be in the same line for effective rapping.	M	Plumb bob	В	%001	Drawing & En	Drawing & Erection Manual				
12.09	Lateral shift of hammers w.r.t. shock pad centers.	Μ	Tape	В	4001	Drawing & En	Drawing & Erection Manual	Log Book			
12.10	Ensure phase angle of hammers and direction of rotation before welding of sleeves.	^		В	100%	Drawing & En	Drawing & Erection Manual				
12.11	Locking of plain bearings and set rings.	^		2	4001	Drawing & En	Drawing & Erection Manual				
12.12	Alignment of plain bearing and proper seating of rapping shaft in the bearing.	>		U	100%	Drawing & En	Drawing & Erection Manual				
12.13	Ensure water level throughout the length of each shaft assembly (use shims if required).	M	Water level / Tape	၁	4001	Drawing & En	Drawing & Erection Manual	Log Book			
12.14	Set ring position and completion of welding.	^		В	100%	Drawing & En	Drawing & Erection Manual	L-11	>		
12.15	Ensure circumferential groove on coupling matches with the edge of clutch.	۸		В	4001	Drawing & En	Drawing & Erection Manual				
12.16	Radial and axial alignment of clutch and coupling.	>		A	400%	Drawing & En	Drawing & Erection Manual				
12.17	Sealing of the opening for CE rapping shaft in the casing.	>		В	100%	Drawing & En	Drawing & Erection Manual				
13	K. EMITTING RAPPING SYSTEM:										
13.01	Check for the straightness of the shaft.	M	Piano wire	В	%001	Drawing & En	Drawing & Erection Manual				
13.02	Ensure that shaft is free from undercuts and burrs.	^		С	400%	Drawing & En	Drawing & Erection Manual				
13.03	Distance between shaft Centre to vertical beam.	Μ	Tape	В	%001	Drawing & En	Drawing & Erection Manual	L-11	^		
13.04	Distance between Centre line of rapping shaft to hitting point on shock beam.	M	Tape	В	400%	Drawing & En	Drawing & Erection Manual	L-11	>		
13.05	Phase angle of hammers and direction of rotation.	>		В	100%	Drawing & En	Drawing & Erection Manual				
13.06	Alignment of bearing & proper seating of rapping shaft in the bearing.	>		В	100%	Drawing & En	Drawing & Erection Manual				



				FIELD QUALITY PLAN	LAN					Mamostr
	SUPPLIERS NAME AND ADDRESS	SYSTEM : Stea	SYSTEM : Steam Generator & Auxiliaries	QP NO.: PP-QBE-2401-UHN-QA-104	:401-UHN-QA-104	PROJECT:	NTPC -LARA stage-II 2x800 MW	2x800 MW		/
मा एवं इ	भारत हेवी इलेक्ट्रिक्ल्स लिमि ोड ्	SUB-SYSTEM .	SI IB-SYSTEM · Electro Static Precinitator	REV. №: 00		PACKAGE:	EPC			
HAI			Electic States Technique	DATE: 06/08/2024		CONTRACT NO.	CS-9587-001R-2-SC-NOA-7333, DATE-29.08.2023	OA-7333, DATE	=-29.08	2023
	PS:ER, KOLKATA AREA : Mechanical Erection	AREA: Mechan	ical Erection	PAGE :10 of 13		MAIN CONTRACTOR	MAIN CONTRACTOR BHEL, PS:ER, KOLKATA	TA		
SI. No	Activity and operation	Type of Check	Characteristics / instruments	Class of check	Quantum of check	Reference Document	Acceptance Norms	Format of Record		Remarks
1	2	3	4	5	9	7	8	6	»Q	
13.07	Ensure water level throughout the length of each shaft assembly (use shims if required).	^		S	100%	Drawing & Erection Manual	ection Manual			
13.08	Level of plain bearing to be ensured by water level.	Σ	Water level / Tape	В	100%	Drawing & Erection Manual	ection Manual	Log Book		
13.09	Set ring position and completion of welding.	>		В	100%	Drawing & Erection Manual	ection Manual	L-11	^	
14	GD Test related activity:									
14.01	Ensure the erection of guide vanes in the ducting system as per the flow model report for uniform distribution. Refer TD NO-031.	>		В	100%	Drawing, Erection Manual/ Flow Model Test Report	nual/ Flow Model Test oort			
14.02	Ensure GD screen orientation as per drawing	>		O	100%	Drawing	ving			
14.03	Deflection plates in the GD screens shall be placed as per flow model report (if applicable) and to be tack welded only after GD test.	>		O	100%	Flow Model Test Report/ GD Test Report	oor/ GD Test Report			
15	G D SCREEN RAPPING SYSTEM:									
15.01	Clearance between shaft axis to primary screen edge.	Σ	Таре	В	100%	Drawing & Erection Manual	ection Manual	Log Book		
15.02	Distance between Centre line of rapping shaft to hitting point at rapping bracket.	M	Tape	В	100%	Drawing & Erection Manual	ection Manual	L-11	٨	
15.03	Lateral shift of hammers w.r.t. hitting point at rapping bracket.	M	Таре	В	100%	Drawing & Erection Manual	ection Manual	Log Book		
15.04	Ensure motor base plate center line is in same vertical plane with center line of rapping shaft.	^	Water Level/Tape	В	100%	Drawing & Erection Manual	ection Manual	Log Book		
15.05	Ensure indicator correctness as per direction of rotation marked in drawing.	^		В	100%	Drawing & Erection Manual	ection Manual			
15.06	Phase angle of hammers and direction of rotation.	۸		В	100%	Drawing & Erection Manual	ection Manual			
15.07	Alignment of bearing and proper seating of rapping shaft in the bearing.	^		၁	100%	Drawing & Erection Manual	ection Manual			
15.08	Ensure circumferential groove on the coupling matches with the edge of clutch.	>		В	100%	Drawing & Erection Manua	ection Manual			
15.09	Radial and axial alignment of clutch and coupling.	^		В	100%	Drawing & Erection Manual	ection Manual	Log Book		
15.10	Set ring position and completion of welding.	>		A	100%	Drawing & Erection Manual	ection Manual			



							9307-001-104-C-091/00/CAT-IIII-Agge.		00/160		гауе. то
			믬	FIELD QUALITY F	PLAN					B!	amexit
	SUPPLIERS NAME AND ADDRESS	SYSTEM : Ste	SYSTEM: Steam Generator & Auxiliaries	QP NO.: PP-QBE	QP NO. : PP-QBE-2401-UHN-QA-104	PROJECT:	NTPC -LARA stage-II 2x800 MW	x800 MW		/	
Shall			SI ID SYSTEM : Electro Static Descipitator	REV. №: 00		PACKAGE:	EPC				
HH	पावर सेक्टर - पूर्वी क्षेत्र, कोलकाता अध्यत्रका महत्र/४ हा हत्त्रघाटता ६ । । । ।		. Electio Static Frecipitatoi	DATE: 06/08/2024	1	CONTRACT NO.	CS-9587-001R-2-SC-NOA-7333, DATE-29.08.2023	JA-7333, DAT E	E 29.08	2023	
1		AREA: Mechanical Erection	nical Erection	PAGE :11 of 13		MAIN CONTRACTOR	MAIN CONTRACTOR BHEL, PS:ER, KOLKATA	ΤA		1	
SI. No	Activity and operation	Type of Check	Characteristics / instruments	Class of check	Quantum of check	Reference Document	Acceptance Norms	Format of Record	ecord	Remark	
1	2	3	4	5	9	7	8	6	, Q		
16	INLET & OUTLET FUNNELS										
16.01	Check Elevation	Σ	Tape/Water level	В	100%	Drawing & Er	Drawing & Erection Manual	L-12	٨		
16.02	Check Length and opening dimensions.	Μ	Таре	Э	100%	Drawing & Er	Drawing & Erection Manual	L-12	٨		
16.03	Ensure erection of Tertiary screen.			О	100%	Drawing & Er	Drawing & Erection Manual				
16.04	Ensure no gap is left after trial assembly and erection.	>		O	100%	Drawing & Er	Drawing & Erection Manual				
16.05	Kerosene test to be performed for funnel pre-assembly joints	^		В	100%	Drawing & Er	Drawing & Erection Manual				
17	HOPPERS										
17.01	Ensure welding of hopper plate with ridges as per drawing.	>		В	100%	Drawing, Technical Directive: 018 & Erection Manual	l Directive: 018 & Erection Manual			Use E7018 wel electrode and 1 LPI is to be ens for these joints.	Use E7018 welding electrode and 100% LPI is to be ensured for these joints.
17.02	Elevation (bottom flange).	M	Tape/Water level	В	100%	Drawing & Eท	Drawing & Erection Manual	L-12	>		
17.03	Spacing w.r.t. reference axes.	Σ	Таре	В	100%	Drawing & Er	Drawing & Erection Manual	L-12	>		
17.04	Weld continuous fillet in the inner side (gas path) of the walls.	^		В	100%	Drawing & Er	Drawing & Erection Manual				
17.05	Ensure correct orientation of hopper manhole door location w.r.t. gas flow direction for each row of hoppers.	^		С	100%	Drawing & Er	Drawing & Erection Manual				
17.06	Ensure surface contact of hopper heater with hopper wall.	۸		В	100%	Drawing, Technical Directive: 022 & Erection Manual	ective: 022 & Erection nual	SR			
17.07	Ensure welding of poke hole tube as per drawing to avoid dust entry into the heating chamber.	^		A	100%	Drawing, Technical Directive: 012 & Erection Manual	ective: 012 & Erection nual	SR			
17.08	Ensure welding of fluidizing pad (customer scope) to avoid damage to heating elements during operation.	>		٨	100%	Drawing & Eท	Drawing & Erection Manual	SR			
17.09	Support for ash handling pipes shall be taken from hopper stiffeners only.	>		В	100%	Drawing & Erection Manual	ection Manual				
17.10	Ensure expansion joints are envisaged by ash handling vendor wherever supports are taken from hoppers.	>		В	100%	Drawing & Err	Drawing & Erection Manual				



			FIEI	FIELD QUALITY PLAN	-LAN					(Kamash
	SUPPLIERS NAME AND ADDRESS	SYSTEM : St	SYSTEM : Steam Generator & Auxiliaries	QP NO.: PP-QBE-2401-UHN-QA-104	.2401-UHN-QA-104	PROJECT:	NTPC -LARA stage-II 2x800 MW	2x800 MW		/
\$ 110 111		CIID_CVCTEM	CIB-CVCTEM · Electro Ctatic Descinitator	REV. №: 00		PACKAGE:	EPC			
1111	पावर सेक्टर - पूर्वी क्षेत्र, कोलकाता ह्यार्क्टर = ह्टान्स्टार हुन । MITTED	30B-3131EIM	: Electro Static Precipitator	DATE: 06/08/2024	1	CONTRACT NO.	CS-9587-001R-2-SC-NOA-7333, DATE-29.08.2023	IOA-7333, DATE	∃ 29 08	2023
	PS:ER, KOLKATA AREA : Mechanical Erection	AREA: Mecha	nical Erection	PAGE :12 of 13		MAIN CONTRACTOR	MAIN CONTRACTOR BHEL, PS:ER, KOLKATA	\TA		
SI. No	Activity and operation	Type of Check	Characteristics / instruments	Class of check	Quantum of check	Reference Document	Acceptance Norms	Format of Record	cord	Remarks
1	2	3	4	5	9	7	8	6	D*	
18	INSULATOR HOUSING									
18.01	Ensure firm connection without any looseness in the copper tubing on both ends of the bushing insulator.	Λ		А	4001	Drawing, Technical Di Ma	Drawing, Technical Directive: 037 & Erection Manual			
18.02	Thermostat for insulator housing heaters shall be fixed at first/second field.	۸		В	400%	Drawing & Er	Drawing & Erection Manual			
19	INSULATION & CLADDING									
19.01	Laying of insulation as per applicable erection drawings.	۸		В	100%	Drawing, Technical Erectior	Drawing, Technical Directive: 012, 045 & Erection Manual			
20	WELDING & NDT									
20.01	Availability of applicable WPS, Field Welding Schedule / Drawing (as applicable)	Я		A	100%	Drawings/ Welding Schedule & WPS	Drawings/ Welding Schedule & WPS	WPS		
20.02	Qualification of welders.	V/R		A	100%	WPS/ ASME Section IX	WPS/ ASME Section IX	WQR	٨	
20.03	Edge preparation and fit up of joints. Ensure proper root gap.	^		c	100%	Drawing	Drawing			
20.04	NDT for new edges prepared at site where t > 32 mm	>		U	100% MPI / LPI	ASTM E165	AWS D1.1	NDT Report	>	
20.05	Pre heating, Post heating and Post Weld Heat Treatment of weld joints, as applicable.	N / W	Time Temperature Recorder	А	As per WPS	WPS / Drawing	WPS / Drawing	HT Chart	>	
20.06	Adoption of correct procedure, use of approved Electrodes and methods.	V/R		A	100%	Drawing & WPS	Drawing & WPS			
20.07	Ensure proper sequence of welding.	^		В	Random in each shift	Drawing	Drawing			
20.08	Visual Inspection of field weldments	V / M	Weld gauge	В	100%	Drawing	AWS D1.1	SR	>	Surveillance by FQA
20.09	NDT on back gouged/ ground grooves prior to welding from second side.	V / P	LPI Kit	O	100% LPI	ASTM E165	AWS D1.1	NDT Report	7	Surveillance by FQA
20.10	NDT on field groove welds for $t \ge 32 \ mm.$	۸		٧	100% RT / UT	AWS D1.1	AWS D1.1	NDT Report	7	Wherever RT is not possible UT to be done
20.11	NDT on field groove welds for $t \ge 25 \ \text{mm} < 32 \ \text{mm}.$	^		A	10% RT/ UT and 100% MPI/ LPI	AWS D1.1	AWS D1.1	NDT Report	7	Wherever RT is not possible UT to be done
20.12	NDT on field groove welds for $t < 25 \ \text{mm}$.	V/P	MPI Kit / LPI Kit	A	10% MPI/ LPI	ASTM E709 / ASTM E165	AWS D1.1	NDT Report	^	



			HEI	IELD QUALITY PLAN	PLAN					Mamosh
	SUPPLIERS NAME AND ADDRESS	SYSTEM : Stea	SYSTEM: Steam Generator & Auxiliaries	QP NO : PP-QBE	QP NO. : PP-QBE-2401-UHN-QA-104	PROJECT:	NTPC -LARA stage-II 2x800 MW	2×800 MW		/
मी एप डे एम	भारत हेवी इलेक्ट्रिकृल्स लिमिोड		CI ID EVETEM : Electric Chatic Descriptions	REV. №: 00		PACKAGE:	EPC			
HH	पावर सेक्टर - पूर्वी क्षेत्र, कोलकाता BUABAT DEAVY EL ECTEICAL EL IMITED		Electro Static Precipitator	DATE: 06/08/2024	1	CONTRACT NO.	CS-9587-001R-2-SC-NOA-7333, DATE-29.08.2023	IOA-7333, DATE	29 08 2	123
	DHAKATI HEAVI ELECTINICALS LIMITED PS:ER, KOLKATA AREA: Mechanical Erection	AREA: Mechan	ical Erection	PAGE 13 of 13		MAIN CONTRACTOR	MAIN CONTRACTOR BHEL, PS:ER, KOLKATA	\TA		
SI. No	Activity and operation	Type of Check	Characteristics / instruments	Class of check	Quantum of check	Reference Document	Acceptance Norms	Format of Record		Remarks
1	2	3	4	5	9	7	8	6	D *	現を宣
20.13	NDT on field fillet welds	>		∢	-100% MPI/ LPI on all fillet welds of built up plate girders - MPI / LPI on other fillet weld: 5% of weld length	ASTM E709 / ASTM E165	AWS D1.1	NDT Report	7	
21	GENERAL									
21.01	Completion of air in leakage test before application of insulation. Soap water solution during air tightness test also to be done for casing walls, hoppers joints, funnels and inner roof.	>	Venturi meter	A	100%	Drawing, Technic∢ Approved	Drawing, Technical Directive: 036 & Approved Procedure			
21.02	Completion of welding of insulation hooks and insulation.	>		В	100%	Drawing & En	Drawing & Erection Manual			
21.03	Completion of galleries around ESP. Ensure approach and access for PG test of the ESP.	>		В	100%	Drawing, Technical Dir Mar	Drawing, Technical Directive: 025 & Erection Manual			
21.04	Ensure proper insulation of all support insulator housing chambers, inner roof and emitting rapping drive.	>		O	100%	Drawing & En	Drawing & Erection Manual			
	Dicitally signed by ARIJD RATAN PAUI	LEGENDS:	LEGENDS: * Decorde identified with fick (1) shall be accontable included by cumplier in OA decompanishing) di reiladus ya babular	not documentation	For Owner Use	NTPC Doc. No. : 9587-001-104-QVM-Q-091 / Rev 00	9587-001-104-0	QVM-Q	-091 / Rev 00
The Park	ALS ad5 5559 AL, PE8C	# Class A Critical Class Ya checks sh witnessed by Owne engineer. CLASS Y Certificate. Surveillance of Cla Engineer and for cl	Reconstructions with taken (y) shall be essentially included by support in CA documentation. Class A: Critical, Class B: Major, Class C: Minor. Class A' checks shall be witnessed by Owner FQA and Execution Engineer, Class 'B' checks shall be witnessed by Main contractor engineer, Class 'C' checks shall be witnessed by Main contractor engineer, CLASS 'A' &' B' CHECKS SHALL BE NTPC CHP STAGE. SR- Site Register, TR- Test Report, LB-Log Book, IR - Inspection Report, MTC - Manufacturer's Test Certificate. Surveillance of Class 'A' checks shall be perform By Owner Head (FQA), Class 'B' by Owner FQA Engineer and for class 'C' Another Executing Engineer authorised by Head (Executing Depti).	in y nadared by supplies in the documentation. No. A and Execution Engineer, Class B' checks shall be witnessed by Main contractor. ITPC CHP STAGE. K. IR - Inspection Report, MTC - Manufacturer's: By Owner Head (FOA), Class B' by Owner FQA integer and the deal (FEACHING) Dealers.	r, Class 'B' checks shall be ed by Main contractor MTC - Manufacturer's Test lass 'B' by Owner FQA lass 'B' by Owner FQA has contracted by the contractor of NTDC.	(국 김대태 NTPC A Mahararia Campany				
	Main Contractor	Dispositioning au system manual	<u>note:</u> Any non-comming deviation to the equality plan index be brought to house of NTPC BDispositioning authority shall be the authorised representative of NTPC as per NTPC FQA system manual	y plan must be broug representative of NTP	C as per NTPC FQA		REVIEWED BY	APPROVED BY		APPROVAL SEAL



म्।


RECORD OF QUALITY CHECKS


REMARKS		DOC. NO.: PP-QBE-2401-HD-QA-204	REV. NO.: 00	LOG SHEET NO.: L-00	SHEET 1 / 1 SHEETS
CLEARED BY SIGN. & DATE			AKEA F	ERECTION	U)
INSPECTED BY SIGN. & DATE	' column.				
FORMAT OF RECORD	"Format of Record" column.	0,00	SOB-SYSTEM	ESP	
DRAWING / DOCUMENT REFERENCE	Note : Any protocol made is to be numbered & mentioned in "F	L	O TO I EIVI	BOILER AUXILIARY	
RESULTS ACHIEVED OK / NOT OK	e is to be numbe			BC	
CHECK NO.	rotocol mad				
SHEET NO. OF QPI	Note: Any pr		PROJECT	UNIT NO.	RATING



			& SPACING OF FOUNDATION PEDESTALS	E C E C E C E C E C E C E C E C E C E C	+ + + +			+ + + + + + + + + + + + + + + + + + +	- - - - - - - - - -		$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	SIGNATURE & DATE QP.NO.: PP-QBE-2401-HD-QA-204	REV. NO.: 00	LOG SHEET NO.: L-01	PAGE 1 / 7
.0		T NO.	Location of ESP with Reference Axes & SPACING O	ED C	+++++++++++++++++++++++++++++++++++++++	_	Fixed Foot	+ + + +	+++++++++++++++++++++++++++++++++++++++		L4 L2 L1 L3 L3 L4 L4 L5 L4 L5 L7 L7 L8	L. OI BOIIEI AAIS (FO			
朝 改立 多 収刊 INSTRUMENT REGN.NO.	DATE OF INSPECTION	DRAWING / DOCUMENT NO.	<u>Location o</u>	EA C III	+	S3	S1			 	S5 ** L8		INSPECTED BY	CLEARED BY	CUSTOMER
nà le					u	ır columı	əliod 10 v	vor tabl s	srence axi	efeЯ			PROJECT	UNIT NO.	RATING

9587-001-104-QVM-Q-091/00/CAT-III/Page: 21 of 76







INSTRUMENT REGN.NO.		
DATE OF INSPECTION		
DRAWING / DOCUMENT REF.		

SPACING OF FOUNDATION PEDESTALS

Tolerance on spacing: ± 10 mm (including over all)

ESP No: 1/2 Pass:

For	Column Row	rs: 1	For	Column Row	/s: 2
Dimension	As per Drawing	Actual	Dimension	As per Drawing	Actual
L1			L1		
L2			L2		
L3			L3		
L4			L4		
L5			L5		
L6			L6		
L7			L7		
L8			L8		
L9			L9		
L10			L10		
For	Column Rov	v: 3		Column Rov	v: 4
Dimension	As per Drawing	Actual	Dimension	As per Drawing	Actual
L1			L1		
L2			L2		
L3			L3		
L4			L4		
L5			L5		
L6			L6		
L7			L7		
L8			L8		
L9			L9		
L10			L10		
For	Column Rov	v: 5		A	
Dimension	As per Drawing	Actual	Dimension	As per Drawing	Actual
L1			D4		
L2			B1		
L3					
L4					
L5					
L6					
L7					
L8					
L9					
L10					

Note:

- 1. Measurements from axis passing through fixed support as reference.
- 2. The axes passing through the fixed support are perpendicular to each other.

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD-QA-
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-01
RATING	CUSTOMER			PAGE 2 / 7





INSTRUMENT REGN.NO.	
DATE OF INSPECTION	
DRAWING / DOCUMENT REF.	

SPACING OF FOUNDATION PEDESTALS

Tolerance on spacing: ± 10 mm (including over all)


ESP No: 1/2 Pass:

1 2					1 033	
For C	Column Rows	s: EA	For C	Column Rows	s: EB	
Dimension	As per Drawing	Actual	Dimension	As per Drawing	Actual	
S1			S1			
S2			S2			
S3			S3			
S4			S4			
S5			S5			
For (Column Row	: EC	For (Column Row	: ED	
Dimension	As per Drawing	Actual	Dimension	As per Drawing	Actual	
S1			S1			
S2			S2			
S3			S3			
S4			S4			
S5			S5			
For (Column Row	: EE	For Column Row: EF			
Dimension	As per Drawing	Actual	Dimension	As per Drawing	Actual	
S1			S1			
S2			S2			
S3			S3			
S4			S4			
S5			S5			
For (Column Row	: EG	For (Column Row	: EH	
Dimension	As per Drawing	Actual	Dimension	As per Drawing	Actual	
S1			S1	_		
S2			S2			
S3			S3			
S4			S4			
S5			S5			

Note:

- 1. Measurements from axis passing through fixed support as reference.
- 2. The axes passing through the fixed support are perpendicular to each other.

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD-QA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-01
RATING	CUSTOMER			PAGE 3 / 7





INSTRUMENT REGN.NO.		
DATE OF INSPECTION		
DRAWING / DOCUMENT REF.		

SPACING OF FOUNDATION PEDESTALS AND DIAGONALS

Tolerance on spacing: ± 10 mm (including over all)

ESP No: 1/2 Pass:

For 0	Column Row	s: EJ	For Column Rows: EK			
Dimension	As per Drawing	Actual	Dimension	As per Drawing	Actual	
S1			S1			
S2			S2			
S3			S3			
S4			S4			
S5			S5			
For 0	Column Row	s: EL				
Dimension	As per Drawing	Actual	Dimension	As per Drawing	Actual	
S1						
S2						
S3						
S4						
S5						
DIAG	DIAGONAL MEASUREMENTS- TOL.: 1mm/M, Max:10mm					
Betweer	n Column Ro	ws: 1&2	Between Column Rows: 2&3			
Diagonal Between	Measure ment	Difference	Diagonal Between	Measure ment	Difference	
EA1&EB2			EA2&EB3			
EA2&EB1			EA3&EB2			
EB1&EC2			EB2&EC3			
EB2&EC1		1	EB3&EC2			
EC1&ED2			EC2&ED3			
EC2&ED1		1	EC3&ED2			
ED1&EE2			ED2&EE3			
ED2&EE1		1	ED3&EE2			
EE1&EF2			EE2&EF3			
EE2&EF1		1	EE3&EF2		1	
EF1&EG2			EF2&EG3			
EF2&EG1		1	EF3&EG2		1	
EG1&EH2			EG2&EH3			
EG2&EH1		1	EG3&EH2			
EH1&EJ2			EH2&EJ3			
EH2&EJ1		1	EH3&EJ2		1	
EJ1&EK2			EJ2&EK3			
EJ2&EK1		1	EJ3&EK2		1	
EK1&EL2			EK2&EL3			
EK2&EL1		1	EK3&EL2		1	

Note:

- 1. Measurements from axis passing through fixed support as reference.
- 2. The axes passing through the fixed support are perpendicular to each other. All dimensions are in mm.

		NAME	SIGNATUR E & DATE	QP.NO.: PP-QBE-2401-HD-QA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-01
RATING	CUSTOMER			PAGE 4 / 7



	बी एच ई एम
	o the s
K	

INSTRUMENT REGN.NO.		
DATE OF INSPECTION		
DRAWING / DOCUMENT REF.		


DIAGONAL MEASUREMENTS

Tolerance: 1mm/M;10mm Max

ESP No: 1/2 Pass:

DIAG	DIAGONAL MEASUREMENTS- TOL.: 1mm/M, Max:10mm						
Betweer	n Column Ro	ws: 3&4	Between Column Rows: 4&5				
Diagonal Between	Measure ment	Difference	Diagonal Between	Measure ment	Difference		
EA3&EB4			EA4&EB2				
EA4&EB3			EA5&EB1				
EB3&EC4			EB4&EC2				
EB4&EC3			EB5&EC4				
EC3&ED4			EC4&ED5				
EC4&ED3			EC5&ED4				
ED3&EE4			ED4&EE5				
ED4&EE3			ED5&EE4				
EE3&EF4			EE4&EF5				
EE4&EF3			EE5&EF4				
EF3&EG4			EF4&EG5				
EF4&EG3			EF5&EG4				
EG3&EH4			EG4&EH5				
EG4&EH3			EG5&EH4				
EH3&EJ4			EH4&EJ5				
EH4&EJ3			EH5&EJ4				
EJ3&EK4			EJ4&EK5				
EJ4&EK3			EJ5&EK4				
EK3&EL4			EK4&EL5				
EK4&EL3			EK5&EL4				

		NAME	SIGNATUR E & DATE	QP.NO.: PP-QBE-2401-HD-QA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-01
RATING	CUSTOMER			PAGE 5 / 7





INSTRUMENT REGN.NO.		
DATE OF INSPECTION		
DRAWING / DOCUMENT REF.		

ELEVATION OF FOUNDATION PEDESTALS


Elevation of foundation pedestal as per drawing: _____ mm

Tolerance on measurements: ± 10 mm.

ESP No : 1 / 2 Pass :

Location	EA1	EB1	EC1	ED1	EE1	EF1	EG1	EH1	EJ1	EK1	EL1
Actual											
Location	EA2	EB2	EC2	ED2	EE2	EF2	EG2	EH2	EJ2	EK2	EL2
Actual											
Location	EA3	EB3	EC3	ED3	EE3	EF3	EG3	EH3	EJ3	EK3	EL3
Actual											
Location	EA4	EB4	EC4	ED4	EE4	EF4	EG4	EH4	EJ4	EK4	EL4
Actual											
Location	EA5	EB5	EC5	ED5	EE5	EF5	EG5	EH5	EJ5	EK5	EL5
Actual											-

		NAME	SIGNATUR E & DATE	QP.NO.: PP-QBE-2401-HD-QA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-01
RATING	CUSTOMER			PAGE 6 / 7





INSTRUMENT REGN.NO.		
DATE OF INSPECTION		
DRAWING / DOCUMENT REF		

ELEVATION OF BOTTOM OF BASE PLATE


Elevation of bottom of base plate as per drawing : _____ mm

Tolerance on measurements : ± 10 mm.

ESP No: 1/2 Pass:

Location	EA1	EB1	EC1	ED1	EE1	EF1	EG1	EH1	EJ1	EK1	EL1
Actual											
Location	EA2	EB2	EC2	ED2	EE2	EF2	EG2	EH2	EJ2	EK2	EL2
Actual											
Location	EA3	EB3	EC3	ED3	EE3	EF3	EG3	EH3	EJ3	EK3	EL3
Actual											
Location	EA4	EB4	EC4	ED4	EE4	EF4	EG4	EH4	EJ4	EK4	EL4
Actual											
Location	EA5	EB5	EC5	ED5	EE5	EF5	EG5	EH5	EJ5	EK5	EL5
Actual											

		NAME	SIGNATUR E & DATE	QP.NO.: PP-QBE-2401-HD-QA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-01
RATING	CUSTOMER			PAGE 7 / 7





INSTRUMENT REGN.NO.		
DATE OF INSPECTION		
DRAWING / DOCUMENT REF		

COLUMN VERTICALITY MEASUREMENTS

Tolerance: 1 mm / M ; 10 mm Max.

ESP No: 1/2 Pass:

Column	l	Inclined	towards	3	Column	I	nclined	towards	3
No.	Left	Right	Front	Rear	No.	Left	Right	Front	Rear


All dimensions are in mm.

For each ESP, separate log sheet to be made.

		NAME	SIGNATU RE & DATE	QP.NO.: PP-QBE-2401-HD-QA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-02
RATING	CUSTOMER			PAGE 1 / 1



बी एय ई एन	INSTRUMENT REGN.NO.		
H)JG	DATE OF INSPECTION		
	DRAWING / DOCUMENT NO.		
	Dispositi	osition of Slide supports & Radial Measurements	
	(m c)		
\$	+++++++++++++++++++++++++++++++++++++++		
83		R 16 (Typ) R 20 (TYP)	
4	+	Eixed Foot	
\$\left(\frac{\pi}{2}\)	/ 	+ + + + + + + + + + + + + + + + + + + +	
SS			
2			ı
88	-	R31 (Typ)	
1			
	9	L4 L2 6 L1 L3 L5 L7 L9 L10 V	
		NAME SIGNATURE / DATE QP.NO.: PP-QBE-24	
PROJECT	INSPECTED BY	REV. NO.: 00	
UNIT NO.	CLEARED BY	LOG SHEET NO.: L-03	
RATING	CUSTOMER	PAGE 1 / 3	





INSTRUMENT REGN.NO.		
DATE OF INSPECTION		
DRAWING / DOCUMENT REF		

Disposition of Slide Supports

Tolerance on spacing: ± 5 mm Max.

ESP No: 1/2 Pass:

As per Drg.:

SPACING/ ROW	L1	L2	L3	L4	L5	L6	L7	L8	L9	L10
1										
2										
3										
4										
5										

AS PER	DRG.										
ROW / SPACING	EA	EB	EC	ED	EE	EF	EG	EH	EJ	EK	EL
S1											
S2											
S3											
S4											

NOTE:

- 1. Maintain the absolute level of top plate of support within \pm 5 mm.
- 2. The verticality of supporting column shall be within 10 mm Max.
- 3. Align the centre line of column w.r.t. bench mark.
- 4. Check the orientation of free guided slide supports.
- 5. Locate slide supports on centre line of column top plate.
- 6. Ensure the correct orientation of all bearings and log in the plan bottom and plan top dimensions of each bearing as per drawing.
- 7. All dimensions are in mm.
- 8. For each ESP, separate log sheet to be made.

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD- QA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-03
RATING	CUSTOMER			PAGE 2 / 3





INSTRUMENT REGN.NO.	
DATE OF INSPECTION	
DRAWING / DOCUMENT REF.	

LEVEL OF TOP PLATE OF SUPPORTS & RADIAL MEASUREMENTS

Tolerance on level: ± 5 mm Max.

ESP No : 1 / 2 Pass :

Locati on	EA1	EB1	EC1	ED1	EE1	EF1	EG1	EH1	EJ1	EK1	EL1
Actual											
Locati on	EA2	EB2	EC2	ED2	EE2	EF2	EG2	EH2	EJ2	EK2	EL2
Actual											
Locati on	EA3	EB3	EC3	ED3	EE3	EF3	EG3	EH3	EJ3	EK3	EL3
Actual											
Locati on	EA4	EB4	EC4	ED4	EE4	EF4	EG4	EH4	EJ4	EK4	EL4
Actual											
Locati on	EA5	EB5	EC5	ED5	EE5	EF5	EG5	EH5	EJ5	EK5	EL5
Actual											

Radial measurements (between fixed & individual supports)

Tolerance: ± 5 mm Max.

	R1	R2	R3	R4	R5	R6	R7	R8	R9	R10
Actual										
	R11	R12	R13	R14	R15	R16	R17	R18	R19	R20
Actual										
	R21	R22	R23	R24	R25	R26	R27	R28	R29	R30
Actual										
	R31	R32	R33	R34	R35	R36	R37	R38	R39	R40
Actual										

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD-QA- 204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-03
RATING	CUSTOMER			PAGE 3 / 3




£ (1)	12)
वी एव	TY ET
\Box	

INSTRUMENT REGN.NO.	DATE OF INSPECTION	DRAWING / DOCUMENT NO.
\$ (1)4		

SPECTION	DOCUMENT NO.	

Inlet / Outlet & Intermediate frames of 5 column arrangement



SI. No.	Check and log	Permissible Deviation	Dimension
_	The level of bottom flange of longitudinal roof beam.	3 mm	L1 to L5
2	Verticality of panels.	10 mm	V1 & V2
3	The opening along the gas flow.	± 10 mm	X1, X2 & X3
4	The centre line of gas path chamber.	±2 mm	B1 & B2
5	Diagonal Difference	15 mm	D1~D2


QP.NO.: PP-QBE-2401-HD-QA-204	REV. NO.: 00	LOG SHEET NO.: L-04	PAGE 1 / 5
SIGNATURE / DATE			
NAME			
	INSPECTED BY	CLEARED BY	CUSTOMER
	PROJECT	UNIT NO.	RATING



मी एए ई एम	INSTRUMENT R
BHI	DATE OF INSPE
	DRAWING / DOC

). -
INSTRUMENT REGN.NO.	DATE OF INSPECTION	DRAWING / DOCUMENT NO.

Inlet / Outlet & Intermediate frames of 3 column arrangement



SI. No.	Check and log	Permissible Deviation	Dimension	
	The level of bottom flange of longitudinal roof beam.	3 mm	L1 to L3	
2	Verticality of panels.	10 mm	V1 & V2	
3	The opening along the gas flow.	± 10 mm	X1, X2 & X3	
4	The centre line of gas path chamber.	±2 mm	B1 & B2	
5	Diagonal Difference	15 mm	D1~D2	


(i
	QP.NO.: PP-QBE-2401-HD-QA-204	REV. NO.: 00	LOG SHEET NO.: L-04	PAGE 2 / 5	
	SIGNATURE / DATE				
	NAME				
		INSPECTED BY	CLEARED BY	CUSTOMER	
		PROJECT	UNIT NO.	RATING	



मी एप ई एम	INST
	DATE
	DRAV

INSTRUMENT REGN.NO.	
DATE OF INSPECTION	
DRAWING / DOCUMENT NO.	

Inlet / Outlet & Intermediate frames of 2 column arrangement



SI. No.	Check and log	Permissible Deviation	Dimension
	The level of bottom flange of longitudinal roof beam.	3 mm	L1 & L2
2	Verticality of panels.	10 mm	V1 & V2
3	The opening along the gas flow.	± 10 mm	X1, X2 & X3
4	The centre line of gas path chamber.	±2 mm	B1 & B2
5	Diagonal Difference	15 mm	D1~D2

QP.NO.: PP-QBE-2401-HD-QA-204	REV. NO: 00	LOG SHEET NO.: L-04	PAGE 3 / 5	
SIGNATURE / DATE				
NAME				
	INSPECTED BY	CLEARED BY	CUSTOMER	
	PROJECT	UNIT NO.	RATING	



HI CO S CIL			SI.No.	2	က	4	1-	- q ;	\ E8	ω	o	10	-	_	2	က	4	- 9; @	ω	6	10	1			PROJECT	CIA
			No. L1	_								0								_	0					
INSTRUMENT REGN.NO.	DATE OF INSPECTION	DRAWING / DOCUMENT NO.	L2																						INSPECTED BY	CI EABED BY
EGN.NO.	CTION	COMENT NO.	L3																				_		\	
			L4																					Ż		
			L5																					NAME		
			V1																							
			V2																					SIC		
			B1																					SIGNATURE / DATE		
			B2																					TE		
			X1																					QP.NO.: P	REV. NO.: 00	OR SHEET NO
			X2																					QP.NO.: PP-QBE-2401-HD-QA-204	00	- I - ON T
			X3																					HD-QA-204		
			D1 ~ D2																							




			D1 ~ D2																										
			X3																							ID-QA-204			
			X2																							QP.NO.: PP-QBE-2401-HD-QA-204	00	NO: L-04	7 5
			X																							QP.NO.: PI	REV. NO.: 00	LOG SHEET NO.:	PAGE 5 /
			B2																							巴			
			B1																							SIGNATURE / DATE			
			V2																							SIG			
			۸1																										
			L5																							NAME			
			L4																										
EGN.NO.	STION	UMENT NO.	F3																										
INSTRUMENT REGN.NO.	DATE OF INSPECTION	DRAWING / DOCUMENT NO.	77																								INSPECTED BY	CLEARED BY	CUSTOMER
			[7]																										
बी एए ई एल			SI.No.	-	2	က	4	5	9	7	∞	6	10	7	-	2	က	4	5	9	7	8	6	9	11				
B	_	J 				•		III	- d	EZ									ΛΙ	- d	S∃		•				PROJECT	ON LINO	RATING



	Danes	h
INSTRUMENT REGN.NO.		
DATE OF INSPECTION		
DRAWING / DOCUMENT REF.		

Location of Transverse Roof Beams



OUTLET MID COLUMN

NOTE:

GAS FLOW

- 1. Take measurements of transverse roof beams location at three places as shown within **5 mm Max.**
- 2. Ensure the level of the bottom flange of the transverse roof beam within 5 mm Max.
- 3. All dimensions are in mm.
- 4. Separate log sheet to be made for each pass of ESP.

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD- QA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-05
RATING	CUSTOMER			PAGE 1 / 3



INSTRUMENT REGN.NO.		
DATE OF INSPECTION		
DRAWING / DOCLIMENT REE		

SPACING OF TRANSVERSE ROOF BEAMS

ESP No.: Pass :

Location	As per Drawing		Measuremen	ts
Location	7.5 per Brawing	1	2	3
D1				
D2				
D3				
D4				
D5				
D6				
D7				
D8				
D9				
D10				
D11				
D12				
D13				
D14				
D15				
D16				
D17				
D18				
D19				
D20				
D21				
D22				
D23				
D24				
D25				
D26				
D27				
D28				
D29				
D30				
D31				
D32				

All dimensions are in mm.

Separate log sheet to be made for each ESP.

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD-QA- 204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-05
RATING	CUSTOMER			PAGE 2 / 3



बी एच ई एन
pha

INSTRUMENT REGN.NO.		
DATE OF INSPECTION		
DRAWING / DOCUMENT REE		


LEVEL OF TRANSVERSE ROOF BEAMS

ESP No.: 1/2 Pass:

Roof		Location Roof Location					
Beam No.	1	2	3	Beam No.	1	2	3
1				17			
2				18			
3				19			
4				20			
5							
6							
7							
8							
9							
10							
11							
12							
13							
14							
15							
16							

For each ESP separate log sheet to be made.

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD- QA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-05
RATING	CUSTOMER			PAGE 3 / 3







INSTRUMENT REGN.NO.		
DATE OF INSPECTION	ļ.	ľ
DRAWING / DOCUMENT REF.		

INSULATOR SUPPORT PANEL MEASUREMENTS

ESP No.: 1/2 Pass:





Permissible variation:

- 1. The positioning of the opening for support insulators w.r.t. GPCL = \pm 2 mm. (S1, S2, R1 & R2)
- 2. The diagonal deviation of the opening for the support of emitting system = **5 mm Max.** (D1& D2)
- 3. Distance between the end hook to centre line of suspension tube = \pm 5 mm. (E)
- 4. Spacing = ± 2 mm. (L1 & L2)

NOTE:

- 1. Refer Roof panel drawing.
- 2. S1, S2, R1 & R2 indicates front & rear readings of a field.
- 3. All dimensions are in mm.
- 4. Separate log sheet to be made for each pass of ESP.

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD - QA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-06
RATING	CUSTOMER			PAGE 1 / 2



बी एच ई एम
other

INSTRUMENT REGN.NO.	
DATE OF INSPECTION	
DRAWING / DOCUMENT REE	

INSULATOR SUPPORT PANEL MEASUREMENT

ESP No.: 1/2 Pass:

							DED			
Location		1	1	ESP	'FIEL	DNUM	BEK	T	1	1
2004.011	1	2	3	4	5	6	7	8	9	10
S1										
S2										
R1										
R2										
L1										
L2										
E										
E										
E										
E										
D1 ~ D2										

All dimensions are in mm.

Separate log sheet to be made for each ESP.

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD-
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLCEARED BY			LOG SHEET NO.: L-06
RAT I NG	CUSTOMER			PAGE 2 / 2




बी एच ई एम
phia

INSTRUMENT REGN.NO.	
DATE OF INSPECTION	
DRAWING / DOCUMENT REF	

SUSPENSION FRAME OF COLLECTING ELECTRODES

ESP No.: 1 / 2 Pass:



NOTE:

- 1. Diagonal difference between corner hooks = **7 mm Max.**
- 2. Tolerance on cumulative pitch between angles = \pm 3 mm Max.
- 3. Log the measurements in sheet 2 / 2.

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD-QA- 204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-07
RATING	CUSTOMER			PAGE 1 / 2



बी एच ई एम
militar.

INSTRUMENT REGN.NO.		
DATE OF INSPECTION		
DRAWING / DOCUMENT REE		

SUSPENSION FRAME OF COLLECTING ELECTRODES - MEASUREMENTS

ESP No.: 1 / 2 Pass :

DU NO.	FRAME NO.	P1	P2	P3	P4	P5	P6	P7	D1	D2	LOCATION
											FRONT
											MIDDLE
											REAR
											FRONT
											MIDDLE
											REAR
											FRONT
											MIDDLE
											REAR
											FRONT
											MIDDLE
											REAR
											FRONT
											MIDDLE
											REAR
											FRONT
											MIDDLE
											REAR
											FRONT
											MIDDLE
											REAR


		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD- QA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-07
RATING	CUSTOMER			PAGE 2 / 2





INSTRUMENT REGN.NO.	
DATE OF INSPECTION	
DRAWING / DOCUMENT REF	

COLLECTING ELECTRODE SUSPENSION ARRANGEMENT



DIMENSION	1 st FIELD	OTHER FIELDS
Α	74	126
В	126	74

NOTE:

Take all measurements from GPCL.

The cumulative measurements between GPCL and collecting electrode suspension frame shall be within ± 3 mm.

Maintain the end hook of support angle in one line and perpendicular to GPCL within ± 3 mm.

Refer suspension frame of collecting electrode detail drawing.

All dimensions are in mm.

Separate log sheet to be made for each pass of ESP.

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD - QA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-08
RATING	CUSTOMER			PAGE 1 / 2



बी एच ई एम)
mbber.	

INSTRUMENT REGN.NO.		
DATE OF INSPECTION		
DRAWING / DOCUMENT REF.		

COLLECTING ELECTRODE SUSPENSION ARRANGEMENT

ESP No.: 1/2 Pass:

								ESP FIELD NUMBERS												
Dimen- sion	,	1	2	2	(3	4	1	5	5	6	3	-	7	8	3		9	1	0
	F	R	F	R	F	R	F	R	F	R	F	R	F	R	F	R	F	R	F	R
L1																				
R1																				
L2																				
R2																				
L3																				
R3																				
L4																				
R4																				
L5																				
R5																				
L6																				
R6																				
L7																				
R7																				
Α																				
В																				


All dimensions are in mm.

Separate log sheet to be made for each ESP.

F - refers to Front side of ESP

R - Refers to Rear side of the suspension arrangement of the respective field.

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD - QA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-08
RATING	CUSTOMER			PAGE 2 / 2




बी एच ई एम
mobber.
BIJEL

INSTRUMENT REGN.NO.	
DATE OF INSPECTION	
DRAWING / DOCUMENT REF.	


SUSPENSION FRAMES OF EMITTING SYSTEM



ENTITING FRAME - BOTTOM




EMITTING FRAME - MIDDLE



NOTE:

- 1. Diagonal difference between corner hooks = 7 mm Max.
- 2. Tolerance on cumulative pitch between angles = ± 3 mm Max.
- 3. Log the measurements in sheet 2 / 2.

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD- QA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-09
RATING	CUSTOMER			PAGE 1 / 2



बी एच ई एम
militar.

INSTRUMENT REGN.NO.		
DATE OF INSPECTION		
DRAWING / DOCUMENT REE		

SUSPENSION FRAME OF EMITTING ELECTRODES - MEASUREMENTS

ESP No.: 1 / 2 Pass:


DU NO.	FRAME NO.	P1	P2	Р3	P4	P5	P6	P7	D1	D2	LOCATION
											FRONT
											MIDDLE
											REAR
											FRONT
											MIDDLE
											REAR
											FRONT
											MIDDLE
											REAR
											FRONT
											MIDDLE
											REAR
											FRONT
											MIDDLE
											REAR
											FRONT
											MIDDLE
											REAR
											FRONT
											MIDDLE
											REAR

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD-QA- 204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-09
RATING	CUSTOMER			PAGE 2 / 2





INSTRUMENT REGN.NO.	
DATE OF INSPECTION	
DRAWING / DOCUMENT REF.	



Permissible variation:

The distance between bottom of roof beam and top of supporting beam (J,K,L,M) ... \pm 5 mm.

The verticality of frame work in both the axes by plumbing on four outer most corner holders. (A1, A2, B1, B2, C1, C2, D1, D2) **5 mm Max.**


The diagonals of the emitting system after assembly on extreme corner. (E, F,G,H) 10 mm Max.

LEGEND: A1, A2 ...D2 refers plumb line.

NOTE:

Separate log sheet to be made for each pass of ESP.

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD - QA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-10
RATING	CUSTOMER			PAGE 1 / 4



बी एच ई एम
militar.

INSTRUMENT REGN.NO.	
DATE OF INSPECTION	
DRAWING / DOCUMENT REF.	

ESP No.: 1/2 Pass:

Dimonoion				ESF	FIELD	NUMBI	ERS			
Dimension	1	2	3	4	5	6	7	8	9	10
A1										
A2										
B1										
B2										
C1										
C2										
D1										
D2										
E ~ F (LS)										
E~F(RS)										
G ~ H (FS)										
G~H(RRS)										
J										
K										
L										
M										

All dimensions are in mm.

Separate log sheet to be made for each pass of ESP.


LEGEND : RS : Right side LS : Left side FS : Front side RRS : Rear side.

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD-QA- 204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-10
RATING	CUSTOMER			PAGE 2 / 4




बी एच ई एल

INSTRUMENT REGN.NO.	
DATE OF INSPECTION	
DRAWING / DOCUMENT REF.	



		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD-QA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-10
RATING	CUSTOMER			PAGE 3 / 4






INSTRUMENT REGN.NO.		
DATE OF INSPECTION		
DRAWING / DOCUMENT REE		

Measure-					FIELD N	UMBERS	3	_		
ment	1	2	3	4	5	6	7	8	9	10
AB										
A1B1										
A2B2										
EF										
CD										
C1D1										
C2D2										
GH										
AC										
A1C1										
A2C2										
EG										
BD										
B1D1										
B2D2										
FH										
AD1										
DA1										
BC1										
CB1										
A1D2										
D1A2										
B1C2										
C1B2										
HA2										
ED2										
FC2										
GB2										
AD										
A1D1										
A2D2										
EH										
ВС										
B1C1										
B2C2										
FG										

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD-QA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-10
RATING	CUSTOMER			PAGE 4 / 4






QP.NO.: PP-QBE-2401-HD-QA-204	REV. NO.: 00	LOG SHEET NO.: L-11	PAGE 1 / 20
SIGNATURE / DATE			
NAME			
	INSPECTED BY	CLEARED BY	CUSTOMER
	PROJECT	UNIT NO.	RATING





INSTRUMENT REGN.NO.	
DATE OF INSPECTION	
DRAWING / DOCUMENT NO.	




QP.NO.: PP-QBE-2401-HD-QA-204	REV. NO.: 00	LOG SHEET NO.: L-11	PAGE 2 / 20
SIGNATURE / DATE			
NAME			
	INSPECTED BY	CLEARED BY	CUSTOMER
	PROJECT	UNIT NO.	RATING



PU 5 UM	11/11
ई के कि	Ha

INSTRUMENT REGN.NO.	
DATE OF INSPECTION	
DRAWING / DOCUMENT NO.	





		NAME	SIGNATURE / DATE	QP.NO.: PP-QBE-2401-HD-QA-204
PROJECT	INSPECTED BY			REV. NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-11
RATING	CUSTOMER			PAGE 3 / 20



f (17)	171	
7003	He	
8	7	


INSTRUMENT REGN.NO.	
DATE OF INSPECTION	
DRAWING / DOCUMENT NO.	

Σ	298 ± 5					
ㅗ	225 ± 5					
ſ	310 ± 5					
エ	310 ± 5					
G2	125 ± 5					
G1	125 ± 5					
S4	155±5					
S3	155±5					
S2	155±5					
S1	155±5					
RR	217.5±7					
RF	217.5±7					
ပ	310 ± 5					
В	350 Min.					
∢	100 + 10 - 00 350 Min.					
Field	No.					

		NAME	SIGNATURE / DATE	QP.NO.: PP-QBE-2401-HD-QA-204
PROJECT	INSPECTED BY			REV. NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-11
RATING	CUSTOMER			PAGE 4 / 20



B 00 \$ 0m	INSTRIMENT REGN NO
	DATE OF INSPECTION
	DRAWING / DOCUMENT NO.



		NAME	SIGNATURE / DATE	QP.NO.: PP-QBE-2401-HD-QA-204
PROJECT	INSPECTED BY			REV. NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-11
RATING	CUSTOMER			PAGE 5 / 20




				REMOVE THIS ANGLE AFTER ERECTION REFER-7x-x25 DRG. SHOCK BAR GUIDE	FIG 6	QP.NO.: PP-QBE-2401-HD-QA-204	REV. NO.: 00	LOG SHEET NO.: L-11	PAGE 6 / 20
			ERNALS	FASTNER	EK	SIGNATURE / DATE			
		JO.	DISPOSITION OF ESP INTERNALS	SHOCK BAR SHOCK BAR GUIDE AND FEEP HOPPER	FIG - 5	NAME			
INSTRUMENT REGN.NO.	DATE OF INSPECTION	DRAWING / DOCUMENT NO.		MAINTAIN (NIM) 9A2 mmO4	FIG - 4		INSPECTED BY	CLEARED BY	CUSTOMER
बी एच ई एम	n)la			SHOCK BAR RIDGE CAP			PROJECT	UNIT NO.	RATING



11/1

INSTRUMENT REGN.NO.	DATE OF INSPECTION	DRAWING / DOCUMENT NO.




PROJECT INSPECTED BY NAME SIGNATURE / DATE AP-QBE-2401-HD-QA-204 PROJECT INSPECTED BY REV. NO.: 00 LOG SHEET NO.: L-11 UNIT NO. CUSTOMER PAGE 7 / 20					
INSPECTED BY INSPECTED BY CLEARED BY CUSTOMER			NAME	SIGNATURE / DATE	QP.NO.: PP-QBE-2401-HD-QA-204
CLEARED BY CLEARED BY CUSTOMER CUSTOMER	PROJECT	INSPECTED BY			REV. NO.: 00
CUSTOMER	UNIT NO.	CLEARED BY			LOG SHEET NO.: L-11
	RATING	CUSTOMER			PAGE 7 / 20



		ä
	F	
ीएए ई एम		
100		


INSTRUMENT REGN.NO.	DATE OF INSPECTION	DRAWING / DOCUMENT NO.



QP.NO.: PP-QBE-2401-HD-QA- 204	REV. NO: 00	LOG SHEET NO.: L-11	PAGE 8 / 20
SIGNATURE / DATE			
NAME			
	INSPECTED BY	CLEARED BY	CUSTOMER
	PROJECT	UNIT NO.	RATING




INSTRUMENT REGN.NO.	DATE OF INSPECTION	ON ENDANISOR ON SINDANA
बी एए ई एम		



		NAME	SIGNATURE / DATE	QP.NO.: PP-QBE-2401-HD- QA-204
PROJECT	INSPECTED BY			REV. NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-11
RATING	CUSTOMER			PAGE 9 / 20




INSTRUMENT REGN.NO.	DATE OF INSPECTION	DRAWING / DOCUMENT NO.
की एप इंस्त	BHE	



	QP.NO.: PP-QBE-2401-HD- QA-204	REV. NO.: 00	LOG SHEET NO.: L-11	PAGE 10 / 20
WELLDING	SIGNATURE / DATE			
*CLD1140	NAME			
		INSPECTED BY	CLEARED BY	CUSTOMER
		PROJECT	UNIT NO.	RATING




INSTRUMENT REGN.NO.	DATE OF INSPECTION	DRAWING / DOCUMENT NO.




QP.NO.: PP-QBE-2401-HD- QA-204	REV. NO.: 00	LOG SHEET NO.: L-11	PAGE 11 / 20
SIGNATURE / DATE			
NAME			
	INSPECTED BY	CLEARED BY	CUSTOMER
	PROJECT	UNIT NO.	RATING



INSTRUMENT REGN.NO.	DATE OF INSPECTION	DRAWING / DOCUMENT NO.
क्षी है प्रमुख		






Copper Tubes are to be fixed with insulators ensuring firm connection without any looseness

		NAME	SIGNATURE / DATE	QP.NO.: PP-QBE-2401-HD-
				QA-204
PROJECT	INSPECTED BY			REV. NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-11
RATING	CUSTOMER			PAGE 12 / 20




INSTRUMENT REGN.NO.	DATE OF INSPECTION	DRAWING / DOCUMENT NO.
की एवं हैं एम		



QP.NO.: PP-QBE-2401-HD- QA-204	REV. NO.: 00	LOG SHEET NO.: L-11	PAGE 13 / 20
SIGNATURE / DATE			
NAME			
	INSPECTED BY	CLEARED BY	CUSTOMER
	PROJECT	UNIT NO.	RATING




INSTRUMENT REGN.NO.	DATE OF INSPECTION	DRAWING / DOCUMENT NO.
	INSTRUMENT REGN.NO.	INSTRUMENT REGN.NO. DATE OF INSPECTION



		NAME	SIGNATURE / DATE	QP.NO.: PP-QBE-2401-HD- QA-204
PROJECT	INSPECTED BY			REV. NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-11
RATING	CUSTOMER			PAGE 14 / 20




F (1)4	INSTRUMENT REGN.NO.	
E	DATE OF INSPECTION	
	DRAWING / DOCUMENT NO.	





INSTRUMENT REGN.NO.	DATE OF INSPECTION	DRAWING / DOCUMENT NO.



QP.NO.: PP-QBE-2401-HD- QA-204	REV. NO.: 00	LOG SHEET NO.: L-11	PAGE 16 / 20
SIGNATURE / DATE			
NAME			
	INSPECTED BY	CLEARED BY	CUSTOMER
	PROJECT	UNIT NO.	RATING




		DATE:
INSTRUMENT REGN.NO.		
INCOMENT RECUIRE		
DATE OF INSPECTION		
	·	
DRAWING / DOCUMENT REE		

LOCATION	ESP FIELD NUMBERS									
LOCATION	1	2	3	4	5	6	7	8	9	10
AA = 200± 5										
AB = 78 Min.										
AC = 200± 5										
AD = 40 Min.										
AE = 40 Min.										
AF = 333± 5										
AG = 7 Min.										
AH = 2 Min.										
AI = 3 Min.										

NOTE:

All dimensions are in mm.

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD-QA- 204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-11
RATING	CUSTOMER			PAGE 17 / 20





INSTRUMENT REGN.NO.		
DATE OF INSPECTION		
DRAWING / DOCUMENT REF.		

WELDING COMPLETION

ESP No.: 1/2 Pass:

Description				ESP F	FIELD	NUM	BERS			
Description	1	2	3	4	5	6	7	8	9	10
Welding of X81 diagonal & horizontal bracing.										
Welding of X48 diagonal & horizontal bracing.										
Welding of top & bottom plates of support bearing.										
Welding of hopper ridge.										
Welding of hopper wall.										
TR beam to LR beam welding.										
LR Beam to LR Beam welding, and splice plate welding.										
Tack welding of all fasteners of inner arms are completed.										
Tack welding of all fasteners of collecting electrodes / shock bar fixing are completed.										
Tack welding of plain bearing fasteners are done in both rapping mechanism.										
Diagonal stays are properly positioned and tack welded.										
All fasteners in emitting frames are tack welded.										
Set rings are positioned & tack welded with a gap of 2 mm in all rapping shafts.										
Shock bar angle of Fig.06 has been removed.										

NOTE:

All the above welding are critical.


For activity completion indicate by tick ($\sqrt{\ }$) mark in the appropriate boxes against each field numbers.

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD-QA- 204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-11
RATING	CUSTOMER			PAGE 18 / 20



INSTRUMENT REGN.NO.	Starre
DATE OF INSPECTION	
DRAWING / DOCUMENT REF.	

MOUNTING ARRANGEMENT OF DEFLECTION PLATE



ESP NO.: 1/2 Pass:

Cornor		ESP FIELD NUMBERS								
Corner	1	2	3	4	5	6	7	8	9	10
A										
В										
С										
D										

NOTE:


Check the four corners of each field and log the measurements A, B, C & D. Separate log sheet to be made for each pass of ESP.

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD - QA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-11
RATING	CUSTOMER			PAGE 19 / 20



INSTRUMENT REGN.NO.	8
DATE OF INSPECTION	
DRAWING / DOCUMENT REF.	

SPRING BACK CHECK ON EMITTING ELECTRODES



Select the emitting electrodes at random for the spring back check.

Enter field number, row number and number of emitting electrode etc. along with spring back values.

Choose minimum 5 numbers / field / tier of emitting electrodes for checking.

Minimum spring back value is 350 mm.

Erection by stretching device & avoid over stretching of electrodes.

ESP No.: 1/2

SI. No.	Field No.	Row No. of EE frame from nearest side wall	No. of EE in the concerned row	Level Top / Bottom	Spring back value (mm)

NOTE: EE – Indicates Emitting Electrode


		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD- QA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-11
RATING	CUSTOMER			PAGE 20 / 20



INSTRUMENT REGN.NO.	
DATE OF INSPECTION	
DRAWING / DOCUMENT REF.	



INTERFACE MEASUREMENTS ON FUNNELS



ESP No.: Pass:

Measurement of Funnels : Funnel Elevation Tolerance : ± 5 mm.

Location	As per drawing	Actual
Inlet funnel elevation		
Outlet funnel elevation		

Funnel disposition tolerance : ± 5 mm.

As per drawing						
Location	Х	Р	R	S	Q	Y
Pass – A						
Pass - B						
Pass - C						
Pass – D						
Pass – E						
Pass – F						

All dimensions are in mm.

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD - OA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-12
RATING	CUSTOMER			PAGE 1 / 3






INSTRUMENT REGN.NO.		
DATE OF INSPECTION		
DRAWING / DOCUMENT REF		

INTERFACE MEASUREMENTS ON HOPPER

ESP No.: 1 / 2 Elevation as per drawing : _____ mm Tolerance : ± 2 mm.



HOPPER		ESP FIELD NUMBERS								
NUMBER	1	2	3	4	5	6	7	8	9	10
1										
2										
3										
4										

NOTE:

All dimensions are in mm.

		NAME	SIGNATURE & DATE	QP.NO.: PP-QBE-2401-HD- QA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-12
RATING	CUSTOMER			PAGE 2 / 3



INSTRUMENT REGN.NO.	acu
DATE OF INSPECTION	
DRAWING DOCUMENT	

INTER FACE MEASUREMENTS ON HOPPER

ESP No.: 1 / 2 Hopper spacing - Tolerance: **10 mm Max.**

Dimension	1	2	3	4	5	6	7	8	9	10
Actual										
Dimension	11	12	13	14	15	16	17	18	19	20
Actual										
Dimension	21	22	23	24	25	26	27	28	29	30
Actual										
Dimension	31	32	33	34	35	36	37	38	39	40
Actual										
Dimension	41	42	43	44	45	46	47	48	49	50
Actual										
Dimension	51	52	53	54	55	56	57	58	59	60
Actual										
Dimension	61	62	63	64	65	66	67	68	69	70
Actual										
Dimension	71	72	73	74	75	76	77	78	79	80
Actual										

		NAME	SIGNATURE & DATE	FQP.NO.: PP-QBE-2401-HD- QA-204
PROJECT	INSPECTED BY			REV.NO.: 00
UNIT NO.	CLEARED BY			LOG SHEET NO.: L-12
RATING	CUSTOMER			PAGE 3 / 3





Minimum General Storage and Preservation Requirement

- 01. Emitting electrode boxes shall be kept in a closed storage and shall be opened only when erection is taken up.
- 02. Collecting electrodes are to be kept in a semi closed storage to protect against rust and damage. Not more than 3 packages are to be stacked one over the other.

Both collecting and emitting electrodes are critical components of ESP. Any damage will affect the performance of ESP.

- 03. Keep the insulators over soft material to avoid any damage. Do not stack any other material over the insulator.
- 04. Electrical components are to be kept in a closed storage to avoid rusting due to moisture and to protect against pilferage.
- 05. Protect the machined components like support bearings against rusting and damage during storage.

For detailed storage instructions for ESP components refer Erection Manual Chapter 4.0.

PROJECT	FQP.NO.: PP-QBE-2401-HD-QA-204
UNIT NO.	REV.NO.: 00
RATING	PAGE 1 / 1



	Charoh
INSTRUMENT REG. NO./TAG	Example 1
DATE OF INSPECTION	
DRAWING / DOCUMENT REF.	

PROTOCOL

'						
			NAME	SIGNATURE & DATE	FQP NO.: PP-QBE-2401-HD-QA-204	
PROJECT		INSPECTED BY			REV.NO.: 00	
UNIT NO.		CLEARED BY			PROTOCOL NO.	
RATING		CUSTOMER			PAGE:	

