

**CORRIGENDUM -1 TO TENDER SPECIFICATION BHEL PSSR SCT 1502**

Sub:Erection, Testing and Commissioning including Supply and Application of Final Painting of Cooling Water Piping, Boiler , Rotating Machines, ESP, and Application of Refractory & Insulation in Unit-3 of 1 x 700 MW set at Bellary Thermal Power Station, Kudatini, Bellary Dist, Karnataka

**One of the bidder asought clarifications on the subject tender and the clarifications are furnished below for information**

<b>SLNO</b>	<b>REF IN TENDER</b>	<b>QUERY</b>	<b>BHEL REPLY</b>
1	TCC, Volume 1A Part-II - Chapter-4 - Preservation, Clause No. 2.4.66.0 :	Since Bidder's scope start from drawing the material from your Site Stores, material preservation activity will not become part of this tender. Please clarify.	Clause No. 2.4.66.0 is deleted
2	TCC, Annexure-ID, Clause No. 2.0	Since the fittings like Tees, Reducers, Elbow Mitre Bends and other pipe fittings, etc. will not be paid separately and the Tonnage of Fittings, i.e. 153 MT is included in total tonnage of CW Piping, i.e. 2600 MT, please clarify the same.	Refer Annexure -1D, the detail in weight schedule -III-CW piping (PGMA 80-468). The 153 MT is included in total tonnage of CW Piping, i.e. 2600 MT
3	TCC, Annexure-ID, Clause No. 12.0	As it is mentioned that the PU coating DFT required is " <u>2 DFT</u> ", please inform us the Unit of "2".	Refer SLNO 1(a) in Annexure - III,Painting Schedule for LP piping,QP:7149.The total DFT of PU coating required is 2000microns
4	TCC, Annexure-ID, Clause No. 13.0	Since all internal surfaces of CW Pipe will have PU Coating and external surfaces will have Concrete Encasing for Underground Piping and Synthetic Enamel Paining for Aboveground Piping, so we assume that there will be no requirement of wrapping coating for this activity. Please confirm.	yes

SLNO	REF IN TENDER	QUERY	BHEL REPLY
5	TCC, Annexure-ID, Clause No. 14.3	Since Bidder has to ensure the sufficient width of the trench for pipe laying and site welding and Civil Work is excluded from the scope, hence we assume that Bidder will identify the insufficient width of the trench and inform to BHEL to get done the necessary excavation work by the responsible Civil Contractor. Please confirm.	yes
6	TCC, Annexure-ID - Detailed Weight Schedule, Sl. No. 05	We assume that these materials will be supplied in duly pre-fabricated condition and only field joint has to be done by Bidder. Please confirm.	The total weight is 153MT. In which the fitting, Mitre bends, tees, flanges are pre fabricated.

**There is no change in other conditions including date of bid submission**

**AGM / Contracts  
BHEL/PSSR**