

Corrigendum - 8 dated 26/03/2026 to CPC Tender No. BHEL/CPC/KRW/C MPH TG T-Yard/26/085

Corrigendum - 8 dated 26/03/2026 to CPC Tender No. BHEL/CPC/KRW/C MPH TG T-Yard/26/085 for the work of "Civil, Structural & Architectural works of Transformer Yard (U-1), Power House Building (U-1) including all Foundation/ Facility/ Structure inside the Building, TG Column and Deck (U-1), Common Control Room Building (U-1 & 2), ESP Control Building (U-1), Mill & Bunker (U-1), DG Building, Mill Reject Silo (U-1), Service Building, Air Compressor House, Central Lube Oil Building, CST Tank & PH, AC & Ventilation Ducting (U-1), Erection and Commissioning of EOT Crane (U-1 & U-2), Fire Fighting Pipe Pedestals/ Trenches (Within Main Power Block Island U-1), Pipe/ Cable Rack (Within Main Power Block Island U-1), Area Paving (Within Main Power Block Island U-1), Worker's Rest Room (U-1), Safety Control Room and Plant Roads & Drains (U-1 & U-2), etc. at 2 x 660 MW CSPGCL KORBA WEST TPP (CHHATISGARH, INDIA)".

A) Technical Conditions of Contract: Chapter X of TCC, Part B: BOQ cum Rate Schedule: - 2900 series (AC ventilation & ducting) of BOQ cum Rate Schedule are revised as below:

Existing in Tender					Revised as				
ST No.	ITEM DESCRIPTION	UOM	TOTAL QTY.	WEIGHTAGE IN % (UPTO 10 DECIMAL POINT)	ST No.	ITEM DESCRIPTION	UOM	TOTAL QTY.	WEIGHTAGE IN % (UPTO 10 DECIMAL POINT)
2900	AC VENTILATION & DUCTING				2900	AC VENTILATION & DUCTING			
2901	Supplying, Erection & Commissioning of finished GSS (zinc coating 275 GSM) AC & Ventilation ducting complete with hangers/ supports, Duct supporting structure, threaded rods, anchor fasteners, nuts for threaded rods, support angle, cleats , Consumable items like gaskets, sealant, adhesives, rivets, screws, nuts, bolts, washers etc. (including testing of ducting system by Smoke Test/Light Test) required for completion of leak proof Ducting system etc. with required fire				2901	Supplying, Erection & Commissioning of finished GSS (zinc coating 275 GSM) AC & Ventilation ducting complete with hangers/ supports, Duct supporting structure, threaded rods, anchor fasteners, nuts for threaded rods, support angle, cleats , Consumable items like gaskets, sealant, adhesives, rivets, screws, nuts, bolts, washers etc. (including testing of ducting system by Smoke Test/Light Test) required for completion of leak proof Ducting system etc. with required fire			

Corrigendum - 8 dated 26/03/2026 to CPC Tender No. BHEL/CPC/KRW/C MPH TG T-Yard/26/085

	<p>dampers, motorised actuators, Grills/Diffusers, Dampers & Thermal Insulation with Cladding of AC & exposed Ventilation Ducting all complete work as per technical specification and instruction of Engineer-In-Charge</p> <p>Note: -Contractor shall ensure availability of commissioning supervisor at Site during commissioning. Also, Civil contractor to rectify/ address any leakages/malfunctioning in duct work without any commercial implication to BHEL.</p> <p>Payment Breakup: a) On receipt of material at site - 60% b) On complete execution as per item description - 40%</p>					<p>dampers, motorised actuators, Grills/Diffusers, Dampers & Thermal Insulation with Cladding of AC & exposed Ventilation Ducting all complete work as per technical specification and instruction of Engineer-In-Charge</p> <p>Note: -Contractor shall ensure availability of commissioning supervisor at Site during commissioning. Also, Civil contractor to rectify/ address any leakages/malfunctioning in duct work without any commercial implication to BHEL.</p> <p>Payment Breakup: a) On receipt of material at site - 60% b) On complete execution as per item description - 40%</p>			
a	<p>Supplying, Erection & Commissioning of finished GSS (zinc coating 275 GSM) AC & Ventilation ducting complete with hangers/ supports, Duct supporting structure, threaded rods, anchor fasteners, nuts for threaded rods, support angle, cleats, Consumable items like</p>	SQM	3100	0.292528399		<p>a 18G.</p> <p>b 20G.</p> <p>c 22G.</p> <p>d 24G.</p> <p>e Fire damper with auto resetting, limit switches, indication lamps etc.</p> <p>f Motorized actuator with single phase power supply for the above fire damper.</p>	SQM	3100	0.292528399
							SQM	2450	0.228953465
							SQM	4900	0.439998007
							SQM	5400	0.479962292
							SQM	50	0.047856025
							No	55	0.055154296

Corrigendum - 8 dated 26/03/2026 to CPC Tender No. BHEL/CPC/KRW/C MPH TG T-Yard/26/085

	gaskets, sealant, adhesives, rivets, screws, nuts, bolts, washers etc. (including testing of ducting system by Smoke Test/Light Test) required for completion of leak proof Ducting system etc. with required fire dampers, motorised actuators , Grills/Diffusers ,Dampers & Thermal Insulation with Cladding of AC & exposed Ventilation Ducting all complete work as per technical specification and instruction of Engineer-In-Charge Note: -Contractor shall ensure availability of commissioning supervisor at Site during commissioning of AC & Ventilation System. Also, Civil contractor to rectify/address any leakages/malfunctioning in duct work without any commercial implication to BHEL								
b	18G.	SQM	2450	0.228953465					
c	20G.	SQM	4900	0.439998007					
d	22G.	SQM	5400	0.479962292					
e	24G.	SQM	50	0.047856025					
f	Fire damper with auto resetting, limit switches, indication lamps etc.	No	55	0.055154296					
g	Motorized actuator with single phase power	No	1	0.001002805					
					g	Spares for above Actuators	No	1	0.001002805
					h	Supply air grill/diffuser with VCD (Extruded Aluminium).	SQM	65	0.041485000
					i	Return air grill/diffuser without VCD (Extruded Aluminium).	SQM	75	0.041034959
					j	MS Grills/Diffusers with VCD complete with fixing frames, nuts, bolts, gasketes, washers etc.	SQM	100	0.021274344
					k	MS Grills/Diffusers without VCD complete with fixing frames, nuts, bolts, gasketes, washers etc.	SQM	10	0.001823778
					l	GI Volume control dampers for Duct.	SQM	90	0.049241951
					m	Thermal insulation with cladding of AC (supply & return air) & exposed ventilation ducting with finish as per specification	SQM	11200	0.530669983

Corrigendum - 8 dated 26/03/2026 to CPC Tender No. BHEL/CPC/KRW/C MPH TG T-Yard/26/085

	supply for the above fire damper.				
h	Spares for above Actuators	SQM	65	0.041485000	
i	Supply air grill/diffuser with VCD (Extruded Aluminium).	SQM	75	0.041034959	
j	Return air grill/diffuser without VCD (Extruded Aluminium).	SQM	100	0.021274344	
k	MS Grills/Diffusers with VCD complete with fixing frames, nuts, bolts, gasketes,washers etc.	SQM	10	0.001823778	
m	MS Grills/Diffusers without VCD complete with fixing frames, nuts, bolts, gasketes,washers etc.	SQM	90	0.049241951	
l	GI Volume control dampers for Duct.	SQM	11200	0.530669983	

Note:

- 1) All other terms and conditions against this NIT shall remain unchanged.**
- 2) This corrigendum is to be submitted duly signed and stamped along with the Techno-commercial bid (Part- I).**

**for BHARAT HEAVY ELECTRICALS LTD
Sr. Manager/ SCT**