



Project: NTPC Patratu STPS (3 X 800 MW)

**CORRIGENDUM
NO. 6 dt.
01.04.2022**

**Machine Package (Package A)-Bucket
Wheel Stacker cum Reclaimer
3X800MW PVUNL, Jharkhand State**

**Tender Ref. No.
Enquiry No.
77/21/6111/JRK Dated
14-02-2022**

Please note the following point

Sl. No.	Event Description	TO NOTE
1	Techno-commercial	Corrigendum issued for the following: 1. Technical clarification issued.
2	All other terms & conditions	Remain unchanged.

Note:

Also, please note that the full tender document can be downloaded from the website
<https://eprocurebhel.co.in/nicgep/app>

Contact Person:	
Technical-	Sandeep Sadu Dy. Manager/ Engineering (Mech) E-MAIL: ssd@bhel.in Ph. No. +91-080-2218 4219
Commercial-	J.R.Sumanjali.K., Manager/ Purchase E-MAIL: jrk@bhel.in Ph. No. +91-080-2218 4314 Shabeer Dewan, DGM/ MM EMAIL: sbd@bhel.in Phone:- +91 80 2218 4585

All other terms and conditions remain the same as per the original enquiry and it's subsequent amendment / addendum / corrigendum /clarification.

Any further addendum / corrigendum/ clarification/ notice of due date extension such issued shall be part of the bidding documents and this will be available at the web site from where the original documents have been received / downloaded by the bidder.

Hence bidders are requested to visit the web site on regular basis.

PRE-BID CLARIFICATION FOR PATRATU STACKER-RECLAIMER PACKAGE							
Sl. No.	Document	Clause No.	Heading / Title	Comments	BHEL reply	vendor reply 29.03.2022	BHEL Reply 01.04.2022
B	Technical						
2	-	-	General	<p>For bid clarity, bidder has not envisaged FDA system and fire extinguishers for E- House and operator cabin, same will be provided by client / others. Client to check & confirm.</p>	<p>Not acceptable. As per Tender Electrical specification – "All fire detection and fire suppression requirement as per Contract specification for Stacker cum reclaimer shall be considered. Automatic direct/indirect low pressure NOVEC 1230 fire suppression system employing linear pneumatic heat detection tube shall be provided for MCC room of stacker reclaimers.</p> <p>For fire detection of stacker-reclaimer, a local fire alarm panel for alarms shall be provided on each stacker-reclaimer machine along with interfaces & connectivity with fire alarm panel placed at CHP control room. The communication shall be as per standard and proven practice of the bidder.</p> <p>Boom conveyor and tripper conveyor of stacker-reclaimer machines shall be provided with Linear Heat Sensing cable.</p> <p>"</p> <p>Signal shall be interfaced with above mentioned (Clause no. 16) BHEL MVWS system for automatic operation of MVWS.</p>	<p>Bidder understands FDA system for E- House & LHS cables for boom conveyor is part of bidder's scope.</p> <p>Due to space constraint, bidder has not envisaged automatic direct/indirect low pressure NOVEC 1230 fire suppression System, however bidder has considered fire extinguishers instead of NOVEC 1230 fire suppression system for E- House.</p> <p>All interface with existing facility shall be in client's scope.</p>	<p>Not acceptable. Shall be as per tender specification. Novec 1230 fire suppression system is mandatory and the same shall be in bidder's scope. Please refer previous reply given by BHEL.</p>