

# **RATE CONTRACT FOR SERVICING JOBS**

## **DURATION OF PACKAGES FOR RATE CONTRACT:**

### **A) OVERHAUL PACKAGE OF 200/210MW SET OF LMW DESIGN:**

| DESCRIPTION  | DURATION<br>DAYS |
|--|------------------|
| 1. COH of HP/IP/LP Turbine & Generator, Valves Strainers including general overhauling of all bearings etc | 40               |

### **B) OH PACKAGE OF 120 /125 MW SET OF KWU DESIGN:**

| DESCRIPTION   | DURATION<br>DAYS |
|---|------------------|
| 1. COH of HP/IP/LPT, Generator, all valves and Strainers including General OH of all Bearings etc | 30               |

### **C) OH PACKAGE OF 190/195/200/210/250 MW SET OF KWU DESIGN:**

| DESCRIPTION  | DURATION<br>DAYS |
|--|------------------|
| 1. COH of HP/IP/LPT, Generator, all valves and Strainers including General OH of all Bearings etc. | 30               |

### **D) OH PACKAGE OF 500MW SET OF KWU DESIGN:**

| DESCRIPTION   | DURATION<br>DAYS |
|---|------------------|
| 01. COH of HP/IP/LPT, Generator and Exciter, all valves and Strainers including General OH of all bearings etc. | 35               |

### **E) Providing expert with >20 years experience in same fields on manday rate basis**

### **F) Boiler Chemical Cleaning work**

| DESCRIPTION   | DURATION DAYS   |
|---|---|
| 1. Chemical Cleaning of Boiler for 200/210/250 MW Unit including supply of required chemicals | 15 DAYS –PREPARATORY<br>+<br>6 DAYS PROCESS +<br>4 DAYS NORMALISATION |
| 2. Chemical Cleaning of Boiler for 200/210/250 MW Unit without supply of required chemicals   |   |
| 3. Chemical Cleaning of Boiler for 500 MW Unit including supply of required chemicals         |   |
| 4. Chemical Cleaning of Boiler for 500MW Unit without supply of required chemicals.           |   |

**G) Air Pre Heater work of Boiler**

| DESCRIPTION  | DURATION |
|--|----------|
| 1. Overhauling of Air Pre heater/ per Heater for /120 MW Unit Boiler           | 15 days  |
| 2. Overhauling of Air Pre heater/ per Heater for 190/ 210MW/ 250MW Unit Boiler | 20/days  |
| 3. Overhauling of Air Pre Heater per Heater for 490/500 MW Unit Boiler         | 25 days  |

**H. Electrical Diagnostic Test of Generator & NFT /Test of Turbine Blades - 2 days for each test**

**I.- Vibration Analysis & Balancing of TG , along with Instrument - Time as required ( time required for completion to be decided by site engineer)**

**===XXX===**