

TENDER

(NIT NO. TA/TCL/**15**/23-24)

FOR

**REPAIRING HEIGHT OF BOUNDARY WALL AT
SOUTH SIDE OF 5MW SOLAR PLANT,
COMMUNITY HALL AND OTHER AREA IN
GOVINDPURA N'HOOD BHEL TOWNSHIP,
BHOPAL.**

PRICE BID

SECTION - VI



**TOWNSHIP CIVIL MAINTENANCE
BHARAT HEAVY ELECTRICALS LIMITED**

**(A Government of India Undertaking)
BHOPAL - 462 022 (M.P)**

PREAMBLE OF PRICE BID

1.0. This Price Bid consists of three Schedules:

1.1 Schedule A

Schedule A consists of single Annexure:

1) Annexure-I includes items based on GST Compliant DSR-2012, Rate Analysis.

Bidders are requested to quote their rate in Percentage above/below/at Par for Annexure-I.

1.2 Schedule B

Schedule B gives the details of free issue materials given by BHEL.

1.3 Schedule C

Schedule C gives the details of Tools & Tackles provided by BHEL on Chargeable Basis.

2.0 The work to be carried out under the contract shall, except as otherwise provided in tender conditions, include all labour, materials, tools, plant, equipment, and transport which may be required in preparation of and for full & entire execution and completion of the Works. The descriptions given in the Schedule of Quantities shall, unless otherwise stated, be held to include waste on materials, carriage and cartage, carrying in return of empties, hoisting, setting, fitting and fixing in position and all other labours necessary in and for the full and entire execution and completion as aforesaid in accordance with good practice and recognized principles as laid down in Technical Specification & elsewhere in Tender Specification.

3.0 The price bid should not contain any condition. Conditional price Bids shall be summarily rejected.

4.0 The bidder should not leave any column blank in Price Schedules.

5.0 Price Quoted shall include all taxes, & duties except GST.

6.0 **Unless otherwise specified in the items involving cement or reinforcement steel, these items shall be issued free of cost by BHEL.**

**TOWNSHIP CIVIL MAINT. & CONST. DIVISION****SCHEDULE 'A'****Annexure: I**

Name of work : Repairing height of Boundary wall at south side of 5MW Solar Plant, Community hall and other area in Govindpura N'Hood BHEL Township, Bhopal.

S.No	It. Code	Description of items	Qty.	Unit	Rate	Amount
1		Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level:				
a)	4.1.3 RA	1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	8.00	cum	2576.38	20611.04
2	4.10RA	Providing and laying damp-proof course 40 mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 12.5 mm nominal size).	90.00	sqm	130.06	11705.40
3		Centring and shuttering including strutting, propping, etc. and removal of form for:				
(a)	5.9.1 RA	Foundations, footings, bases of columns, etc. for mass concrete.	20.00	sqm	155.49	3109.80
(d)	5.9.6 RA	Columns, pillars, piers, abutments, posts and struts.	20.00	sqm	349.52	6990.40
4		12 mm cement plaster of mix:				
	13.4.2 RA	1 : 6 (1 cement : 6 coarse sand).	200.00	sqm	99.21	19842.00
5		15 mm cement plaster on the rough side of single or half brick wall of mix:				
	13.5.2 RA	1 : 6 (1 cement : 6 coarse sand).	230.00	sqm	114.32	26293.60
6		Finishing walls with acrylic smooth exterior paint of required shade:				
	13.46.1 RA	New work (Two or more coats applied @1.67 litre/10 sqm) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm).	1305.00	sqm	60.04	78352.20
7	6.3.2 RA	Brick work with Ghol bricks having compressive strength not less than 50 Kg/cm ² in super structure above plinth level upto floor V level in all shapes and sizes in cement mortar 1:6 (1cement:6 Coarse sand) .-with modular bricks	30.00	Cum	6613.04	198391.20
8	19.6	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement: 2 fine sand) including testing of joints etc. complete				
	19.6.4RA	300 mm dia. R.C.C. pipe	30.00	Metre	366.47	10994.10
					Total Rs.	376289.74
Percentage quoted by the Contractor			%	Above	Below	At Par
Percentage quoted by the Contractor in words						
Signature of Contractor						

SCHEDULE – “B”								
Name of work :Repairing height of Boundary wall at south side of 5MW Solar Plant, Community hall and other area in Govindpura N’Hood BHEL Township Bhopal.								
1	Cement	—	Issued free of cost at Gadia Store/ sub-division					
<p>Note: If the contractor fails to return to the department unconsumed portion of total quantities of respective free issue material after completion of work or as and when instructed by Engineer-incharge, recovery at twice the respective material cost of the item as procured/decided by BHEL shall be made from the contractor's bill(s).</p>								
SCHEDULE – “C”								
----- NIL -----								
Signature of Contractor								