

VOLUME-IE PRICE SCHEDULE

PROJECT: 2XFr6B GTG-RUPPL,DAHEJ

BHARAT HEAVY ELECTRICALS LIMITED

Volume-IE Price Schedule

	TENDER NO.: BHEL/PESD-E&C/RUPPL-GTG/001 Project :: RUPPL- 2xFr-6B GTG	REV00 DATE : 16/08/12
	PRICE SCHEDULE FOR E&C OF 2xFr-6B GTG ::	
	Bidder ::	Price offer no and Date :
	NOTES ::	
1	This document details the price/payment schedule format for the enquiry. No other format will be entertained and evaluated.	
2	Duly signed & stamped unpriced price schedule format shall be submitted along with Technical offer by bidder as a token of his concurrence that his price schedule is to be submitted in this format & prices shall be offered for all the items appearing in this price format .	
3	Bidder shall fill up prices of all items and submit to BHEL in separate sealed cover. All prices shall be submitted exclusive of taxes and applicable taxes shall be indicated separately.	
4	Unit rates would be used to arrive at final contract value.For payment purpose,final contract value will be as per clause 2.13 of GCC	
5	All the bills will be settled from BHEL, PE&SD, -Hyderabad only.	

Volume-IE Price Schedule	
TENDER NO.: BHEL/PESD-E&C/RUPPL-GTG/001	REV00
PROJECT :: RUPPL-2xFr-6B GTG	DATE : 16/08/12
BIDDER ::	PRICE OFFER No. & DATE ::

Sl.No	Description	Unit Price for 1 GTG (A)	Unit Price in words	No. of Sets (B)	Total Price C=(A)x(B)	Total Price(C) in Words (Rs.)
1	E&C * Price for Mechanical items as per Annexure-1,Part-A			2		
2	E&C* Price for Electrical,C&I items as per Annexure-1,Part-B			2		
3	E&C *Price for Piping as per Annexure-1,Part-C			1		
4	E&C *Price for Common items as per Annexure-1,Part-D			1		
5	Hiring charges for Porta Cabin for 16 Months as per Annexure-3			2		
Total E&C price for project(X)						

* E&C: Erection,Testing,Painting & Commissioning

Sl.No	Description	Weight in Metric tons	Rate per Metric ton in words	Rate per Metric ton in figures	Total Price (Y)	Total Price(Y) in Words (Rs.)
1	Material handling(MH) consisting of receipt,unloading & storing of materials	1700				

Total E&C+ MH price till complete hand over to customer Z= (X) + (Y)(In Figures)		Rs
Total E&C & MH Price in Words	Rupees	

Notes:

- 1 Bidders shall quote for all items
- 2 Total price (Z) = (X)+(Y) shall be considered for price evaluation on lumpsum basis i.e for finalising the L1 bidder.
- 3 Applicable Taxes shall be indicated seperatly for each item / service.

TENDER NO.: BHEL/PESD-E&C/RUPPL-GTG/001	REV00
PROJECT :: RUPPL-2xFr-6B GTG	DATE : 16/08/12
BIDDER ::	PRICE OFFER No. AND DATE ::

Unit rates for arriving at Final Contract Value

Sl. No.	Description of Equipment	Unit	Unit Price
INSTRUMENTATION			
1	Orifice Plate Assemblies	nos	
2	Mass Flow Meter/ HSD/NAPHTHA	nos	
3	Mass Flow Meter/ HITECH	nos	
4	Differential Pressure Transmitters	nos	
5	Pressure Gauges	nos	
6	Pressure Transmitters	nos	
7	Temperature Gauges	nos	
8	Temperature Transmitters	nos	
9	Hand Held Calibrator	nos	
10	Thermowells	nos	
11	Junction Boxes	nos	
12	FRP Canopies	nos	
POWER CABLES			
13	3C X 4 SQMM CU COND PVC/FRLS ARMED CABLE	metre	
14	3CX6 ,1.1KV PVC/FRLS AL COND ARMED CAB	metre	
15	3CX16,1.1 KV PVC/FRLS AL COND ARMED CAB	metre	
16	3CX35,1.1 KV PVC/FRLS AL COND ARMED CAB 3CX50,1.1KV PVC/FRLS AL	metre	
17	COND ARMED CAB 3CX70,1.1 KV PVC/FRLS AL	metre	
18	COND ARMED CAB	metre	
19	1CX120,1.1KV PVC/FRLS AL COND ARMED CAB	metre	
20	3.5CX 95,1.1KV PVC/FRLS AL COND ARMED CAB	metre	
21	3CX 95,1.1KV PVC/FRLS AL COND ARMED CAB	metre	
CONTROL CABLES			
22	5C X 2.5 Sq .mm	metre	
23	10C X 2.5 Sq .mm	metre	
24	3CX2.5 PVC/FRLS CU COND ARMED CABLE,1.1	metre	
25	7CX2.5 PVC/FRLS CU COND ARMED CABLE,1.1	metre	

TENDER NO.: BHEL/PESD-E&C/RUPPL-GTG/001	REV00
PROJECT :: RUPPL-2xFr-6B GTG	DATE : 16/08/12
BIDDER ::	PRICE OFFER No. AND DATE ::

Unit rates for arriving at Final Contract Value

Sl. No.	Description of Equipment	Unit	Unit Price
26	12CX2.5 PVC/FRLS CU COND ARMD CABL 1.1KV	metre	
27	19CX2.5 PVC/FRLS CU COND ARMD CABL 1.1KV	metre	
28	24CX2.5 PVC/FRLS CU COND ARMD CABL 1.1KV	metre	
	SIGNAL CABLES		
29	10T X 0.5 Sq .mm	metre	
30	SIGNAL CABLE SINGLE PAIR 1.5MM2 SHLDG	metre	
31	SIGNAL CABLE 6 PAIR 0.5 SQ MM ORDINARY	metre	
32	SIGNAL CABLE 12 PAIR 0.5 SQ MM ORDINARY	metre	
33	SIGNAL CABLE 6PAIR 1.5MM2 SHLDG	metre	
34	SIGNAL CABLE TWELVE PAIR 1.5MM2 SHLDG	metre	
35	6 PAIR,20AWG,CHROMEL-ALUMEL EXN CABLE	metre	
36	12PAIR,20AWG,CHROMEL-ALUMEL EXT CABLE	metre	
37	8 TRIAD 1.5 SQ MM CABLE	metre	
38	1 TRIAD 1.5 SQ MM CABLE	metre	
39	1PAIR,16AWG,CHROMEL-ALUMEL EXT CABLE	metre	
40	1T x 1.5 SQ MM NON-INTRINSIC SAFE CABLE	metre	
41	2P x 1.5 SQ MM NON-INTRINSIC SAFE CABLE	metre	
42	4PX1.5 SQ MM NON-INTRINSIC SAFE CABLE	metre	
43	10PX1.5 SQ MM NON-INTRINSIC SAFE CABLE	metre	
	IMPULSE TUBING		
44	SS Tube 12.7X2.1 SS304 for Instruments listed above	metre	

Note:

1	Unit rate per metre / no shall be quoted for ETC of each item.
2	Unit rates shall be used for calculating the final amount of cable work and payment to bidder shall be governed by the clause 2.13 of GCC.

TENDER NO.: BHEL/PESD-E&C/RUPPL-GTG/001	REV00
PROJECT :: RUPPL-2xFr-6B GTG	DATE: 16/08/12
BIDDER ::	PRICE OFFER No. AND DATE ::

Unit rates for arriving at Final Contract Value

Piping erection including spring hangers,supports,hydraulic testing,insulation & painting

Table 1: Handling of pipes and fitup

Sl.No:	Material	Item Description & Size mm	IBR	Unit Rate for Handling & Fitup Rs.
<i>Pipes</i>				
1	A106GRB	PIPE(SMLS)- 26.7X 5.56 CS SA106 GR B	YES	
2	A106GRB	PIPE(SMLS)- 33.4X 4.55 CS SA106 GR B	YES	
3	A106GRB	PIPE(SMLS)- 48.3X 5.08 CS SA106 GR B	YES	
4	A106GRB	PIPE(SMLS) 60.3X 5.54 CS SA106 GR B	NO	
5	A106GRB	PIPE(SMLS) 114.3X 6.02 CS SA106 GR B	NO	
6	A106GRB	PIPE(SMLS)168.3X 7.11 CS SA106 GR B	NO	
7	A106GRB	PIPE(SMLS) 168.3X10.97 CS SA106 GR B	YES	
8	A106GRB	PIPE(SMLS) 273.1X 9.27 CS SA106 GR B	NO	
9	A312TP321	PIPE SS 21.3 X 3.7 A312 TP321	NO	
10	A312TP321	PIPE SS 26.7 X 3.9 A312 TP321	NO	
11	A312TP321	PIPE SS 48.3 X 3.7 A312 TP321	NO	
12	A312TP321	PIPE SS 60.3 X 3.9 A312 TP321	NO	
13	A312TP321	PIPE(SMLS) 88.9X5.5 S.S SA312 GRTP 321	NO	
14	A312TP321	PIPE(SMLS) 168.3X7.1 S.S SA312 GRTP321	NO	
15	IS1239	PIPE CS 34.2 X 4 SAW GALV	NO	
16	IS1239	PIPE CS 60.8 X 4.5 SAW GALV	NO	

Table 2: Pipe Welding

Sl.No:	Material	Item Description & Size mm	IBR	Unit Rate for Welding Rs.
<i>Pipes</i>				
1	A106GRB	PIPE(SMLS)- 26.7X 5.56 CS SA106 GR B	YES	
2	A106GRB	PIPE(SMLS)- 33.4X 4.55 CS SA106 GR B	YES	
3	A106GRB	PIPE(SMLS)- 48.3X 5.08 CS SA106 GR B	YES	
4	A106GRB	PIPE(SMLS) 60.3X 5.54 CS SA106 GR B	NO	
5	A106GRB	PIPE(SMLS) 114.3X 6.02 CS SA106 GR B	NO	
6	A106GRB	PIPE(SMLS)168.3X 7.11 CS SA106 GR B	NO	
7	A106GRB	PIPE(SMLS) 168.3X10.97 CS SA106 GR B	YES*	
8	A106GRB	PIPE(SMLS) 273.1X 9.27 CS SA106 GR B	NO	
9	A312TP321	PIPE SS 21.3 X 3.7 A312 TP321	NO	
10	A312TP321	PIPE SS 26.7 X 3.9 A312 TP321	NO	
11	A312TP321	PIPE SS 48.3 X 3.7 A312 TP321	NO	
12	A312TP321	PIPE SS 60.3 X 3.9 A312 TP321	NO	
13	A312TP321	PIPE(SMLS) 88.9X5.5 S.S SA312 GRTP 321	NO	
14	A312TP321	PIPE(SMLS) 168.3X7.1 S.S SA312 GRTP321	NO	
15	IS1239	PIPE CS 34.2 X 4 SAW GALV	NO	
16	IS1239	PIPE CS 60.8 X 4.5 SAW GALV	NO	
17	A312TP321	PIPE(SMLS) 114.3X6.02 S.S SA312 GRTP 321	NO	

(*)- Radiography has to be carried out as per BHEL guidelines . Price to be included in welding rate itself.

Table 3: Thermal insulation (application) including cladding,fixing arrangements etc.

PIPE SIZE in Inch	INS THK MM	Unit Rate for Insulation Application Rs.
6	75	
1.5	75	
1	60	
0.75	60	

Note:

1	Unit rate per metre / no shall be quoted for ETC of each item.
2	<u>Unit rates shall be used for calculating the final amount of piping and payment to bidder shall be governed by the clause 2.13 of GCC.</u>

TERMS OF PAYMENT

PROJECT: 2XFr6B GTG-RUPPL,DAHEJ

BHARAT HEAVY ELECTRICALS LIMITED

Project:2xFr6B GTG, RUPPL-Dahej		Date:16/08/12					
TENDER NO.:BHEL/PESD-E&C/RUPPL-GTG/001							
Doc Title: Terms of Payment to Bidder							
1) Payment schedule for E&C portion							
BHEL PO price(X) of Bidder for E&C of 2xFr6B GTG(100%): Rs.							
		% Payment for GT-1 Equipment	Amount in Rs	% Payment for GT-2 Equipment	Amount in Rs	% Payment for Common Items	Amount in Rs
I	On Progressive Completion of Erection of GT Equipment with aux. as per following break up details:						
A-1	Gas Turbine & Auxiliaries						
A-1.1(a)	Making Foundation ready for placement of skid [fdn block casting in RUPPL scope]	2.0%		2.0%			
A-1.1(b)	Placement of GT Skid in Position	2.0%		2.0%			
A-1.1(c)	Grouting of GT Foundation	0.5%		0.5%			
A-1.1(d)	Bypass stack	1.0%		1.0%			
A-1.1(e)	Accessory base	0.5%		0.5%			
A-1.1(f)	Inlet Ducting	0.5%		0.5%			
A-1.1(g)	Exhaust Ducting	1.0%		1.0%			
A-1.1(h)	Air Filter Equipment	1.0%		1.0%			
A-1.1(i)	Turbine Vent Fans	0.5%		0.5%			
A-1.1(j)	Air Processing Skid	0.5%		0.5%			
A-1.1(k)	Lube Oil Mist Eliminator	0.25%		0.25%			
A-1.1(l)	Compressor Water Skid	0.5%		0.5%			
A-1.1(m)	Lube Oil Centrifuge	0.25%		0.25%			
A-1.1(n)	Water Wash skid	0.5%		0.5%			
A-1.1(o)	Gas valve Module	0.5%		0.5%			
A-1.1(p)	APU Cooler	0.5%		0.5%			
A-1.1(q)	Fuel Drain Tank	1.0%		1.0%			
A-1.1(r)	Hi-tech Dozing Skid (Naptha)	0.5%		0.5%			
A-1.1(s)	Cooling Water Module	1.0%		1.0%			
A-1.1(t)	GT off base Enclosure	0.5%		0.5%			
	Sub - Total of (A-1)	15.00%		15.00%			
A-2	Gas Turbine Generator						
A-2.1(a)	Making Foundation ready for placement of skid [fdn block casting in RUPPL scope]	1.0%		1.0%			
A-2.1(b)	Placement of Generator	1.0%		1.0%			
A-2.1(c)	Alignment of GT Rotor and Load Gear Box	1.0%		1.0%			
A-2.1(d)	Grouting of Generator Foundation	0.5%		0.5%			
A-2.1(e)	Generator Air Cooler	0.5%		0.5%			
A-2.1(f)	Co2 System	1.0%		1.0%			
	Sub - Total of (A-2)	5.00%		5.00%			
A-3	Piping						
A-3.1(a)	GT Integral Piping	0.5%		0.5%			
A-3.2(b)	Fuel Piping	0.5%		0.5%			
A-3.3(c)	Cooling Water Piping	1.0%		1.0%			
	Sub - Total of (A-3)	2.00%		2.00%			
B	Electrical						
B-1.1(a)	Generator Aux. Compartment(GAC)	1.0%		1.0%			
B-1.1(b)	415V GT MCC	0.5%		0.5%			
B-1.1(c)	125V DC Charger	0.25%		0.25%			
B-1.1(d)	125V Battery	0.25%		0.25%			
B-1.1(e)	GT DCDB, 125 VDC	0.25%		0.25%			
B-1.1(f)	CONTROL & METERING PANEL	0.5%		0.5%			
B-1.1(g)	RELAY PANEL	0.25%		0.25%			
B-1.1(h)	LT Power Cables	1.5%		1.5%			
	Sub - Total of (B)	4.50%		4.50%			
C	Control & Instrumentation						
C-1.1(a)	Mark VI Panel	0.5%		0.5%			
C-1.1(b)	Field Instruments in Fuel, Cooling Water Area	0.50%		0.50%			
C-1.1(c)	GT Auxiliary Panel	0.25%		0.25%			
C-1.1(d)	UPS 15kVA	0.25%		0.25%			
C-1.1(e)	Control Cables	1.50%		1.50%			
C-1.1(f)	Signal Cables	0.5%		0.5%			
	Sub - Total of (C)	3.50%		3.50%			
	Total of I	30.00%		30.00%			

Project:2xFr6B GTG, RUPPL-Dahej							Date:16/08/12
TENDER NO.:BHEL/PESD-E&C/RUPPL-GTG/001							
Doc Title: Terms of Payment to Bidder							
1) Payment schedule for E&C portion							
BHEL PO price(X) of Bidder for E&C of 2xFr6B GTG(100%): Rs.							
		% Payment for GT-1 Equipment	Amount in Rs	% Payment for GT-2 Equipment	Amount in Rs	% Payment for Common items	Amount in Rs
II	On Progressive Completion of Erection of GT Equipment common items as per following break up details:						
1	Lubricity Additive Dosing Skids					0.75%	
2	2 m ³ HSD/ NAPHTHA DRAIN TANKS					1.00%	
3	Portable LO Drain Pump					0.50%	
4	Compressor Water Washing skid					1.00%	
5	Lube oil Centrifuge					0.75%	
6	Cooling water Module						
6.1	Tube Bundle					0.50%	
6.2	Structure(Assembled at site)					0.50%	
6.3	Fan					0.50%	
6.4	Motor					0.50%	
6.5	Pump with motor					0.50%	
6.6	CW Piping items(assembled at site)					1.50%	
7	Utility/common Piping					1.00%	
8	Mark-VIe simulator & HMI & Accessories					0.50%	
9	Master Slave Clock					0.50%	
	Total of II					10.00%	
III	Final Painting (including supply of paints)	4.0%		4.0%		2.00%	
IV	Commissioning:						
1	Oil Flushing of GT System	1.0%		1.0%			
2	GT Cranking	2.0%		2.0%			
3	FSNL of GT	2.0%		2.0%			
4	GT Synchronization	3.0%		3.0%			
5	Trial Operation	2.0%		2.0%			
	Total of III	10.00%		10.00%			
	Total of I, II III & IV	44.00%		44.00%		12.00%	
2) Payment schedule for Material Handling Portion							
a. BHEL PO price(Y) of Bidder for Material Handling of 2xFr6B GTG(100%)							
b. Payment for Material Handling shall be made after completion of receipt,unloading and storage at BHEL stores/site on pro-rata basis.							
Note:							
1	On placement of order by BHEL , successful bidder shall be paid as per the above schedule.						
2	On completion of respective work ,bidder shall be paid % of total E&C value indicated against that work.						
3	On completion of respective work ,bidder shall be paid % of total Material Handling value indicated against that work.						

Rev 00
16th Aug.
2012

Volume-IC TECHNICAL CONDITIONS OF CONTRACT (TCC)

(Doc. No.: BHEL/PESD-E&C/RUPPL-GTG/TCC/001)

BHARAT HEAVY ELECTRICALS LIMITED



SI No	DESCRIPTION	Chapter	PAGE No.
Volume-IC	Part-I: Contract specific details		
1	Project Information	Chapter-1	4
2	Scope of Work	Chapter-2	5
3	Facilities in the scope of Contractor/BHEL (Scope Matrix)	Chapter-3	7
4	T&Ps and MMEs to be deployed by Contractor	Chapter-4	13
5	Time Schedule	Chapter-5	22
6	Terms of Payment	Chapter-6	24
7	Taxes and other Duties	Chapter-7	25
8	Specific Inclusion	Chapter-8	27
9	Specific Exclusion	Chapter-9	30
10	Scope of equipment for ETC	Chapter-10	31
11	Tentative weight details & dimension of equipment/system	Chapter-11	39
Volume-IC	Part-II : Technical Specifications		
1	General	Chapter-1	40
2	Civil Works, Foundation, Grouting	Chapter-2	49
3	Equipment Installation-Mechanical	Chapter-3	51
4	Piping Installation	Chapter-4	53
5	Welding, Heat Treatment, Radiography and Insulation	Chapter-5	57

6	Equipment Installation- Electrical, Control & Instrumentation	Chapter-6	65
7	Handling of Heavier equipment	Chapter-7	90
8	Hydrostatic Testing Preservation & other tests	Chapter-8	91
9	Pre Commissioning Tests, Commissioning, Post Commissioning	Chapter-9	94
10	Chemical cleaning/Oil Flushing	Chapter-10	98
11	Painting	Chapter-11	100

CHAPTER-1
PROJECT INFORMATION

1.1	<p>INTRODUCTION BHEL is in receipt of an order from M/s Reliance Utilities and Power Private Limited (RUPPL) for supply, erection, commissioning and testing of 2 No.s of Frame 6B Gas Turbine Generator Packages at their petrochemical complex at Dahej, Gujarat, India.</p> <p>LOCATION: The project site is located at Dahej SEZ area. Nearest Railway station is Bharuch, which comes on Mumbai Delhi main route and nearest Airport is Vadodara which is 70 kms from Bharuch. The proposed site is 50 kms from Bharuch railway station and connected by a six lane highway from Bharuch.</p> <table style="width: 100%; border: none;"> <tr> <td style="width: 15%;">i.)</td> <td style="width: 55%;">Latitude</td> <td style="width: 30%;">: 21° 39'</td> </tr> <tr> <td>ii.)</td> <td>Longitude</td> <td>: 72° 33'</td> </tr> <tr> <td>iii.)</td> <td>Near</td> <td>: Dahej Luhara, Guj. (Gulf of Kutch)</td> </tr> <tr> <td>iv.)</td> <td>Nearest Town</td> <td>: Bharuch</td> </tr> <tr> <td>v.)</td> <td>Nearest Highway</td> <td>: NH8 & SH6 (Dahej Road)</td> </tr> <tr> <td>vi.)</td> <td>Nearest Commercial Port</td> <td>: Gujarat Chemical Terminal Port Company Limited</td> </tr> <tr> <td>vii.)</td> <td>Nearest Airport</td> <td>: Vadodara</td> </tr> <tr> <td>viii.)</td> <td>Nearest Railway Station</td> <td>: Bharuch</td> </tr> </table> <p>Site Elevation :415 meter above MSL</p>	i.)	Latitude	: 21° 39'	ii.)	Longitude	: 72° 33'	iii.)	Near	: Dahej Luhara, Guj. (Gulf of Kutch)	iv.)	Nearest Town	: Bharuch	v.)	Nearest Highway	: NH8 & SH6 (Dahej Road)	vi.)	Nearest Commercial Port	: Gujarat Chemical Terminal Port Company Limited	vii.)	Nearest Airport	: Vadodara	viii.)	Nearest Railway Station	: Bharuch																								
i.)	Latitude	: 21° 39'																																															
ii.)	Longitude	: 72° 33'																																															
iii.)	Near	: Dahej Luhara, Guj. (Gulf of Kutch)																																															
iv.)	Nearest Town	: Bharuch																																															
v.)	Nearest Highway	: NH8 & SH6 (Dahej Road)																																															
vi.)	Nearest Commercial Port	: Gujarat Chemical Terminal Port Company Limited																																															
vii.)	Nearest Airport	: Vadodara																																															
viii.)	Nearest Railway Station	: Bharuch																																															
1.2	<p>CLIMATIC CONDITIONS</p> <table style="width: 100%; border: none;"> <tr> <td style="width: 15%;">i.</td> <td style="width: 55%;">Meteorological Data</td> <td style="width: 30%;">: Dry Climate</td> </tr> <tr> <td>ii.</td> <td>Maximum Recorded Ambient Temperature</td> <td>: 47 ° C</td> </tr> <tr> <td>iii.</td> <td>Low Ambient Design Temperature</td> <td>: 5.6 ° C</td> </tr> <tr> <td>iv.</td> <td>Electrical Design Temperature for equipment located outdoors</td> <td>: 47 ° C</td> </tr> <tr> <td>v.</td> <td>Design Surface Temperature (surfaces exposed to solar radiation)</td> <td>: 55°C</td> </tr> <tr> <td>vi.</td> <td>Relative Humidity Annual mean</td> <td></td> </tr> <tr> <td></td> <td> Maximum</td> <td>: 89%</td> </tr> <tr> <td></td> <td> Normal</td> <td>: 79 %</td> </tr> <tr> <td></td> <td> Minimum</td> <td>: 56%</td> </tr> <tr> <td>vii.</td> <td>Average annual mean wind speed</td> <td>: 44 m/sec</td> </tr> <tr> <td>viii.</td> <td>Annual Average Rain fall</td> <td>: 1002 mm</td> </tr> <tr> <td>ix.</td> <td>Predominant Wind Direction</td> <td>: South west to North East</td> </tr> <tr> <td>x.</td> <td>Seismic Zone</td> <td>: Zone-III as per IS 1893</td> </tr> <tr> <td>xi.</td> <td>Basic Wind Speed</td> <td>: As per IS-875 (Part-3)</td> </tr> <tr> <td>xii.</td> <td>Design Seismic Zone</td> <td>: 3 with zone factor of 0.16</td> </tr> <tr> <td>xiii.</td> <td>Importance Factor</td> <td>: 1.5</td> </tr> </table>	i.	Meteorological Data	: Dry Climate	ii.	Maximum Recorded Ambient Temperature	: 47 ° C	iii.	Low Ambient Design Temperature	: 5.6 ° C	iv.	Electrical Design Temperature for equipment located outdoors	: 47 ° C	v.	Design Surface Temperature (surfaces exposed to solar radiation)	: 55°C	vi.	Relative Humidity Annual mean			Maximum	: 89%		Normal	: 79 %		Minimum	: 56%	vii.	Average annual mean wind speed	: 44 m/sec	viii.	Annual Average Rain fall	: 1002 mm	ix.	Predominant Wind Direction	: South west to North East	x.	Seismic Zone	: Zone-III as per IS 1893	xi.	Basic Wind Speed	: As per IS-875 (Part-3)	xii.	Design Seismic Zone	: 3 with zone factor of 0.16	xiii.	Importance Factor	: 1.5
i.	Meteorological Data	: Dry Climate																																															
ii.	Maximum Recorded Ambient Temperature	: 47 ° C																																															
iii.	Low Ambient Design Temperature	: 5.6 ° C																																															
iv.	Electrical Design Temperature for equipment located outdoors	: 47 ° C																																															
v.	Design Surface Temperature (surfaces exposed to solar radiation)	: 55°C																																															
vi.	Relative Humidity Annual mean																																																
	Maximum	: 89%																																															
	Normal	: 79 %																																															
	Minimum	: 56%																																															
vii.	Average annual mean wind speed	: 44 m/sec																																															
viii.	Annual Average Rain fall	: 1002 mm																																															
ix.	Predominant Wind Direction	: South west to North East																																															
x.	Seismic Zone	: Zone-III as per IS 1893																																															
xi.	Basic Wind Speed	: As per IS-875 (Part-3)																																															
xii.	Design Seismic Zone	: 3 with zone factor of 0.16																																															
xiii.	Importance Factor	: 1.5																																															

CHAPTER- 2 SCOPE OF WORK

Bidder shall note that their offer will be considered subject to the approval of -BHEL's customer(M/s RUPPL).

The work to be carried out under the scope of these specifications is broadly as under:

- 1) Receipt, collection, unloading, handling, stacking, storage & preservation, verification of entire project material including mechanical, electrical and control & instrumentation equipment and other material as received by road / rail from manufacturing units/ transporter's go-down under the scope of material handling.
- 2) Collection of material from BHEL/ client's stores/storage yard and transportation to site of work including heavy consignments like Gas Turbines, Gas Turbine Generators and other equipment under the scope of this tender specification, Un packing , pre-assembly, assembly and pre-erection checks as applicable.
- 3) Supply of 2nos Portable cabins with furniture & other fittings on hiring basis for a period of 16months. These porta cabins shall be used as BHEL site office & bidder shall take back the cabins after 16 months. Details of porta cabins are given in Annexure-3.
- 4) Lifting , Placement, Erection, Fit-up, Alignment of main equipment with Aux. systems, Off base piping, External system etc. and their welding/bolting/fastening etc. as per scope of these specifications.
- 5) Erection, Alignment, Fit-up and welding/bolting/fastening, Pre-heat treatment/Post Heat treatment etc. of Equipment with Aux., systems, Field piping & Integral Piping with supports etc. including primer painting of site weld joints with Chlorinated based Zinc Phosphate primer.
- 6) Non-destructive examination, Radiography, pre-heat treatment & post weld heat treatment as per requirement.
- 7) Chipping & preparation of foundations for equipment & structure's erection.
- 8) Secondary grouting of Equipment & Structures including the associated form works like shuttering and related facilities & grout mixing process with supply of approved grouting material.
- 9) Erection/Checking/cleaning & setting of hangers, cold setting and hot setting of hangers & supports.
- 10) Erection, Testing & commissioning of Mechanical, Electrical, C&I equipment as listed in Annexure-1.
- 11) Laying (in the trenches/trays provided by M/s RUPPL), testing & commissioning of the power, control & signal cables as listed in Annexure-1.
- 12) Provisioning, Servicing and setting of valves, actuators, Dampers, Power Cylinders etc.
- 13) Application of thermal insulation with retainers, fixing components, cladding sheet etc. of Equipment, Auxiliaries , Ducts, Piping, Tanks, Vessels, including bypass stacks and other associated equipment as per scope under these specifications.
- 14) Erection, Laying, Welding, NDE/Radiography of temporary Piping, Valves, Tanks, Supports etc. for Air Blowing, Chemical Cleaning/ Flushing etc. and their subsequent dismantling after completion of work

-
- 15) Handling and filling of Chemicals, Lubricants/gas/ preservatives during erection, preservation, chemical cleaning / flushing / blowing, pre-commissioning, Commissioning and subsequent topping up till trial operation completion.
 - 16) Preservative coating/ rapping of Buried / Underground piping if required.
 - 17) Conductance of Hydraulic test, Pneumatic test, Oil flushing, Kerosene testing, Chemical cleaning/Flushing, Air blowing/water Flushing, Steam blowing etc.
 - 18) Surface preparation, application of primer, preservation painting and Final painting(including supply of required paint) of Structures, Piping with valves, fittings, supports etc.
 - 19) Final painting(including supply of required paint) of main equipment(GT enclosure, Generator) related Auxiliaries, Systems etc.
 - 20) Pre-commissioning checks/tests, trial runs/testing and commissioning.
 - 21) Trial operation.
 - 22) Assistance for PG test.
 - 23) Handing over of fully erected, commissioned, tested Gas turbo-generator, equipment / tanks /vessels/piping, associated auxiliaries, including bought out items etc of 2 units of Fr6B GTG sets to customer at RUPPL- DAHEJ.
 - 24) Dismantling of BHEL stores after completion of the project and transportation of debris to a place designated by M/s RUPPL within a radius of 10Km. Details of Stores are given in Annexure-3.

CHAPTER- 3
FACILITIES IN THE SCOPE OF CONTRACTOR/BHEL (SCOPE MATRIX)

Sl.No	Description	Scope / to be taken care by		Remarks
		BHEL	Bidder	
3.1	ESTABLISHMENT			
3.1.1	FOR CONSTRUCTION PURPOSE:			
A	Open space for office (as per availability)	Yes		Location will be finalized after joint survey with owner
B	Open space for storage (as per availability)	Yes		Location will be finalized after joint survey with owner
C.1	BHELs site office (Supply of 2nos Portable cabins with furniture & fittings on hiring basis for a period of 12months).		Yes	
C.2	Construction of bidder's office, canteen and storage building including supply of materials and other services		Yes	
D	Bidder's all office equipment, office / store / canteen consumables		Yes	
E	Canteen facilities for the bidder's staff, supervisors and engineers etc		Yes	
F	Firefighting equipment like buckets, extinguishers etc		Yes	
G	Fencing of storage area, office, canteen etc of the bidder		Yes	
3.1.2	FOR LIVING PURPOSES OF THE BIDDER			
A	Open space for labor colony (as per availability)	Yes		Location will be finalized after joint survey with owner

Sl.No	Description	Scope / to be taken care by		Remarks
		BHEL	Bidder	
B	Labor Colony with internal roads, sanitation, complying with statutory requirements		Yes	
3.2	ELECTRICITY			
3.2.1	Electricity For construction purposes of Voltage 415 V (to be specified whether chargeable or free)			FREE
A	Single point source	Yes		At a distance of 200.0.M from site
B	Further distribution including all materials, Energy Meter, Protection devices and its service		Yes	In case of inadequate supply / non-availability of construction Power from customer, contractor shall have to arrange construction power at his own expenses to meet project schedules.
C	Duties and deposits including statutory clearances if applicable		Yes	
3.2.2	Electricity for the office, stores, canteen etc of the bidder (to be specified whether chargeable or free)			FREE
A	Single point source	Yes		At a distance of 200.0 M from site
B	Further distribution including all materials, Energy Meter, Protection devices and its service		Yes	
C	Duties and deposits including statutory clearances if applicable		Yes	
3.2.3	Electricity for living accommodation of the bidder's staff, engineers, supervisors etc	Yes		FREE

Sl.No	Description	Scope / to be taken care by		Remarks
		BHEL	Bidder	
A	Single point source	Yes		At a distance of 250.0 M from site
B	Further distribution including all materials, Energy Meter, Protection devices and its service		Yes	
C	Duties and deposits including statutory clearances if applicable		Yes	
3.3	WATER SUPPLY			
3.3.1	For construction purposes: (to be specified whether chargeable or free)			FREE
A	Making the water available at single point	Yes		In case of inadequate supply / non-availability of construction water from customer, contractor shall have to arrange construction water at his own expenses to meet project schedules.
B	Further distribution as per the requirement of work including supply of materials and execution		Yes	
3.3.2	<u>Water supply for bidder's office, stores, canteen etc</u>			FREE
A	Making the water available at single point	Yes		
B	Further distribution as per the requirement of work including supply of materials and execution		Yes	
3.3.3	<u>Water supply for Living Purpose</u>			FREE
A	Making the water available at single point	Yes		
B	Further distribution as per the requirement of work including supply of materials and execution		Yes	
3.4	LIGHTING			

Sl.No	Description	Scope / to be taken care by		Remarks
		BHEL	Bidder	
A	For construction work (supply of all the necessary materials) 1. At office/storage area 2. At the preassembly area 3. At the construction site /area		Yes	
B	For construction work (execution of the lighting work/ arrangements) 1. At office/storage area 2. At the preassembly area 3. At the construction site /area		Yes	
C	Providing the necessary consumables like bulbs, switches, etc during the course of project work		Yes	
D	Lighting for the living purposes of the bidder at the colony / quarters		Yes	
3.5	COMMUNICATION FACILITIES FOR SITE OPERATIONS OF THE BIDDER			
A	Telephone, fax, internet, intranet, e-mail etc		Yes	
3.6	COMPRESSED AIR wherever required for the work		Yes	
3.7	TRANSPORTATION			
A	For site personnel of the bidder		Yes	
B	For bidder's equipment and consumables (T&P, Consumables etc)		Yes	

Sl.No	Description	Scope / to be taken care by		Remarks
		BHEL	Bidder	
3.8.0	ERECTION FACILITIES	BHEL	Bidder	
3.8.1	Engineering works for construction:			
a	Providing the erection drawings for all the equipment covered under this scope	Yes		
b	Drawings for construction methods	Yes	Yes	In consultation with BHEL
c	As-built drawings – where ever deviations observed and executed and also based on the decisions taken at site- example – routing of small bore pipes		Yes	”
d	Shipping lists etc for reference and planning the activities	Yes		”
e	Preparation of site erection schedules and other input requirements		Yes	”
f	Review of performance and revision of site erection schedules in order to achieve the end dates and other commitments	Yes	Yes	”
g	Weekly erection schedules based on SI No. e		Yes	”
h	Daily erection / work plan based on SI No. g		Yes	”
i	Periodic visit of the senior official of the bidder to site to review the progress so that works are completed as per schedule. It is suggested this review by the senior official of the bidder should be done once in every month.		Yes	
j	Preparation of preassembly bay		Yes	
k	Laying of racks for gantry crane if provided by BHEL or brought by the contractor/bidder himself		Yes	

Sl.No	Description	Scope / to be taken care by		Remarks
3.8.0	ERECTION FACILITIES	BHEL	Bidder	
L	Arranging the materials required for preassembly		Yes	

CHAPTER-4
T&Ps and MMEs to be deployed by Contractor

SN	DESCRIPTION	CAPACITY	MINIMUM QUANTITY
	<u>MECHANICAL:</u>		
1.	TURN BUCKLES	AS PER REQMT	AS PER REQMT
2.	'D' SHACKLES	AS PER REQMT	AS PER REQMT
3.	STEEL WIRE ROPES	AS PER REQMT	AS PER REQMT
4.	MANILA ROPES	AS PER REQMT	AS PER REQMT
5.	CHAIN PULLEY BLOCK/TIRFUR	AS PER REQMT	AS PER REQMT
6.	PIPE BENDING MACHINE – 2" SIZE	2"	2 NOS
7.	ELECTROHYDRAULIC PIPE BENDING MACHINE	AS PER REQMT.	1 NO
8.	GRINDING MACHINE	AS PER REQMT	4 NOS
9.	DRILLING MACHINES	1/4", 1/2", 3/4" & 1"	1 NO. EACH
10.	COPPER TUBE BENDER AND CUTTER SIZES	6MM, 8MM, 1/2", 1/4"	1 NO. EACH
11.	DYE SETS FOR THREADING.	UPTO 2" PIPE	2NOS
12.	SPIRIT LEVEL	AS PER REQMT	2 NOS.
13.	TAP SETS FOR BOTH BSP AND MPT THREAD	UPTO 1" EACH	1 SET EACH
14.	MEASURING INSTRUMENTS LIKE MICROMETRES AND CALIPERS	AS PER REQMT	1 SET EACH
15.	WELDING GENERATORS	AS PER REQMT	2 NO.
16.	WELDING TRANSFORMER	AS PER REQMT	2 NO.
17.	TIG WELDING SET	AS PER REQMT	2 NO.
18.	MECHANICAL TOOL KIT FOR FITTERS	AS PER REQMT	4 NOS.

SN	DESCRIPTION	CAPACITY	MINIMUM QUANTITY
19.	ELECTRICIAN TOOL KIT	AS PER REQMT.	4 NOS.
20.	FLOOD LIGHT FITTINGS	AS PER REQMT.	2 NOS.
21.	FIRE EXTINGUISHERS	AS PER REQMT.	5 NOS.
22.	DISTRIBUTION BOARDS WITH POWER CABLE COMPLETE AS REQUIRED	AS PER REQMT.	3 NOS.
23.	PAINTING BRUSH	AS PER REQMT.	1 SET
24.	FIRE PROOF TARPAULIN	AS PER REQMT.	AS PER REQMT.
25.	SAFETY BELTS AND SAFETY HELMETS	AS PER REQMT.	AS PER REQMT.
26.	24V A/C TRANSFORMER & HAND LAMPS	AS PER REQMT	AS PER REQMT.
27.	MIG WELDING MACHINE WITH ACCESSORIES AIR COOL TYPE	AS PER REQMT	4 NOS.
28.	TORQUE WRENCH SET	AS PER REQMT	2 NOS.
29.	ELECTRODE DRYING OVENS	AS PER REQMT	1 SET
30.	FERRULE PRINTING MACHINE	AS REQUIRED	AS PER REQMT
31.	HYDRAULIC JACKS	250T /100T	4 NOS.EACH
32.	TUFFER CAPACITY	15T	2NOS
33.	CHAIN PULLEY BLOCKS 5/10T	5/10T	2 NOS EACH
34.	MOBILE PICKUP / CARRY CRANE (SUITABLE CAPACITY)	AS REQUIRED	1 NO.EACH
35.	TRUCK / TRAILER	AS PER REQMT.	AS PER REQMT.
36.	CRAWLER CRANE OF SUITABLE CAPACITY / SUITABLE ARRANGEMENTS TO FACILITATE ERECTION OF GAS TURBINE, GAS TURBINE GENERATOR AND OTHER EQUIPMENT ETC.	AS PER REQUIREMENT	AS PER REQUIREMENT

SN	DESCRIPTION	CAPACITY	MINIMUM QUANTITY
37.	MOBILE PICK AND CARRY CRANE	10-12 TON	1 NOS
38.	TRAILER WITH HORSE	AS PER REQUIREMENT	AS REQUIRED
39.	AIR COMPRESSOR (ELECTRIC)	140 CFM	AS REQUIRED
40.	TIG WELDING SET	-	3 SETS/AS PER REQUIREMENT
41.	3 ph DISTRIBUTION BOARD WITH COMPLETE SET UP FOR DRAWL OF CONSTRUCTION POWER & FITTED WITH ENERGY METER	200 Amps-1 SETS, 600 Amps- 1 Sets	2 SETS/AS PER REQUIREMENT
42.	PRE HEATING / STRESS RELIEVING SET (HEATING CONTROL PANEL, CABLES, HEATING ELEMENTS etc)	AS PER REQUIREMENT	4 SETS/AS PER REQUIREMENT
43.	RADIOGRAPHY ARRANGEMENT INCLUDING THE SOURCE	IR 192	3 SETS/AS PER REQUIREMENT
44.	ELECTRO-HYDRAULIC PIPE BENDING MACHINE	FOR UP TO 100 mm Nb PIPES	AS PER SITE REQUIREMENT
45.	WELDING GENERATOR (ELECTRIC & DIESEL)	300 AMPS	APPROX. 30 Nos. / AS REQUIRED
46.	RADIOGRAPHY FILM VIEWER	AS PER REQMT	1 NO.
47.	ELECTRIC WINCH	3 TON / 2 TON	AS PER REQMNT
48.	HAND WINCH	1 TON	AS PER REQMNT
49.	ELECTRIC CABLE FOR DRAWAL & DISTRIBUTION OF CONSTRUCTION POWER	AS PER SITE REQUIREMENT	AS PER SITE REQUIREMENT
50.	PIPE BENDING MACHINE – HAND OPERATED	UP TO 50 mm Nb PIPES	AS PER SITE REQUIEREMENT

SN	DESCRIPTION	CAPACITY	MINIMUM QUANTITY
51.	BAKING OVEN AND HOLDING OVEN WITH THERMOSTAT AND TEMPERATURE GAUGE FOR BAKING COATED WELDING ELECTRODES	AS PER REQUIREMENT	02 EACH
52.	PORTABLE OVEN FOR COATED WELDING ELECTRODES	AS PER REQUIREMENT	15
53.	ELECTRIC MOTOR DRIVEN HYDRAULIC TEST PUMP WITH DRIVE AND STARTER ETC.	150 Kg/Cm ²	1 NO.
54.	MIXER FOR GROUTING OF EQUIPMENT FOUNDATIONS	AS PER REQUIREMENT	AS PER REQUIREMENT
55.	VACUUM CLEANER (INDUSTRIAL)	AS PER REQUIREMENT	AS PER REQUIREMENT
56.	JACKING BOLTS / PRESSOUT BOLTS OF ALL SIZES	AS PER REQUIREMENT	AS PER REQUIREMENT
57.	GANG OPERATED AND HAND OPERATED HYDRAULIC JACKS WITH SUFFICIENT LONG HOSES OF VARIOUS CAPACITIES FOR GT, AND GTG	50 MT/100 MT	AS PER REQUIREMENT
58.	TORQUE WRENCH	0 TO 200 NM	AS PER REQUIREMENT
59.	SLINGS OF VARIOUS CAPACITY AND QUANTITIES FOR HANDLING OF EQUIPMENT	AS PER REQUIREMENT	AS PER REQUIREMENT
60.	BOLT STRETCHING DEVICE	AS PER REQUIREMENT	AS PER REQUIREMENT
61.	FEELER GAUGE S OF VARIOUS SIZES	AS PER REQUIREMENT	AS PER REQUIREMENT
62.	SPANNERS / EYE BOLTS (OF ALL SIZES)	AS PER REQUIREMENT	AS PER REQUIREMENT

SN	DESCRIPTION	CAPACITY	MINIMUM QUANTITY
63.	ANY OTHER MAJOR T&P REQUIRED FOR SATISFACTORY COMPLETION OF THE WORKS.	AS PER REQUIREMENT	AS PER REQUIREMENT
	<u>ELECTRICAL, CONTROL & INSTRUMENTATION:</u>		
1.	1 Phase/3 PHASE VARIAC	AS PER REQUIREMENT	1 NO. EACH
2.	SINGLE PHASE VARIAC 28 AMPS	AS PER REQUIREMENT	1 NO.
3.	PORTABLE AIR COMPRESSOR WITH DRIER AND REGULATOR MAKE "TOSHNIWAL"/"KHOSLA"	RATED FOR 7/10 KG/CM2	1 NO.
4.	SOLDERING IRON "SOLDRON" MAKE	25 WATT	2 NOS.
5.	VACUUM PUMP	AS PER REQUIREMENT	1 NO.
6.	MULTIMETRES		
	a) DIGITAL 3 1/2 DIGIT OF REPUTED MAKE	AS PER REQUIREMENT	6 NOS.
	b) ANALOG MOTWANE MAKE	AS PER REQUIREMENT	3 NOS.
	c) DIGITAL 4 1/2 DIGIT OF REPUTED MAKE	AS PER REQUIREMENT	2 NO.
7.	STANDARD MILLI AMPS/MILLIVOLTS SOURCE	RANGE 0 TO 60 mA AND 0 TO 100 mV	2 NOS
8.	INSULATION TESTER HAND OPERATED	250V/500V/1000 V RATED MAINS/BATTERY OPERATED	1 NO. EACH

SN	DESCRIPTION	CAPACITY	MINIMUM QUANTITY
9.	INSULATION TESTER MAINS OPERATED	2500/5000V	2 NO.
10.	CRIMPING TOOLS	AS PER REQUIREMENT	2 NOS.
11.	CRIMPING TOOL HYDRAULIC	UPTO 600 SQ.MM	1 NO.
12.	DC POWER SUPPLY -MAKE "APLAB" OR EQUIVALENT (VARIABLE SOURCE)	0 TO 250 V DC, 5 A	2 NO
13.	PHASE SEQUENCE INDICATOR	AS PER REQUIREMENT	1 NO.
14.	FREQUENCY SOURCE	45 TO 55 HZ WITH 110V	1 NO.
15.	TONG TESTER REPUTED MAKE	AC 5/10, 25/60/300 AMP RANGE	1 NO. EACH
16.	TONG TESTER \	DC 30/60/300 AMP	1 NO.
17.	STOP WATCH	AS PER REQUIREMENT	1 NO.
18.	TARPOLIN FIRE PROOF	AS REQUIRED	AS REQUIRED
19.	DC SHUNT	400 AMP 75 MV	1 NO.
20.	3 PHASE SHIFTER	AS REQUIRED	1 NO.
21.	INDUSTRIAL TYPE VACUUM CLEANER	AS REQUIRED	1 NO.
22.	MICRO OHM METER	AS REQUIRED	1 NO.
23.	DECADE RESISTANCE BOX	AS REQUIRED	2 NOS.
24.	TELETALK 2 WIRE SYSTEM	AS REQUIRED	6 SETS
25.	PORTABLE BLOWER WITH HEATING ARRANGEMENT	AS REQUIRED	1 NO.
26.	TORQUE WRENCH	(12-60Nm, 50-225 Nm)	1 NO EACH

SN	DESCRIPTION	CAPACITY	MINIMUM QUANTITY
27.	WATTMETER AC/DC	0-125-250V, 0-5-10A	1 NO
28.	OSCILLOSCOPE	AS REQUIRED	1 NO
29.	TACHOMETER NON CONTACT TYPE 0 to 4000 RPM	0 to 4000 RPM	1 NO
30.	TAN DELTA TEST KIT	AS REQUIRED	1 NO
31.	RHEOSTAT	AS REQUIRED	3 NOS
32.	POLARITY TEST KIT	AS REQUIRED	1 NO
33.	NON – CONTACT TYPE DIGITAL THERMOMETER	AS REQUIRED	1 NO
34.	RELAY TESTING KIT	AS REQUIRED	1 NO
35.	FERRULE PRINTING MACHINE	AS REQUIRED	1 NO
36.	PHANTAM LOAD KIT	AS REQUIRED	1 NO
37.	DEAD WEIGHT TESTER AND WITH WEIGHTS AND TEST GAUGE FACILITY. MAKE ‘BUDENBERG OR ‘RAVIKA’	RATED 400 KG/CM2	1 NO
38.	OIL TEMPERATURE BATH SUITABLE TO CALIBRATE THE INSTRUMENTS WITH STANDARD TEMPERATURE GAUGES AND THERMOSTATIC CONTROL	RANGE 0 – 200 DEG. C	2 NOS.
39.	MUFFLE FURNACE WITH STANDARD TEMPERATURE GAUGES	800 DEG. C	1 NO
40.	STANDARD GAUGES MAKE “BUDENBERG” OR ”H GURU” OR “ODIN”	12” DIAL SIZE	AS REQUIRED
	A) PRESSURE GAUGE(VACUUM GAUGE)	– 1-0 KG/CM2	1 NO.
	B) PRESSURE GAUGE	0 – 5 OR 6 KG/CM2	AS REQUIRED

SN	DESCRIPTION	CAPACITY	MINIMUM QUANTITY
	C) PRESSURE GAUGE	0 – 10 KG/CM2	AS REQUIRED
	D) PRESSURE GAUGE	0 – 25 KG/CM2	AS REQUIRED
	E) PRESSURE GAUGE	0 – 60 KG/CM2	1 NO.
	F) PRESSURE GAUGE	0 – 100 KG/CM2	1 NO.
	G) PRESSURE GAUGE	0 – 250 KG/CM2	1 NO.
	H) PRESSURE GAUGE	0 – 600 KG/CM2	1 NO.
	I) PRESSURE GAUGE	0.2 TO 1 KG/CM2	1 NO.
41.	MANOMETERS	(+/-) 1000MMWC	2 NOS.
42.	WITH HAND BULB FOR LAB AND SMALL MANOMETERS FOR FIELD PURPOSE.	AS REQUIRED	AS REQUIRED
43.	MANOMETER (+/-) 500MM MERCURY COLUMN WITH HAND BULB FOR LAB AND SMALL MANOMETER FOR FIELD PURPOSE.	(+/-) 500MM MERCURY COLUMN	1 NO.
44.	INCLINED MANOMETER	(+/-) 300 MMWC	1 NO.
45.	GLASS THERMOMETER	0-120 DEG. C, 0-200 DEG.C AND 0-600 DEG.C	1 NO. EACH
46.	RTD/PT 100 SOURCE	AS REQUIRED	1 NOS.
47.	DECADE RESISTANCE BOX	AS REQUIRED	1 SETS.
48.	FUNCTION GENERATOR	AS REQUIRED	1 NO.

Any other major T&P required for satisfactory completion of the works.

B: MEASURING AND MONITORING DEVICES (MMD):

As per requirement - to be finalized at site.

NOTE:

This above list is only indicative and neither exhaustive nor limiting. Quantities indicated above are only the minimum required. Contractor shall deploy all necessary T&P to meet the schedules & as prescribed by BHEL engineer and required for completion of work.

CHAPTER-5 TIME SCHEDULE

5.1 SCHEDULE & MOBILIZATION

5.1.1 INITIAL MOBILIZATION AND TENTATIVE SCHEDULE

Contractor shall reach at site, make his site establishment and be ready to commence the work within two weeks from the date of fax Letter of Intent or as per directions of Construction Manager/ Project Manager of BHEL.

The contractor has to subsequently augment his resources in such a manner that all the works are completed to achieve the following schedule:

ACTIVITY	SCHEDULE OF COMPLETION FOR FIRST UNIT (i.e. Unit-1)
Enabling works	1 st month
Material handling	2 nd month to 09 th month
Erection of GT & its auxiliaries	5 th month
GT Inlet, Exhaust ducting & GT Box up	8 th month
Commissioning of Auxiliaries & FSNL	9 th month
Synchronisation	10 th month
Trial run & Handing over	11 th month

THE PHASE DIFFERENCE BETWEEN SUCCESSIVE UNITS IS 1 MONTH.

ABOVE PERIOD STARTS FROM THE DATE OF LOI.

The total contract period is 16 Months from the date of LOI and the bidder has to complete the entire erection & commissioning of both the sets within 12 months in all aspects including trial run.

5.1.2

In order to meet above schedule and other intermediate targets/activities as set by BHEL Engineer- In charge at site, to meet customer requirements/project schedule, i.e **Commissioning schedule of GT-1 : August,2013 & Commissioning schedule of GT-2 is September,2013.** Bidder shall arrange all necessary resources and work force in consultation with BHEL engineer at site & without any cost implication to BHEL, to undertake works concurrently in all possible fronts as made available to contractor.

5.1.3

Contractor shall specifically note that if there is some delay in supply of materials / release of work fronts / other reasons. Contractor shall have to work round the clock on such critical activities as a part of catch up programme to meet the project requirement to the extent possible and shall also provide required resources as part of scope of work.

CHAPTER-6

TERMS OF PAYMENT

The progressive payment for erection, testing and commissioning on accepted price of contract value per unit of GTG Package rates will be released as per the payment terms given in attached document titled “Terms of Payment”.

CHAPTER-7 TAXES AND OTHER DUTIES

7.1.0 TAXES, DUTIES, LEVIES

7.1.1

The contractor shall pay all (save the specific exclusions as enumerated in this contract) taxes, fees, license charges, deposits, duties, tools, royalty, commissions or other charges which may be levied on the input goods & services consumed and output goods & services delivered in course of his operations in executing the contract. In case BHEL is forced to pay any of such taxes, BHEL shall have the right to recover the same from his bills or otherwise as deemed fit.

However, provisions regarding Service Tax and Value Added Tax (VAT) on output services and goods shall be as per following clauses.

7.1.2 Service Tax & Cess on Service Tax

Service Tax and Cess on Service Tax as applicable on output Services are excluded from contractor's scope; therefore contractor's price/rates shall be exclusive of Service Tax and Cess on Output Services. In case, it becomes mandatory for the contractor under provisions of relevant act/law to collect the Service Tax & Cess from BHEL and deposit the same with the concerned tax authorities, such applicable amount will be paid by BHEL.

Contractor shall submit to BHEL documentary evidence of Service Tax registration certificate specifying name of services covered under this contract. Contractor shall submit serially numbered Service Tax and Cess Invoice, signed by him or a person authorized by him in respect of taxable service provided, and shall contain the following, namely,

- I. The name, address and the registration number of the contractor,**
- II. The name and address of the party receiving taxable service,**
- III. Description, classification and value of taxable service provided and,**
- IV. The service tax payable thereon.**

All the four conditions shall be fulfilled in the invoice before release of service tax payment.

Contractor shall obtain prior written consent from BHEL before billing the amount towards such taxes.

With introduction of Cenvat Credit Rules 2004, which came into force w.e.f. 10.09.2004, Excise Duty paid on Input Goods including Capital Goods and Service Tax paid on Input Services that are used for providing the output services can be taken credit of against the Service Tax payable on output services. However BHEL may opt for availing the abatement provision in which case cenvat credit may not be available on input duty.

7.1.3 VAT (Sales Tax /WCT)

As regards Value Added Tax (VAT) on transfer of property in goods involved in Works Contract (previously known as Works Contract Tax) applicable as per local laws, the price quoted by the contractor shall be **exclusive** of the same. Where such taxes are required to be paid by the contractor, this will be reimbursed on production of proof of payment made to the authorities by the Contractor. In any case the Contractor shall register himself with the respective Sales Tax authorities of the state and submit proof of such registration to BHEL along with the first RA bill. The contractor has to take all necessary steps to **minimize tax on input goods** by purchasing the materials from any registered dealer of the concerned state only. In case contractor opts for composition, it will be with the prior express consent of BHEL. Deduction of tax at source shall be made as per the provisions of law unless otherwise found exempted. In case tax is deducted at source as per the provisions of law, this is to be construed as an advance tax paid by the contractor and no reimbursement thereof will be made unless specifically agreed to.

7.1.4 Modalities of Tax Incidence on BHEL

Wherever the relevant tax laws permit more than one option or methodology for discharging the liability of tax/levy/duty, BHEL will have the right to adopt the appropriate one considering the amount of tax liability on BHEL/Client as well as procedural simplicity with regard to assessment of the liability. The option chosen by BHEL shall be binding on the Contractor for discharging the obligation of BHEL in respect of the tax liability to the Contractor.

7.1.5 New Taxes/Levies

In case the Government imposes any new levy/tax on the output service/ goods/work after award of the contract, the same shall be reimbursed by BHEL at actual.

In case any new tax/levy/duty etc. becomes applicable after the date of Bidder's offer, but before the Price BID opening, the Bidder/Contractor must convey its impact on his price duly substantiated by documentary evidence in support of the same before opening of Price Bid. Claim for any such impact after opening the Price Bid will not be considered by BHEL for reimbursement of tax or reassessment of offer.

No reimbursement/recovery on account of increase/reduction in the rate of taxes, levies, duties etc. on input goods/services/work shall be made. Such impact shall be taken care of by the Price Variation/Adjustment Clause (PVC) if any. In case PVC is not applicable for the contract, Bidder has to make his own assessment of the impact of future variation if any, in rates of taxes/duties/levies etc. in his price bid.

CHAPTER-8 SPECIFIC INCLUSIONS

SPECIFIC INCLUSIONS

8.1

All terminal connections for equipment & piping covered in this specification. Impulse/pneumatic piping between customer's battery limit and equipment.

8.2

Supply of 2nos Portable cabins with furniture & other fittings on hiring basis for a period of 16months. These porta cabins shall be used as BHEL site office & bidder shall take back the cabins after 16 months. Details of porta cabins are given in Annexure-3.

8.3

Servicing and assembly of control valves/regulating valves, fixing of filter elements/strainers is part of scope of work.

8.4

It may be specifically noted that it should not be construed or claimed by the contractor that with the technical specification and "exclusions and/or inclusions" detailed in this tender specification, BHEL has covered the entire scope of work and/or the details thereof to be executed by the contractor.

8.5

Complete control fluid system is included in this specification. Associated assistance for commissioning like lube oil flushing, filling and topping up of lube oil etc shall be part of the work.

8.6

Erection and welding of Impulse piping from various equipment & pipings tapping point to root valve.

8.7

Chipping of foundation, placement, erection, alignment, commissioning, grouting, mounting of equipment mount instruments and other fittings of BHEL (PESD bought out items) supplied Packages like Misc. Pumps, Tanks & Vessels etc. & other packages are in scope of the work. Erection and commissioning of these Equipment/Pumps & Packages will be required to complete to meet the commissioning schedule/ milestone activities of other areas like CW Systems, Service water requirement, fuel oil handling plant etc. Contractor shall plan and complete erection & commissioning of these equipment on priority as per decision of BHEL

Engineer/customer requirement. Details of such systems are furnished in relevant Appendix.

8.8

Most of the Misc. Pumps with drive motors, base frame, fittings etc. will be supplied in loose parts/ dismantled condition as skid mount. These pumps along with drive and fittings shall be assembled at site. The Delivery these will be taken from BHEL stores/storage yard and will be assembled/installed at different locations as per drawing and instruction of BHEL Engineer at site. The work involved is preservation, assembly, installation, erection, alignment, foundation grouting including providing non-shrink free flow grout mix material, fixing of loose items, filling of lubricants, greasing, commissioning, no load/ load trial run of motors & pumps. All the works shall be carried out as part of scope of work.

These Misc. pumps will be required for erection and commissioning of other systems, pipings, equipment which will be under scope of erection. Contractor shall carry out the installation, erection and alignment works etc. as per priority decided by BHEL Engineer at site to enable the other agencies to proceed with their work. Contractor shall carry out the welding of terminal point/interface/matching & connected flanges joints, pipe joints etc. of other system & as scope of work. The decision of BHEL Engineer shall be final and binding on contractor.

8.9

Contractor shall take specific note of same and shall carry out the erection, fit-up, welding, NDT & Radiography requirement including Pre-heat treatment, post heat treatment and providing the required filler wires and welding electrodes as part of scope of work as per drawing/BHEL procedure and instruction of BHEL Engineer at site.

8.10

Supply of detergents for offline compressor water wash for first fill around 227 Liters and for flushing 160 Liters.

8.11

Earthing of BHEL supplied Equipment.

8.12

Any material for temporary piping (pipe, valve, structural steel etc.) required for hydraulic test, chemical cleaning, flushing or steam/air blowing of the pipelines.

8.13

Supply & application of required paints for exposed surfaces (Final painting) shall be in the scope of bidder.

8.14

Dismantling of BHEL stores after completion of the project. Details of Stores are given in Annexure-4.

8.14

Supply of Rubber mats (for placing in front of LT switchgear panels), Danger boards, Copper Tinned lugs of various type (pin, ring, fork, snap-on), PVC cable ties, PVC ferrules (printed), PVC buttons and tapes, cable identification tag of metallic, clamping and dressing material with hardware, PVC sleeves, Clamping material for Impulse tubing etc within the quoted price. The quality of material shall be got approved from BHEL engineer prior to their procurement.

CHAPTER-9 SPECIFIC EXCLUSIONS

9.0 EXCLUSIONS

The following are specific exclusions from the scope of work/specification: -

- A) All cable connections except those specified as scope of work.
- B) Civil works to the extent not specifically provided for in this tender.

CHAPTER-10
SCOPE OF EQUIPMENT FOR ETC

**A) LIST OF GT & ITS AUXILIARIES PER UNIT TO BE ERECTED,
TESTED & COMMISSIONED (ETC):**

Two numbers Frame-6B (PG6581 B) Gas Turbines each of which is characterized by the following equipment and accessories except where mentioned otherwise:

1. Base mounted, single-shaft Frame-6B Split base, Gas Turbine and accessory compartment consisting of:

Accessory compartment consisting of:

- i. Diesel Engine starting system (for one machine and motor for the other Machine)
- ii. Hydraulically operated, solenoid-valve controlled jaw clutch with automatic
- iii. Disengagement at turbine self-sustaining speed.
- iv. Hydraulic torque converter
- v. Heavy duty, multi-shaft accessory gear box
- vi. Diaphragm type accessory coupling.
- vii. DC motor driven hydraulic ratchet rotor turning device
- viii. Fuel system consisting of:
 - On base Liquid Fuel System (suitable for Naphtha and HSD consisting of:
 - Shaft driven fuel pump externally lubricated with stop & bypass valves
 - Main atomizing air compressor (shaft driven)
 - Starting belt driven air compressor
 - Atomizing air pre-cooler
 - Circular Flow divider
 - Piping, valves, duplex filter & necessary instrumentation etc.

-
- ix. Gas Fuel System (suitable for Natural gas) consisting of
 - Stop/speed ratio valve & control valve located in off base Gas Module
 - Piping, valves filters & necessary instrumentation etc.
 - Necessary piping, valves and instrumentations etc.
 - 400 micron Gas strainer (mounted off-base)
 - Interconnection wiring in rigid metal conduit
 - Base mounted terminal boxes
 - x. Closed, forced fed lubricating oil system including:
 - Shaft driven main oil pump
 - Full flow AC motor driven auxiliary lube oil pump
 - Partial flow DC motor driven emergency oil pump
 - Dual filters with transfer valve for Lube Oil & Hydraulic oil systems
 - Shaft driven hydraulic oil pump
 - Full flow AC MOTOR DRIVEN AUXILIARY Hydraulic pump
 - Necessary piping, controls and instrumentation etc.
 - xi. Off-base Enclosure thermal & acoustic for Accessory compartment limiting near field noise Pr. Level to 85 dBA @ 1.0 m laterally & 1.5 m elevation from GT enclosure.
 - xii. Negative ventilation system
 - xiii. Fire & Gas detection cum & monitoring system with CO₂ protection with UV detector and monitor
 - xiv. Necessary on-base piping
 - xv. Necessary on-base cables (power, control & signal), electrical equipment & instrumentation - suitable for Class-1, Division-2, Group-D
 - xvi. Lighting in accessory compartment

Turbine compartment consisting of:

- Seventeen stage, axial flow, corrosion protected compressor

-
- Ten-chamber, reverse flow type combustion system with standard combustors
 - UV Flame detectors
 - 3-stage turbine with PLASMA GUARD coated first stage buckets
 - Dual ignition system
 - Vibration sensors (seismic type) with monitoring by GT Mark-Vie panel
 - Thermocouple for measuring critical turbine temperature (exhaust)
 - Thermocouples for measuring bearing drain temperatures
 - Boroscope openings
 - Inlet and exhaust plenums
 - Off-base Enclosure thermal & acoustic for Accessory compartment limiting near field noise Pr. Level to 85 dBA @ 1.0 m laterally & 1.5 m elevation from GT enclosure
 - Negative ventilation system
 - Fire & Gas detection and monitoring system with CO2 protection with UV detector and monitor
 - Interconnection wiring in rigid metal conduits
 - Base mounted terminal boxes
 - Necessary on-base piping
 - Necessary on-base cables (power, control & signal), electrical equipment & instrumentation-suitable for class-1, Division-2, Group-D
 - Lighting in turbine compartment
2. Inlet Air System (Carbon steel) consisting of :
- Filter compartment with:
 - i. Self-cleaning filter cartridges

-
- ii. Lighting and instrumentation
 - iii. Air processing unit
 - iv. Inlet ducting with silencer
 3. Space provision for
 - i. Installing chiller coils in the inlet air duct (chilling system is in scope of RIL)
 - ii. Transition piece from inlet ducting to inlet plenum
 - iii. Necessary structural supports
 4. Internally insulated Exhaust Gas system (side Exhaust) consisting of:
 - Expansion joints
 - Exhaust ducting
 - Electrically operated Diverter damper with rotor actuators and 2x 100% seal air fans
 - Electrically operated Guillotine damper with rotor actuators and 2x100% seal air fans.
 - 30 m high bypass stack (height from machine base-line) including Transition piece & silencer
 - Necessary structural supports
 5. Control & Electrical equipment (mounted in control room) as follows:
 - Speedtronic MARK Vie GT control panel
 - 125 V DC Battery and battery charger (Ni-Cd) with DCDB.
 - UPS
 - Aux. panel
 6. Control and signal cables -Lot (as per layout)
 7. Walkways
 8. Foundation hardware
 9. Special tools & tackles (including special tools Rotor removal pads, hydraulic wrench, alignment gauges) (one set for the project).
 10. Startup and commissioning spares.
 11. Off-base compressor cleaning and washing skid for off-line/on-line cleaning (one number for the project).
 12. Boroscope kit (One number for the project).
-

-
13. Mobile Lube oil centrifuge - 1000 LPH (One number for the project).
 14. Lube oil drain pump (capacity - 2 m3).
 15. Steam injection for NO_x control upto 65 ppmvd @ 15% O₂ for Liquid fuel and 50ppmvd @ 15% O₂ for Natural gas fuel.
 16. Diaphragm type load coupling
 17. Load gear box between GT & Generator with duplex thermocouple for LGB bearings
 18. Hitec dosing skid for Naphtha
 19. 2 nos accumulators for Naphtha and HSD in common line (with online diagnostic facility).
 20. Fuel flow measurement (micro motion) for both liquid fuel and natural gas fuels
 21. Fuel drain tank 2m³ with 2x100% drain pump
 22. All Naphtha, HSD, DM water & cooling water, instrument air, service air piping within battery limits
 23. Motorised 3-way valve for naphtha / HSD change over
 24. Bently Vibration Monitoring system 3500 & System -1.
 25. First fill of lube oil and detergent for 2 nos GTG Packages.
 26. 1 no. Cooling water module for black start GT.
 27. 1 no. Training Simulator common for 2/3 GTs.
 28. 1 no. Performance Monitoring Package
 29. Marshalling Panel for Mark VI-e Control System
 30. Radar Type Transmitters

B) LIST OF GENERATOR & ITS AUXILIARIES PER UNIT TO BE ERECTED, TESTED & COMMISSIONED :

1. Closed circuit air cooled Generator (VPI) suitable for outdoor-Installation, consisting of
 - Stator with output leads at the top {3 ph + 3 N} of the machine.
 - Rotor suitable for Overhang BLE
 - Bearings, base frame, built in RTDs
 - Space heaters with controls
 - Side mounted Air to water coolers with {n+1 }cooler elements.
 - Liquid level detector
 - Enclosure for Generator
 - Walkway
 - 1 No. Air Gap Flux probe with common reader.
2. Overhang Brushless Exciter and PMG along with portable stroboscope.
3. Generator Auxiliary Compartment (GAC) comprising of CTs, PTs, LA & SP eqpt.
NGT with secondary loading resistor and cable termination facility for onward connection of HT cables, HT Power cables are not in scope of supply.
4. Generator simplex vertical control panel and multifunctional microprocessor based numerical relay panel with protections for generator and generator transformer. 1 No. redundant multifunctional relay for generator protection and Generator transformer protection. (Relay test kit is not envisaged)
5. Interconnecting control cables for connection between generator and generator control and relay panels as per layout.
6. Digital Automatic Voltage Regulator.
7. Fire detection and CO2 protection including for Exciter compartment

NOTE: The Auto synchroniser is an integral part of the MARK-VI-e control of the Gas Turbine.

C) LIST OF C&I EQUIPMENT PER UNIT TO BE ERECTED, TESTED & COMMISSIONED :

1.0 Gas Turbine Control System {Mark VI-e) comprising of (per unit)

- Turbine governing and protection system Auto run up, start, synchronizing, block loading & safe auto shutdown system (suite of two panels) - 1 Set
- Mark-Vie HMI station (OWS cum EWS) - 2 Nos
(With single 22" TFT monitors)
- LaserJet printers, A4 size (one each for each OWS/EWS) - 2 Nos
- Fibre Optic NET between local control compartment & remote (main) control room, as per layout.
- Multi-unit control functions in the remote HMI OWS.
- Redundant GSM link to plant DCS
- Dual IRIG-B interface for time synchronization
- Redundant historian (common for 2/3 GTGs) - 1 No

2.0 EXCITATION Systems:

- Digital Automatic Voltage Regulator (Dual Auto with built in Manual channel) - 1 No

3.0 MASTER CLOCK (common for 2 GTGs)

- Master clock system with 10 Nos - 1 Set
- Slave clocks (100 mm digital display units)

4.0 DIGITAL BRUSHLESS EXCITATION SYSTEM

Digital automatic voltage regulator equipment with Dual Auto Channel will comprise of the following features:

- Auto Channels (Two)
- Terminal voltage control of generator in closed loop
- Over excitation limiter

-
- Under excitation Limiter
 - Stator current limiter
 - V/Hz limiter
 - Reactive drop compensator
 - Power system stabilizer
 - COMMON CIRCUITS
 - A Follow-up circuit for a smooth changeover from one channel to the other
 - Main exciter field suppression circuit
 - Programmable logic controller for sequential operation control

SIGNAL EXCHANGE WITH DCS/GCP: Hardwired (about 20 Points)

WEIGHTS & DIMENSIONS OF ABOVE EQUIPMENT ARE GIVEN IN ANNEXURE-1.

CHAPTER-11
TENTATIVE WEIGHT DETAILS & DIMENSION OF EQUIPMENT/SYSTEM
For Tentative weights & dimensions of items to be erected refer Annexure-1

NOTE :

1. Apart from the above erection inputs also find attached the following tentative input Plot plan(Annexure-5).

Bidder is requested to be aware of the various fronts interconnected with Gas turbines by referring the above drawings.

2. The information furnished in this Annexure- 1 is only a description regarding the item to be erected by the contractor. BHEL reserves the right of adding or excluding any components / items / system according to the site requirements / customer requirements to complete various systems in all respects. Any other systems / components, quantities which are the integral to equipment supplied by the manufacturing unit also to be erected and commissioned by the contractor within the quoted / accepted rate / lump sum value.
3. The dimensions, weights, quantities for scope of works are tentative. The works for complete scope as per site, systems/schemes and drawing requirement shall be carried out within accepted lump sum price. Unit rates in price format (Volume-I E) shall be used for calculating the final amount of piping/cabling and payment to bidder shall be governed by the clause 2.13 of GCC.

Part-II: Technical Specifications

CHAPTER-1 GENERAL

1.1

All the work shall be carried out as per the instructions of BHEL engineer. BHEL engineers decision regarding the correctness of the work and method of working shall be final and binding on the Bidder.

1.2

The Bidder shall at his cost perform any services, tests etc, although not specified but nevertheless required for the completion of work.

1.3

The work shall conform to dimensions and tolerances specified in the various drawings, documents etc. That will be provided during the course of installation. If any portion of the work is found to be defective in workmanship or not conforming to drawings or other specifications, the Contractor shall dismantle and re-do the work duly replacing the defective materials at his cost failing which the work will be got done by BHEL at the cost and risk of the contractor.

1.3

The terminal points as decided by BHEL shall be final and binding on the Contractor.

1.4

The indicative schedule of weight of major equipment given in Part-1,Chapter-11 are meant for providing a general idea to the Contractor about the magnitude of the work involved.

1.5

During the course of execution of this work, certain rework/ modification/ rectification/ repairs/ fabrication etc. will be necessary on account of feedback from various power plants already commissioned and/or units under erection and commissioning and also on account of design discrepancies and manufacturing defects and site operation/maintenance requirements. Contractor shall carryout such rework/ modification/rectification/fabrication/repairs etc., promptly and expeditiously. Daily log sheets indicating the details of work carried out, man hours, consumables used etc, shall be maintained by the Contractor and got signed by BHEL engineer every day. Claims of contractor, if any, for such works will be dealt as per clauses of Section-2.15 of General Conditions of Contract.

1.6

All tools and tackles, fixtures, equipment, materials, manpower, supervisors/ engineers, consumables etc. required for this scope of work shall be provided by the Contractor. All expenditure including taxes and incidentals in this connection will have to be borne by him unless otherwise specified in the relevant clause.

1.7

The contractor shall make adequate security arrangements including employment of security personnel and ensure protection from theft, fire, pilferage, damage and loss of materials/equipment issued to him for the work. Special care will have to be taken to guard against pilferage / theft of copper tubing, brass fittings, brass valves and other costly materials.

1.8

All equipment shall be handled very carefully to prevent any damage or loss. No bare wire ropes, slings etc, shall be used for handling of the equipment without the specific permission of the engineer.

1.9

Contractor shall ensure proper housekeeping and remove all scrap materials periodically from various work area covered in the scope and deposit the same at the place earmarked for this purpose. In case of contractor's failure to do the same, BHEL reserves the right to remove scrap at contractor's cost and risk.

1.10

Access to site for inspection by BHEL and customer engineers shall be made available by the contractor at all times.

1.11

Contractor shall mobilize sufficient quantity of sleepers for stacking of materials in his custody.

1.12

Contractor to note that all the erection procedures/erection Quality Plan and other erection documentation has to be approved by BHEL/RUPPL prior to erection.

1.13

Bidder to indicate the space required for fabrication yard (both open & closed) in the offer.

1.12 COLLECTION AND RETURN OF EQUIPMENT, MATERIALS & CONSUMABLES

1.12.1

Contractor shall take delivery of the components, equipment, lubricants, chemicals, special consumables, steel etc from the storage yard/stores/sheds of BHEL/ client. The Contractor should note that the transport of equipment to erection site, assembly yards etc should be done by the prescribed route, without disturbing the other works and contractors and in the most professional manner. Special equipment such as laboratory equipment, measuring and controls equipment, special electrodes, valves, shims, packing materials for joints and seals, lubricants,

actuators etc, shall be stored, when taken over by the Contractor, in appropriate manner as per BHEL's instructions.

1.12.2

The contractor shall return all parts, materials, consumables etc. remaining extra over the normal requirement with proper identification tags to BHEL stores. In case of any misuse or use over actual requirement, BHEL reserves the right to recover the cost of parts/materials used in excess or misused, with departmental charges.

1.12.3

Transportation of Spares, lube oil, Chemicals, Gas cylinders etc. from stores is included in the scope of this contract. The contractor shall have to return all the empty and excess drums to the customer/BHEL stores. Similarly, transport of chemicals for various pre-commissioning activities/ processes mentioned in clauses herein from BHEL/customer's stores and charging of chemicals into the system for carrying out various pre-commissioning activities and processes mentioned herein and returning of remaining and/or the empty containers of the chemicals to customer/BHEL stores is the responsibility of contractor. After completion of oil flushing operation, the used oil shall be filled in empty drums and which in turn shall be returned to BHEL/customer's stores.

1.13

Installation and welding of Tapping Points for taking performance test measurements shall be carried out by the contractor as part of this work for the equipment covered under this tender specification under the guidance of BHEL engineer. The scope will be limited to all the tapping points for which materials are available and their locations identified within the regular contract period and extensions thereof.

1.14

All packing and forwarding material shall be returned as soon as the material is unpacked. The location for storage of such materials shall be as indicated by BHEL Engineer.

1.15

Contractor shall furnish the consumption details of chemicals, lubricants, TIG welding filler wire, welding electrodes and other consumables on monthly basis.

1.16

The terminal points decided by BHEL should be final and binding on the contractor for deciding the scope of work and effecting payment for the work done.

1.17

The work shall conform to dimensions and tolerances specified in the various drawings / documents that will be provided during various stages of erection. If any portion of work is found to be defective in workmanship, not conforming to drawings or other stipulations due to contractor's fault, the contractor shall dismantle and re-do the work duly replacing the defective materials at his cost, failing which the work will be got done by BHEL and recoveries will be

effected from the contractor's bills towards expenditure incurred including cost of materials and departmental overheads of BHEL.

1.18

The contractor shall perform any services, tests etc. Which may not be specified but nevertheless required for the completion of work within quoted rates.

1.19

All cranes, transport equipment, handling equipment, tools, tackles, fixtures, equipment, materials, manpower, supervisors/ engineers, consumables etc required for this scope of work shall be provided by the contractor. All expenditure including taxes and incidentals in this connection will have to be borne by him unless otherwise specified in the relevant clauses. The contractor's quoted rates should be inclusive of all such contingencies.

1.20

All works such as cleaning, leveling, aligning, trial assembly, dismantling of certain equipment / components for checking and cleaning, surface preparation, fabrication of sheets, tubes and pipes as per general engineering practice and as per BHEL engineer's instructions at site, cutting, gouging, weld depositing, grinding, straightening, chamfering, filing, chipping, drilling, reaming, scrapping, lapping, fitting up etc., as may be applicable in such erection works and which are treated incidental to the erection works and necessary to complete the work satisfactorily, shall be carried out by the contractor as part of the work within the quoted rates.

1.21

The contractor shall make all fixtures, temporary supports, steel structures required for jigs & fixtures, anchors for load and guide pulleys required for the work. BHEL will not provide any steel for this.

1.22

Plant materials should not be used for any temporary supports / scaffolding / preparing pre-assembly bed etc.

1.23

The details of equipment to be erected under this contract is generally as per the details of quantity given in Chapter-10. These details are approximate and meant only to give a general idea to the tenderer about the magnitude of the work involved. Actual quantum and type of equipment will be based on the erection documents which will be furnished in the course of erection and the weight and quantity as per the relevant engineering documents will only be admissible for the billing purpose.

1.24

All works such as cleaning, levelling, aligning, hot alignment, trial assembly, dismantling of certain equipment/components for checking and cleaning, surface preparation, fabrication of sheets, tubes and pipes as per general engineering practice and as per BHEL engineer's instructions at site, cutting, grinding, straightening, chamfering, filling, machining, chipping,

drilling, reaming, scraping, lapping, shaping, fitting-up, drilling of holes, making dowel pins, minor rectification of foundation bolts etc. are incidental to the erection/commissioning and any other work/activity which is necessary to complete the work satisfactorily, shall be carried out by the contractor as part of the work.

1.25

Cleaning, servicing, lubrication of actuators, pumps, headers, control valves, other valves, tanks, vessels etc. during erection and commissioning stages is in the scope of work. However, gaskets/packings for replacement will be provided by BHEL free of cost.

1.26

All equipment shall be preserved and protected periodically before and after erection as per advice of BHEL engineer. All bearings of turbine rotors, generator rotor, and other rotating machines shall be thoroughly cleaned, greased/painted with preservative agents periodically as instructed by BHEL engineer.

1.27

All racks or assembled units like Gas Unit, Seal Oil Valve Rack, Gas Cylinder Racks etc supplied from manufacturing units will be tested in BHEL/ Customer stores or at site. This may require transportation, filling of oil, water etc in these racks for carrying out testing of these racks. Defects noticed during testing of these racks will have to be rectified by the contractor free of charges. Further, any pipeline / flanges / fittings not found assembled properly, the same have to be rectified / corrected by the contractor free of charges.

1.28

All the materials during pre-assembly, storing shall be stored well above ground level as necessary to avoid water ingress etc, by use of wooden/ concrete blocks/ sleepers. No material shall be stored directly on the ground at any time. Concrete blocks/ Sleepers have to be provided by the contractor.

1.29

The contractor shall carry out any other tests as desired by BHEL engineer on erected equipment covered under the scope of this contract during testing, pre-commissioning and commissioning, to demonstrate the completion of any part or whole of work performed by the contractor.

1.30

After chemical cleaning/pickling of lubricating system (including oil piping, oil tank and other fittings) of rotating machines, oil flushing for lubricating systems as per instructions of BHEL engineer shall be carried out. Cleaning of oil tank of lubricating oil system of GTG set, rotating machinery and other system as per scope of tender specification before and after oil flushing is in the scope of work.

1.31

Transportation of oil drums from customer's/BHEL's stores, filling of oil for flushing, first fill of lubricants and subsequent topping up during commissioning and post commissioning is included in the scope of this contract. The contractor shall have to return all the empty drums to the customer/BHEL stores. Similarly, for various pre-commissioning/ commissioning activities/ processes mentioned in various clauses, transport of chemicals from BHEL/customer's stores, charging of chemicals into the system and returning of remaining and/or the empty containers of the chemicals to customer/BHEL stores is the responsibility of the contractor.

1.32

No BHEL crane will be available under this tender specification for erection of Gas Turbine, Gas Turbine Generator, Bypass Stack, Feed Storage Tanks or any other equipment. Contractor shall take specific note of this aspect and shall arrange all necessary T&P and lifting/handling/transportation arrangements for placement on required foundation/elevation, erection of equipment including the heavier consignments/equipment like gas turbine, gas turbo-generator, GT inlet ducts, GT off base enclosure, Filter unit of GT, Feed storage Tanks etc.. Gas Turbines and Gas Turbine Generators shall be required to be lifted by suitable capacity Crane/ jacks & support structure etc. to take minimum possible time in lifting and placement then on respective foundations. The contractor shall take specific note of same and shall arrange required arrangements as per site requirement.

1.33

For any class of work for which no specifications have been laid down in these specifications, work shall be executed as per the instructions of BHEL & suit the site requirement.

1.34

The contractor shall perform all required services which may not be specified herein but nevertheless required for the completion of work within quoted rates.

1.35

All cranes, transport equipment, handling equipment, tools, tackles, fixtures, equipment, manpower, supervisors/engineers, consumables (excluding those indicated as BHEL scope), etc required for this scope of work shall be provided by the contractor and shall conform to Safety Requirements/ Load Testing etc. as per BHEL/RIL rules & Regulations at site.

1.36

All expenditure including taxes and incidentals in this connection will have to be borne by the contractor unless otherwise specified in the relevant clauses elsewhere here. The contractor's quoted rates shall include of all such contingencies. In this connection refer relevant clause of general conditions of contract.

1.37

The contractor shall take due precaution during Materials Handling and Erection, testing & commissioning of equipment/works under these specifications to avoid deface, injure, damages, destruction by contractor or his workmen or servants to any pipelines, railway lines, roads,

canals, cables, culverts, drains, sewer, telephone & telegraph lines, water mains, dykes, poles, pillars, fences, wires, supports and embedment's and other underground or over ground works, Structural or constructions whatsoever and shall at his own cost and initiative forthwith restore and repair any damage thereto the entire satisfaction of customer/BHEL at his own expense or in default, the customer/ BHEL site engineer may cause the same to be made good by other agency or by other means and deduct the expense with BHEL overhead (of which the site engineer's decision is final) from any sums that may be then or at any time thereafter become due to the contractor or from his security deposit or any other money due.

1.38

As such, the marine cover and erection all risk cover insurance for the project for permanent incorporation of materials and services at site lies with customer. The contractor shall have to take necessary all risk insurance policy (motor vehicles act, worker's compensation act, fatal accidents act, personal injuries insurance act, emergency risk insurance act and/or other industrial legislation from time to time India with insurance company(ies) approved by owner) **for his manpower and his employees deployed at site under work compensation act including but not limited to third party insurance at RUPPL- Dahej project along with his T&Ps before starting of the work and shall submit the necessary document/policy in support of above to BHEL/customer at site. This will be also essential for taking the gate pass/entry pass etc. from customer & their related departments/security at site. The insurance policy taken shall be kept in-force till completion of contract. The workmen's compensation insurance and third party insurance liability limits shall be as customer specification. Contractor shall indemnify the customer RUPPL/ BHEL harmless against such losses, which are on account of contractor.**

1.39

Recoveries will be made from contractor's bills for any liability accrued to BHEL/RIL for the accidents and refund of the same shall be considered later, after the claim is fully settled by insurance authorities.

1.40

Customer has taken the marine cover and erection all risk cover insurance for the project for permanent incorporation of materials and services at site. However contractor shall take all due precautions, arrange & follow the safety & security requirements/regulations for materials issued to him & works under his execution and shall be responsible for safety & security of these materials & works for any loss or damages. For any damage / loss to the material during inland transportation, storage, erection, final testing, commissioning stage etc., contractor shall intimate promptly to BHEL/customer and shall prepare & submit the necessary detailed report / documents / information, facilitating inspection / discussions by the officials / surveyors deputed by insurer with all expenditure on contractor's account. Contractor shall take care for timely information for conducting survey, submission of monetary estimate & furnish the requisite

documents to surveyors/insurer, taking necessary precautions so that the loss/damage is not aggravated further, protecting damaged goods etc. As part of scope of work.

Contractor shall promptly make repair / rectify/replace and make good any damage or loss to RUPPL/BHEL materials and works on above account as per instructions of BHEL engineer incharge at site without any delay & waiting for settlement of insurance claim from insurer. Contractor's claim (if any) for such works will be settled as per applicable item rate of contract after settlement of claim from insurer / customer & after ascertaining / establishing that contractor is not responsible for such loss or damages. The contractor's claim for such repair / replacement shall not be more than the payment settled by insurer / customer and in such case the contractor's payment will be limited to seventy percent of settled amount by insurer/customer against claim amount.

1.41

The contractor shall submit survey report/performance report of the tools and plants deployed by him and being utilized on the work under the scope. These survey reports/performance reports are to be obtained by contractor from the customer of BHEL/insurance authorities and submitted to BHEL at no extra cost.

1.42

Contractor shall deploy & maintain, the separate exclusive workforce / manpower arrangements and T&Ps resources including the Cranes & heavy lift equipment /arrangements for Material Handling and Erection & Commissioning scope of works.

1.43

All vehicles/ electrical motors devices shall have to be provision of fire extinguisher/muffler facilities etc.

1.44

Contractor shall provide FIRST AID / emergency medical facilities & Emergency Vehicle facilities at project premise/work site to meet any exigency / emergency requirement and shall maintain these facilities throughout the contract period & extension period (if any) as scope of work.

1.45

The equipment/systems/piping/components under these specification shall require to connect / hookup with other systems / equipment / piping / components / terminal points etc. of Customer / other erection vendors. Contractor shall carry out the termination of these systems / equipment / piping with customer/other vendor's terminal points and shall involve welding, bolting/flange joints, cutting, edge preparation, radiography, NDE etc. of terminal point systems (which may not be included in these specifications and may have been erected by other vendor) shall be carried out by contractor as per instruction of BHEL engineer at site including welding / bolting of counter/matching flange joints as scope of work. Decision of BHEL engineer shall be final and binding on contractor.

1.46

As such the external barricading of project plot area will be carried out by civil agency as scope of civil works. Contractor under these specification shall carry out his internal barricading/ cordoning off (as applicable) of area of his operations, providing safety nets, safety tapes, passenger trolley for high height working etc. as per safety requirements/safety concern and regulations enforced by RIL/BHEL at site before under taking the day-to-day works. All such works/arrangements shall be carried out by contractor as scope of work.

1.47

For structures, supports, stairways, platforms, galleries, hand rails, grills, etc. the structural materials may be supplied in random length which may have to be cut to required profile in order to suit the requirement a incidental to the work. Also it may sometimes be necessary to remove some of the erected members to facilitate erection of bigger / pre-assembled equipment. In such cases, the removal and re-erection of such works as agreed by BHEL Engineer will have to be done by contractor as incidental to work.

1.48

All the handrails and toe guards shall be provided as per drawing and safety requirements. After cutting the floor grills to suit the site condition, the cut edges shall be painted with two coats of cold galvanizing paints conforming to Indian Standard.

1.49

For any items or class of work not specified herein but required for total completion of work, the same shall be carried out as per BHEL requirement. However, payment of these items/class of work shall be regulated on the basis of rate arrived at by either of the following methods:

- a) Based on rate of identical/similar items in the rate schedule.
- b) Based on the rate arrived from nearby items in the rate schedule.

Wherever any item rate for similar type of work or nearby item rate does not exist in the rate schedule, rate will be worked out on the basis of work element or from fundamentals of estimation.

CHAPTER-2 CIVIL WORKS, FOUNDATION, GROUTING

2.0 PREPARATION OF FOUNDATION AND GROUTING

2.1

Buildings, foundations and other necessary civil works for supporting structures, equipment etc, will be provided by the customer. The checking of dimensional accuracy, axes, elevation, levels etc, with reference to bench marks of foundations and anchor bolt pits and also adjustments of foundation level, dressing and chipping of foundation surfaces of all equipment contractor/BHEL shall prepare protocols before taking over the foundations. Dressing and chipping of foundations up to 25mm for achieving proper levels will be within the scope of contractor.

2.2

All minor foundations and anchor points required for installing erection equipment like winches, anchors etc. are to be cast by the contractor.

2.3

The complete work of Secondary Grouting of equipment is included in the scope of contractor. Contractor shall arrange all grouting material, manpower; T&P, formwork and shuttering materials.

2.4

Cleaning of the foundation surfaces, pocket holes, anchor bolt pits and de-watering and making them free of oil, grease, sand and other foreign materials by soda washing, water washing, compressed air and other approved methods will be within the scope of this work.

2.5

BHEL will provide only shims and packer plates (either machined or plain), which are received from BHEL's manufacturing plants and go as permanent part of the equipment. Additional packer plates and shims if required will have to be prepared by the contractor out of steel plates, steel sheets to meet site requirements.

2.6

The contractor shall carry out scrapping and matching of embedded plates, permanent spacers and all the matching parts of turbine, generator, pumps and other equipment under scope wherever required. The support and sole plates matching and concrete surface bedding is also covered in the scope of work. The fine dressing of concrete shall be with Prussian blue-match checks.

2.7

Packer plates shall not only be blue matched with foundations but also inter-packer contact surfaces, contact surfaces between packer and pedestals, contact surface between packer and

foundation frame etc. shall also be blue matched and required percentage contact shall be achieved by chipping and scrapping as per engineer's instructions.

2.8

Buildings, foundations and other necessary civil works for supporting structures, equipment etc, will be provided by the BHEL/customer. The checking of dimensional accuracy, axes, elevation, levels etc, with reference to bench marks of foundations and anchor bolt pits and also adjustments of foundation level, dressing and chipping of foundation surfaces of all equipment contractor/BHEL shall prepare protocols before taking over the foundations. Dressing and chipping of foundations upto 25mm for achieving proper levels will be within the scope of work/specification.

2.9

All minor foundations and anchor points required for installing erection equipment like winches, anchors etc. are to be cast by the contractor.

2.10

The complete work of secondary grouting of equipment including grouting material supply is in the scope of work/specification. Contractor shall arrange all manpower, T&P, form work and shuttering materials, all grouting materials such as ordinary Portland cement, sand, stone chips etc & quick-setting-non-shrink-free-flow special grout mix of required specification (like conbextra-gp-2 or equivalent).

2.11

The quick-setting-non-shrink-free-flow special grout mix shall be purchased only from the following BHEL approved vendors:

1. M/S FOSROC CHEMICALS (INDIA) PVT LTD;
2. M/S SIKA INDIA PVT LTD;
3. M/S PAGEL CONCRETE TECHNOLOGIES PVT LTD;
4. M/S PIDILITE INDUSTRIES LTD.

In order to ensure the quality, the major grouting of equipment using any of above grout mixes shall essentially be done as per the recommendations of supplier with regard to grout preparation and use of machinery etc under the supervision of the respective supplier. BHEL has arrangement with above suppliers for supervision services and the supervision charges for the same will be borne by BHEL. However, the contractor shall ensure readiness of equipment for grouting in all respect before such a service is requisitioned and the duration is not prolonged unduly. Any overstay required due to contractor shall be charged to the contractor with BHEL's departmental charges. Contract shall consult BHEL engineer before deciding upon the vendor for the above.

CHAPTER-3

EQUIPMENT INSTALLATION - MECHANICAL

3.1

Erection of GT with aux, diverted dampers, guillotine dampers, Bypass stack, Common System Equipment and Balance of plant Equipment with other related equipment & auxiliaries at site is in the scope of work.

3.2

For the skid mounted equipment, the checking and realignment required at site is in the scope of work.

3.3

Components like generator auxiliary compartment, load gear and enclosures etc received loose are to be erected in position by contractor.

3.4

Air filter, inlet ducting, exhaust ducting will be supplied in individual assembled sections with inside insulation. Site job involves complete assembly and erection.

3.5

Water wash skid shall involve welding of stainless steel pipe from skid to the GT. The piping shall be site routed. The contractor shall complete the job within quoted rate.

3.6

Ducts, enclosures and other fabricated/pre-fabricated parts/ components etc. have to be checked for dimensional accuracy, configuration, proper matching and minor rectifications, wherever necessary will have to be done before erection. This will involve making appropriate bed of steel structures over the concrete locks. Steel, in random sizes, for this purpose will be provided by BHEL from the packing materials / scraps etc., where as necessary concrete blocks shall be arranged by the contractor. Bed shall be fabricated as per requirement. These shall be dismantled & returned to BHEL at appropriate stage. No separate payment for making / dismantling such bed is envisaged.

3.7

Any fixtures, concrete block supports, steel structures, required for temporary supporting for pre-assembly or checking and welding for lifting and handling during pre-assembly and erection shall be arranged by the contractor.

3.8

It shall be the responsibility of the contractor to provide temporary ladders on columns, Bypass Stack, Ducting etc in a manner prescribed by BHEL using their own material till such time as permanent stairways are completed.

3.9

Welding of all attachments on casing, non-pressure parts, pressure parts/ piping , equipment, tanks, vessels etc. including those required for insulation work is in the scope of work.

3.10

Ducts / expansion bellows are normally supplied in loose wall plates / segments and these are to be assembled and welded at site before erection. All joints connecting ducts, expansion pieces and dampers shall be seal welded. These welds have to be tested by LPI and made leak proof as per technical instruction / requirement.

3.11

Certain structural items like silencer supports, roof cladding structure, platform etc., will be supplied in running lengths which shall be cut to required suitable sizes and adjusted/trimmed as part of work.

3.12

The platforms of permanent nature for approaching different equipment like actuators, valves, instruments etc. as per site / BHEL client's requirements, which may not be indicated in drawings, but essential for safe access, shall be made by the contractor from structural steel / materials supplied in random lengths / sizes as per scope of work as per instruction of BHEL Engineer at site.

3.13

Contractor shall provide the following for GTG, Common System Equipment and Balance of plant equipment and other related equipment with auxiliaries' erection:

- ❖ Temporary bolts of required size for honing of generator coupling
- ❖ Spanner & torque wrench/bolt stretching device for Tightening of load and accessories coupling bolts.

3.14

Rain hood protection shall be provided for the equipment e.g. Fuel/HSD, Naphtha forwarding skid and other skids etc. located outside/ in open space as per drawings & instructions .

3.15

The Bypass Stacks will be supplied in pre insulated loose ducts / sections and have to be assembled / erection at site involving welding, bolting, tack welding, insulation at joints ,work and erection of Aviation Light and lightning arrestor. All these works are covered under the scope of work of contractor under these specifications.

CHAPTER- 4 PIPING INSTALLATION

4.1

The scope of work in piping system (air, Gas, Water, Oil, Steam etc.) will include cutting to required length, edge preparation, laying, fixing and welding of the elbows/fittings/valves etc., fixing supports/hangers/shock absorbers/ guides and restraints etc. and carrying out all other activities/works to complete the erection and also carrying out all pre-commissioning/ commissioning operations mentioned in these specifications as per BHEL engineer's instructions and/or as per approved drawings. **Weld joints and NDT requirement for all GTG Integral piping and other piping as applicable under tender specification shall be as per drawings/schemes and suiting to site requirement. The necessary drawings/documents for these weld joints will be provided at site during execution of work.**

4.2

Piping weight indicated in Chapter-11 includes Off base pipings with valves/fittings, supports and all other piping schemes like fuel, gas, instrument air & service air, cooling water, service water piping, potable water piping, underground / buried piping(if any), process air/n2 piping etc. (excluding GTG sets integral piping) for GTG, and balance of plant equipment / systems & related auxiliaries. Contractor shall carry out the erection and complete the piping works of respective system as per sequence, schedule and program decided by BHEL engineer/customer at site in order to achieve the commissioning schedule of respective equipment/ systems and over all commissioning schedule of project as whole.

4.3

Carrying out of piping as per the specifications between equipment constituting terminal points, whether the terminal equipment fall within the scope of the work/specification or not, is within the scope of the work/ specification. The contractor shall complete terminal joints at either ends, with due NDE & PWHT if applicable, for all the piping schemes covered in the scope of work.

4.4

Fit up and welding/bolting/fastening of piping to the terminal points (such as stubs, valves, flanges on terminal points/equipment, stubs on headers, battery limits etc) forming part of the scope of work/specification and stress relieving and radiography of joints so made are also within the scope of work. Permanent fasteners and gaskets will be supplied by BHEL.

4.5

Interconnection/ Hook-up, if any, with the existing system shall form part of work. Such interconnections, hook-ups may require shut down of running plant and the relevant work has to be completed within such planned shutdowns. This may call for working with enhanced resources and on extended hours. Contractor's offer shall cover all such contingencies.

4.6

All drains / vents / relief / escapes / safety valve piping to various tanks/ sewage / drain canal / sump / atmosphere etc. from the stubs on the piping and equipment erected by contractor is completely covered in the scope of this tender specification.

4.7

As far as possible pre-assembly shall be done. The pipe laying shall be carried out from the available terminal point/points or any other area between the terminal points. The erection can be carried out on temporary supports to obtain proper alignment and welding. After fixing the permanent supports, all the temporary supports shall be removed. The alignment, distances and loading of the supports shall be checked and the required settings to be ensured as per requirement.

4.8

All welded joints should be painted with anticorrosive paint immediately after completion of radiography and stress relieving works. Necessary paints and other consumables for the above work are in the scope of the contractor.

4.9

Spring suspension/constant load hangers may have to be pre-assembled for required load and erection carried out as per instructions of BHEL. Adjustments, removal of temporary arrests/locks, cutting of excess thread length of hanger tie-rod etc., have to be carried out as and when required. Load setting of spring hangers, as per BHEL's documents/ instructions, during various stages of erection & testing and after floating of piping/ducting during cold and hot condition will have to be done. This exercise may have to be repeated till satisfactory results are achieved.

4.10

Layout of field routed/ small bore piping shall be done as per site requirement. Necessary sketch for routing these lines should be got approved from BHEL by the contractor. There is a possibility of slight change in routing the above pipe lines even after completion of erection. Such changes will be incidental to work hence no separate/ additional payment will be made.

4.11

Normally the high pressure valves will have prepared edges for welding. But, if it becomes necessary, the contractor shall prepare new edges or recondition the edges by grinding or chamfering to match the corresponding tubes and pipes. All fittings like "T" pieces, weld neck flanges, reducers, etc., shall be suitably matched with pipes for welding (this is applicable to piping work also).

4.12

Hydraulic / pressure testing of pipelines, wherever called for, shall be conducted as part of work till satisfactory results are obtained.

4.13

Connection (flanged, bolted, welded) of piping to the terminal points/equipment etc. is in the scope of work even though such terminal point/equipment may not form part of this work. All NDE including radiography of joints so made, post-weld-heat-treatment if any, is also within the scope of work/specification. The terminal points work is inclusive of cutting of existing lines, edge preparation, welding/blanking and hook up work.

4.14

It should be ensured that all the terminal point connections are done without transferring any undue load or strain to the other equipment. Necessary protocols have to be prepared for such fit-up alongwith BHEL /customer representative before connecting. All NDE including radiography of joints so made, post weld heat treatment if any, are also within the scope of work / specification.

4.15

The non-IBR piping will be sent as plain pipes. The attachments for tapping points and / or supports will be sent as loose items. Site work will involve fabrication, drilling, fitting, pre-heating, welding, NDE & PWHT as per applicable BHEL documents. Rate quoted shall take account of all these work as no separate payment is envisaged for such work.

4.16

For integral piping all attachments etc will be supplied as loose items and are to be welded to the main pipes at site as per instructions. Necessary drilling of holes on main pipe for welding stub shall also be done at site by the contractor.

4.17

Underground / buried piping (if any) shall involve rapping & coating protective coating as per drawing requirement. Erection, laying, welding, Rapping & Coating of this pipe shall be carried out and payment for all such work shall be paid as applicable carbon steel piping erection & commissioning.

4.18

The following items of work shall be incidental and forming part of piping fabrication and erection:

- (1) To locate cause of vibrations in equipment/auxiliaries/pipelines and carrying out necessary corrections in case the same is attributed to the contractor.
- (2) Fabrication and erection & welding of racks, steel supports, guides, restraints for all the piping. Steel for this purpose will be supplied by BHEL free of charge in random and running lengths.

-
- (3) Pre-assembly of spring suspension/hangers and shock absorber as per requirement.
 - (4) Erection of steam traps, filters, flow nozzles/ flow indicators/ flow orifices other measuring elements in the piping. These may have been supplied either by BHEL or their customer. This may involve cutting of pipe lines, fresh edge preparation and welding with stress relieving wherever applicable.
 - (5) Fabrication / making of bends for pipes and tubes of diameter upto 65mm.
 - (6) Matching of all fittings like tees, bends, flanges, reducers valves, socket fittings, etc with pipes for welding.
 - (7) Servicing of valves, Power Cylinders and actuators etc.
 - (8) Cleaning of all pipes by chemicals/wire brushing / blowing by compressed air.
 - (9) Welding of root valves with small length of piping to the pressure, flow and level tapping points on piping or flow nozzles/orifices/metering/ measuring elements fixed on piping.
 - (10) welding of blanks with stress relieving if required on a temporary basis.

4.19 SERVICE & INSTRUMENT AIR PIPES

4.19.1

Laying of S.S. /G.I. Pipes with fittings and supports of instrument air lines/process air shall include air blowing, hacksaw / cutting from running length to the size, threading, welding, installation of isolation valves, headers, root valves, moisture traps, check valves, supports and clamps etc by providing the required consumables shall be carried out by contractor.

4.19.2

Line shall be provided with proper slope as per drawing / standards and shall be supported at recommended pitching.

CHAPTER-5

WELDING, HEAT TREATMENT, RADIOGRAPHY AND INSULATION

5.1

The method of welding (viz) arc, TIG or other method will be indicated in the detailed drawing/documents. BHEL engineer will have the option of changing the method of welding as per site requirement.

5.2

Welding of high pressure joints shall be done by IBR certified high pressure welders who have been permitted by CIB of state concerned for deployment at the site of work.

5.3

Welding of all attachments to pressure parts, piping shall be done only by the qualified and approved welders.

5.4

All the welders (structural and high pressure) shall be tested and approved by BHEL engineer before they are actually engaged on work though they may possess the IBR/other certificate. BHEL reserves the right to reject any welder without assigning any reason.

5.5

Unsatisfactory and continuous poor performance may result in discontinuation of concerned welder.

5.6

Removal of welding slag and burrs by hand files, with brushes and/or flexible grinders will be carried out simultaneously.

5.7

The welded surface shall be cleaned of slag and painted with primer paint to prevent rusting, corrosion. For this consumables like paint etc will be in the contractor's scope.

5.8

Hp joint fit-ups, should be protected, where required, by use of tapes/protective paint as may be prescribed by BHEL. The contractor shall supply consumables like protective paints/tapes etc.

5.9

Preheating, inter-pass heating, post weld heating and stress relieving after welding are part of erection work and shall be performed by the contractor in accordance with BHEL engineer's instructions. Normally the electric resistance heating method will be adopted. Contractor shall arrange to supply heating equipment with automatic recording devices. Also the contractor shall have to arrange for labor, all heating elements, thermocouples and attachment units, graph

sheets, thermal chinks, & insulating materials like mineral wool, asbestos cloth, ceramic beads, asbestos ropes etc., required for all heating and stress relieving works.

5.10

All the recorded graphs for heat treatment works shall be the property of BHEL and shall be handed over to BHEL engineer when demanded.

5.11

The contractor shall maintain welding records in the form as prescribed by BHEL containing all necessary details, and submit the same to the BHEL engineer as required. Interpretation of the BHEL engineer regarding acceptability of the welds shall be final.

5.12

Heat treatment may be required to be carried out at any time (day and night) to ensure the continuity of the process. The contractor shall make all arrangements including labor required for the work as per direction of BHEL.

5.13

On all oil, instrument, gas, air (Instrument air/services air) piping, Cooling water Piping, etc. both TIG welding and subsequent arc welding or total TIG welding process is to be adopted as instructed by BHEL engineer.

5.14

All weld joints on piping shall be ground / filed / dressed on completion of welding and before NDE as per instructions BHEL engineer.

5.15

The Contractor shall procure all electrodes and filler wires of approved quality / brand as per the standards and specifications of BHEL and instruction of BHEL Engineer.

5.16

Contractor should purchase the electrodes as per the recommendations of BHEL engineer, welding manual, welding schedule and other relevant documents. The electrodes shall be purchased only from BHEL approved manufacturers.

5.17

The purchase of electrodes shall be accompanied by proper test certificate and these certificates should be submitted regularly for the scrutiny of BHEL engineer.

5.18

All electrodes shall be stored in a clean dry area. The storage room shall be of permanent nature and damp proof, and the room shall be exclusively meant for storage of welding electrodes and filler wires. Excepting for a vent in the top, it is not preferred to have any other opening like windows or ventilators. The temperature inside the room has to be kept in the range of 8-10⁰ c above atmospheric temperature and humidity should be less than 50%. This is to be

accomplished by using electric heaters or infrared lamps. The storage room must be provided with hygrometer and thermometer. Temperature and humidity are to be monitored regularly. 15-20 holders, welding cables, connecting cables to equipment and other welding accessories including temporary electrical connection from construction power point to individual equipment like winches, hoisting equipment, welding generators, transformers, heat treatment equipment and other construction equipment shall be arranged by contractor.

5.19

All racks and other items used for storage of electrodes shall be of steel and not of wood.

5.20

All electrodes soon after purchase shall be offered for inspection to the BHEL engineer. Contractor shall be strictly prohibited from using electrodes not inspected/approved by BHEL engineer.

5.21

All welding consumables shall be issued to the welders only by authorised person who is controlled by contractor's welding engineer. The necessary baking requirements are to be ensured by Contractor's welding engineer.

5.22

All welders shall be tested and approved by BHEL engineer/customer before they are actually engaged on work though they may possess the requisite certificate. BHEL reserves the right to reject any welder without assigning any reasons. Statutory requirements like IBR approval for welders are to be complied with before starting of the work. If required, the welders may have to undergo Procedure Qualification test also. The decision of BHEL Engineer will be final in this regard.

5.23

All charges for testing of contractor's welders including destructive and non-destructive tests conducted by BHEL at site shall have to be borne by the contractor. However for initial testing of welders the test will be provided by BHEL. However, If deployed welders fails in initial testing due to lack of experience OR frequent testing of new welders, due to non-availability/non-deployment of earlier qualified/tested welders, it shall be the responsibility of Contractor to provide necessary test plates at his cost for above testing.

5.24

BHEL engineer is entitled to stop any welder from his work if his work is unsatisfactory for any technical reason or if there is a high percentage of rejection of joints welded by him, which, in the opinion of BHEL engineers, will adversely affect the quality of welding though the welder has earlier passed the tests prescribed. The fact that the welders have passed the test does not relieve the contractor from his contractual obligations to check the performance of the welders. Contractor shall submit a monthly performance record of all welders.

5.25

All welded joints shall be subject to acceptance by BHEL engineer whose decision will be final and binding.

5.26

Pre-heating and stress relieving before and after welding are part of erection work and shall be performed by the contractor in accordance with instructions of BHEL engineer. Contractor has to arrange for the recorders along with accessories and suitable technicians for heat treatment purpose. The temperature recorders and thermocouples shall be duly calibrated. During preheat and stress relieving operations the temperature shall be measured as per the instructions of BHEL engineers by thermocouples and recorded graphs for the heat treatment works carried out shall be the property of BHEL.

5.27

For the purpose of stress relieving, thermocouples have to be attached to the weld joint. The number of temperature measuring points and locations are as per the standards of BHEL. Thermocouples have to be attached using battery operated portable thermocouple attachment unit and not by manual arc welding. Contractor shall arrange sufficient number of thermocouple attachment units.

5.28

Wherever necessary, contractor should provide temperature indicator/temperature recorder as required by BHEL engineer for measuring preheat temperature for welding or for controlling temperature of metal for hot correction etc. Decision of BHEL engineer on method and of checking preheat temperature or controlling temperature for hot correction and welding shall be final and binding on contractor.

5.29

Heat treatment may be required to be carried out at any time (day or night) to ensure the continuity of the process. The contractor shall make all necessary arrangements including labour required for the same as per directions of BHEL.

5.30

Heat treatment requirements shall be as per the Welding Schedules of BHEL

5.31

For weld joints of heavy structural items like beams, I-sections, if heat treatment is required, the same shall be carried out as part of the work.

5.32

Checking effectiveness of stress relieving by hardness tests (either by Poldi Hardness Tester or other approved test methods as per BHEL engineer's instruction) including necessary testing equipment is within the scope of the work/specification.

5.33

TIG welding process is to be used for all root pass welds in pipes. Subsequent welding after root pass can be carried out by manual metal arc welding with basic coated electrodes. For the pipe of thickness less than 6mm, the entire welding has to be carried out by TIG welding. However, BHEL site engineer will have the option of changing the method adopted. For manual arc welding shall be done as per weaving technique and the width of weaving shall not exceed 1.5 times of the dia of the electrodes.

5.34

Two pieces to be joined shall be individually checked for the weld edge preparation and profile dimensions and with respect to the template. Dye penetrant check shall be carried out on edge prepared surfaces at random. The percentage shall depend on piping system as specified by BHEL engineer.

5.35

Joint fit up will be a stage for inspection.

5.36

All joints shall be offered for visual inspection after root run. Subsequent welding should be made only after the approval of root run.

5.37 **SOCKET WELDING:**

5.37.1

In execution of this work, considerable number of socket weld joints is involved. The exact quantity of such socket welds or probable variation in the quantum cannot be furnished. The tenderer shall take notice of this while quoting as no extra claim on this account will be entertained at a later date. The socket welding on hp parts/ hp piping shall be done by the IBR qualified welders contractor has to adhere to the procedures/specification as indicated in the drawing for socket welding.

5.37.2

Welding electrodes have to be stored in enclosures having temperature and humidity control arrangement. This enclosure shall meet BHEL specifications.

5.37.3

Welding electrodes, prior to their use, call for baking for specified period and will have to be held at specified temperature for specified period. Also, during execution, the welding electrodes have to be carried in portable ovens.

5.38 RADIOGRAPHY

5.38.1

Radiographic inspection of welds shall be arranged by the contractor including all consumables like isotope camera, x-ray film, chemicals etc. Scaffolding and approaches for taking radiographs.

5.38.2

The contractor shall provide the necessary skilled technician and labourers for taking the radiographs. While taking radiographs, the contractor has to use proper penetrometer/ image quality indicators as instructed by the BHEL engineer. All the processed and accepted films will be the property of BHEL. In this regard, the contractor has to adhere to the safety rules/regulations laid by BARC authorities from time to time. It may please be noted that invariably the radiographic work will be carried after the normal working hours.

5.38.3

Contractor shall note that 100% radiography shall be taken on all high pressure welding till such time the welders' performance is found to be satisfactory. Subsequently, subject to consistency in welder's performance, the percentage of radiography will be based on BHEL's standard practice/code requirement. The defects shall be rectified immediately and to the satisfaction of BHEL engineer. The decision of BHEL engineer regarding acceptance/rejection of the joints will be final and binding on the contractor.

5.38.4

Wherever radiographs are not accepted, on account of bad shot, joints shall be re-radiographed and re-shots submitted for evaluation. Radiographs shall be taken on joints after carrying out repairs. However, if defect persists after first repair, as per radiograph, carrying out repairs and radiography shall be repeated till joint is made acceptable in case, the joint is not repairable, the same shall have to be cut and repaired at contractor's cost. Decision of BHEL engineer in all these matters is final and binding on the contractor.

5.38.5

100% radiography of weld joints of certain piping have to be carried out as per BHEL standards/drawings/specification.

5.38.6

Radiography work of welds connected with this contract shall be arranged by the contractor including provision of services of technician and necessary equipment and consumables like isotope camera, x-ray/gamma ray films, chemicals etc., and necessary labor required such as riggers, helpers, etc., to assist the technician for carrying out the radiography work and making other arrangements such as providing scaffolding, approaches, platform lighting arrangements, etc., at their cost and the work has to be arranged as per the instruction of BHEL. It may please be noted that invariably the radiography work will be carried out after the normal working hours and close of other site activities only.

5.38.7

Radiography inspection of welds shall be performed in accordance with requirements and recommendation of BHEL engineer. The quantum of radiographic inspection shall be as per provision of IBR/BHEL's erection documents. They may, however be increased depending upon the performance of the individual welder at the discretion of BHEL engineer/boiler inspecting authority.

5.38.8

All x-ray / gamma ray films of joints shall be preserved properly and be handed over to BHEL. These shall become the property of BHEL.

5.38.9

The field welded joints shall be subject to dye-penetrant / other non-destructive examination as specified in the respective engineering documents/ as instructed by BHEL.

5.38.10

Where required, surface preparation, like smooth grinding of welded area, prior to radiography shall be done as specified. It may also become necessary to adopt inter-layer radiography/MPT/UT depending upon the site/technical requirement necessitating interruptions in continuity of the work and making necessary arrangements for carrying out the above work. The contractor shall take all this into account in his offer.

5.38.11

Welding of necessary instrumentation tapping points, thermocouple pads, root valves, flow metering & measurement devices, and control valves to be provided on GT & their respective auxiliaries, integral & external pipe/off base/system covered within the scope of this specification, will also be the responsibility of the contractor and shall be done as per the instructions of BHEL site engineer. The installation of all the above items will be contractor's responsibility even if:

- A) Items are not specifically indicated under the respective product groups as given in the technical specifications.
- B) Items are supplied by an agency other than BHEL.

NDE/NDT and post weld heat treatment for above shall be done as per the specifications and drawing requirement as part of scope of work.

5.39 INSULATION

5.39.1

Application of wool insulation/mattress, pipe sections etc., sheet metal cladding, welding of hooks/supports to hold insulation of equipment, piping, tanks, vessels, duct with fittings, common system equipment and balance of plant equipment covered under this contract, shall include, but are not limited to, the following :-

-
- A) Where indicated, removable type of insulation to be provided for valves, expansion joints, etc. as per the drawings or as directed by BHEL engineer.
- B) Wool insulations are received at site as bonded and unbounded mattresses in standard sizes. These are to be dressed / cut to suit work by the contractor.
- C) Application of insulation and refractory works and sheet metal covering as given in various drawings/ specifications of BHEL, supplied to the contractor.
- D) Outer sheet cladding by fabrication of aluminum/ GI sheets to the sizes and shapes specified in drawings, beading, swaging, beveling of sheets, crowning the sheets, if necessary, fixing the same to supports, over wool insulation with screws/retainers as specified in BHEL drawings or as instructed by BHEL engineer.
- E) Welding of hooks/supports on equipment including on pr. Parts and piping to support wool insulation, as per the drawings or as instructed by BHEL engineers.
- G) The contractor shall leave certain gaps and openings while doing the work as per the instructions of BHEL engineer to facilitate inspection by statutory(boiler) inspector or cut open during commissioning to fix gauges, fittings and instruments. These gaps will have to be finished as per drawings at a later date by the contractor at no extra cost to BHEL.
- H) Wastage allowance for the materials issued shall be as under:-
- | | |
|---------------------|----|
| i) Wool Insulation | 2% |
| ii) Cladding sheets | 2% |

CHAPTER-6 EQUIPMENT INSTALLATION -ELECTRICAL AND C&I

The contractor's scope of services for various equipment indicated in Part-1, Chapter 11 are detailed in this chapter.

The work will comprise of, *but not limited to the following*:

6.1 Installation of Control panels and LT Switchgear

6.1.1

Electrical control panels, Electronic Control panels, Unit Supervisory Control DESK,LT Switchgear, 415V LT MCCs are normally supplied in suit of either one/two/three or loose shipping sections with integral base frame or loose base frame. These panels may have to be installed as stand-alone or in-group consisting of number of panels in each row, depending upon the plant layout and foundation arrangement.

6.1.2

The panels shall be transported from stores to the place of installation in vertical position. Care shall be taken such that the Switches, Lamps, Instruments etc. mounted on the panel does not get damaged during transit.

6.1.3

Installation of panel shall include fixing of base frame, leveling, alignment, fixing of anti-vibration pads, removal of side covers, fixing of cubicle interconnection hardware's, Bus bar jointing, wiring interconnection, Welding and Grouting of panels and base frames, mounting of panel Canopy wherever supplied as part of panel, drilling of gland plates, sealing of panels/ cable entries. Where the base frame is not supplied as part of panel supply, the contractor shall fabricate the base frame from structural items at site. Payment for such fabrication will be effected on measured quantity at the rate applicable for structural steel fabrication and installation. Special material required for fireproof sealing of the panels shall be supplied by the contractor within the quoted rates. Proper sealing of all the holes and Cable entries (even if the cable has been laid by others) in the panel is in the contractor's scope.

6.1.4

Panels have to be shifted to their locations through floor openings, temporary openings like floor grills, door etc. which shall be a part of work and no claim whatsoever will be entertained with regard to non-availability of opening as per shortest route etc. Panels have to be erected at different locations and elevation in end user's (M/s RUPPL) LT Switchgear room, Unit Control Room etc.

6.1.5

Panel and instruments once erected in position should be properly protected using necessary care to prevent ingress of dust/moisture. This will have to be periodically cleaned and surroundings have to be kept tidy.

6.1.6

Whenever the panels to be mounted on cable trenches, channel supports have to be provided across the cable trench over which the base frame of panel shall be mounted. For such work, Structural Steel fabrication & installation rate shall be applicable.

6.1.7

Normally the panels shall be supplied with meters, relays, electronic modules, contactors, pushbuttons etc mounted and pre-wired. However, if such devices are supplied loose/separately for safety in transit, contractor shall mount the same, as part of panel installation work and no extra payment shall be made for this.

6.1.8

Supplier's instruction manuals, packing slips, door keys etc. Received along with the panels will be handed over to BHEL's engineer on opening of the panels.

6.1.9

Regular cleaning of the panels as per the instruction of BHEL engineer till handing over of the set to customer is to be carried out by the contractor free of cost.

6.2 415V MOTOR CONTROL CENTERS (MCC) & DC DISTRIBUTION BOARDS

6.2.1

Motor control centers are single / double front draw out type consisting of circuit breakers units, contactor/starter, switch fuse units, protection & metering relays/ instruments etc. arranged in multi tier construction. These MCC are mainly supplied to cater to the requirements of drives, valve actuators etc.

6.2.2

DC distribution Board is single front non-draw out type consisting of MCCB/SFU, contactors, starters, fuse units, MCB etc arranged in multi-tier construction. DCDB shall be located in LT switchgear room to cater the dc supply requirement.

6.2.3

The scope of work for the LT switch board and DCDB covers receipt of materials from stores, transportation to the respective location, erection, testing, commissioning and handing over.

6.2.4

Rubber mats shall be supplied by bidder for placing in front of LT switchgear panels and the same shall be laid wherever required as part of work.

6.2.5

The scope of work for the LT switch board and DCDB covers receipt of materials from stores, transportation to the respective location, erection, testing, commissioning and handing over.

- a) Checking of installation for correctness.
- b) Mechanical functional checking/ adjustment of individual breaker.
- c) Measurement of Insulation resistance of individual breaker, complete switchgear board and combined insulation resistance of individual breaker with cable connected to drives.
- d) Testing of Protection Relay, Thermal over relay, Power transducers, Energy/ Ammeters, Voltmeters, Power factor, frequency & metering etc. in static & dynamic condition relay
- e) Conducting test such as Insulation Resistance measurement, Ratio, polarity, magnetization characteristic, winding resistance on CT and PT.
- f) Checking of electrical control & protection interlock of individual breaker and integration with other system.
- g) Calibration of energy meters, tri-vector meters, voltmeters, ammeters, power current & voltage transducers etc.
- h) Provide assistance for checking the electrical operation of individual breakers from remote panels / MMI package in End user's scope).

6.3 Cable Laying (Power / Control / Instrumentation shielded cables / Triad Cable / plug-in cables / UTP cables for Ethernet / armored / Un-Armored, single / multi-core, PVC/HR PVC / FRLS / Teflon / XLP insulation)

6.3.1 Cable laying (erection) will include:

- a) Cutting to the required length, laying in overhead/underground cable trench/ through pipes/flexible conduits. Cable rollers have to be used as per requirement. The contractor shall prepare the drum schedule in order to minimize the wastage.
- b) Dressing/Clamping in tray etc.
- c) Drilling of holes in gland plates in panels and junction boxes for the entry of cable.
- d) Cable glanding, splicing, dressing of spliced wire inside the panel and JB's

-
- e) Providing printed ferrules. Wherever required ferrules shall be one-piece heat shrinkable type. **Contractor has to arrange for suitable ferrule printing machine(s).**
 - f) Termination by using crimp type lugs copper tinned/ aluminum (insulated/ un-insulated).
 - g) Providing identification cable tags, aluminum at both the ends and at appropriate interval (30m) throughout the route length. Tags are to be arranged by the contractor.
 - h) Continuity checking, insulation resistance checking, High Voltage test on HT cables, as applicable.
 - i) LT Power cable trefoil clamps (Die cast Aluminum of good quality) are to be arranged by the contractor within the quoted rates.

6.3.2 Entry to the panels, JB may be from top, side or bottom. All cable shall be supported and clamped near the panels/JBs.

6.3.3 Wherever cable glanding is not possible, either due to the gland plate size limitations or more number of cable entries, suitable alternative arrangement as specified by BHEL/end user shall be done. Pre-Fab plug-in cables, for such cases, cables may have to be lifted inside the panel either making cut-out in gland plate and providing Rubber profile for sharp edge protection or alternatively, provide 4/6" PVC pipe coupling gland and these pipe coupling gland shall be supplied by contractor within the quoted rate of cable laying.

6.3.4 Copper Tinned lugs of various type (pin, ring, fork, snap-on), PVC cable ties, PVC ferrules (printed), PVC buttons and tapes, cable identification tag of metallic, clamping and dressing material with hardware, PVC sleeves etc shall be supplied by the contractor within the quoted price for cable laying. The quality of material shall be got approved from BHEL engineer prior to their procurement.

6.3.5 All care should be taken to avoid abrasion, tension, twisting, kinking, and stretching of cables during installation.

6.3.6 Cable shielding – all signal cables are supplied with bare shielded copper wire/with braided wire shield, generally shield wire is kept isolated at instrument/field device end and continuity is maintained through JBs and getting earth at panel end only. While terminating the shield wire either in panel or JBs, PVC sleeves is to be used to avoid two-point earthing. Supply of PVC sleeves of appropriate color is in contractor's scope.

6.3.7 Wherever cable ducts/tray, conduits pass through fire barriers such as walls, floors etc., the openings/ passage shall be sealed using fireproof/ weatherproof sealing compound. Similarly cable entry in panels, MCC, Instruments, Electrical Actuators etc are also required to be sealed. These shall be done as per the specifications of BHEL. Required consumable shall be in contractor scope of supply within quoted rate for cabling.

6.3.8 Normally, junction boxes are received with mounted cables glands. While terminating the cables as per drawings, the cable glands to be removed and fixed. Wherever cable glands are not received along with junction boxes, no separate payment will be made for fixing the cable glands to the junction boxes including the drilling of holes.

6.3.9 Many of the cables may have to be laid in the cable trenches constructed by end user. For this purpose, the cover of trenches has to be opened for working inside. All safety precautions have to be observed while laying the cables in the trench. After completing the work, the trench has to be cleaned and covers put back into position. The contractor, if required, shall do de-watering of trenches.

6.3.10 Terminations:

The types of cable terminations are as detailed below:

- a) Power cable: Crimping hydraulic / Manual
- b) Control cable: Manual crimping
- c) Crimped/soldered plug-in-type Screwed type.

All console devices / computer peripherals shall be screwed, crimped, soldered plug in type.

UTP cable with RJ 45 connector. The contractor shall arrange for special tools and skilled manpower required for any type of cable termination (like fiber optic jointing kit and RJ45 crimping tool etc) as mentioned above. Additionally ferrule printing machine(s) for printing of sleeved ferrules of various sizes will also be arranged by the Contractor.

6.3.11

Looping wire at terminal block of panels and electrical actuator as shown in the inter-connection diagram is to be done by contractor at no extra cost.

6.4 Wastage allowance

Contractor shall carefully plan the cutting schedule of each cable drum in consultation with BHEL site engineer such that wastages are minimized. Recovery will be made in case the wastages are exceeding the wastage allowances fixed in this contract.

The erection contractor shall make every effort to minimize wastage during erection work. In any case, the wastage shall not exceed the following limits;

Power Cables	1.5%
Control & Instrumentation Cables	2.0%
Fabrication steel	2.0%

Impulse pipe/tubes/GI pipes/copper tube**1.0%**

If however, the bidder quotes for more wastage than specified above, the excess portion will be considered for adjustment during the tender evaluation at the quoted supply rate of material. If the actual wastage be more than the specified figure, then equivalent price of the excess portion will be deducted from the contractor's bill. Cable cut-pieces in lengths 10 m & above in both the above categories will be considered as useable and shall be taken in to account for computing net issued quantity when returned to BHEL stores/storage yard.

6.5 CABLE TRAYS/CABLE DUCTS**6.5.1**

Various types of sheet metal, Galvanized Cable Tray, i.e. Perforated, Ladder type, sheet metal duct, solid bottom trays, pre-fabricated structural trays etc., will be supplied in standard lengths along with accessories and hardware viz coupler plate, tray covers and tray clamps etc.

6.5.2

Installation of cable tray/cable duct shall include cutting, laying, jointing, fixing tee/reducers/bends/clamps, fixing of tray covers, hardware, welding of tray supports as per tray route layout etc.

6.5.3

Fabrication of bends/tee/ reducers from straight length is within the scope of work and rate quoted shall be inclusive of this. All site welds of cable trays shall be painted with approved primer and cold galvanizing paint, which shall be arranged by the contractor.

6.5.4

In case, structural cable trays, bends, tees, reducers etc., are required to be fabricated from structural steel and installed, unit rate applicable for fabrication and installation of structural steel shall be applicable in such instances.

6.5.5 Cable trays/duct etc may have to be routed underground in cable trench, overhead on structure, along the walls, floors etc. for various applications.

6.6 **STRUCTURAL STEEL FABRICATION AND INSTALLATION**

6.6.1

Structural steel material like MS angles, channels, beams, flats, plates etc. shall be supplied in running meter and the same shall be used for fabrication of panel base frame, cable tray supports, Canopies for instruments/panels/ drives/JB's/Push Buttons etc., Instrument/Junction box frames, Impulse Pipe/Instrument Air Pipe supports and instruments etc.

6.6.2

This shall include cutting to size, contouring of ends for connections if required, Welding, Grinding of excess weld deposits/burrs, drilling of holes for mounting of device/instrument, installation at location, leveling, alignment, providing bracings and painting etc. No gas cut holes will be permitted.

6.6.3

All the fabricated supports/frames for instruments, trays, pipes, electrical equipments, etc., shall be epoxy painted after sand blasting and surface preparation as per painting specifications. Paints and other associated items are in the scope of the contractor.

6.6.4

Frame installation at site may involve mounting either on concrete floor by grouting/using anchor fasteners or on steel structure by welding etc. All consumables including anchor fasteners shall be arranged by the contractor. Where required, as part of work, concrete floors may have to be chipped out to reinforcement depth for anchoring the frames. Wherever grouting is required, contractor shall arrange all the required material including cement/grout mix, shuttering, labour etc., and meet all other requirements as part of work.

6.6.5

In certain packages, members of frames/rack for mounting of junction boxes/ instruments may be supplied readymade. These have to be assembled prior to installation. The installation rate as quoted shall include assembly of the frames.

6.6.6

Gas cutting of tray/impulse pipe support and holes in frame is not permitted. Only hacksaw cutting/ drilled hole shall be permitted.

6.7 Earthing installations

6.7.1

All equipments shall be earthed by two separate and distinct connections. Earthing terminals will be available in all equipment supplied by BHEL.

6.7.2

The earthing conductors shall be of mild steel/GI strip/ wires. All connections from equipment to main earthing conductors shall be made as illustrated in earthing drawing / as per instruction of BHEL engineer.

6.7.3

A continuous earthing conductor shall be installed in all cable trays and securely clamped to each tray section by suitable connectors to form a continuous earthing system. When two or more trays supporting power cables run in parallel, a continuous earthing conductor shall be provided on trays only with tap offs to the control cable trays. All valve and damper motors and rapping motors will be earthed to this conductor.

6.7.4

All joints in the earthing system shall be welded type. Earthing connections to all equipments including motors shall be bolted type.

6.7.5

Earthing connections shall be free from tinning scale paint, enamel, grease, rust or dirt at the time of making joint.

6.7.6

Metallic sheaths, screens/shields and armor of all multicore cables shall be bonded and earthed.

6.7.7

Earthing conductors along their run on columns, beams, walls etc. shall be supported by suitable cleats at intervals of 750 mm.

6.7.8

Welded joints on GI earthing conductors shall be coated with one coat of bituminous paint in case of buried earth grid or earth flats to be laid in cable trench. For site welded GI strips/wires which are exposed these are required to be painted with one coat of cold galvanising zinc paint. Contractor to arrange the required paints and other items at his cost.

6.7.9

Mark VI panels, Control panels & Man-Machine-Interface

GT and electrical control system panels are based on digital distribution control philosophy. The various components / devices are located in control room / panel room and shift in charge room. The entire work of erection, testing, commissioning of the connected devices / equipments as listed in rate schedule is to be carried out including laying of peripherals cables (either plug-in or plugs to be fabricated at site), placement of computer furniture in computer room as per lay out. The computer furniture shall be supplied either assembled or in knocked down condition, which have to be assembled at site. The quoted rate shall be inclusive of cable laying, termination and assembling / placement of furniture against each devices as given in the rate schedule. Loose devices like recorders, indicators, and monitors are supplied loose.

6.8 INTEGRATED TESTING OF CONTROLS AND PROTECTIONS & RELAY TESTING

6.8.1

Integrated electrical testing/commissioning of generator control and protection relay panels, LT MCC & other electrical panels and associated equipment shall involve various activities like relay testing/setting, simulation checks, testing of energy meters, on/off line functional checks on integrated system. The brief scope of work under the “integrated testing/ commissioning of generator controls and protections relay panel & associated equipments” is defined as below, but not limited to the following.

- a) Relay testing in static condition for generator, transformers, and associated system by secondary current injection at different current and recording the time duration.
- b) Testing and checking of control and protection interlock scheme in static condition and simulation of protection device contact from internal and external devices.
- c) Measurement of Insulations, Winding Resistance, Polarization Index of winding of Generator & associated equipment/ system, DC resistance test & Impedance test on rotor, Brushless excitation system at the time of rotor insertion as well as during pre-commissioning stage / commissioning stage/ post commissioning stage.
- d) Relay setting and checking the stability of protection relays in static and dynamic condition during the OCC (open circuit characteristic) & SCC (short circuit characteristic)
- e) Functional checks / testing of synchronizing schemes during the static and dynamic by simulation / back charging of generator transformer conditions.
- f) Monitoring & recording the various parameters during open circuit and short circuit conditions test on generator & associated field equipment like generator transformer, unit auxiliary transformer. Recording and monitoring measurement.
- g) Testing of protection current transformer for ratio test by primary injection, magnetization characteristic, polarity test, and IR measurement. Functional checks of relays of protection system by primary injection.

-
- h) Testing of potential transformer for ratio test by voltage ratio, polarity test, insulation resistance measurement etc, testing of surge capacitors, PT isolator in PTPS cubicle etc. (these are housed in generator side line & neutral cubicle).
 - i) Measurement of Insulation resistance of individual equipment and connected together.
 - j) Tan delta test on generator & other equipments as required.
 - k) Calibration of energy meters, tri-vector meters, voltmeters, ammeters, current & power transducers etc.
 - l) Providing temporary shorting link on bus duct or any other location while testing & normalization after the test.
 - m) Testing & commissioning generator circuit breaker.
 - n) High voltage test on inter connecting cable between generator and line/ neutral side cubicle.
 - o) Testing of relays, meters, internal devices, functional checks of electrical panels LT MCC and other panels/ equipments.
 - p) Contractor shall discuss & finalize testing procedure with BHEL engineer in-charge for the test to be conducted on generator control & relay panel testing. Drawing & documents shall be provided by BHEL at the time of testing. BHEL decision in this regard shall be final and binding on the contractor.
 - q) Checking & testing of neutral grounding transformer & resistor.
 - r) Compilation of test records.
 - s) In case contractor has not done similar work, they are free to tie –up with experienced agency who has carried out similar nature of work and having adequate resources i.e. Experienced manpower, T&P / testing/ measuring instruments. Contractor shall submit documents in support of such tie –up arrangement of such parties along with the offer. Credential of such parties shall be submitted with technical bid along with tie-up MOU.
 - t) It is to be noted in general that for any testing of protection relays, MCC etc., where the contractor is not sufficiently experienced, they shall arrange for the services of suitable agencies for carrying out the work, within the quoted rates.
 - u) In case of party quoting for the work have their own resource or resourced capability to take up relay testing etc. At site, the evidence of same is to be annexed to the technical bid

OR ALTERNATIVELY

Bidder can tie-up with agencies experienced in Relay testing. Sufficient proof of the credentials and experience of the agency in this field of work shall be annexed to the technical bid & BHEL's approval shall be obtained.

6.9 GENERATOR INSTALLATION

Scope of contractor shall includes Unloading the Generator assembly near GT area, collection from unloaded place, dragging/lifting & placement on required foundation & elevation. Any other arrangements/T&P/attachments including Lifting Slings for lifting & placement of Generator shall be provided by contractor as scope of work.

6.10 GENERATOR SYSTEM TESTING

The following major works also shall be in the scope of the Contractor

- a) Generator stator winding resistance and PI value measurement / check
- b) Generator rotor winding resistance, impedance, IR value measurement before and after rotor insertion.
- c) Generator Bushing HV test
- d) Main exciter winding resistance, IR value measurement / check
- e) PMG winding resistance, IR value measurement / check
- f) Testing and commissioning of generator and exciter accessories viz., heaters, blowers, stroboscope, diodes, enclosure lighting, potential measurement of bearings (TE &EE) etc
- g) Meggering during drying out of generator.
- h) Meggering of generator bushing and its accessories. This test has to be conducted many times during erection and commissioning stages.

Other than the above, minor testing / checks will also be involved in the generator area, which are also in the scope of the contractor. *Any instruments / tools etc required for carrying out the above shall be arranged by the contractor within the quoted rates.*

6.11 Battery/battery charger/UPS

6.11.1

HDP Tubular or NiCd (or similar type) or Lead acid Batteries will be supplied loose along with battery interconnection in the series/parallel links/bus bar, lugs, steel/wooden battery stand either assembled or knocked down condition, cables and associated charger and UPS system.

6.11.2

In case of Lead acid battery, the electrolyte shall be supplied in plastic cans. After installation, the electrolyte has to be filled in batteries and charging/discharging shall be carried out to achieve specific gravity of electrolyte and stability of battery/battery bank. If required, discharging of the charging cycle shall be repeated to achieve the desired results. However, BHEL engineer's decision shall be final. Any preparatory arrangement required to be done for

charging and discharging of battery, the contractor shall arrange consumables, safety equipments etc., at his own cost.

6.11.3

In case of NiCd (or similar type) batteries are normally supplied in charged condition, due care shall be exercised while handling/installation of the same. If the battery charge is found to be less than the required level, the charging/discharging cycle shall be carried out as per instruction of BHEL engineer.

6.11.4

Battery charging/discharging is a continuous process and skilled manpower shall be deployed by the contractor round-the-clock.

6.11.5

Contractor shall arrange suitable load, cables, safety equipments and consumables for discharging the battery during charging and discharging cycle at his cost.

6.11.6

Contractor shall provide skilled manpower for periodic maintenance after the battery are fully charged for the activities such as checking of electrolyte level, specific gravity, topping up with distilled water and cleaning till the set is handed over to customer and record of the same shall be maintained and submitted before handing over of the system.

6.12 CONTROL & INSTRUMENTATION

6.12.1

Contractor shall mount all flow indicators, centrifugal/speed switches of motors, accumulators, pressure regulators, etc which are received loose and which are to be erected/mounted at site on air lines, water lines, oil lines, auxiliaries and firemen floor and other operating floors on power house and other equipment. These are to be mounted during erection for finalizing routing/position etc. They are to be dismantled after completion of erection work and handed over to BHEL for calibration. After calibration, these instruments shall be remounted by the contractor in their respective positions just before commissioning.

6.12.2

Certain instrumentation like, pressure gauges, power cylinders, flow meters, valve actuators, flow indicators, etc are received in assembled condition as integral part of equipment. Contractor shall dismantle such equipment at an appropriate stage under the instruction of BHEL and hand them over to BHEL for calibration and storage. Contractor shall re-erect them in position just before commissioning of the equipment.

6.12.3

Seal welding of Thermowells, plugs before Hydro test of equipment and piping systems is also within the scope of this work/specification. Contractor shall also remove the seal welded plugs by process of grinding and fix and seal weld Thermowells after Hydro test/steam blowing of lines.

6.12.4

Providing necessary engineer/supervisors/technicians/electricians as required by BHEL engineer for drying out the LT motors is within the scope of the work. Job includes testing the motor for finding out PI & IR values and making necessary cabling connection for heating for dry out from the nearest source of supply and maintaining and controlling the temperature till the IR and PI values are achieved as per standards. However, BHEL will provide necessary motorised insulation testers for this purpose. The contractor shall provide necessary power cables and other tools and consumables for the above works free of charges. Before undertaking dry out/trial run of HT motors, the end shields and covers shall be opened on both the ends of the motor for inspection, cleaning and greasing of bearings.

6.12.5

Welding of all Thermowells, draft, pressure and temperature instrumentation points, and all other instrumentation points on piping, and auxiliaries is within the scope of this work.

6.12.6

All Motors shall be preserved with space heaters(if any) on, and provided with proper cover till the commissioning of the motors.

6.12.5.7

Mounting of instrumentation on turbine, generator and exciter and auxiliaries which are the integral part and supplied with main equipment shall be the part of scope of work and contractor shall render necessary services for their commissioning.

6.12.8

Trial run of all motors including checking direction of rotation in uncoupled condition, check alignment and re-couple the motor to driven equipment.

6.12.9

After initial trial of rotating equipment, control and power cabling for motors and other equipment/instrumentation may have to be disconnected for checking alignment and resetting/realignment/hot alignment. Contractor will have to provide services for disconnection and reconnection of control and power cables.

6.12.10

Certain instrumentation like pressure switches, air sets, filter regulators, pressure gauges, and junction boxes, power Cylinders, dial thermometers, flow meters, valve actuators, flow indicators etc. are received in assembled condition as integral part of equipment. Contractor shall

dismount such instruments for calibration and hand over the same to c & i erection agency of BHEL. Mounting of such instruments will be done by the C&I erection agency.

6.12.11 Field instrumentation

- a) Various type of primary/secondary/ indicating/ recording instrument for pressure, temperature, flow, level, speed, turbo-supervisory and analytical measurement shall be supplied either loose or mounted along with the equipment.
- b) Scope of work under calibration, erection// testing/ commissioning shall include calibration, setting, adjustment, supply and fixing of instrument tag plates as specified by BHEL, report making, installation, servicing, minor repairs, putting instrument into service, signal checking from field upto the functional group panels and remote indicating/recording instrument, functional checks, interlock and protection/alarm checks by simulating the field devices, trouble shooting during pre-commissioning/ commissioning and till the unit is handed over to the customer.
- c) Contractor shall establish calibration laboratory with adequate facilities and they should arrange standard test instruments duly calibrated from the agencies approved by BHEL. Calibration report of the same should be submitted prior to start of calibration of the field instruments/devices.
- d) It is the responsibility of contractor to make erection, calibration/ testing and commissioning protocols for various equipments/devices installed by them and they should get duly certified by customer/BHEL engineer and should be submitted to BHEL engineer regularly. However, sample formats will be given by BHEL and have to be printed by contractor in adequate numbers.
- e) Installation of instrument shall also include drilling of holes and tapping for mounting of instrument and local instrument frames/panels and supply of hardware for mounting of the instrument.
- f) Some devices line solenoid valves, position feedback transmitters, limit switches, air filter regulators, airlock relays, positioners etc., are supplied assembled along with mechanical equipments like pneumatic control valves, power cylinders, trip valves, dampers, motorised actuators, etc. These will need removal, calibration/testing, refixing, adjustment, etc., and commissioning. Separate payment shall not be made for this. The rates quoted for the commissioning of these equipments (viz., pneumatic control valves, power cylinders, trip valves, dampers, etc.) should take care of the above. Also, the contractor shall remove such devices prior to erection either at site or at store to avoid damages/pilferages and keeping in safe custody and the same shall be installed prior to commissioning of such equipment.
- g) Transmitter enclosure / open racks for various packages which are to be erected and commissioned at various locations of the Boiler, turbine and outdoors, shall be supplied with internal tubing, air filter regulators, rotameters, provision of continuous or intermittent purging arrangements wherever required, etc. The quoted rates for these

racks / enclosures shall include the erection and commissioning of all such items inside these racks / enclosures.

- h) Sometimes recalibration of equipments may become necessary due to reasons not attributable to the contractor, e.g. Lapse of Time after first calibration, Need for change in range/parameter, etc. If re-calibration is required due to no fault of the contractor, recalibration shall be done without any cost implication to BHEL. The contractor shall keep record of such instrument with the reason for re-calibration and certified by the BHEL Engineer.
- i) For the very few cases where required, the contractor shall carry out re-orientation of bottom/top entry arrangement for process connection if needed due to site condition in existing instrument rack/enclosure/ JB and re-location of existing instrument including removing of the existing tubing and re-installation of the same at appropriate location due to any change in grouping of the instrument and no extra payment shall be applicable.
- j) In certain cases instruments / devices are supplied on equipment or drawn by other agencies as part of mechanical package. The same are to be received or to be collected from other agencies for keeping in safe custody to avoid damages. The same are to be erected back after calibration for which unit rate shall be applicable for erection and calibration. Contractor shall maintain record of such instrument duly certified by BHEL engineer. However for removal of such instrument, no separate rate/payment shall be applicable.
- k) For such of those instruments/devices such as temperature gauge/switches, pressure gauge/switches, transmitter pressure/flow/ level/DP, level probe/switch etc, which are received, assembled with mechanical equipments and are to be calibrated, only calibration rate will be paid as per applicable rate for respective instruments/devices. No payments shall be made for removal and re-fixing of such instruments.
- l) Wherever thermowells are supplied along with temperature gauges, thermocouples, temperature switches, thermostats, etc., the contractor has to co-ordinate with the mechanical engineer for identification and fixing of thermowells on the pipeline. However actual fixing of thermowells on pipeline and seal welding shall be done by mechanical contractor and is not a part of instrument installation.
- m) All field mounted instruments are to be located in such a way as not to obstruct walkways or plant equipment access but shall be easily accessible for maintenance. Hand rails shall not be used for mounting or supporting instruments.

-
- n) Racks/stands and supports for instruments and transmitters shall be fixed on RCC column/floor by chipping and grouting or by welding to steel structure. In no case these shall be welded to floor grills.
 - o) The power cylinders support/base erection will be welded to steel structure or by grouting. The power cylinder will be properly aligned and linkage mechanism wherever required shall be connected to the driven equipment. All accessories for power cylinders line air sets, solenoid valves, air lock, limit switches, if supplied loose, shall be fixed, aligned and connected up.
 - p) When installing flow and pressure transmitters/switches for Liquid /steam/condensate vapor services, the instrument is to be mounted below its primary element or tapping point. For gas service applications, the instrument is to be mounted above Primary element tapping point.
 - q) During erection and commissioning stage, the site mounted instrument shall be protected suitably. Contractor shall provide suitable security arrangement in main control room, and other areas where equipments are positioned, at no extra cost.
 - r) All brackets/racks and support steel work for tubing impulse lines/instruments shall be painted with two coats of primer and two coats of final color prior to installation. Paints, etc supply in the scope of contractor.
 - s) Contractor shall arrange for own fire fighting equipments for the materials stored under contractor's custody.

6.12.12 LAYING OF PIPES/TUBES (IMPULSE PIPE)

- a) Installation of impulse pipe of CS/AS/SS material shall include cleaning, air flushing, cutting to length from the running meter, edge preparation, cold bending, welding of sockets/ reducers/ tee/ cross/ isolating valves/union nut and nipples/tail pieces etc., mounting of SS/CS three/five valve manifolds and compression fittings, condensate pot/equalizing vessel, providing supports, clamping, conducting leak test/hydraulic pressure test, painting and other accessories as per instrument hook-up diagram. Piping works shall involve either arc or TIG welding.
- b) IBR certified welders shall be deployed for welding of impulse pipe and contractor shall take approval for welder and welding consumables from BHEL site engineer.
- c) All fittings and accessories for impulse pipe and air line shall be provided by BHEL. Quoted rate for piping shall include cost of installation of such fittings as no separate rate is envisaged.

-
- d) Contractor shall provide GI clamps for impulse pipe and GI pipes within the quoted rates for installation of the same.

6.12.13 INSTRUMENT & SERVICE AIR PIPING (SS/GI PIPE)

Laying of pipe (SS/GI) for instrument air line shall include air blowing, cutting from the running meter length, threading, installation of Elbows/ Tee/Reducer/ Moisture traps/Auto drain pot/check valves/isolating valves, supporting clamping, conducting leak test etc. Threaded joints of air pipeline shall be made leak proof by using Teflon tapes or sealing compound. Seal welding of threaded joints may be called for if required. This shall be done within the quoted rate.

6.12.14 COPPER TUBING/PIPE/SS TUBE

Installation of Copper Tube/SS Tube/Copper pipe shall include cutting into required length, laying, bending, cleaning, brazing wherever required, fixing of fittings like compression Fittings/Tees/End connectors/straight connectors/bulk heads/valves etc. Supporting, clamping including supply of clamps and hardware, flushing and conducting leak test. Suitable tube cutters, benders and de burring tools will be used for such jobs.

6.12.15 Guidelines for handling and storage of electronic cubicles / subassemblies / loose items.

- a) Immediately after unloading at site, the electronic equipment should be kept in a covered area. Handling and lifting of package should be done without jerks or impacts. Packing case should not be dropped or slid along the floor under any circumstances. Suitable forklift should be used to move the case to its final position. All above points are to be strictly followed as electronic equipments may get damaged due to vibration and shock.
- b) After unloading at site, the package of the equipment shall be inspected for external damage. In case the package is damaged, package number and details of damage should be noted. The details of damage should be reported to concerned site engineer.
- c) Cases should be opened/unpacked using correct nail pullers. While opening the planks, care should be taken to see that equipment inside is not damaged. Cases should not be unpacked in areas where they are exposed to rain, water/liquid splashing, dust or other harmful materials like chlorine gas, sulphur dioxide etc.
- d) After opening the case, all supports provided for transport are to be removed with due care.
- e) Hinged frames should not be opened when equipment is not secured to floor as this is likely to cause it to topple over. The hinged frame can be opened only if the equipment is still fixed on to bottom wooden pallet.

6.12.16 Storage

- a) The equipment should be preferably in its original package and should not be unpacked until it is absolutely necessary for its installation or advised by BHEL engineer. The equipment should be best protected in its cases. It should be arranged away from walls.
- b) The wooden pallet provided for packing itself can be retained for raised platform to protect equipment from ground damp, sinking into ground and to circulate air under the stored equipment. This will also help in lifting packing with fork-lifter.
- c) Periodic inspection if silica gel placed inside the equipment is necessary. It has to be replaced or regenerated when de - colorization takes place.
- d) Due care should be taken to ensure that the equipment is not exposed to fumes, gases etc., which can affect electrical contacts of relays and terminal boards.
- e) The storage room and the equipment should be checked at regular interval to ensure protection from termites, mould growth, condensation of water etc., which can damage the equipment.
- f) All the equipments, materials and goods kept in the store room should be identified and registered in a book. Inspection report should be recorded. Any discrepancy observed should be communicated to site engineer.
- g) The packing material shall be retained if the cubicle is to be repacked after inspection.
- h) All subassemblies should be kept in a separate place where it is easily accessible.
- i) Subassemblies should have a protective cover in case it is stored without wooden packing/case to prevent accumulation of dust. Silica gel packets should also be kept along with it.
- j) Subassemblies should not be stacked one above the other.
- k) The loose items supplied for the main equipment falls into various categories like tools, cables, prefabricated cables, console inserts, recorders, VDU/CRT, other display units, printers, sensors and transducers, cable glands, cable ducts, frames, racks, etc. These are to be categorised and stored separately.

6.12.17 Guidelines for handling of electronic modules

- a) All the modules shall be handled by qualified persons only.
- b) Electronic modules should only be touched when it is absolutely essential to do so.

-
- c) Before touching any electronic module, the operator should discharge the static electricity by earthing himself or better still, ensure constant discharge by wearing an earthed wrist strap.
 - d) The operator should not wear clothing made entirely from synthetic fibers, but a mixture containing at least 65% cotton.
 - e) The PCB should always be held by front panel or by module frame and electronic components / connectors should never be touched.
 - f) The electronic modules should not be placed close to television sets or CRT units.
 - g) Soldering irons and any other tools used must be grounded.
 - h) All modules using CMOS components are packed in antistatic bags when transported loose to avoid ESD failures. The antistatic bags must always be used to transport modules at site from one place to the other.

6.12.18 MISC. INSTRUMENT/ EQUIPMENT CALIBRATION, ERECTION, TESTING, AND COMMISSIONING

- a. contractor shall carry out testing & commissioning of panels, electrically operated valves, pneumatic control valves, pneumatic trip valves, solenoid valves, limit switches, HT/LT motors including drying out, and any other integral devices forming part of various mechanical skids/equipments, & piping etc.
- b. The scope of commissioning of electrically operated actuators for valves, dampers, gates etc., will include meggering, adjustments of mechanical/ electrical or electronic position transmitters, setting of limit/torque switches, cable checking, internal wiring checking, cleaning / heating for increase in IR value, local/remote operation, replacement of limit/torque switches if required, etc.
- c. The scope of commissioning of devices like solenoid valves, feedback position transmitters, limit switches, air filter regulators, airlock relays, positioners etc., which are integral part of pneumatic control valves / power cylinders / trip valves electrically operated valves etc., will involve adjustments / servicing, calibration etc. As incidental to work, contractor shall remove such devices prior to erection either at site or at store to avoid damage/pilferage and for keeping in safe custody. These shall be installed at appropriate stage as instructed by BHEL. The above removal and re fixing will be done within the quoted rates.
- d. Whenever additional instrumentation work viz gauges, transmitters, temperature elements and laying of impulse piping, is to be carried out for performance

guarantee test, the same has to be executed by the contractor as per the rate applicable already provided in the Unit rates.

- e. Certain instrumentation like pressure switches, pressure gauges, dial thermometers, transmitters etc. are received in assembled condition as integral part of equipments. Dismounting, calibration, and re-erection of such instruments, where required for safe keeping or any other purpose as instructed by engineer, is in the scope of work. Only the rate applicable for calibration for respective instrument item will be paid.
- f. All batteries for various AC and DC systems are to be taken into service as per standard method of initial charging and discharging, recording specific gravity values, etc. Contractor has to make arrangement for suitable loads during charging / discharging cycle.
- g. Battery charging/discharging is a continuous process and skilled manpower shall be deployed by the contractor round-the-clock.
- h. Contractor shall arrange suitable load, cables, safety equipment and consumables for discharging the battery during charging and discharging cycle at his cost.
- i. Contractor shall provide skilled manpower for periodic maintenance after the battery are fully charged for the activities such as checking of electrolyte level, specific gravity, topping up with distilled water and cleaning till the set is handed over to customer and record of the same shall be maintained and submitted before handing over of the system.
- j. Wherever panels, pneumatic power cylinders and control valves have been erected by the mechanical contractor, calibration/ commissioning has to be carried out by the contractor..
- k. In the case of electronic water level indicator , electrodes may be supplied loose and the same need to be fixed in the pressure vessel as per the drawings. No extra charges will be payable.
- l. The calibration of position transmitters of the NRVs in the turbine extraction system has to be carried out by the contractor. Position transmitters are to be erected by contractor if supplied loose.
- m. Dimension and weight as mentioned against control panels, MCCs, etc. in weight schedule are only approximate and there may be changes in dimension and weight

in actual supply of the equipment and no rate variation shall be applicable on this account.

- n. Wherever brief description of the system is given under various sub-heads, it is only for the understanding system requirements. It does not indicate the total specification of work. For such system, other clauses are also applicable wherein work details are specified.
- o. Normally, cable glands on junction boxes side are received in mounted condition. While terminating the cables as per drawings, the cable glands are to be removed and fixed. Wherever cable glands are not received along with junction boxes, the cable glands as per the requirement will be provided by BHEL and the contractor has to make necessary holes/adjust the available holes in the JB for fixing these. No separate payment will be made for drilling of holes and fixing the cable glands to the junction boxes. Nameplates for JBs will be supplied separately. These are to be suitably written and fixed onto the JBs. Wherever nameplates for JBs are not supplied, the JB no. are to be written with paint on JBs for identification. Separate payment will not be made for this.
- p. The push buttons and indicators in C&I systems are provided as loose with different type of connectors. The fixing of connectors and their wiring from push buttons to indicators shall be the responsibility of contractor. No separate payment will be made for fixing of connectors. The cable laying and termination charges will be paid as per applicable Unit rate.

6.12.19 Calibration, testing & commissioning

Calibration, testing & commissioning activity as specified in this technical specification and unit rate schedule against various equipments, devices, systems etc. are broadly described hereunder. However, there may be some overlapping between the activities, i.e. Erection, calibration and testing, commissioning. The classification of each activity is only a guideline for understanding the volume of work in each activity. The contractor shall have no claim for performing or providing manpower assistance for such overlapping work, which is also within the scope of work.

Scope of work under erection/calibration/testing/commissioning shall include calibration, setting, adjustment, writing instrument tag number with paint, report making, installation, servicing, minor repairs/servicing, putting instrument into service, signal checking from field upto the functional group panels and remote indicating instrument, functional checks, interlock and protection/alarm checks by simulating the field devices, trouble shooting during pre-commissioning/post-commissioning till system is handed over to the customer.

Contractor shall establish calibration laboratory with adequate facilities and they should arrange standard test instruments duly calibrated from recognized agencies and calibration report of the same to be submitted prior to start of calibration of the field instruments/devices.

A. Calibration

- Verification of instruments for range, type etc; with respect to instrument schedule, data sheet or system document.
- Codification of instruments as per system tag numbers
- Calibration/adjustment of instrument as per system requirement/set values.
- Providing head correction in case of pressure measuring instruments.
- Verification of installation of instruments for range, type, tag number as per physical location of process point as per process, instrumentation diagram.
- Checking and ensuring the proper functioning of instruments.
- All the recorders shall be made functional with proper chart movement and ink marking.
- Preparation of computerised calibration certificates in the formats specified by BHEL Engineers and getting those signed by the customer is in the scope of the contractor.

Completion of erection and commissioning protocols with customer.

B. Erection

- Drawal of material from store, verification, inspection as per shipping list, drawings and documents.
- Preservation, upkeep, safe custody of the erected equipment till handing over.
- Verification of installation as per drawing and document for the correctness of cabling, JB's, impulse pipe, various field device, panels, instruments etc.
- Continuity check & IR value of cables.
- Verification of correction of cable termination with respect to instrument, electrical hook-up diagram, panel interconnection diagram, JB schedule.
- Checking earthing of the equipments and cable shield wire continuity.
- Energizing the functional group control panels and field devices.
- Flushing of impulse pipe before making the instruments process connections through.
- Any leakage damages to impulse pipe, field device connections, air connections etc. Shall be fully attended by contractor.
- Wherever thermowells are supplied along with temperature gauges, thermocouples, temperature switches, thermostats, etc., the contractor has to co-ordinate with the mechanical contractor for identification and fixing of thermowells on the pipeline. However actual fixing of thermowells on pipeline and seal welding shall be done by mechanical contractor and is not a part of instrument installation.

C. TESTING & COMMISSIONING

- Checking/verification of binary/analog input and output signal from field and panel and upto recording/indicating instrument/MMI monitors.

-
- Adjustment, testing, calibration of pneumatic drive (control valve, trip valve, power cylinder for gate/dampers etc), electrical actuator operated valve/gate/dampers of other functional elements.
 - Checking and operating electrical/pneumatic drive through functional group panel, remote control desk, PMS/MMI, CRT operation and repeatability and smooth operation to be checked.
 - Checking the interlock, protection and alarm for various processes by stimulation of field devices/process changes.
 - Functional check of sub-loop control, sub group control and auto loop and fine-tuning.
 - Adjustment of limit switches/feed back position transmitter checking the L.S. of actuator for correct position indication and repeatability shall be ensured.
 - LT motor IR value measurement, bearing/winding RTD checking, checking the LT load connector, providing assistance for trial run of motor which includes monitoring temperature rise winding/bearing during trial run.
 - Contractor shall prepare calibration/testing report/protocols.
 - During trial run of various systems, the performance of any instrument found erratic, unsatisfactory are required re-adjustment, re-calibration etc. Contractor shall attend to the defects.
 - Observing and checking the performance of the various devices on load/process variation. Any deficiencies/defect noticed during the variable load conditions, the same shall be attended promptly.
 - Observe the proper functioning of sub-group/sub-loop control.
 - Check the operation of various control in manual /auto mode for smooth functioning.
 - Clearing of all defective signals arising during commissioning and during trial operation of unit.
 - Any wiring correction or minor modification in control panel wiring noticed during the pre-commissioning, it shall be carried out.

D. Post-commissioning

- Contractor shall rectify the defect observed/informed by customer during the trial run.
- Contractor shall submit the as- built drawing as per guidelines and instruction of BHEL engineer.
- After trial run/handing over of the equipment, if due to unforeseen reasons, certain works crop up, the contractor shall provide all the assistance.

E. PG Test Assistance

- For PG test assistance, laying of impulse pipes, cables, etc. and installation of instrument tapping points shall be done by the contractor. These activities may be carried out at any point of time before or after Completion of Facilities. Payments will be made as per item rates of comparable similar or identical items in the rate schedule. Such temporary

installations shall have to be dismantled and returned to BHEL Stores, after the completion of PG Test for which no separate payment is admissible.

6.12.20

The work under this scope being quite sophisticated and also quite extensive, for proper planning, monitoring, reporting, etc of ongoing works, the contractor shall establish his own computer(s) and printer(s) at his site office, along with suitable operator(s), consumables, etc. *Non-establishment of above equipment will attract penalty @ Rs 20000 (Rs Ten thousand only) per month.*

6.13 TROUBLESHOOTING DURING PLANT OPERATION

During pre-commissioning / commissioning stages when the plant will be under various stages of operation, it will be necessary to have continuous (day and night) presence of suitable manpower along with required tools to attend to any defects etc that may arise during such operation. The contractor will be required to put such personnel in shifts in both electrical and C&I area. The bidder must also take this aspect into consideration.

6.14

Certain instrumentation like pressure switches, air sets, filters, regulators, pressure gauges, junction boxes, power Cylinders, dial thermometers, flow meters, valve actuators, flow indicators, centrifugal/speed switches of motors, accumulators etc. are received in assembled condition as integral part of equipment. Contractor shall dismount, where instructed so, such instruments for calibration and storage/re-erection. Calibration will be done by C&I erection agency.

6.15

Fixing and seal welding of thermo wells & plugs of equipment or other piping system is within the scope of work. Contractor shall also remove the seal welded plugs by process of grinding and fix and seal weld thermo wells after hydro test/ of lines as part of work.

6.16

Actuators/drives of valves, dampers, gates, powered vanes etc. May have to be serviced, lubricated, before erection, during pre-commissioning & commissioning, including carrying out minor adjustments required as incidental to the work.

6.17

All electrical motors have to be tested for IR & PI values prior to the trial run. Where required, dry out may have to be carried out by using external heating source. Contractor shall make all arrangements in this regard and complete the work as instructed. BHEL will provide the motorized insulation testers.

CHAPTER- 7 HANDLING OF HEAVIER EQUIPMENT

Heavy and voluminous Equipment/consignments like GT Skid, Generator Assembly shall be handled carefully. All arrangements, Tools & Tackles, Trailer of suitable capacity(if required), slings etc. to handle heavy equipment right from un loading, transportation to site of works and erection & their placement on respective elevation/foundation shall be arranged by contractor as part of scope of work. Contractor shall plan his activities/operations as per instructions of BHEL Engineer. **BHEL Shall not provide any T&P for the specific work.**

CHAPTER- 8

HYDROSTATIC TESTING, PRESERVATION AND OTHER TESTS

8.1

Contractor shall carry out the following tests required to complete the erection and commissioning of the GTG Set:

- (1) Hydraulic testing of piping & Vessels(if any):Required capacity Hydraulic test pump/Fill pump and other necessary arrangement shall be provided by contractor to carry out hydraulic testing, Chemical cleaning of the equipment and piping as part of scope of work under this tender specification.
- (2) Ultrasonic test
- (3) Dye Penetrant test
- (4) Magnetic Particle Test.

All above facilities (men, materials, equipment, consumables etc) with operating engineer/experienced person and proper approach wherever required shall be provided by the contractor for satisfactory completion of the above tests.

8.2

Contractor shall lay all necessary temporary piping, welding, supports, install pumps, valves, pressure gauges, electric cables and switches etc, required for the Air leak test, Chemical cleaning etc.. After the test is over, all the temporary piping, pumps, etc will be removed. It may also specifically be noted that servicing, erection and dismantling of piping and equipment for conducting above tests will be done by the contractor. No separate payment shall be made for this purpose.

8.3

All the above tests shall be repeated till all the equipment, piping and systems satisfy the technical and statutory requirements. All related works form part of the scope.

8.4

For the installation of temporary system as above BHEL will provide only the piping, structural items for supports and access platforms, tanks/ plates for fabrication of tank, valves, gauges and their fittings, and thermal insulation only. These will be supplied in random sizes / lengths. However, fabrication, erection, dismantling of the same after completion of the process, and handing over back to BHEL stores will be the responsibility of the contractor. All above works shall be carried out by contractor. The works of all other temporary piping for remaining applicable tests shall be carried by contractor as scope of work. All pumps of adequate capacities and specifications to meet the requirement, suitable motors and their starters, foundation/ frames, cables, switches etc shall be arranged by the contractor (other than which are to be provided by BHEL free of hire charges on returnable basis).

Cleaning, servicing of tanks, valves, pumps, equipment, during various stages of erection and commissioning are in the scope of work. Gaskets, packing & spares for replacement will be provided free of charges by BHEL.

8.5

Hydro test of piping may have to be repeated several times to meet technical and statutory requirements before application of insulation.

8.6

While conducting hydraulic test of steam lines, water lines, oil lines either individually or grouping a few lines or in portions. Blanks/spools may have to be put up at terminal points, strainers, walls, flanges etc. After conducting the tests, the blanks shall be removed and the lines restored. Contractor shall carry out all such incidental work to satisfactorily conduct the hydro test. Wherever work is involved in the terminal points, Contractor shall carry out the same as per instruction of BHEL engineer. The decision of BHEL engineer is final and the same is binding on the contractor.

The contractor shall carry out any other tests as desired by BHEL engineers on erected equipment covered in the scope of this contract during testing and commissioning to demonstrate the satisfactory completion of any part or whole of work performed by the contractor.

8.7

For various pre-commissioning / commissioning activities / processes mentioned in various clauses, transport of chemicals from BHEL/ customer's stores, charging of chemicals into the system and returning of remaining chemicals and the empty containers of the chemicals to customer / BHEL stores is the responsibility of the contractor.

8.8

During trials/ tests, pre-commissioning / commissioning, replacing / changing mechanical / other seals of equipment like pumps, removal and cleaning / replacing of filters etc is within the scope of work.

8.9

In case any defect is noticed during tests, trial runs of all equipment and their auxiliaries, such as interferences, rubbing, loose components, abnormal noise or vibration, strain on connected equipment etc., the contractor shall immediately attend to these defects and take necessary corrective measures. If any readjustment and realignment are necessary, the same shall be done as per BHEL engineer's instructions. Claim, if any, for these works from the contractor shall be governed by relevant clauses.

8.10

Contractor shall cut / open / dismantle work, if needed, as per BHEL engineer's instructions during commissioning for inspection, checking and make good the works after inspection is over.

Similarly, during the course of erection, if certain portion of equipment erected by the contractor has to be undone for enabling other contractors / agencies of BHEL / customer to carry out their work, contractor shall carry out such jobs expeditiously and promptly and make good the job

after completion of work by other contractors / agencies of BHEL / customer as per BHEL engineer's / agencies of BHEL / customers instructions. Claims, if any, in this regard shall be governed as per relevant clauses .

8.11 PRESERVATION OF COMPONENTS

Contractor shall arrange for preservation of components/ materials issue to him as per BHEL's storage and preservation manual and/or as per instructions of BHEL engineer.

One or more of following methods shall be adopted for preservation:

Coating with preservative paints/lubricant/inhibitors.

Capping/wrapping/covering.

Filling/immersion in oil/chemicals etc.

CHAPTER-9

PRE-COMMISSIONING TESTS, COMMISSIONING AND POST COMMISSIONING

9.1

Commissioning of the GTG equipment with associated Aux. and other Equipment with auxiliaries shall involve the following tests though not limited to these, various testing, trial runs of various equipment erected and systems installed;

- (a) Trial run of Pumps other various rotating machineries / pumps.
- (b) Trial run of all motors/ drives for various auxiliaries.
- (c) Chemical Cleaning of various systems & piping, Oil flushing of lube oil system, Air cleaning/blowing of pipelines, closed systems, Tanks and Vessels.
- (d) Flushing of all pipelines by air/oil/water/Chemicals/steam as the case may be.
- (e) Servicing of all valves, Hydraulic Power cylinders, fittings.
- (f) Manual/mechanical cleaning of Pumps, tanks /vessels and other various equipment erected by the contractor. This may have to be repeated several times during the commissioning process.
- (g) Chemical cleaning of piping systems as per requirement. Contractor shall carry out disassembly and reassembly of vulnerable components like gauges, instruments etc. as instructed by BHEL during this process.
- (h) Cranking of GT
- (i) FSNL and synchronisation.
- (j) Trial operation
- (k) Full load operation

The above activities/tests/trial runs may have to be repeated till satisfactory results are obtained and also to meet the technical and statutory requirements.

9.2

Contractor shall lay temporary pipelines with fittings and accessories etc. as instructed by BHEL engineer for the purpose of pre-commissioning and commissioning activities like chemical cleaning, oil flushing etc. of piping and other equipment as part of the scope of work. Temporary installations shall be dismantled by contractor and returned to BHEL stores as specified elsewhere in this T.S.

9.3

The contractor shall provide necessary assistance to facilitate/enable electrical and instrumentation testing and commissioning of equipment under this scope of work, to BHEL and their Testing & Commissioning agency.

9.4

The contractor shall carry out any other test as desired by BHEL engineer on erected equipment covered under the scope of this contract during testing, pre-commissioning and commissioning, to demonstrate the completion of any part or parts of work performed by the contractor.

9.5

In case any malfunctioning and / or defect is found during tests / trial runs such as loose components, undue noise or vibrations, strain on connected equipment etc. The contractor shall immediately attend to these defects/ malfunctioning and take necessary corrective measures. If any readjustment and realignments are necessary, the same shall be done as per BHEL engineer's instructions, free of cost.

9.6

The cleaning of Lube oil tank etc. is in general by wire brush / abrasive paper etc. In case of tenacious rusting spots found if any, the same shall be cleaned thoroughly mechanically by buffing wheel etc. If manual / mechanical cleaning is not proper, the cleaning by sand blasting as per instructions of BHEL engineer before and after oil flushing is responsibility of contractor.

9.7

The contractor shall associate for initial and subsequent fillings of gas in generator gas system as and when required till unit is handed over to Customer.

9.8

The contractor shall carry out leak test of generator air cooling system to the satisfaction of BHEL engineer.

9.9

Replacing/changing mechanical/other seals of equipment, pumps etc. during commissioning stage is within the scope of work.

9.10

During the stages of commissioning, and till Unit is handed over, if any part of GTG and auxiliaries need repair/rectification/rework/replacement, the same shall be done expeditiously and promptly by the contractor. Contractor's claim if any, for such repair/rectification/rework/replacement etc. for reasons not attributable to the contractor, will be governed by relevant clauses of this specification. The parts to be replaced shall however, be provided by BHEL free of cost.

9.11

During this period, though BHEL's and customer's engineers will also be associated in the work, the contractor's responsibility will be to make available resources in his scope till such time the commissioned units are taken over by the customer.

9.12

In case any malfunctioning and/or defects are found during tests, trial run such as loose component, undue noise or vibration, strain on connected equipment etc., The contractor shall immediately attend to these defects/ malfunctions and take necessary corrective measures. If any readjustment or realignment is necessary, same shall be done as per BHEL engineer's instruction.

9.13

The pre-commissioning activities will start prior to Lube oil flushing, etc. of the GTG and various trials, commissioning operations shall continue till the GTG is handed over to customer. Simultaneous commissioning checks, activities will be in progress in various areas like trial run of various equipment, checking of equipment erected, making ready for trial runs, filling up of lubricants, chemicals etc. All these works need specialised gangs including electricians, Instrument Technicians, Fitters, in each area to render assistance to BHEL commissioning staff. Contractor shall earmark separate manpower for various commissioning activities. This manpower shall not be disturbed or diverted. The mobilisation of these commissioning gangs shall be sufficient so that planned commissioning activities are taken up in time and also completed as per schedule and the work is to be undertaken round the clock if required.

9.14

Contractor shall cut open works if needed as per BHEL engineer's instructions during commissioning for inspection, checking and make good the works after inspection is over, without any extra payment.

9.15

After the start of commercial operation of machine, commissioning activities will continue. It shall be the responsibility of contractor to provide following manpower along with supervisor as part of commissioning assistance for a period of three months **per Unit**.

- | | |
|--------------------------------------|------------|
| 1) Supervisor | 1 Nos. |
| 2) Pipe fitter/Millwright fitter | 1 Nos. |
| 3) welder | 1 Nos. |
| 4) Rigger | 1 Nos. |
| 5) Electrician/instrument technician | 1 No. each |
| 6) unskilled worker | 3 Nos. |

9.16

The above figures shows only minimum required over and above labour required for completing pending erection and commissioning works and clearing of punch lists. Contractor has to provide number of personnel and other resources as per work demand.

9.17

It shall be specifically noted that above employees of the contractor may have to work round the clock along with BHEL commissioning engineers.

9.18

During commissioning, opening of valves, changing of gaskets, checking, realigning of rotating and other equipment, attending to leakages in piping, tanks etc. and adjustments of erected equipment may arise. Valves shall be serviced and lubricated to the satisfaction of BHEL engineer during the erection and commissioning as per BHEL engineer's instructions.

9.19

It is the responsibility of the contractor to provide for necessary resources till the completion of work under these specifications, even in case erection, testing and commissioning of the GTG and other equipment are delayed due to reasons not attributable to the contractor.

CHAPTER-10

CHEMICAL CLEANING & OIL FLUSHING

10.1

Contractor shall lay and erect temporary pipelines with fittings and accessories and also erect/commission the chemical cleaning/circulating pumps after servicing as per requirements, tanks and other installations, as a system as instructed by BHEL for the purpose of chemical cleaning, water flushing, water washing, oil flushing of piping and shall provide all other arrangements as per requirement as part of scope of work. Contractor have to arrange the Chemical cleaning pumps as per requirement. It shall be specifically noted by the contractor that all pipes for above works shall be supplied in random length and in loose condition. Contractor has to assemble and erect them as per schemes / drawings provided by BHEL. Further, flanges, bend etc. for completing the scheme shall be machined/ fabricated by the contractor at his own cost . However, plates / steel etc. for the same will be provided by BHEL free of charges.

10.1

After the chemical cleaning/Flushing has been successfully completed, dismantling of all temporary installations as instructed by BHEL is within the scope of work under this specification. The dismantled materials shall be dressed and returned to BHEL as stated elsewhere in this tender spec.

10.2

Preservation of the cleaned surfaces will be the responsibility of contractor under the guidance of BHEL engineer.

10.3

Carrying out repairs, if any, is in the scope of work/specification.

10.4

For chemical cleaning of the piping system, contractor will have to lay temporary piping to connect the entire system irrespective of whether the equipment/system connected is in the scope of contractor or not. Decision of BHEL Engineer in this regard will be final and binding on the contractor.

10.5

During the initial stages of work, trenches for draining water may not be available after alkali flushing or mass flushing for discharging and emptying. Necessary low point drains and temporary piping for this will have to be provided by contractor from materials provided by BHEL.

10.6

Laying effluent discharge line from mixing tank (for acid cleaning or any other chemical cleaning process) as per the instructions of BHEL engineer and dismantling, servicing for preservation and handing over the same to BHEL stores after completion of the job is within the scope of work/specification.

10.7

Radiographic examination of weld joints on temporary pipes as required by the Engineer In-charge should be carried out.

10.8

Contractor shall also carry out the repairs or attend leaks etc., in the temporary piping and equipment for the above operations / activities while carrying out the above activities / operations.

10.9

For chemical cleaning of system which consist of equipment/piping erected by the contractor and also equipment/piping erected by other contractors of BHEL/customer's contractor has to arrange for workers and supervisory staff as required supplementing/complimenting the labour and supervisory staff mobilised by other agencies for chemical cleaning of the portion of equipment erected by them in the system. Decisions on the strength of gangs and supervisory staff for deployment of labour and allocation of work for them at site, by BHEL engineer is final and binding on the contractor.

10.10

Contractors quoted rate shall be inclusive of fabrication, cost of consumables, erection, dismantling of temporary piping and servicing of the equipment and valves and handing over to BHEL. No separate payment on this account shall be entertained.

10.11

After acid cleaning/pickling of lubricating system (including oil piping of lube oil system, HP Oil supply system, oil tank and other fittings) of rotating machines, oil flushing for lubricating systems, etc. as per instructions of BHEL Engineer shall be carried out. Cleaning of oil tank of lubricating oil system of rotating machineries, cooler etc. before and after oil flushing is the responsibility of the contractor.

10.12

For full welding of structures, tanks and piping etc., only welding generators shall be used. The use of welding transformers will be subject to the approval of BHEL Engineer.

10.13

Erection and commissioning of connecting piping – permanent and temporary for oil purification equipment and all operations for cleaning, oil flushing, dismantling of temporary piping during pre and post-commissioning of equipment up to full load shall be the responsibility of contractor as part of scope of work

CHAPTER-11 PAINTING

Scope:

- Supply of Paints for Touch-up, full and final painting
- Final Painting of GT enclosure and auxiliary equipment
- Touch-up painting for panels
- Full Painting (surface preparation, primer to final coat of painting) of structures, supports and piping

11.1

All protective paints for the protection of weld joint fit-ups, application of primers on finished weld joints are in the scope of contractor. Supply & application of required paints for exposed surfaces shall be in the scope of bidder.

11.1.1

The primer and thinner will be provided by contractor as part of scope of work along with other arrangements for surface preparation and paint application like sand/shot-blasting, consumables like surface cleaning agents, paint brush, brush cleanser, labour and necessary tools and plants as required for completion of work.

11.1.2

Contractor shall submit manufacturer's batch test certificate / test certificate from BHEL approved laboratory for the primers and paints. Prior approval of BHEL for each and every batch of the primer & paints shall be mandatory. In order to achieve a desired minimum paint dry film thickness (DFT) as specified in BHEL drawing, number of coats may be applied and method of application shall be as recommended by the paint manufacturer. **Contractor shall arrange required paints & primers and other consumables for above works.**

11.2

Preservation of all components/equipment during various stages of erection, commissioning till handing over is in the contractor's scope. All prescribed methods of surface cleaning prior to application of preservative paint shall be followed by the contractor. **Contractor has to arrange all primer and paints, and other consumables like wire brush, painting brush required for this work.**

11.3

All exposed metal parts of the equipment including piping, supports, structures, railing, tanks/vessels, GT sets, Common System Equipment, Balance of Plant Equipment with associated auxiliaries etc. as covered under these tender specifications, as applicable shall be painted after thoroughly cleaning the surface from dust, rust, greases, oils, scales, etc, by wire brush, scrapping etc; as specified in relevant erection documents.

The above parts shall then be painted with specified no. of coats of specified paint over the shop primer/paint. Also, where the shop primer/paint has peeled off, the affected area shall be cleaned thoroughly by the specified method and then primer coat applied. Similarly, certain components may be supplied without any primer/paint coat from shop. The surface of such items shall be cleaned as per specifications, coated with suitable primer and then coated with final paint coats. The dry film thickness after final coat should be as per specification.

11.4

In addition, color banding, legend and identification marking, direction of flow/rotation marking etc. is part of work.

11.5

The surface preparation/cleaning, treatment, Identification marking Color Codes and Final/Finish painting works shall be carried out by contractor as per BHEL/RIL Specification .For any non-confirmation/dispute between BHEL & RIL specification, the procedure/instructions as laid down in customer & their consultant's specification shall supersede BHEL specification and shall be binding on contractor.

Painted surface thickness as per standard shall be demonstrated by the contractor. Paint thickness measurement instrument shall be in the scope of contractor.

Painting the inner side of aluminum/GI/steel cladding, with anti-corrosive paint as specified. Also all other accessories for painting, cleaning the surfaces etc. shall be arranged by the contractor.

Touch-up painting of switchgear panel, 415 Volt LT MCC, Control Panels or any other equipment /devices wherever necessary.

11.6 STRUCTURALS

Structural components may be supplied by BHEL without any primer/paint coat. The surface of such items shall be cleaned as per specifications and then coated with two coats of Primer.

11.7 PANELS, JUNCTION BOXES

11.7.1

Panels and Junction Boxes shall be Touch-up painted as and where original shop paint is peeled off. Necessary surface cleaning and preparation shall be done by the contractor as per relevant painting codes followed by two coats of Primer and two coats of Finish Paint.

11.7.2

The contractor shall provide the Primer (ROZC as per IS:2074) for the scope of painting work indicated in Section-4 as well as for protection of site weld joints and gas cut locations. Contractor shall also arrange to provide the required thinner and other consumables, T&P etc

required for application of ROZC Primer. All paints and thinners shall be sourced only from BHEL approved manufacturers.

11.7.3

In addition, color banding, legend and identification marking; direction of flow/rotation marking etc. is part of the work.

11.7.4

Contractor shall ensure that all steel structure used for electrical installation shall be painted with one coat of Red Oxide Zinc Chromate primer and two coats of Aluminum Alkyd paints of approved shade for indoor installations. However for outdoor installations and corrosive areas like Battery room, contractors shall carry out hot dip Galvanization.