COPY RIGHT AND CONFIDENTIAL
The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED
it must not be used directly or indirectly in any way detrimental to the interest of the company.

DRAWING NO. PE-DG-434-641-C038

FIRST ANGLE PROJECTION | ALL DIMENSIONS ARE IN MM



2 TERRACE FLOOR AT EL +9.00M LVL.



2 AHU TERRACE AT EL +13.30M LVL.

2 MUMTY EL +13.30M LVL.



NOTES: –
1. ALL DIMENSIONS ARE IN MM.
2. ALL LEVELS MENTIONED ARE FINISHED FLOOR LEVELS.

AREA STATEMENT:
1. TERRACE FLOOR AREA – 151 SQ.M.
2. ATRIUM AREA – 80 SQ.M.
3. FIRST FLOOR COVERED AREA – 151 SQ.M.

LEGEND:	
	250MM THK. AAC BLOCK WALL
	200MM THK. AAC BLOCK WALL
	150MM THK. AAC BLOCK WALL

SCHEDULE OF OPENINGS 2
WINDOWS & VENTILATORS:

S.NO	SYMBOL	OPENINGS	SILL w.r.t. F.F.L.	LINTEL w.r.t. F.F.L.	NOS.
1	AW 4	1500X1500	+7.35M	+4.35M	2
2	AV 2	900X600	+9.3M	+9.9M	15

SCHEDULE OF OPENINGS 2
DOORS: TERRACE FLOOR

S.NO	SYMBOL	OPENINGS	SILL w.r.t. F.F.L.	LINTEL w.r.t. F.F.L.	NOS.
1	SD 1	1500x2400	+9.3M	+11.7M	1
2	FPD 1	1200x2400	+9.15M	+11.5M	1

SCHEDULE OF FINISHES 2
FALSE CEILING/PAINTING

1	ACRYLIC EMULSION PAINT
2	ACRYLIC DISTEMPER
3	DESIGNER CERAMIC WALL TILES DADO UP TO FALSE CEILING LEVEL
4	ACID/ALKALI RESISTANT TILE AND CHEMICAL RESISTANT PAINT ABOVE DADO
5	ACRYLIC EMULSION PAINT AND GLASS MOSAIC TILES CLADDING
6	CALCIUM SILICATE FALSE CEILING
7	GI CLIP IN METAL FALSE CEILING
8	CHEMICAL RESISTANT PAINT.

FINISHING SCHEDULE 2
INTERNAL FINISHING SCHEDULE– TERRACE FLOOR

AREA	FLOORING	WALL: SKIRTING	WALL: DADO	WALL: PAINTING	CEILING: FALSE CEILING	CEILING: PAINTING	REMARKS
AHU	C	C	—	2	—	2	FALSE CEILING AS PER APPROVED PATTERN/ DRAWING.
RCC STAIRCASE AREA							

NOTE:

EXTERNAL FINISHING SCHEDULE

PORCH AREA	CEMENT CONCRETE FLOORING
EXTERNAL FINISH	EXTERNAL FINISH SHALL BE COMBINATION OF SOLVENT BASED EXTERIOR PAINT & ALUMINIUM COMPOSITE PANEL AS/ELEVATION DETAIL DRG.

ALL WALL AND ROOF AREAS ABOVE FALSE CEILING SHALL BE PLASTERED AND WHITE WASHED.

SCHEDULE OF FINISHES 2
FLOORING

A	HEAVY DUTY DUST PRESSED CERAMIC TILES.
B	VETRIFIED CERAMIC TILES.
C	CEMENT CONCRETE WITH METALLIC HARDENER TOPPING
D	CEMENT CONCRETE WITH METALLIC HARDENER TOPPING & FALSE FLOOR
E	ACID, ALKALI RESISTANT TILE.
F	GRANITE STONE

REV	DATE	ALTD	CHD	APPD	REV	DATE	ALTD	CHD	APPD
1.	27.11.19	KRITI	SANCHIT	ANURAG	1.	07.08.19	SANJANA	SANCHIT	ANURAG
	DRAWINGS REVISED AS PER COMMENTS RECEIVED BY N.T.P.C ON 04.09.19					DRAWINGS REVISED AS PER COMMENTS RECEIVED BY N.T.P.C ON 02.07.19			

JOB NO.
STATUS
DRG./REF. NO. (INTERNAL)
PRINT SCALE IN METRE 40 30 20 10 0 40 30 20 10 0

NTPC DRAWING NO. 9585-001-315-PVC-C-0498A

PROJECT : 3X800MW PATRATU SUPER THERMAL POWER PLANT

OWNER : एन टी पी सी लिमिटेड NTPC Limited (A Government of India Enterprise) CONSULTANCY WING

BHARAT HEAVY ELECTRICALS LTD
POWER SECTOR
PROJECT ENGINEERING MANAGEMENT
NEW DELHI

GREEN BUILDING CONSULTANT: GREENTREE BUILDING ENERGY (P) LTD.

COPY RIGHT AND CONFIDENTIAL
The information on this document is the property of BHARAT HEAVY ELECTRONICS LIMITED it must not be used directly or indirectly in any way detrimental to the interest of the company.

	DRAWING	NAME	SIGN	DATE
DRN.	SAMARTH	SAM	11/06/19
DESN.	SANCHIT	SAN	11/06/19
CHD	SANCHIT	SAN	11/06/19
APPD	ANURAG	ANG	11/06/19

TITLE IT BUILDING ARCHITECTURAL DRAWING
CONCEPTUAL TERRACE FLOOR PLAN AT EL+9.00M

MPL	ELEC	C&I	MSE	MAX	DEPT.	SCALE 1:80	DRAWING NO.
					SIGN		PE-DG-434-641-C038
					DATE		SHEET 3 OF 3 REV. 2

Nov 27, 2019 – 5:27pm
FORMAT SIZE A1