

















AREA STATEMENT:

1. GROUND FLOOR AREA - 688 SQ.M.
2. FIRST FLOOR AREA - 688 SQ.M.
3. TERRACE FLOOR AREA - 151 SQ.M.
3. ATRIUM AREA - 80 SQ.M.
4. TOTAL NET AREA - 1447 SQ.M.

	250MM THK. AAC BLOCK WALL
	200MM THK. AAC BLOCK WALL
	150MM THK. AAC BLOCK WALL

SCHEDULE OF OPENINGS					
DOORS: GROUND FLOOR					
S.NO	SYMBOL	OPENINGS	SILL w.r.t.	LUNTEL F.F.L.	NOS.
1		7100x3000	±0.0M	3.0M	1
2		1200x2700	±0.0M	2.7M	1
3		1200x2400	±0.0M	2.4M	6
4		1000x2400	±0.0M	2.4M	4
5		600X1800	+0.3M	2.1M	4
6		1200x2400	±0.0M	2.4M	2
7		1200x2100	±0.0M	2.1M	1
8		900x2100	±0.0M	2.1M	2
9		750x2100	±0.0M	2.1M	3
10		600X1800	+0.3M	2.1M	1
11		1200x2400	±0.0M	2.4M	3
12		2000x3500	±0.0M	3.5M	1

SCHEDULE OF FINISHES	
FLOORING	(A) HEAVY DUTY DUST PRESSED CERAMIC TILES.
	(B) VETRIFIED CERAMIC TILES.
	(C) CEMENT CONCRETE WITH METALLIC HARDENER TOPPING
	(D) CEMENT CONCRETE WITH METALLIC HARDENER TOPPING & FALSE FLOOR
	(E) ACID, ALKALI RESISTANT TILE.
	(F) GRANITE STONE


SCHEDULE OF FINISHES 	
FALSE CEILING/PAINTING	① ACRYLIC EMULSION PAINT
	② ACRYLIC DISTEMPER
	③ DESIGNER CERAMIC WALL TILES DADO UP TO FALSE CEILING LEVEL.
	④ ACID/ALKALI RESISTANT TILE AND CHEMICAL RESISTANT P.T. ABOVE DADO
	⑤ ACRYLIC EMULSION PAINT AND GLASS MOSAIC TILES CLADDING
	⑥ CALCIUM SILICATE FALSE CEILING
	⑦ GI CLIP IN METAL FALSE CEILING
	⑧ CHEMICAL RESISTANT PAINT.

INTERNAL FINISHING SCHEDULE- GROUND FLOOR							REMARKS
AREA	FLOORING	WALL			CEILING		
		SKIRTING	DADO	PAINING	FALSE CEILING	PAINING	
ENTRANCE/RECEPTION	①	②	③	④	⑤	⑥	FALSE CEILING AS PER APPROVED PATTERN/ DRAWING.
BATTERY ROOM	①	②	③	④	⑤	⑥	
PANTRY	①	—	③	④	—	⑥	
AC CONTROL ROOM	①	—	—	②	—	—	
MCC ROOM	①	②	—	②	—	②	
MEETING ROOM	①	②	—	①	②	—	
IT STORE ROOM	①	②	—	①	②	—	
COMMUNICATION ROOM	①	②	—	①	②	—	
FAQ ROOM	①	②	—	①	②	—	
OFFC. CABLES & TERMINATORS ROOM	①	②	—	②	—	②	
TELEPHONE EXCHANGE ROOM	①	②	—	①	②	—	
IT SERVER ROOM	①	②	—	①	②	—	
IT OPERATOR ROOM	①	②	—	①	②	—	
TOILET	—	—	③	—	⑥	—	
PASSAGE	③/④/⑤	③/④	—	①	②	①	
RCC STAIRCASE AREA	①	②	—	②	—	①	


NOTE:

EXTERNAL FINISHING SCHEDULE	
PORCH AREA	CEMENT CONCRETE FLOORING
EXTERNAL FINISH	EXTERNAL FINISH SHALL BE COMBINATION OF SOLVENT BASED EXTERIOR PAINT & ALUMINIUM COMPOSITE PANEL AS/ELEVATION DETAIL DRC.
ALL WALL AND ROOF AREAS ABOVE FALSE CEILING SHALL BE PLASTERED AND WHITE WASHED.	

REV △	DATE	ALTD	CHD	APPD	REV △	DATE	ALTD	CHD	APPD
	27.11.19	KRITI	SANCHIT	ANURAG		07.08.19	SANJANA	SANCHIT	ANURAG
1.	DRAWINGS REVISED AS PER COMMENTS RECEIVED BY N.T.P.C ON 04.09.19				1.	DRAWINGS REVISED AS PER COMMENTS RECEIVED BY N.T.P.C ON 02.07.19			

COPY RIGHT AND CONFIDENTIAL		DRAWING NAME		SIGN	DATE
The information on this document is the property of BHARAT HEAVY ELECTRONICS LIMITED it must not be used directly or indirectly in any way detrimental to the interest of the company.		DRG. SAMARTH			SAM
		DRG. SACHIN			SAC
		DRG. SAHIL			SAH
		DRG. ANIRAG			ANR
		APPRO		ANR	17/06/19

TITLE IT BUILDING ARCHITECTURAL DRAWING CONCEPTUAL GROUND FLOOR PLAN AT EL+0.00M										A

MPL	ELEC	CBI	MSE	MAX	DEPT.	SCALE 1:80	DRAWING NO. PE-DG-434-641-C038	
SIGN						SHEET	1 OF 3	REV. 2
3	2					1		