PROJECT : 2 X 800 MW YERMARUS TPS

PACKAGE : DC LEAD ACID PLANTE BATTERY

PRICE FORMAT : TENDER ENQUIRY No. PE/PG/YTP/E-3405/2011 DATED 28.01.12

Annexure-A

TECH SPEC: PE-TS-362-508-E001 Rev0

S. No.	Item Description	Unit	QTY	Unit Ex-worksprice (Rs.) or Unit FOB Price	Total Ex-works price or Total FOB Price	Import levies	ED including cess @ 10.3%	CST @ 2% against form-C/E1 or VAT@...% , as applicable	Freight @...% incl service tax	Total FOR Price or Total FOB Price	Remarks
(A)		1	2	3	4	5	6	7	8	9=4+5+6+7+8	
1.0	**LEAD ACID PLANTE 220V BATTERY1**	Nos.	4								220V DC, AH capacity to be decided by bidder as per annexure-II of Section-C, 1.85 ECV, 108 cells, Lead-Acid Plante high discharge battery with 100% electrolyte + 10% extra electrolyte, all accessories listed, suitable termination arrangement and metal/teakwood racks
1.1	LIST OF ACCESSORIES WITH EACH BATTERY SET										
1.1.1	Hydrometer (in step of 0.005)	Nos.	2								Part of item 1.0
1.1.2	Set of Hydrometer syringes (suiatble for vent holes in different cells)	Nos.	2								
1.1.3	Thermometer for measuring electrolyte temperature	Nos.	2								
1.1.4	Wall mounting type holder made of teak wood for hydrometer and thermometer	Nos.	2								
1.1.5	Digital Cell testing voltmeter (3-0-3V)	Nos.	2								
1.1.6	Alkali mixing jar	Nos.	1								
1.1.7	Rubber apron	Nos.	2								
1.1.8	Pair of Rubber gloves	Nos.	2								
1.1.9	Set of Spanners	Nos.	2								
1.1.10	No smoking' notice	Set	2								
1.1.11	Goggles (industrial)	Set	2								
1.1.12	Instruction card	Nos.	10								
1.1.13	Minimum & maximum room temperature indicator for each battery room	Set	1								
1.1.14	Cell Lifter	Set	1								
2.0	**E & C SPARES**	**Set**	**1**								
2.1	Intercell connector	Nos.	5								
2.2	Vent plug	Nos.	5								
2.3	Gloves	Set	2								
3.0	**TYPE TEST**	**LOT**	**1**								
3.1	Ampere hour and watt-hour efficiency test	LUMPSUM									
3.2	Endurance tests	LUMPSUM									
3.3	Test for capacity & test for voltage during discharge	LUMPSUM									
3.4	Test for retention of Charge	LUMPSUM									
	TOTAL (1.0 + 2.0 + 3.0) :										
(B)	**OPTIONAL ITEMS**										
1.0	SUPERVISION OF COMMISSIONING	No.	1								
2.0	SUPERVISIONOF E&C	Set	1								
3.0	INCREMENTAL INCREASE IN BATTERY RATING	Set	1								With a rating of 20AH

Notes: In case of foreign bidders, FOB prices is to be quoted and the quoted prices shall be loaded by import levies, Freight Charges & Insurance

Particulars of Bidder/ Authorised representative								
Name & Designation	**Signature**	**Date**	**Company Seal**					