

Schedule 'A'

Annexure-II

Name of work :Epoxy Flooring suitable for Air Caster Movement in New Transformer Block at BHEL, Bhopal

Sl.No.	Description of item	Qty	Unit	Rate	Amount
				Rate to be quoted by the contractor	
1	Levelling of the floor : Repairing of cracks, crumbled joints small size damages & Undulations found in the existing floor has to be removed then filled with epoxy screeding to the required thickness to bring the level within tolerance limits is to be provided.	20	Cum		
				Total= Rs	

Note

- 1 Contractor have to stand five years guarantee for his work in case any defect during the gaurantee period, the same is to be made good by the contractor free of cost. S.D will be kept with BHEL against above defect liability period five years.
2. Contractor have to submit the Test certificate of materials used for flooring from recognised & Certified Laboratories.
3. For demarcating the different areas, colours will be approved by the engineer - in-charge.

Sr.Engineer (MOD/Civil)