

BHARAT HEAVY ELECTRICALS LIMITED
RAMACHANDRAPURAM, HYDERABAD-32
PROJECTS DEPARTMENT

Tender schedule for the work of “Re-routing of Service lines at GT complex to facilitate the storage of materials for T&C Production”.

TENDER NOTICE No.: PROJ-EC/ELEC/OT/2012-13/09 dtd 21.08.2012 (Item No .1).

(The quotations should be on our Tender schedule only. Any deviations/deletions etc. should be brought out separately in your letter pad and enclosed to our tender documents).

Page 1/2

SL.No	Description of work	Qty	Unit	Unit rate in Rs.	Amount in Rs.
1	The scope of work involves collection of materials / equipment from stores / yard, shifting, laying, erection of pipe lines, flanges , elbows, Tees, reducers etc. They are to be aligned and joined by tack welding / flange joint with bolts, nuts, washers and gaskets and clamped on supports at a height of +14 Mtrs. to 0 Mtrs level as per drawing / BHEL Engineer's instructions. The rates quoted includes all the above work with contractor's welding electrodes, consumables and welding equipments. The Contractor has to arrange own transportation for material shifting.				
	Laying of Pipe lines :				
a	CS Pipe dia. 2"	170	RM	149	25330
b	CS Pipe dia. 1"	340	RM	56	19040
2	Butt Weld Joints : Carbon Steel : Root run TIG welding with contractors TIG welding set, Tungsten electrode. DP test to be done on all joints. If necessary 5% of joints to be X-ray tested for which the contractor has to give assistance however X ray equipment is under BHEL scope.				
a	CS Pipe dia. 2"	60	Jts.	1013	60780
b	CS Pipe dia. 1"	100	Jts.	335	33500
3	DISMANTLING:				
	Scope of work : Scope includes dismantling of support structures & shifting of pipes to the new location. NOTE: contractor has to make own arrangement of transportation like lorry/mobile cranes/trailer for shifting of the materials/equipments.	5	Ton	5875	29375
	FABRICATION & ERECTION :				
4	Fabrication : The scope includes fabrication of columns, trusses, support structures, pipe racks, hanger supports, pipe supporting brackets etc. and erection of above mentioned fabricated structures. The scope of above works includes collection of BHEL free issue MS materials from store / yard.	15	Ton	8500	127500

Tender schedule for the work of “Re-routing of Service lines at GT complex to facilitate the storage of materials for T&C Production”.

TENDER NOTICE No.: PROJ-EC/ELEC/OT/2012-13/09 dtd 28.08.2012 (Item No .1).

Page 2/2

SL.No.	Description of work	Qty	Unit	Unit rate in Rs.	Amount in Rs.
5	Supply of paints and painting materials, painting of pipes and other structurals by thoroughly cleaning all the surfaces free from scales, dirt and other foreign matter. Each coat shall be applied in an even and uniform film free from lumps, streaks, runs and uncoated spots. Make : ASIAN/BURGER/SHALIMAR/NEROLAC. One coat of rust preventive oxide primer with 40 microns thick and one coat of Synthetic enamel paint as approved by BHEL.	250	Sq.M	70	17500
	TOTAL AMOUNT				313025

(Rupees Three Lakhs Thirteen Thousand and twenty five only)

Note:- The Tenderers are required to quote their tender value in Percentage (%) basis at excess or less or on par with estimated value.

Tender percentage (%)	In words	Figures
Less		
Estimated rates only (On par)		
Excess		

Note:

1. VAT ,Service Tax are extra and will be released on submission of the valid documents.
2. The gases like Oxygen, DA, Organ will be issued free of cost.
3. All the unused/excess materials issued by BHEL shall be returned to the stores after use.
4. The items/quantities indicated in the schedule are tentative and may increase or decrease or delete.
5. The Price discount/increase offered by the agency is proportionately applicable for all the items in the schedule.