



Bharat Heavy Electricals Limited

Heavy Equipment Repair Plant

Tarna Shivpur Varanasi-221003

website: <https://herp.bhel.com>

Enquiry Number : E-RC-304-23-0712-61-1 Date : 29/Mar/2024

Enquiry For Material :-

Sl No	Material Description	Material Code	Quantity	Unit
1	L.J. HOUSING (HY-6.0 F) - ROUGH M/CD FORGING AS PER DRG. 36137690010/08 WITH MATL AS PER SPECN. AA19332/10	RV1930132018	150.0	NOS
2	JOURNAL SHAFT (HY-33.F) - ROUGH M/CD FORGING AS PER DRG. 36137690011/03 WITH MATL AS PER SPECN. AA19332/10	RV1930132026	80.0	NOS
3	L.J. HOUSING (HY-312.A.02) - ROUGH MACHINED FORGING AS PER DRG. HY-312.A.02.F WITH MATL AS PER SPECN. AA19332/10	RV1930132310*	50.0	NOS
4	JOURNAL SHAFT (HY-312.A.01) - ROUGH M/CD FORGING AS PER DRG. 36100090173/01 WITH MATL AS PER SPECN. AA19332/10	RV1930132400	50.0	NOS
5	U.J. HOUSING (HY-312.A.05.X) - ROUGH M/CD FORGING AS PER DRG. 36100090168/01 WITH MATL AS PER SPECN. AA19332/10	RV1930132427	45.0	NOS
6	UPPER JOURNAL HOUSING (HY-902.03.F) - ROUGH M/CD FORGING AS PER DRG. NO. 36108802393/01 WITH MATL AS PER SPECN. AA19332/10	RV1930132677	25.0	NOS
7	LOWER JOURNAL HOUSING (HY-902.04.F) - ROUGH M/CD FORGING AS PER DRG. 36108802392/03 WITH MATL. AS PER SPECN. AA19332/10	RV1930132689	30.0	NOS
8	JOURNAL SHAFT (HY-902.01) - ROUGH M/CD FORGING AS PER DRG. NO. 36108802391/01 WITH MATL AS PER SPECN. AA19332/10	RV1930132697	15.0	NOS
9	R/MCD FORGING OF JOURNAL SHAFT(HY-1101.09.F) AS PER DRG. 36100490184/01 WITH MATL. AS PER SPECN. AA19332/10	RV1930132824	5.0	NOS
10	R/MCD FORGING OF TRUNION SHAFT(HY-1102.01) AS PER DRG. 46100490249/00 WITH MATL. AS PER SPECN. AA19332/10(BHEL HYD MATL CODE BA9413253250)	RV1930132832	5.0	NOS

Remarks

Remarks

1. THIS INDENT HAS BEEN RAISED FOR ENTERING INTO FRAMEWORK AGREEMENT WITH VENDORS FOR FORGING. SEPARATE INDENTS WILL BE GIVEN TIME TO TIME AS PER REQUIREMENT FOR PLACING THE PO UNDER THIS RC. ITEM QUANTITY MENTIONED IN THE INDENT IS TENTATIVE & IT MAY INCREASE OR DECREASE AS PER OUR FINAL REQUIREMENT.

2. RATES OF ITEMS AGAINST FA WILL BE FIRM & VALID FOR ORDERING FOR A PERIOD OF ONE YEAR FROM THE DATE OF AGREEMENT. PRICE VARIATION CLAUSE (PVC) IS NOT ACCEPTABLE.AFTER FINALIZATION OF RATE CONTRACT, PO QUANTITY WILL BE PLACED AS PER REQUIREMENT.

(B) SUPPLY CONDITION :

1. ITEM TO BE SUPPLIED AT BHEL HERP STORES.
2. PRE-DESPATCH INSPECTION WILL BE CARRIED OUT AT PARTY'S WORKS BY BHEL REPRESENTATIVE AS PER QUALITY PLAN RV/C&F/21 REV-10

(C) TECHNICAL DELIVERY CONDITION :

1. MATERIAL SHOULD BE AS PER SPEC. MENTIONED IN THE DESCRIPTION/DRG.
2. DIMENSIONS AND TOLERANCES TO BE MAINTAINED AS PER DRG.
3. HEAT TREATMENT CHART IS REQUIRED.
4. DIMENSION REPORT IS REQUIRED.
5. ALL TECHNICAL REQUIREMENT MENTIONED IN THE DRG./SPEC & QP MUST BE STRICTLY FULFILLED.
6. VENDOR SHOULD PROCURE RAW MATERIAL FOR FORGING FROM BHEL APPROVED SOURCES AS PER PMD SA01

(D) TEST CERTIFICATE :

- 1) REQUIRED FOR CHEMICAL & MECHANICAL PROPERTIES FOR EACH HEAT No.
- 2) TEST RESULTS OF UST AND MPI FOR FOR ITEM SPEC. AA19332

(E) GUARANTEE CERTIFICATE: REQUIRED FOR 24 MONTHS AGAINST ANY MANUFACTURING DEFECTS FROM THE DATE OF RECEIPT AT BHEL HERP.

(F) PACKING INSTRUCTIONS: ALL ITEM SHOULD BE SUPPLIED IN LOOSE CONDITION WITH PROPER STACKING AT VEHICLE.

(G) RATE CONTRACT VALIDITY: FOR 1 (ONE) YEAR FROM THE RC-PO DATE.

(H) SPECIAL REMARKS:

1. DUE TO LARGE QUANTITY & VALUE OF MILL SPARES, MORE THAN ONE SOURCE SHOULD BE CONSIDERED FOR MEETING OUR REQUIREMENT.
2. ITEM WISE MAXIMUM QTY IN EACH LOT (WHICH MAY BE REQUIRED IN A PARTICULAR ORDER) WILL BE AS MENTIONED IN ANNEXURE-- RC-LOT-BA02/02.
- 3 .DELIVERY IS WITHIN 04 MONTHS FROM DATE OF PO FOR FIRST LOT. THERE WILL BE A GAP OF 01 MONTH BETWEEN TWO CONSECUTIVE LOTS.EARLY DELIVERY IS ACCEPTABLE.

(I) SPLITTING CONDITION:

1. THERE WILL BE NO DISTRIBUTION IN ITEMS NO RV1930132824, RV1930132832, RV1930132689, RV1930132697, RV1930132677.

2. THERE WILL BE SPLITTING BETWEEN TWO VENDORS IN THE RATIO OF L1:L2::60:40 IN ITEMS NO RV1930132026, RV1930132310
RV1930132400, RV1930132427.

3. THERE WILL BE SPLITTING BETWEEN THREE VENDORS IN THE RATIO OF L1:L2:L3::50:35:15 IN ITEMS NO RV1930132018.

4. THE EQUATED L1 RATES OF ITEMS WOULD BE COUNTER OFFERED TO THE NEXT HIGHER BIDDER IN ORDER OF THEIR RANKING AND THE QUANTITY WOULD BE GIVEN TO THE BIDDER WHO ACCEPT THE EQUATED L1 PRICE ON THE BASIS OF THEIR RANKING IN THE PRICE BID.

5. IF NONE OF THE OTHER BIDDERS ACCEPT THE L1 PRICE, THEN THE ENTIRE QUANTITY OF THE TENDER WOULD BE ORDERED TO THE ORIGINAL L1 PARTY ONLY.

6. IN NO CASE, H1 BIDDER SHALL BE COUNTER OFFERED EQUATED L1 RATE.

7. AT ANY POINT OF TIME OR IF THE PERFORMANCE OF ANY VENDOR IS FOUND UNSATISFACTORY, THE ABOVE DISTRIBUTION RATIO MAY BE CANCELLED OR CHANGED BY BHEL AND ITEMS MAY BE PROCURED FROM PERFORMING VENDORS.

(J) REVERSE AUCTION:

1. BHEL SHALL BE RESORTING TO REVERSE AUCTION (RA) (GUIDELINES AS AVAILABLE ON WWW.BHEL.COM) FOR THIS TENDER. RA SHALL BE CONDUCTED AMONG ALL THE TECHNO-COMMERCIALLY QUALIFIED BIDDERS. PRICE BIDS OF ALL TECHNO-COMMERCIALLY QUALIFIED BIDDERS SHALL BE OPENED AND SAME SHALL BE CONSIDERED AS INITIAL BIDS OF BIDDERS IN RA. IN CASE ANY BIDDER (S)DO(ES) NOT PARTICIPATE IN ONLINE REVERSE AUCTION, THEIR PRICE BID ALONG WITH APPLICABLE LOADING, IF ANY, SHALL BE CONSIDERED FOR RANKING.

IF ANY OF THE VENDORS DO NOT ACCEPT THE ABOVE POINT, THEIR OFFER MAY BE LIABLE FOR REJECTION WITHOUT INTIMATION.

2. RA WILL BE CARRIED OUT ON INDIVIDUAL LINE ITEM WISE BASIS COVERED IN THE ENQUIRY AND RATE CONTRACT SHALL BE DONE ACCORDINGLY (ITEM WISE).

(K). AS THE ENQUIRY EVALUATION IS ON ITEM WISE BASIS , BIDDERS ARE ALLOWED TO QUOTE FOR PARTIAL LINE ITEMS/SELECTED LINE ITEMS OF ENQUIRY.

(L) CLAUSE FOR INTEGRITY PACT (IP) SHALL BE AS PER ANNEXURE-1 & 2 ATTACHED. BIDDER SHALL SUBMIT THE ATTACHED ANNEXURE-1 FILLED, SIGNED AND STAMPED.

(M) OTHER TERMS & CONDITIONS OF THIS ENQUIRY SHALL BE AS PER ATTACHED GTC.

ANNEXURE--RC-LOT-BA02/02

S.NO	MaterialCode	Description	RC QTY	MAX LOT
1	RV1930132018	L.J. HOUSING (HY-6.0 F) - ROUGH M/CD FORGING AS PER DRG. 36137690010/08 WITH MATL AS PER SPECN. AA19332/10	150	30
2	RV1930132026	JOURNAL SHAFT (HY-33.F) - ROUGH M/CD FORGING AS PER DRG. 36137690011/03 WITH MATL AS PER SPECN. AA19332/10	80	20
3	RV1930132824	R/MCD FORGING OF JOURNAL SHAFT(HY-1101.09.F) AS PER DRG. 36100490184/01 WITH MATL. AS PER SPECN. AA19332/10	5	5
4	RV1930132832	R/MCD FORGING OF TRUNION SHAFT(HY-1102.01) AS PER DRG. 46100490249/00 WITH MATL. AS PER SPECN. AA19332/10(BHEL HYD MATL CODE BA9413253250)	5	5
5	RV1930132689	LOWER JOURNAL HOUSING (HY-902.04.F) - ROUGH M/CD FORGING AS PER DRG. 36108802392/03 WITH MATL. AS PER SPECN. AA19332/10	30	10
6	RV1930132310*	L.J. HOUSING (HY-312.A.02) - ROUGH MACHINED FORGING AS PER DRG. HY-312.A.02.F WITH MATL AS PER SPECN. AA19332/10	50	20
7	RV1930132400	JOURNAL SHAFT (HY-312.A.01) - ROUGH M/CD FORGING AS PER DRG. 36100090173/01 WITH MATL AS PER SPECN. AA19332/10	50	20
8	RV1930132427	U.J. HOUSING (HY-312.A.05.X) - ROUGH M/CD FORGING AS PER DRG. 36100090168/01 WITH MATL AS PER SPECN. AA19332/10	45	20
9	RV1930132697	JOURNAL SHAFT (HY-902.01) - ROUGH M/CD FORGING AS PER DRG. NO. 36108802391/01 WITH MATL AS PER SPECN. AA19332/10	15	5
10	RV1930132677	UPPER JOURNAL HOUSING (HY-902.03.F) - ROUGH M/CD FORGING AS PER DRG. NO. 36108802393/01 WITH MATL AS PER SPECN. AA19332/10	25	10

PQR

Sl. No.	BHEL Terms	Supplier's ComplianceYES/NO
1	Offers are accepted from:	
1.a	Only Manufacturer's Offers shall be considered for the Tender Enquiry.	
2	Supplier shall give list of In-House Facilities:	
2.a	Vendor shall have in-House necessary Manufacturing facilities required for manufacturing and supply of item/s as per drawing/specification.	
2.b	BHEL reserves right to visit the Works of the Manufacturer for Physical verification of the Manufacturing facilities (as declared by them) and assessment of their Quality systems during Technical Evaluation of the Offers.	
3	Experience:	
3.a	Bidders shall submit the necessary documents proving their Experience in Supplying same or similar items to any Power Plant equipment Manufacturer (worldwide or within India) in last three years from the date of Enquiry. Documentary evidences to be submitted in the form of Customer's Purchase Order copies / Material Acceptance Report and item drawings/specifications. Documentary evidences submitted shall strictly meet all the technical requirement of the NIT.	
3.b	BHEL reserves right to verify the details from the Bidder's customers based on Documents submitted as a part of past experience. BHEL may ask for other relevant documents in line with above to review the capacity and capability of vendor with respect to enquired items.	
4	Manufacturing Process Plan:	
4.a	Bidders shall submit detailed Manufacturing process Plan along with the Technical Offer.	
5	Annual Turnover:	
5.a	Turnover of the supplier should be as per GeM (Government e-market place) guide lines (Maximum limit to be taken). Bidders should enclose Audited Balance sheets and Profit & Loss account statement of last three consecutive years in the Part I bid.	
6	Others	
6.a	Bidder will supply item/s exactly as per enquiry.	
Note: Non Submission of the above requested documents/non compliance to the above points will result in rejection of the Offers without further Notice/Intimation to the Bidder and no correspondance will be entertained at later date.		

On Bidder's office letter pad

Make in India (Model Certificate) Annexure-I

Self-Declaration

Enquiry No.	
Enquiry Date	

In line with Government public procurement order Number P-45021/2/2017-B.E-II dated 15.06.2017, and further modified order dt. 28.05.2018, 29.05-2019 and 04.06.2020

I / We hereby declare that I / We are a "Local Supplier" meeting the requirement of minimum local content (.....%) defined in the above government notification for the goods against above mentioned enquiry Number.

Details of location at which local value addition will be made is as follows:

Door No.	
Street / Address 1	
Street / Address 2	
District	
State	
Country	
PIN Code	

We also understand that the false declarations will be considered as breach of Integrity and liable for action.

For Company Name:

Seal:

Signature:

Date:

Place:

(Please fill all the yellow color field)

INTEGRITY PACT**Between**

Bharat Heavy Electricals Ltd. (BHEL), a company registered under the Companies Act 1956 and having its registered office at "BHEL House", Siri Fort, New Delhi - 110049 (India) hereinafter referred to as "The Principal", which expression unless repugnant to the context or meaning hereof shall include its successors or assigns of the ONE PART

and

_____, (description of the party along with address), hereinafter referred to as "The Bidder/ Contractor" which expression unless repugnant to the context or meaning hereof shall include its successors or assigns of the OTHER PART

Preamble

The Principal intends to award, under laid-down organizational procedures, contract/s for _____

_____. The Principal values full compliance with all relevant laws of the land, rules and regulations, and the principles of economic use of resources, and of fairness and transparency in its relations with its Bidder(s)/ Contractor(s).

In order to achieve these goals, the Principal will appoint Independent External Monitor(s), who will monitor the tender process and the execution of the contract for compliance with the principles mentioned above.

Section 1- Commitments of the Principal

1.1 The Principal commits itself to take all measures necessary to prevent corruption and to observe the following principles:-

1.1.1 No employee of the Principal, personally or through family members, will in connection with the tender for, or the execution of a contract, demand, take a promise for or accept, for self or third person, any material or immaterial benefit which the person is not legally entitled to.

1.1.2 The Principal will, during the tender process treat all Bidder(s) with equity and reason. The Principal will in particular, before and during the tender process, provide to all Bidder(s) the same information and will not provide to any Bidder(s) confidential/ additional information through which the Bidder(s) could obtain an advantage in relation to the tender process or the contract execution.

1.1.3 The Principal will exclude from the process all known prejudiced persons.

1.2 If the Principal obtains information on the conduct of any of its employees which is a penal offence under the Indian Penal Code 1860 and Prevention of Corruption Act 1988 or any other statutory penal enactment, or if there be a substantive suspicion in this regard, the Principal will inform its Vigilance Office and in addition can initiate disciplinary actions:

Section 2 - Commitments of the Bidder(s)/ Contractor(s)

- 2.1 The Bidder(s)/ Contractor(s) commit himself to take all measures necessary to prevent corruption. He commits himself to observe the following principles during his participation in the tender process and during the contract execution.
- 2.1.1 The Bidder(s)/ Contractor(s) will not, directly or through any other person or firm, offer, promise or give to the Principal or to any of the Principal's employees involved in the tender process or the execution of the contract or to any third person any material, immaterial or any other benefit which he/ she is not legally entitled to, in order to obtain in exchange any advantage of any kind whatsoever during the tender process or during the execution of the contract.
- 2.1.2 The Bidder(s)/ Contractor(s) will not enter with other Bidder(s) into any illegal or undisclosed agreement or understanding, whether formal or informal. This applies in particular to prices, specifications, certifications, subsidiary contracts, submission or non-submission of bids or any other actions to restrict competitiveness or to introduce cartelization in the bidding process.
- 2.1.3 The Bidder(s)/ Contractor(s) will not commit any penal offence under the relevant Indian Penal Code (IPC) and Prevention of Corruption Act; further the Bidder(s)/ Contractor(s) will not use improperly, for purposes of competition or personal gain, or pass on to others, any information or document provided by the Principal as part of the business relationship, regarding plans, technical proposals and business details, including information contained or transmitted electronically.
- 2.1.4 Foreign Bidder(s)/ Contractor(s) shall disclose the name and address of agents and representatives in India and Indian Bidder(s)/ Contractor(s) to disclose their foreign principals or associates. The Bidder(s)/ Contractor(s) will, when presenting his bid, disclose any and all payments he has made, and is committed to or intends to make to agents, brokers or any other intermediaries in connection with the award of the contract.
- 2.2 The Bidder(s)/ Contractor(s) will not instigate third persons to commit offences outlined above or be an accessory to such offences.
- 2.3 The Bidder(s)/ Contractor(s) shall not approach the Courts while representing the matters to IEMs and will await their decision in the matter.

Section 3 - Disqualification from tender process and exclusion from future contracts

If the Bidder(s)/ Contractor(s), before award or during execution has committed a transgression through a violation of Section 2 above, or acts in any other manner such as to put his reliability or credibility in question, the Principal is entitled to disqualify the Bidder(s)/ Contractor(s) from the tender process or take action as per the separate "Guidelines on Banning of Business dealings with Suppliers/ Contractors", framed by the Principal.

Section 4 - Compensation for Damages

- 4.1 If the Principal has disqualified the Bidder from the tender process prior to the award according to Section 3, the Principal is entitled to demand and recover the damages equivalent Earnest Money Deposit/ Bid Security.
- 4.2 If the Principal has terminated the contract according to Section 3, or if the Principal is entitled to terminate the contract according to section 3, the Principal shall be entitled to

demand and recover from the Contractor liquidated damages equivalent to 5% of the contract value or the amount equivalent to Security Deposit/ Performance Bank Guarantee, whichever is higher.

Section 5 - Previous Transgression

- 5.1 The Bidder declares that no previous transgressions occurred in the last 3 years with any other company in any country conforming to the anti-corruption approach or with any other Public Sector Enterprise in India that could justify his exclusion from the tender process.
- 5.2 If the Bidder makes incorrect statement on this subject, he can be disqualified from the tender process or the contract, if already awarded, can be terminated for such reason.

Section 6 - Equal treatment of all Bidders/ Contractors / Sub-contractors

- 6.1 The Principal will enter into agreements with identical conditions as this one with all Bidders and Contractors. In case of sub-contracting, the Principal contractor shall be responsible for the adoption of IP by his sub-contractors and shall continue to remain responsible for any default by his sub-contractors:
- 6.2 The Principal will disqualify from the tender process all bidders who do not sign this pact or violate its provisions.

Section 7 - Criminal Charges against violating Bidders/ Contractors /Subcontractors

If the Principal obtains knowledge of conduct of a Bidder, Contractor or Subcontractor, or of an employee or a representative or an associate of a Bidder, Contractor or Subcontractor which constitutes corruption, or if the Principal has substantive suspicion in this regard, the Principal will inform the Vigilance Office.

Section 8 - Independent External Monitor(s)

- 8.1 The Principal appoints competent and credible Independent External Monitor for this Pact. The task of the Monitor is to review independently and objectively, whether and to what extent the parties comply with the obligations under this agreement.
- 8.2 The Monitor is not subject to instructions by the representatives of the parties and performs his functions neutrally and independently. He reports to the CMD, BHEL.
- 8.3 The Bidder(s)/ Contractor(s) accepts that the Monitor has the right to access without restriction to all contract documentation of the Principal including that provided by the Bidder(s)/ Contractor(s). The Bidder(s)/ Contractor(s) will grant the monitor, upon his request and demonstration of a valid interest, unrestricted and unconditional access to his contract documentation. The same is applicable to Sub-contractor(s). The Monitor is under contractual obligation to treat the information and documents of the Bidder(s)/ Contractor(s) / Sub-contractor(s) with confidentiality in line with Non- disclosure agreement.
- 8.4 The Principal will provide to the Monitor sufficient information about all meetings among the parties related to the contract provided such meetings could have an impact on the contractual relations between the Principal and the Contractor. The parties offer to the Monitor the option to participate in such meetings.

- 8.5 The role of IEMs is advisory, would not be legally binding and it is restricted to resolving issues raised by an intending bidder regarding any aspect of the tender which allegedly restricts competition or bias towards some bidders. At the same time, it must be understood that IEMs are not consultants to the Management. Their role is independent in nature and the advice once tendered would not be subject to review at the request of the organization.
- 8.6 For ensuring the desired transparency and objectivity in dealing with the complaints arising out of any tendering process, the matter should be examined by the full panel of IEMs jointly as far as possible, who would look into the records, conduct an investigation, and submit their joint recommendations to the Management.
- 8.7 The IEMs would examine all complaints received by them and give their recommendations/ views to CMD, BHEL, at the earliest. They may also send their report directly to the CVO and the Commission, in case of suspicion of serious irregularities requiring legal/ administrative action. IEMs will tender their advice on the complaints within 10 days as far as possible.
- 8.8 The CMD, BHEL shall decide the compensation to be paid to the Monitor and its terms and conditions.
- 8.9 IEM should examine the process integrity, they are not expected to concern themselves with fixing of responsibility of officers. Complaints alleging mala fide on the part of any officer of the organization should be looked into by the CVO of the concerned organisation.
- 8.10 If the Monitor has reported to the CMD, BHEL, a substantiated suspicion of an offence under relevant Indian Penal Code/ Prevention of Corruption Act, and the CMD, BHEL has not, within reasonable time, taken visible action to proceed against such offence or reported it to the Vigilance Office, the Monitor may also transmit this information directly to the Central Vigilance Commissioner, Government of India.
- 8.11 The number of Independent External Monitor(s) shall be decided by the CMD, BHEL.
- 8.12 The word 'Monitor' would include both singular and plural.

Section 9 - Pact Duration

- 9.1 This Pact shall be operative from the date IP is signed by both the parties till the final completion of contract for successful bidder and for all other bidders 6 months after the contract has been awarded. Issues like warranty / guarantee etc. should be outside the purview of IEMs.
- 9.2 If any claim is made/ lodged during currency of IP, the same shall be binding and continue to be valid despite the lapse of this pact as specified above, unless it is discharged/ determined by the CMD, BHEL.

Section 10 - Other Provisions

- 10.1 This agreement is subject to Indian Laws and jurisdiction shall be registered office of the Principal, i.e. New Delhi.

- 10.2 Changes and supplements as well as termination notices need to be made in writing. Side agreements have not been made.
- 10.3 If the Contractor is a partnership or a consortium, this agreement must be signed by all partners or consortium members.
- 10.4 Should one or several provisions of this agreement turn out to be invalid, the remainder of this agreement remains valid. In this case, the parties will strive to come to an agreement to their original intentions.
- 10.5 Only those bidders / contractors who have entered into this agreement with the Principal would be competent to participate in the bidding. In other words, entering into this agreement would be a preliminary qualification.

For & On behalf of the Principal

(Office Seal)

Place-----

Date-----

Witness:-----

(Name & Address) -----

For & On behalf of the Bidder/

Contractor

(Office Seal)

Witness:-----

(Name & Address) -----

Clause on IP in the tender

Integrity Pact (IP)

- (a) IP is a tool to ensure that activities and transactions between the Company and its Bidders/ Contractors are handled in a fair, transparent and corruption free manner. Following Independent External Monitors (IEMs) on the present panel have been appointed by BHEL with the approval of CVC to oversee implementation of IP in BHEL.

SI	IEM	Email
1.	Shri Otem Dai, IAS (Retd.)	iem1@bhel.in
2.	Shri Bishwamitra Pandey, IRAS (Retd.)	iem2@bhel.in
3.	Shri Mukesh Mittal, IRS (Retd.)	iem3@bhel.in

- (b) The IP as enclosed with the tender is to be submitted (duly signed by authorized signatory) along with techno-commercial bid (Part-I, in case of two/ three part bid). Only those bidders who have entered into such an IP with BHEL would be competent to participate in the bidding. In other words, entering into this Pact would be a preliminary qualification.
- (c) Please refer Section-8 of IP for Role and Responsibilities of IEMs. In case of any complaint arising out of the tendering process, the matter may be referred to any of the above IEM(s). All correspondence with the IEMs shall be done through email only.

Note:

No routine correspondence shall be addressed to the IEM (phone/ post/ email) regarding the clarifications, time extensions or any other administrative queries, etc on the tender issued. All such clarification/ issues shall be addressed directly to the tender issuing (procurement) department's officials whose contact details are provided below:

Details of contact person(s):

(1)
Name: _____
Deptt: _____
Address: _____
Phone: (Landline/ Mobile) _____
Email: _____
Fax: _____

(2)
Name: _____
Deptt: _____
Address: _____
Phone: (Landline/ Mobile) _____
Email: _____
Fax: _____

**GENERAL COMMERCIAL TERMS & CONDITIONS OF ENQUIRY
(FOR INDIAN VENDORS)**

**Amendment- 24
ANNEXURE-A**

ITEM DESCRIPTION:

ENQUIRY NO:

Sl No	BHEL STANDARD TERMS & CONDITIONS	Confirmation of supplier (Yes/No)
1	A) OFFER MUST BE SUBMITTED IN TWO PART BID SYSTEM NAMELY TECHNO-COMMERCIAL BID & PRICE BID FOR THE ITEM AS PER ENQUIRY IN SEPARATE SEALED COVERS: (I) TECHNO – COMMERCIAL BID & (II) PRICE BID SHOULD BE CLEARLY SUPERSCRIBED THE ENQUIRY NO. AND DUE DATE ON THE ENVELOPES. (B) UN-PRICED OFFER WITH TECHNICAL BID IS REQUIRED TO BE FURNISHED BY THE VENDOR. TECHNICAL OFFER SHOULD CLEARLY REFLECT AT LEAST OUR MATERIAL CODE, ITEM DESCRIPTION & QUANTITY. (C) THE DIFFERENCE BETWEEN “UN-PRICED OFFER” AND “PRICED OFFER” SHOULD BE ONLY THE PRICES WHEREVER APPLICABLE. THE RATES AND AMOUNT SHOULD BE CLEARLY WRITTEN IN FIGURES AND WORDS BOTH WITHOUT ANY CUTTING / OVERWRITING. (D) IMPORTANT POINT FOR VENDOR WHO HAVE NOT SUBMITTED THE SRF (SUPPLIER REGISTRATION FORM) SO FAR: THE VENDORS, WHO HAVE NOT SUBMITTED THE SRF SO FAR, MUST SUBMIT THE SAME ALONG WITH PART- 1 BID. THE SRF TO BE DOWNLOADED FROM WWW.BHEL.COM OR https://herp.bhel.com .	
2	BID SHOULD BE FREE FROM CORRECTION, OVERWRITING, USING CORRECTIVE FLUID, ETC. ANY INTERLINEATION , CUTTING , ERASURE OR OVERWRITING SHALL BE VALID ONLY IF THEY ARE ATTESTED UNDER FULL SIGNATURE(S) OF PERSON(S) SIGNING THE BID ELSE BID SHALL BE LIABLE FOR REJECTION .	
3	YOUR TECHNO COMMERCIAL BID SHOULD MENTION THAT PRICE BID HAS BEEN SENT IN A SEPARATE ENVELOPE GIVING ITS REFERENCE.	
4	VENDOR TO ENSURE THAT ITEM & QUANTITY MENTIONED IN THE OFFERS ARE EXACTLY SAME AS PER ENQUIRY. IF ANY DEVIATION IS THERE PARTY MUST MENTION SPECIFIC HEREWITH OTHERWISE BHEL SHALL CONSIDER THAT ITEM & QUANTITY AS REQUIRED IN ENQUIRY.	
5	PLEASE MAKE SURE THAT THERE IS NO DISCREPANCY IN BETWEEN ACCEPTED TERMS & CONDITIONS MENTIONED IN THE CHECK LIST AND QUOTATION SUBMITTED BY VENDOR AND IF FOUND SO THEN THE TERMS & CONDITIONS WHICH ARE BENEFICIAL TO BHEL WOULD ONLY BE CONSIDERED.	
6	THE TENDER RECEIVED AFTER 14:00 HRS ON THE DUE DATE WILL NOT BE CONSIDERED.	
7	PART-I CONTAINING THE TECHNO-COMMERCIAL BID WILL BE OPENED ON THE DATE AND TIME SPECIFIED IN THE ENQUIRY, IN THE PRESENCE OF THOSE TENDERERS WHO WISH TO ATTEND. PART-II i.e., PRICE BID WILL BE OPENED ONLY OF THOSE BIDDERS WHO ARE FOUND TECHNO-COMMERCIALY SUITABLE AFTER SCRUTINY OF THEIR PART-I OFFERS.	
8	NO REVISED OFFERS WILL BE ACCEPTED UNLESS ASKED BY BHEL AFTER OPENING OF PART-1 BID IN ANY CASE.	
9	THE RATE OF GST SHOULD BE CLEARLY MENTIONED IN THE OFFER.	
10	VALIDITY OF OFFER SHOULD BE MINIMUM 90 DAYS FROM THE DATE OF TECHNO - COMMERCIAL BID OPENING OR 60 DAYS FROM THE REVERSE AUCTION DATE.	
11	BHEL RESERVES THE RIGHT TO REJECT THE OFFER, WHICH IS HAVING DEVIATIONS TO THE TERMS AND CONDITIONS GIVEN IN THE TENDER ENQUIRY.	
12	PRICING TERMS: PRICES ONCE QUOTED SHALL REMAIN FIRM WITHIN THE VALIDITY OR ANY EXTENSION THEREOF FOR PLACEMENT OF ORDER, TILL COMPLETE EXECUTION OF THE ORDER, WITHOUT ANY ESCALATION/INCREASE FOR ANY REASON, WHATSOEVER, UNLESS SPECIFICALLY PROVIDED FOR IN THE ENQUIRY & PO. IN CASE OF FOREIGN VENDORS, THE QUOTED PRICE SHALL BE TAKEN AS INCLUSIVE OF THIRD PARTY INSPECTION AND TESTING CHARGES AS CALLED FOR IN THE NIT.	
13	BID EVALUATION: UNLESS SPECIFIED IN THE TENDER, VENDOR MUST NOTE THAT BHEL WILL ARRIVE THE L1 STATUS FOR EACH ITEM ON LANDED COST BASIS. ACCORDINGLY, ORDER SHALL BE PLACED ON LOWEST BIDDER ON INDIVIDUAL ITEM BASIS ONLY, UNLESS BHEL ASK FOR TERMS OTHER THAN THIS ON EXCEPTION BASIS. IN THE COURSE OF EVALUATION, IF MORE THAN ONE BIDDER HAPPENS TO OCCUPY L-1 STATUS, EFFECTIVE L-1 WILL BE DECIDED BY SOLICITING DISCOUNTS FROM THE RESPECTIVE L-1 BIDDERS. IN CASE MORE THAN ONE BIDDERS HAPPENS TO OCCUPY THE L-1 STATUS EVEN AFTER SOLICITING DISCOUNT, THE L-1 BIDDER SHALL BE DECIDED BY A TOSS/DRAW OF LOTS, IN THE PRESENCE OF THE RESPECTIVE BIDDER(S) OR THEIR REPRESENTATIVE(S). RANKING WILL BE DONE ACCORDINGLY. BHEL'S DECISION IN SUCH SITUATION SHALL BE FINAL AND BINDING.	
14	TERMS OF DELIVERY: I. FOR INDIGENOUS SUPPLIERS: THE TERMS OF DELIVERY SHOULD BE QUOTED ON F.O.R. DESTINATION (BHEL HERP STORES VARANASI) BASIS ONLY (i.e. FREIGHT & INSURANCE ON VENDOR'S ACCOUNT ONLY). IF ANY BIDDER STILL QUOTES OTHER DELIVERY TERM IN PLACE OF BHEL HERP STORES, THEIR OFFER MAY NOT BE CONSIDERED FOR FURTHER PROCESSING. IT MUST BE SPECIFICALLY NOTED.	
15	IF ANY INDIAN SUPPLIERS ARRANGE SUPPLY FROM FOREIGN PRINCIPLES/WORKS, TERMS OF DELIVERY SHOULD BE QUOTED ON CIF JNPT MUMBAI (INDIA) SEA PORT BASIS ONLY (i.e. FREIGHT & INSURANCE ON VENDOR'S ACCOUNT UPTO JNPT MUMBAI (INDIA) SEA PORT) OR CFR MUMBAI AIRPORT. HOWEVER FREIGHT CHARGES AS PER BHEL TRANSPORT CONTRACT FROM JNPT MUMBAI SEAPORT/MUMBAI AIRPORT TO BHEL VARANASI FOR EACH ITEM WILL BE LOADED AT THE TIME OF TOTAL LANDED COST CALCULATION.	
16	INSURANCE CHARGES SHALL BE TO VENDOR'S ACCOUNT ONLY IF PRICE QUOTED ON BHEL HERP STORES BASIS. IN CASE PRICE QUOTED IS ON CIF JNPT MUMBAI BASIS/ CFR MUMBAI AIRPORT BASIS, INSURANCE UP TO CIF JNPT MUMBAI/ MUMBAI AIRPORT SHALL BE IN VENDOR ACCOUNT.	
17	PAYMENT TERMS: I.FOR MSEs VENDORS: 100% AGAINST SRV WITHIN 45 DAYS THROUGH EFT (ELECTRONIC FUND TRANSFER) FROM THE DATE OF RECEIPT OF MATERIAL (DATE OF SRV) AT BHEL HERP VARANASI STORES AS PER PO. II.FOR MEDIUM ENTERPRISES VENDORS: 100% AGAINST SRV WITHIN 60 DAYS THROUGH EFT (ELECTRONIC FUND TRANSFER) FROM THE DATE OF RECEIPT OF MATERIAL (DATE OF SRV) AT BHEL HERP VARANASI STORES AS PER PO. III. FOR NON- MSME: 100% AGAINST SRV WITHIN 90 DAYS THROUGH EFT (ELECTRONIC FUND TRANSFER) FROM THE DATE OF RECEIPT OF MATERIAL (DATE OF SRV) AT BHEL HERP VARANASI STORES AS PER PO. IV.BHEL HERP WILL MAKE PAYMENTS IN TWO PARTS: - PART-I: BASIC INVOICE VALUE AND ALL OTHER CHARGES (EXCEPT GST AMOUNT) WILL BE PAID AS PER P.O. PAYMENT TERMS. PART-II: GST PORTION OF INVOICE VALUE WILL BE PAID ONLY AFTER FULFILLING FOLLOWING CONDITIONS: (A) PAYMENT OF GST AMOUNT INTO GOVT. ACCOUNT BY SUPPLIER AGAINST INVOICE RAISED TO BHEL. (B) FILING OF GST RETURN (C) DISPLAY OF GST CREDIT AGAINST BHEL GSTIN NO.09AAACB4146P2ZC IN GSTR-2B ON GSTN PORTAL. Note: 1. PAYMENT WILL BE MADE AFTER ACCEPTANCE OF MATERIAL. 2. ADVANCE PAYMENT IS NOT ACCEPTABLE BY BHEL HERP VARANASI IN ANY CASE. 3. IF ANY SUPPLIER FALLS UNDER “NON MSE” OR “NON MEDIUM” CATEGORY, THEIR PAYMENT TERM WILL BE CONSIDERED AS NON MSME SUPPLIER PAYMENT WITHOUT ANY INTIMATION.	
18	LOADING OF PAYMENT TERM: IN CASE OF DEVIATION, LOADING OF INTEREST RATE @SBI MCLR RATE + 6% (AS ON PART-1 OPENING DATE) SHALL BE LOADED WHILE ARRIVING AT LANDED COST TO BHEL.	
19	LIQUIDATED DAMAGES/ LATE DELIVERY (LD) PENALTY CLAUSE: SUBJECT TO FORCE MAJEURE CONDITIONS, FAILURE TO SUPPLY WITHIN PURCHASE ORDER DELIVERY SCHEDULE WILL MAKE THE SUPPLIER LIABLE TO AN UNCONDITIONAL PENALTY OF 0.5 % PER WEEK OR PART THEREOF SUBJECT TO THE MAXIMUM OF 10% OF THE UNDELIVERED PURCHASE ORDER VALUE EXCLUDING TAXES & DUTIES. NO GRACE PERIOD SHALL BE GIVEN.	
20	LOADING OF LIQUIDATED DAMAGES (LD): DEVIATION TO ABOVE STANDARD PENALTY CLAUSE, MAXIMUM LOADING OF 10% (IN CASE OF NON ACCEPTANCE OF LD CLAUSE) OR PART THEREOF (IN CASE OF PART ACCEPTANCE OF LD) SHALL BE LOADED WHILE ARRIVING LANDED COST TO BHEL. LOADING OF DELIVERY TERM: FURTHER IF DEVIATION IS FOUND IN THE ACCEPTED DELIVERY TERM AS WELL AS ACCEPTED PENALTY TERM, SUITABLE LOADING BASED ON TRANSPORTATION TIME TO BE TAKEN SHALL BE LOADED WHILE ARRIVING LANDED COST TO BHEL HERP STORES WHICH MAY BE AS BELOW: (i) 1% OF THE BASIC COST FOR INDIAN SUPPLIERS,	

**GENERAL COMMERCIAL TERMS & CONDITIONS OF ENQUIRY
(FOR INDIAN VENDORS)**

**Amendment- 24
ANNEXURE-A**

21	DELIVERY PERIOD: VENDOR SHOULD STRICTLY QUOTE THE DELIVERY PERIOD AS MENTIONED IN NIT.	
22	IF ANY VENDOR DOES NOT SUPPLY THE ITEM WITHIN THE PURCHASE ORDER DELIVERY PERIOD, BHEL MAY/MAY NOT ACCEPT THE SUPPLY AT ITS SOLE DISCRETION.	
23	BANK GUARANTEE: THE COST OF BHEL FREE ISSUE MATERIALS PER SET/PER ASSEMBLY AND TOTAL COST OF FIM FOR THE ENQUIRY ARE MENTIONED IN NIT. IN THIS REGARD: 1. PARTY WILL HAVE TO SUBMIT EQUAL AMOUNT OF SECURITY DEPOSIT (IN THE FORM OF 25% BG/FDR/DD/CHEQUE/BANK TRANSFER AND 75% INDEMNITY BOND) TOWARDS THE COST OF BHEL MATERIALS TO BE ISSUED TO THEM BEFORE THE ISSUE OF BHEL MATERIALS TO THEM. AT ANY POINT OF TIME, PROPORTIONATE SECURITY DEPOSIT OF TOTAL/CUMMULATIVE MATERIAL VALUE SHOULD BE MAINTAINED. 2. BHEL MAY ASK THE SUPPLIER FOR SUBMISSION OF FULL SECURITY DEPOSIT AMOUNT OR PART DEPENDING UPON THE AVAILABILITY OF FREE ISSUE MATERIALS AT OUR END. 3. PARTY MUST HAVE TO SUBMIT THE SAME WITHIN 02 WEEK TIME FROM THE DATE OF WRITTEN INTIMATION BY BHEL WITHOUT FAIL OTHERWISE IT WOULD TREATED AS FAILURE OF HONOURING PO TERMS AND ACCORDINGLY BHEL MAY CANCEL THE PURCHASE ORDER AND INITIATE ALTERNATE PROCUREMENT ACTION AT SUPPLIER RISK & COST. 4. IN CASE OF ABSENCE OF DESIRED SECURITY DEPOSIT AT BHEL END AND ALSO NON RESPONSE OF POINT NO. 03 AS ABOVE, I. BHEL MAY HOLD THE PENDING PAYMENTS OF SUPPLIER AVAILABLE AT BHEL END WITHOUT ANY INTIMATION. II. IF NO PAYMENT IS PENDING AT BHEL END, ACTION FOR ALTERNATE PROCUREMENT ACTION MAY BE INITIATED. 5. THE FORMAT OF BG SHALL BE PER ATTACHED ANNEXURE-BG/FIM ONLY.	
24	TRANSPORTATION CHARGES FOR SENDING BHEL FREE ISSUE MATERIALS (FIM) TO THE PARTY WORKS WILL BE BORNE BY BHEL ONLY. THE FREIGHT CHARGES FOR SENDING THE BHEL FIM FROM HERP STORES TO PARTY'S WORK FOR EACH ITEM WILL BE LOADED AS PER BHEL TRANSPORT CONTRACT AT THE TIME OF TOTAL LANDED COST CALCULATION. HOWEVER, VARANASI/LOCAL BASED VENDORS WILL LIFT THE FIM FROM BHEL STORES AND BORNE ITS TRANSPORTATION CHARGES.	
25	IF BHEL ISSUES FREE ISSUE MATERIALS TO THE SUPPLIER, IT MUST BE RETURNED WITHIN THE TIME LIMIT AS PRESCRIBED IN GST LAW (PRESENTLY 01 (ONE) YEAR FROM THE DATE OF FREE ISSUE DATE) TO COMPLY THE GST RULES. IF ANY VENDOR DOES NOT RETURN THE BHEL FREE ISSUE MATERIALS AS MENTIONED ABOVE, THE FINANCIAL IMPLICATION ON ACCOUNT OF THIS, IF ANY, SHALL BE RECOVERED FROM THE PARTY BILLS.	
26	REVERSE AUCTION: BHEL SHALL BE RESORTING TO REVERSE AUCTION (RA) (GUIDELINES AS AVAILABLE ON WWW.BHEL.COM) FOR THIS TENDER. RA SHALL BE CONDUCTED AMONG ALL THE TECHNO-COMMERCIALY QUALIFIED BIDDERS. PRICE BIDS OF ALL TECHNO-COMMERCIALY QUALIFIED BIDDERS SHALL BE OPENED AND SAME SHALL BE CONSIDERED AS INITIAL BIDS OF BIDDERS IN RA. IN CASE ANY BIDDER(S) DO (ES) NOT PARTICIPATE IN ONLINE REVERSE AUCTION, THEIR SEALED ENVELOPE PRICE BID ALONG WITH APPLICABLE LOADING, IF ANY, SHALL BE CONSIDERED FOR RANKING.	
27	IF ANY OF THE VENDORS DO NOT ACCEPT THE ABOVE POINT MENTIONED AT SL. NO. 26, THEIR OFFER MAY BE LIABLE FOR REJECTION WITHOUT INTIMATION.	
28	RISK PURCHASE: IN CASE OF DELAY IN SUPPLIES/ DEFECTIVE SUPPLIES/NON EXECUTION OF PURCHASE ORDER ETC. (FOR DETAILS, REFER GUIDELINES FOR RISK PURCHASE), BHEL MAY CANCEL THE ORDER IN FULL OR PART THEREOF/ MAY ALSO MAKE THE PURCHASE OF SUCH MATERIALS FROM ELSEWHERE/ALTERNATIVE SOURCES AT THE RISK & COST OF SUPPLIER. BHEL MAY ALSO MANUFACTURE THE ITEM IN-HOUSE IN PART OR FULL DEPENDING UPON THE URGENCY OF THE ITEM. GUIDELINES FOR RISK PURCHASE IS AVAILABLE ON BHEL WEBSITE "https://herp.bhel.com" at "Notice". RESPECTIVE BIDDERS / SUPPLIERS MAY REFER THIS GUIDELINE BEFORE SUBMITTING THEIR OFFER AGAINST BHEL, HERP TENDER ENQUIRIES. IN CASE RISK PURCHASE IS APPLIED, BHEL SHALL TAKE ACTION AGAINST THE NON-PERFORMING AND/OR DEFAULTING SUPPLIERS/ CONTRACTORS IN LINE WITH THIS GUIDELINE ONLY.	
29	BHEL MAY SHORT CLOSE/CANCEL AN ORDER AT ANY TIME DURING THE CURRENCY OF THE CONTRACT/PO IRRESPECTIVE OF THE PO DELIVERY DATE, IF (I) THE WORK PROGRESS OF THE VENDOR IS POOR, OR (II) THE DELIVERY REQUIREMENT OF THE ITEM IS VERY CRITICAL & NOT BEING MET BY THE VENDOR ON WHICH ORDER HAS BEEN PLACED, OR (III) THERE IS NO RESPONSE FOR IMPROVEMENT IN DELIVERY AS PER BHEL REQUIREMENT,	
30	THE OFFERS OF THE BIDDERS WHO ARE ON THE BANNED LIST AND ALSO THE OFFER OF THE BIDDERS, WHO ENGAGE THE SERVICES OF THE BANNED FIRMS, SHALL BE REJECTED. THE LIST OF BANNED FIRMS IS AVAILABLE ON BHEL WEB SITE www.bhel.com	
31	RESERVATION RIGHTS OF BHEL: – BHEL RESERVES THE RIGHT TO REJECT ANY OR ALL QUOTATIONS WITHOUT ASSIGNING ANY REASONS THEREOF. BHEL ALSO RESERVES THE RIGHT TO INCREASE OR DECREASE THE TENDERED QUANTITIES. VENDORS SHOULD BE PREPARED TO ACCEPT ORDER FOR REDUCED QUANTITIES WITHOUT ANY EXTRA CHARGES. VENDOR SHOULD ALSO BE PREPARED FOR GIVING DISCOUNT IN CASE OF INCREASE IN QUANTITY.	
32	NON-DISCLOSURE AGREEMENT: ALL DRAWINGS AND STANDARDS ARE PROPRIETARY OF BHEL. IT MUST NOT BE USED IN ANY WAY DETRIMENTAL TO THE INTEREST OF THE COMPANY. ALL SUPPLIERS SHALL FURNISH NDAS (NON-DISCLOSURE AGREEMENT) AGAINST USE OF DOCUMENTS FURNISHED BY BHEL TOWARDS UN-AUTHORIZED USE EXCEPT FOR THE PURPOSE IT HAS BEEN FURNISHED.	
33	A. SETTLEMENT OF DISPUTES & ARBITRATION: I. ALL QUESTIONS/INTERPRETATIONS REGARDING SUBJECT MATTER OF THE CONTRACT SHALL BE DECIDED BY THE BHEL ON THE REQUEST OF THE VENDOR AND THE DECISION OF THE BHEL SHALL BE FINAL. II. IN CASE OF DISPUTE, STEPS SHALL BE TAKEN BY THE PARTIES TO THE CONTRACT TO SETTLE THE SAME THROUGH NEGOTIATIONS. III. IN CASE, DISPUTE IS NOT SETTLED IN NEGOTIATIONS, IT SHALL BE REFERRED TO CONCILIATOR APPOINTED BY THE COMPETENT AUTHORITY OF THE BHEL. <i>THE CONCILIATION PROCEEDINGS WITH RESPECT TO A DISPUTE AS DEFINED IN THE BHEL CONCILIATION SCHEME, 2018 AND SUBSEQUENT REVISIONS CAN BE INITIATED UNDER THE SCHEME AT ANY STAGE WHETHER BEFORE, DURING OR EVEN AFTER THE COMMENCEMENT OF ARBITRATION PROCEEDINGS OR LITIGATION BEFORE COURTS. THIS CONCILIATION SCHEME IS AVAILABLE ON OUR WEBSITES https://herp.bhel.com AND www.bhel.com .</i> IV. IN CASE DISPUTE IS NOT SETTLED IN CONCILIATION PROCEEDINGS, THE SAME SHALL BE REFERRED TO ARBITRATION AS PER CORPORATE GUIDELINES OF THE BHEL AND THE ARBITRATION PROCEEDING SHALL BE CONDUCTED AS PER PROVISIONS OF THE ARBITRATION AND CONCILIATION ACT, 1996 READ WITH CORPORATE GUIDELINE AS AMENDED FROM TIME TO TIME. V. THE VENDOR SHALL CONTINUE TO PERFORM THE CONTRACT, PENDING SETTLEMENT OF DISPUTE(S). B. JURISDICTION: ALL DISPUTES OR DIFFERENCES ARISING OUT OF OR IN CONNECTIONS WITH THE CONTRACT SHALL BE SUBJECT TO THE EXCLUSIVE JURISDICTION OF THE COURT AT VARANASI (U.P.) ONLY.	
34	SPECIAL NOTE FOR BIDDERS: THE QUOTATION SHOULD BE FROM PRINCIPAL / ORIGINAL EQUIPMENT MANUFACTURER ONLY. THE OFFER OF THOSE OEM, AUTHORISING THEIR TRADER / DEALER / DISTRIBUTOR TO QUOTE AND TAKE ORDER IS LIABLE FOR DISQUALIFICATION. SINCE BHEL PREFER TO DEAL DIRECTLY WITH OEM AND NOT THROUGH DEALER / TRADER / DISTRIBUTOR OF OEM, THEREFORE, OEM MUST DIRECTLY QUOTE, TAKE ORDER AND DELIVER THE MATERIAL UNDER THEIR GUARANTEE / WARRANTEE.	
35	I. FOLLOWING DOCUMENTS SHOULD BE ENCLOSED AND ADDRESSED TO DGM (FINANCE) AND SAME SHALL BE DISPATCHED TO MM DEPTT. BHEL, HERP, TARNA, SHIVPUR, VARANASI-221003 FOR PAYMENT PURPOSE: a) 05 (FIVE) COPIES OF GST INVOICES b) COPY OF GR/RR. c) TEST CERTIFICATE AND GUARANTEE/WARRANTEE CERTIFICATE AND PDI REPORT, IF APPLICABLE. (ONE COPY). II. FURTHER TO ABOVE, 02 (TWO) COMPLETE SETS OF DOCUMENTS (COPIES OF ABOVE MENTIONED DOCUMENTS AT SL. NO. I FOR INDIAN SUPPLIERS (UNDER THIS CLAUSE) SHALL BE SENT FOR PURCHASE AND QUALITY DEPARTMENTS. ORIGINAL COPIES OF TC, GC, PDI REPORTS & OTHER QUALITY PAPERS SHALL BE ATTACHED IN THE SET OF DOCUMENTS FOR QUALITY DEPARTMENTS. III. THE VENDOR SHOULD PROVIDE BILLS & OTHER DOCUMENTS COMPLETE IN ALL RESPECT AS PER PURCHASE ORDER ALONGWITH DESPATCH OF MATERIALS. BHEL SHALL SEEK CLARIFICATION(S) (IF ANY) RELATED TO PAYMENT DOCUMENTS IN ONE GO. THE VENDOR SHOULD PROVIDE ALL SUCH CLARIFICATION(S) IMMEDIATELY. ANY DELAY IN PROCESSING OF PAYMENT, DUE TO NON RECEIPT OF CLARIFICATION(S) SOUGHT BY BHEL, SHALL BE ATTRIBUTABLE COMPLETELY TO VENDOR. IV. DIGITALLY SIGNED INVOICE IS ALSO ACCEPTABLE FOR PROCESSING OF PAYMENT.	
36	THE VENDOR SHALL ENSURE THAT THEIR BANK DETAILS ARE UPDATED WITH US FOR TIMELY PAYMENT THROUGH EFT (ELECTRONICS FUND TRANSFER).	

**GENERAL COMMERCIAL TERMS & CONDITIONS OF ENQUIRY
(FOR INDIAN VENDORS)**

**Amendment- 24
ANNEXURE-A**

37	GUIDELINES FOR SUSPENSION OF BUSINESS DEALINGS WITH SUPPLIERS/ CONTRACTORS: THE REVISED GUIDELINES FOR SUSPENSION OF BUSSINESS DEALINGS ARE AVAILABLE ON BHEL WEBSITE AT “www.bhel.com” on “SUPPLIER REGISTRATION PAGE”. RESPECTIVE BIDDERS / SUPPLIERS MAY REFER THIS BEFORE QUOTING AS PER THEIR REQUIREMENT. ACTION AGAINST THE DEFAULTED SUPPLIERS/ CONTRACTORS' SHALL BE TAKEN AS PER THESE GUIDELINES ONLY.	
38	VENDOR MUST FOLLOW THE SEQUENTIAL DELIVERY SCHEDULE i.e. ITEMS TO BE SUPPLIED IN SUCH A MANNER THAT THE PURCHASE ORDER HAVING OLDER DELIVERY SCHEDULE SHOULD BE SUPPLIED EARLIER AND PURCHASE ORDER HAVING LATTER DELIVERY SCHEDULE TO BE SUPPLIED LATTER. IF ANY VENDOR DOES NOT FOLLOW THE SEQUENTIAL DELIVERY SCHEDULE ESPECIALLY FOR SAME ITEM, BHEL MAY ACCOUNT FOR THE ITEM IN SEQUENTIAL MANNER OR MAY RECOVER THE FINANCIAL IMPUCATION.	
39	ALL ABOVE ACCEPTED TERMS & CONDITIONS SHALL BE PART OF PURCHASE ORDER WITH OR WITHOUT MENTIONING IN THE PO/CONTRACT BASED ON YOUR ACCEPTANCE AND OFFER SUBMITTED.	
40	IMPORTANT INSTRUCTION: I.VENDORS ARE REQUESTED TO QUOTE THEIR RATE WITH DESCRIPTION MENTIONED IN THE ENQUIRY CONSIDERING ALL TECHNICAL TERMS & CONDITIONS OF THE ENQUIRY. ALSO RATES QUOTED SHOULD BE EXACTLY AS PER SL. NO. OF HARD COPY OF THE ENQUIRY (IF ENQUIRY HAS BEEN FLOATED THROUGH CONVENTIONAL MODE) OR AS PER SL. NO. APPEARING IN THE e-Procurement PORTAL (IF ENQUIRY HAS BEEN FLOATED THROUGH e-Procurement) ONLY. IT MUST BE FOLLOWED UP TO AVOID CONFUSION AT LATER STAGES. ALSO RATES TO BE SUBMITTED BOTH IN NUMERICS AS WELL AS IN WORD. IN CASE OF DISCREPENCY, RATES SUBMITTED IN WORDS SHALL BE CONSIDERED FOR FURTHER PROCESSING. II.DOCUMENTS SUBMITTED WITH THE OFFER SHOULD BE SIGNED AND STAMPED IN EACH PAGE BY AUTHORIZED REPRESENTATIVE OF THE BIDDER. II.IN CASE OF PDI, VENDOR SHALL RAISE ONLINE INSPECTION CALL IN ONLINE INSPECTION PORTAL/INTIMATE BHEL IN WRITTING (WHERE INSPECTION IS IN BHEL HERP SCOPE) AT LEAST 01 WEEK IN ADVANCE OR AS MUTUALLY AGREED PERIOD ABOUT THE DATE AND PLACE AT WHICH GOODS WILL BE READY FOR INSPECTION. IV.PURCHASER OR HIS AUTHORIZED REPRESENTATIVE SHALL BE ENTITLED TO CARRY OUT SURVEILLANCE INSPECTION OF MATERIAL AND WORKMANSHIP AT SELLER'S PREMISES OR AT HIS SUB-CONTRACTOR'S PREMISES AT ALL REASONABLE TIMES DURING EXECUTION OF THE CONTRACT. SUCH INSPECTION, EXAMINATION AND TESTING, IF MADE, SHALL NOT ABSOLVE THE SELLER FROM HIS OBLIGATIONS UNDER THE CONTRACT. V.SUCH PRE-DISPATCH INSPECTION, EXAMINATION AND TESTING, IF MADE, AT VENDOR'S WORKS SHALL NOT ABSOLVE THE SELLER FROM HIS OBLIGATIONS TO MANUFACTURE/MACHINING THE GOODS UNDER THE CONTRACT. IF DEFECTS ARE FOUND AT LATER STAGE, IT IS THE SOLE RESPONSIBILITY OF THE VENDOR TO REPLACE/RECTIFY THE SAME.	
41	IMPORTANT CLAUSE FOR GST: INPUT TAX CREDIT OF GST CAN BE AVAILED BY BHEL ONLY WHEN THE MATERIAL HAS BEEN PHYSICALLY RECEIVED AND GST INVOICE IS IN POSSESSION OF BHEL. THEREFORE, SUPPLIERS SHOULD ENSURE THE FOLLOWING IN RESPECT OF POS ISSUED BY BHEL: I. GST INVOICE SHOULD CONTAIN ADDRESS, GST NO. AND PAN NO. OF BHEL AS WELL AS OF SUPPLIER. APPLICABLE HSN CODE OF THE MATERIAL SHOULD BE INDICATED IN THE GST INVOICE. II. FIVE COPIES OF GST INVOICE AND LORRY RECEIPT MAY BE DESPATCHED ALONGWITH SHIPMENT OF THE GOODS IN ORDER TO AVOID ANY DELAY IN AVAILING INPUT CREDIT BY BHEL. III. DECLARE SUCH INVOICE IN HIS GSTR-1 RETURN FOR THE MONTH OF DESPATCH OF MATERIAL. IV. PAYMENT OF GST TO STATUTORY AUTHORITIES WITHIN PRESCRIBED TIME. V. IN CASE OF DISCREPANCY IN THE DATA UPLOADED BY THE BIDDER IN THE GSTN PORTAL VIS-A-VIS THE TAX INVOICE OR IN CASE OF ANY SHORTAGES OR REJECTION IN THE SUPPLY, THEN BHEL WILL NOT BE ABLE TO AVAIL THE TAX CREDIT. BIDDER HAS TO RECTIFY THE DATA DISCREPANCY IN THE GSTN PORTAL OR ISSUE CREDIT NOTE OR DEBIT NOTE (DETAILS ALSO TO BE UPLOADED IN GSTN PORTAL) FOR THE SHORTAGES OR REJECTIONS IN THE SUPPLIES OR ADDITIONAL CLAIMS FOR PROCESSING OF SUCH INVOICES. VI. GST TDS DEDUCTED AS PER GST ACT, IS UPLOADED IN GSTN PORTAL ALONG GSTR7. BIDDERS CAN DIRECTLY DOWNLOAD THE GST TDS CERTIFICATE FROM THE GSTN PORTAL. IN CASE GST CREDIT IS DELAYED /DENIED TO BHEL DUE TO NON OR DELAYED RECEIPT OF GOODS AND OR TAX INVOICE OR EXPIRY OF TIMELINE PRESCRIBED IN GST LAW FOR AVAILING SUCH ITC OR ANY OTHER REASON NOT ATTRIBUTABLE TO BHEL, GST AMOUNT SHALL BE RECOVERABLE FROM VENDOR ALONG WITH INTEREST /PENALTY LEVIABLE ON BHEL. IN CASE SUPPLIERS DELAYS DECLARING SUCH INVOICE IN HIS RETURN AND GST CREDIT AVAILED BY BHEL IS DENIED OR REVERSED SUBSEQUENTLY AS PER GST LAW, GST AMOUNT PAID BY BHEL TOWARDS SUCH ITC REVERSAL SHALL BE RECOVERABLE FROM SUPPLIER ALONGWITH INTEREST LEVIED/LEVIABLE ON BHEL. IN CASE OF RAISING ANY SUPPLEMENTARY TAX INVOICE (DEBIT/ CREDIT NOTE), THE SUPPLIER SHALL ISSUE THE SAME CONTAINING ALL THE DETAILS AS REFERRED TO IN SECTION 34 READ WITH SECTION 31 OF GST ACT & RULES REFERRED THERE UNDER .	
42	STATUTORY VARIATION CLAUSE : ANY INCREASE IN THE RATE OF GST SHALL BE PAYABLE ONLY FOR DELIVERIES COMPLETED WITHIN THE SCHEDULED DELIVERY PERIOD, IN OTHER WORDS INCREASE IN THE RATE OF GST SHALL NOT BE PAYABLE FOR VALUE OF CONSIGNMENT DELIVERED AFTER THE SCHEDULED PURCHASE ORDER DELIVERY PERIOD.2.NEW TAXES AND DUTIES , IF IMPOSED SUBSEQUENT TO DUE DATE OF OFFER SUBMISSION, BY STATUTORY AUTHORITY DURING CONTRACT PERIOD (INCLUDING EXTENSION IF THE SAME IS NOT ATTRIBUTABLE TO BIDDER) SHALL BE REIMBURSED BY BHEL ON PRODUCTION OF RELEVANT SUPPORTING DOCUMENTS TO THE SATISFACTION OF BHEL . HOWEVER, BIDDER SHALL TAKE PRIOR APPROVAL OF BHEL BEFORE DEPOSITING NEW TAXES AND DUTIES.	
43	IMPORTANT INSTRUCTION FOR MSEs SUPPLIERS: I. “MSE SUPPLIERS CAN AVAIL THE INTENDED BENEFITS ONLY IF THEY SUBMIT ALONG WITH OFFER, ATTESTED COPIES OF EITHER EM-II CERTIFICATE HAVING DEEMED VALIDITY (FIVE YEARS FROM THE DATE OF ISSUE OF ACKNOWLEDGEMENT IN EM-II) OR VALID NSIC CERTIFICATE OR EM-II CERTIFICATE ALONG WITH CA CERTIFICATE (FORMAT ENCLOSED AS PER ANNEXURE-1 WHERE DEEMED VALIDITY OF EM-II CERTIFICATE OF FIVE YEARS HAS EXPIRED) APPLICABLE FOR THE RELEVANT F/Y (LATEST AUDITED).DATE TO BE RECKONED FOR DETERMINING THE DEEMED VALIDITY WILL BE THE DATE OF BID OPENING (PART -1 IN CASE OF TWO PART BID). NON SUBMISSION OF SUCH DOCUMENTS WILL LEAD TO CONSIDERATION OF THEIR BID AT PAR WITH OTHER BIDDERS. NO BENEFIT SHALL BE APPLICABLE FOR THIS ENQUIRY IF ANY DEFICIENCY IN THE ABOVE REQUIRED DOCUMENTS ARE NOT SUBMITTED BEFORE PRICE BID OPENING. IF THE TENDER IS TO BE SUBMITTED THROUGH e-procurement PORTAL, THEN THE ABOVE REQUIRED DOCUMENTS ARE TO BE UPLOADED ON THE PORTAL. DOCUMENTS SHOULD BE NOTARIZED OR ATTESTED BY A GAZETTED OFFICE. II.IN CASE OF ANY CHANGE IN THE MSE STATUS OF THE BIDDER, IT SHALL BE RESPONSIBILITY OF THE BIDDER TO NOTIFY THE CHANGE AS A PART OF THE BID DOCUMENT. IF AT A LATER DATE IT COMES TO NOTICE OF BHEL, THAT THE CHANGE IN THE STATUS HAS NOT BEEN INTIMATED BY THE BIDDER AND THE ORDER IS OBTAINED UNDER THE PREMISE OF AN MSE, THEN BHEL WOULD CANCEL THE PENDING ORDER AGAINST THIS TENDER AND TAKE NECESSARY ACTION SUSPENSION OF THE BUSSINESS DEALING WITH THE BIDDER AS PER PROCUREMENT POLICY OF BHEL. III.25 % OF THE TENDERED QUANTITY IS EARMARKED FOR MSE SUPPLIERS IN THIS TENDER. IV.OUT OF THIS 25% TENDERED QUANTITY RESERVED FOR MSE SUPPLIERS, 6.25% SHALL BE EARMARKED FOR PROCUREMENT FROM MSEs OWNED BY SC/ST ENTREPRENEURS. V.OUT OF THIS 25% TENDERED QUANTITY RESERVED FOR MSE SUPPLIERS, 3% SHALL BE EARMARKED FOR PROCUREMENT FROM MSEs OWNED BY WOMEN. VI.IN CASE MSE VENDOR PARTICIPATING IN THE TENDER QUOTES WITHIN THE PRICE BAND OF “L1+15%”, THEY WILL BE ALLOWED TO SUPPLY THE 25% PORTION OF THE REQUIREMENT SUBJECT TO ACCEPTANCE OF L1 PRICE (ON LANDED COST BASIS) BY MSE VENDOR. IN CASE OF MORE THAN ONE SUCH MSE VENDOR WITHIN THE “L1+15% PRICE BAND” THE SUPPLY SHALL BE SHARED PROPORTIONATELY (TO 25% TENDERED QUANTITY). VII.IF THE L1 VENDOR HAPPENS TO BE A MSE VENDOR AGAINST ANY ITEM CODE, THEN 100% OF THE TENDERED QTY (FOR RESPECTIVE ITEM CODE) SHALL BE PROPOSED TO ORDER ON THE L1 (MSE) VENDOR, EVEN THOUGH THERE MAY BE OTHER MSE VENDORS WITHIN THE “L1+15% PRICE BAND”. VIII.IN CASE AFTER OPENING OF PRICE BID, IT IS SEEN THAT NO MSE HAS BECOME L1, THEN DEPENDING ON THE NATURE OF THE ITEM, IF IT IS NOT POSSIBLE TO SPLIT THE TENDERED ITEMS/QUANTITIES ON ACCOUNT OF REASONS LIKE CUSTOMER CONTRACT REQUIREMENTS OF SUPPLYING ONE MAKE FOR A GIVEN PROJECT OR TECHNICAL REASONS LIKE TENDERED ITEMS BEING A SYSTEM etc. THEN BHEL WOULD NOT COUNTER OFFER THE L1 PRICES EVEN THOUGH THERE MAY BE MSE BIDDERS WITHIN THE “L1+15% PRICE BAND” OF L1.	
44	THE STARTUPS AS DEFINED IN THE GAZETTE OF INDIA NOTIFICATION NO.: G.S.R. 127 (E) DATED 19/02/2019 WILL BE EXEMPTED FROM FULFILLING THE CRITERIA, IF MENTIONED, IN THE PQR (PRE-QUALIFYING REQUIREMENT) REGARDING PRIOR TURNOVER AND PRIOR EXPERIENCE. HOWEVER, THERE MAY BE CIRCUMSTANCES (LIKE PROCUREMENTS OF ITEMS RELATED TO PUBLIC SAFETY, HEALTH, CRITICAL SECURITY OPERATIONS AND EQUIPMENTS ETC.) WHERE BHEL MAY PREFER THE VENDORS TO HAVE PRIOR EXPERIENCE RATHER THAN GIVING ORDER TO NEW ENTITIES. FOR SUCH PROCUREMENTS, BHEL MAY NOT RELAX THE CRITERIA OF PRIOR EXPERIENCE/TURNOVER FOR THE STARTUPS.	
45	PURCHASE PREFERENCE FOR INDIAN VENDORS: FOR THIS PROCUREMENT, THE LOCAL CONTENT TO CATEGORIZE A SUPPLIER AS A CLASS I LOCAL SUPPLIER / CLASS II LOCAL SUPPLIER /NON LOCAL – SUPPLIER AND PURCHASE PREFERENCE TO CLASS I LOCAL SUPPLIER, IS AS DEFINED IN PUBLIC PROCUREMENT (PREFERENCE TO MAKE IN INDIA), ORDER 2017 DATED 04.06.2020 ISSUED BY DPIIT. IN CASE OF SUBSEQUENT ORDERS ISSUED BY THE NODAL MINISTRY, CHANGING THE DEFINITION OF LOCAL CONTENT FOR THE ITEMS OF THE NIT, THE SAME SHALL BE APPLICABLE EVEN IF ISSUED AFTER ISSUE OF THIS NIT, BUT BEFORE OPENING OF PART –II BIDS AGAINST THIS NIT.	

**GENERAL COMMERCIAL TERMS & CONDITIONS OF ENQUIRY
(FOR INDIAN VENDORS)**

**Amendment- 24
ANNEXURE-A**

	MODEL CLAUSE FOR TENDER. I. ANY BIDDER FROM A COUNTRY WHICH SHARES A LAND BORDER WITH INDIA WILL BE ELIGIBLE TO BID IN THIS TENDER ONLY IF THE BIDDER IS REGISTERED WITH THE COMPETENT AUTHORITY. II. "BIDDER" (INCLUDING THE TERM 'TENDERER', 'CONSULTANT' OR 'SERVICE PROVIDER' IN CERTAIN CONTEXTS) MEANS ANY PERSON OR FIRM OR COMPANY, INCLUDING ANY MEMBER OF A CONSORTIUM OR JOINT VENTURE (THAT IS AN ASSOCIATION OF SEVERAL PERSONS, OR FIRMS OR COMPANIES), EVERY ARTIFICIAL JURIDICAL PERSON NOT FALLING IN ANY OF THE DESCRIPTIONS OF BIDDERS STATED HEREINBEFORE, INCLUDING ANY AGENCY BRANCH OR OFFICE CONTROLLED BY SUCH PERSON, PARTICIPATING IN A PROCUREMENT PROCESS. III. "BIDDER FROM A COUNTRY WHICH SHARES A LAND BORDER WITH INDIA" FOR THE PURPOSE OF THIS ORDER MEANS: - a) AN ENTITY INCORPORATED, ESTABLISHED OR REGISTERED IN SUCH A COUNTRY; OR b) A SUBSIDIARY OF AN ENTITY INCORPORATED, ESTABLISHED OR REGISTERED IN SUCH A COUNTRY; OR c) AN ENTITY SUBSTANTIALLY CONTROLLED THROUGH ENTITIES INCORPORATED, ESTABLISHED OR REGISTERED IN SUCH A COUNTRY; OR d) AN ENTITY WHOSE BENEFICIAL OWNER IS SITUATED IN SUCH A COUNTRY; OR e) AN INDIAN (OR OTHER) AGENT OF SUCH AN ENTITY; OR f) A NATURAL PERSON WHO IS A CITIZEN OF SUCH A COUNTRY; OR g) A CONSORTIUM OR JOINT VENTURE WHERE ANY MEMBER OF THE CONSORTIUM OR JOINT VENTURE FALLS UNDER ANY OF THE ABOVE IV. THE BENEFICIAL OWNER FOR THE PURPOSE OF (III) ABOVE WILL BE AS UNDER: 1. IN CASE OF A COMPANY OR LIMITED LIABILITY PARTNERSHIP, THE BENEFICIAL OWNER IS THE NATURAL PERSON (S) WHO, WHETHER ACTING ALONE OR TOGETHER, OR THROUGH ONE OR MORE JURIDICAL PERSON, HAS A CONTROLLING OWNERSHIP INTEREST OR WHO EXERCISES CONTROL THROUGH OTHER MEANS. EXPLANATION – a. "CONTROLLING OWNERSHIP INTEREST" MEANS OWNERSHIP OF OR ENTITLEMENT TO MORE THAN TWENTY-FIVE PER CENT. OF SHARES OR CAPITAL OR PROFITS OF THE COMPANY b. "CONTROL" SHALL INCLUDE THE RIGHT TO APPOINT MAJORITY OF THE DIRECTORS OR TO CONTROL THE MANAGEMENT OR POLICY DECISIONS INCLUDING BY VIRTUE OF THEIR SHAREHOLDING OR MANAGEMENT RIGHTS OR SHAREHOLDER'S AGREEMENTS OF VOTING AGREEMENTS; 2. IN CASE OF A PARTNERSHIP FIRM, THE BENEFICIAL OWNER IS THE NATURAL PERSON (S) WHO, WHETHER ACTING ALONE OR TOGETHER, OR THROUGH ONE OR MORE JURIDICAL OF CAPITAL OR PROFITS OF THE PARTNERSHIP; 3. IN CASE OF AN UNINCORPORATED ASSOCIATION OR BODY OF INDIVIDUALS, THE BENEFICIAL OWNER IS THE NATURAL PERSON (S), WHO, WHETHER ACTING ALONE OR TOGETHER, OR THROUGH ONE OR MORE JURIDICAL PERSON, HAS OWNERSHIP OF OR ENTITLEMENT TO MORE THAN FIFTEEN PERCENT OF THE PROPERTY OF CAPITAL OF PROFITS OF SUCH ASSOCIATION OR BODY OF INDIVIDUALS; 4. WHERE NO NATURAL PERSON IS IDENTIFIED UNDER (1) OR (2) OR (3) ABOVE, THE BENEFICIAL OWNER IS THE RELEVANT NATURAL PERSON WHO HOLDS THE POSITION OF SENIOR MANAGING OFFICIAL; 5. IN CASE OF TRUST, THE IDENTIFICATION OF BENEFICIAL OWNER (S) SHALL INCLUDE IDENTIFICATION OF THE AUTHOR OF THE TRUST, THE TRUSTEE, THE BENEFICIARIES WITH FIFTEEN PERCENT OR MORE INTEREST IN THE TRUST AND ANY OTHER NATURAL PERSON EXERCISING ULTIMATE EFFECTIVE CONTROL OVER THE TRUST THROUGH A CHAIN OF CONTROL OR OWNERSHIP. V. AN AGENT IS A PERSON EMPLOYED TO DO ANY ACT FOR ANOTHER, OR TO REPRESENT ANOTHER IN DEALINGS WITH THIRD PERSON. CERTIFICATE: IN ORDER TO AVAIL THE BENEFITS, VENDORS TO SUBMIT (ALONG WITH OFFER) THE SELF-CERTIFICATION THAT THE ITEM OFFERED MEETS THE CONTENT REQUIREMENT FOR CLASS-I/ CLASS-II LOCAL SUPPLIER AS THE CASE MAY BE, INDICATING THE PERCENTAGE OF LOCAL CONTENT. AND SHALL GIVE DETAILS OF LOCATION AT WHICH THE LOCAL VALUE ADDITION IS MADE (refer attached Make in India (Model Certificate no I)).	
46	FORCE MAJEURE: NOTWITHSTANDING ANYTHING CONTAINED IN THE CONTRACT, NEITHER THE VENDOR NOR THE BHEL SHALL BE HELD RESPONSIBLE FOR TOTAL OR PARTIAL NON-EXECUTION OF ANY OF THE CONTRACTUAL OBLIGATIONS, SHOULD THE OBLIGATION BECOME UNREASONABLY ONEROUS OR IMPOSSIBLE DUE TO OCCURRENCE OF A 'FORCE MAJEURE' WHICH DIRECTLY AFFECTS THE OBLIGATIONS TO BE PERFORMED BY THE BHEL OR THE VENDOR ; SUCH EVENTS INCLUDE WAR, MILITARY OPERATIONS OF ANY NATURE, BLOCKAGES, REVOLUTIONS, INSURRECTIONS, RIOTS, CIVIL COMMOTIONS, INSURGENCY, SABOTAGE, ACTS OF PUBLIC ENEMY, FIRES, EXPLOSION, EPIDEMICS, QUARANTINE RESTRICTIONS, FLOODS, EARTHQUAKE, OR ACTS OF GOD, RESTRICTIONS BY GOVT. AUTHORITIES; OVER WHICH THE VENDOR OR THE BHEL HAS NO CONTROL. THE PARTY CLAIMING TO BE AFFECTED BY FORCE MAJEURE SHALL NOTIFY THE OTHER PARTY IN WRITING WITHOUT DELAY, WITHIN TWO WEEKS ON THE INTERVENTION AND ON THE CESSATION OF SUCH CIRCUMSTANCE. EXTENSION OF TIME SOUGHT BY THE VENDOR ALONG WITH SUPPORTING EVIDENCE AND SO GRANTED BY THE BHEL FOR THE SUPPLY/ WORK AFFECTED, IF ANY, SHALL NOT BE CONSTRUED AS WAIVER IN RESPECT OF REMAINING DELIVERIES. RESCHEDULING OF DELIVERIES ON ACCOUNT OF FORCE MAJEURE CONDITIONS, IF SO AGREED BY THE BHEL, WILL NOT ENTAIL THE VENDOR TO CLAIM ANY INCREASE IN THE PRICE ON WHATSOEVER ACCOUNT. NOTWITHSTANDING ABOVE PROVISIONS, BHEL SHALL RESERVE THE RIGHT TO CANCEL THE ORDER/ CONTRACT, WHOLLY OR PARTLY, IN ORDER TO MEET THE OVERALL PROJECT SCHEDULE AND MAKE ALTERNATIVE ARRANGEMENTS. IF DEEMED NECESSARY, BHEL MAY TAKEOVER PARTLY PROCESSED MATERIAL AT A MUTUALLY AGREED PRICE.	
47	FRAUD PREVENTION POLICY : THE BIDDER ALONG WITH ITS ASSOCIATE/ COLLABORATORS/ SUB-CONTRACTORS/ SUB-VENDORS/ CONSULTANTS/ SERVICE PROVIDERS SHALL STRICTLY ADHERE TO BHEL FRAUD PREVENTION POLICY DISPLAYED ON BHEL WEBSITE WWW.BHEL.COM AND SHALL IMMEDIATELY BRING TO THE NOTICE OF BHEL MANAGEMENT ABOUT ANY FRAUD OR SUSPECTED FRAUD AS SOON AS IT COMES TO THEIR NOTICE.	
48	SHORT SHIPMENTS/ WARRANTY/GUARANTEE REPLACEMENTS: IN CASE OF ANY SHORT SHIPMENT DURING INITIAL SUPPLY WHICH IS SUBSEQUENTLY DISPATCHED BY THE VENDOR OR ANY GUARANTEE / WARRANTY REPLACEMENTS SHALL BE DISPATCHED ON "FOR-BHEL STORES/DESIGNATED DESTINATION" BASIS FOR INDIGENOUS ITEMS. TAXES, IF ANY PAID BY INDIGENOUS VENDOR FOR GUARANTEE /WARRANTY REPLACEMENT, REPAIR ACTIVITY EXCLUDING SHORT SUPPLY SHALL BE TO VENDOR'S ACCOUNT ONLY. THE VENDOR HAS TO RAISE A CREDIT NOTE FOR SHORT SUPPLIED QUANTITY AS PER GST PROVISIONS.	
49	E WAY BILL: THE SUPPLIER HAS TO ARRANGE FOR E WAY BILL AS APPLICABLE FOR ANY MOVEMENT OF GOODS ALONG WITH OTHER PRESCRIBED DOCUMENTS AS PER GST LAW. THE SUPPLIER HAS ALSO TO COMPLY WITH ANY AMENDMENT AS PRESCRIBED FROM TIME TO TIME UNDER E WAY BILL RULE. ANY FINANCIAL IMPLICATION ARISES ON BHEL DUE TO NONCOMPLIANCE OF E WAY BILL RULE WILL BE PASSED ON TO THE SUPPLIER.	
50	THE BIDDER DECLARES THAT THEY WILL NOT ENTER INTO ANY ILLEGAL OR UNDISCLOSED AGREEMENT OR UNDERSTANDING, WHETHER FORMAL OR INFORMAL WITH OTHER BIDDER (S). THIS APPLIES IN PARTICULAR TO PRICES, SPECIFICATIONS, CERTIFICATIONS, SUBSIDIARY CONTRACTS, SUBMISSION OR NON- SUBMISSION OF BIDS OR ANY OTHER ACTIONS TO RESTRICT COMPETITIVENESS OR TO INTRODUCE CARTELIZATION IN THE BIDDING PROCESS. IN CASE, THE BIDDER IS FOUND HAVING INDULGED IN ABOVE ACTIVITIES, SUITABLE ACTION SHALL BE TAKEN BY BHEL AS PER EXISTANT POLICIES / GUIDELINES.	
51	THE BIDDER SHALL REGISTER THEMSELVES ON GEM PORTAL AND SHALL QUOTE THEIR GEM SELLER ID IN THEIR OFFER. GEM SELLER ID IS MANDATORY FOR PLACEMENT OF PURCHASE ORDER EXCEPT IN CASES WHERE FREE ISSUE MATERIAL IS TO BE ISSUED BY BHEL .	
52	REJECTION/REPLACEMENT: THE SELLER SHALL ARRANGE REPLACEMENT / REPAIR UNDER ITS OBLIGATION UNDER THE CONTRACT. SELLER SHALL BE GIVEN GROUND RENT FREE PERIOD OF 90 DAYS FROM THE DATE OF REJECTION TO LIFT REJECTED MATERIAL. BEYOND 90 DAYS, A GROUND RENT OF 0.25% OF VALUE OF REJECTED MATERIAL PER WEEK WILL BE LEVIED FOR A MAXIMUM PERIOD OF 4 WEEKS. BEYOND THIS PERIOD SUPPLIER FORFEITS THEIR RIGHT TO THE MATERIALS.	
53	CONFLICT OF INTEREST AMONG BIDDERS/AGENTS: A BIDDER SHALL NOT HAVE CONFLICT OF INTEREST WITH OTHER BIDDERS. SUCH CONFLICT OF INTEREST CAN LEAD TO ANTI-COMPETITIVE PRACTICES TO THE DETRIMENT OF PROCURING ENTITY'S INTERESTS. THE BIDDER FOUND TO HAVE A CONFLICT OF INTEREST SHALL BE DISQUALIFIED. A BIDDER MAY BE CONSIDERED TO HAVE A CONFLICT OF INTEREST WITH ONE OR MORE PARTIES IN THIS BIDDING PROCESS, IF a) THEY HAVE CONTROLLING PARTNER (S) IN COMMON; OR b) THEY RECEIVE OR HAVE RECEIVED ANY DIRECT OR INDIRECT SUBSIDY FINANCIAL STAKE FROM ANY OF THEM; OR c) THEY HAVE THE SAME LEGAL REPRESENTATIVE/AGENT FOR PURPOSES OF THIS BID; OR d) THEY HAVE RELATIONSHIP WITH EACH OTHER, DIRECTLY OR THROUGH COMMON THIRD PARTIES, THAT PUTS THEM IN A POSITION TO HAVE ACCESS TO INFORMATION ABOUT OR INFLUENCE ON THE BID OF ANOTHER BIDDER; OR e) BIDDER PARTICIPATES IN MORE THAN ONE BID IN THIS BIDDING PROCESS. PARTICIPATION BY A BIDDER IN MORE THAN ONE BID WILL RESULT IN THE DISQUALIFICATION OF ALL BIDS IN WHICH THE PARTIES ARE INVOLVED. HOWEVER, THIS DOES NOT LIMIT THE INCLUSION OF THE COMPONENTS/ SUB-ASSEMBLY ASSEMBLIES FROM ONE BIDDING MANUFACTURER IN MORE THAN ONE BID; OR f) IN CASES OF AGENTS QUOTING IN OFFSHORE PROCUREMENTS, ON BEHALF OF THEIR PRINCIPAL MANUFACTURERS, ONE AGENT CANNOT REPRESENT TWO MANUFACTURERS OR QUOTE ON THEIR BEHALF IN A PARTICULAR TENDER ENQUIRY. ONE MANUFACTURER CAN ALSO AUTHORISE ONLY ONE AGENT/DEALER. THERE CAN BE ONLY ONE BID FROM THE FOLLOWING:	

**GENERAL COMMERCIAL TERMS & CONDITIONS OF ENQUIRY
(FOR INDIAN VENDORS)**

**Amendment- 24
ANNEXURE-A**

	1. THE PRINCIPAL MANUFACTURER DIRECTLY OR THROUGH ONE INDIAN AGENT ON HIS BEHALF; AND 2. INDIAN/FOREIGN AGENT ON BEHALF OF ONLY ONE PRINCIPAL; OR g) A BIDDER OR ANY OF ITS AFFILIATES PARTICIPATED AS A CONSULTANT IN THE PREPARATION OF THE DESIGN OR TECHNICAL SPECIFICATIONS OF THE CONTRACT THAT IS THE SUBJECT OF THE BID; OR h) IN CASE OF A HOLDING COMPANY HAVING MORE THAN ONE INDEPENDENTLY MANUFACTURING UNITS, OR MORE THAN ONE UNIT HAVING COMMON BUSINESS OWNERSHIP/MANAGEMENT, ONLY ONE UNIT SHOULD QUOTE. SIMILAR RESTRICTIONS WOULD APPLY TO CLOSELY RELATED SISTER COMPANIES. BIDDERS MUST PROACTIVELY DECLARE SUCH SISTER/ COMMON BUSINESS/ MANAGEMENT UNITS IN SAME/ SIMILAR LINE OF BUSINESS.	
54	VENDOR MUST VISIT OUR WEBSITE https://herp.bhel.com REGULARLY FOR ENQUIRY/PO/CLARIFICATIONS/FOR ANY LATEST UPDATES.	
55	MSME VENDORS CAN AVAIL BENEFITS OF PAYMENT THROUGH TREDS/RXIL.	
56	"THE OFFERS OF THE BIDDERS WHO ARE UNDER SUSPENSION AS ALSO THE OFFERS OF THE BIDDERS, WHO ENGAGE THE SERVICES OF THE FIRMS DEBARRED ACROSS BHEL, SHALL BE REJECTED. THE LIST OF FIRMS DEBARRED ACROSS BHEL IS AVAILABLE ON BHEL WEBSITE WWW.BHEL.COM. 1.0 INTEGRITY COMMITMENT, PERFORMANCE OF THE CONTRACT AND PUNITIVE ACTION THEREOF: 1.1. COMMITMENT BY BHEL: BHEL COMMITS TO TAKE ALL MEASURES NECESSARY TO PREVENT CORRUPTION IN CONNECTION WITH THE TENDER PROCESS AND EXECUTION OF THE CONTRACT. BHEL WILL DURING THE TENDER PROCESS TREAT ALL BIDDER(S) IN A TRANSPARENT AND FAIR MANNER, AND WITH EQUITY. 1.2. COMMITMENT BY BIDDER/ SUPPLIER/ CONTRACTOR: 1.2.1. THE BIDDER/ SUPPLIER/ CONTRACTOR COMMIT TO TAKE ALL MEASURES TO PREVENT CORRUPTION AND WILL NOT DIRECTLY OR INDIRECTLY INFLUENCE ANY DECISION OR BENEFIT WHICH HE IS NOT LEGALLY ENTITLED TO NOR WILL ACT OR OMIT IN ANY MANNER WHICH TANTAMOUNT TO AN OFFENCE PUNISHABLE UNDER ANY PROVISION OF THE INDIAN PENAL CODE, 1860 OR ANY OTHER LAW IN FORCE IN INDIA. 1.2.2. THE BIDDER/ SUPPLIER/ CONTRACTOR WILL, WHEN PRESENTING HIS BID, DISCLOSE ANY AND ALL PAYMENTS HE HAS MADE, AND IS COMMITTED TO OR INTENDS TO MAKE TO AGENTS, BROKERS OR ANY OTHER INTERMEDIARIES IN CONNECTION WITH THE AWARD OF THE CONTRACT AND SHALL ADHERE TO RELEVANT GUIDELINES ISSUED FROM TIME TO TIME BY GOVT. OF INDIA/ BHEL. 1.2.3. THE BIDDER/ SUPPLIER/ CONTRACTOR WILL PERFORM/ EXECUTE THE CONTRACT AS PER THE CONTRACT TERMS & CONDITIONS AND WILL NOT DEFAULT WITHOUT ANY REASONABLE CAUSE, WHICH CAUSES LOSS OF BUSINESS/ MONEY/ REPUTATION, TO BHEL. IF ANY BIDDER/ SUPPLIER/ CONTRACTOR DURING PRE-TENDERING/ TENDERING/ POST TENDERING/ AWARD/ EXECUTION/ POST-EXECUTION STAGE INDULGES IN MALPRACTICES, CHEATING, BRIBERY, FRAUD OR AND OTHER MISCONDUCT OR FORMATION OF CARTEL SO AS TO INFLUENCE THE BIDDING PROCESS OR INFLUENCE THE PRICE OR ACTS OR OMMITS IN ANY MANNER WHICH TANTAMOUNT TO AN OFFENCE PUNISHABLE UNDER ANY PROVISION OF THE INDIAN PENAL CODE, 1860 OR ANY OTHER LAW IN FORCE IN INDIA, THEN, ACTION MAY BE TAKEN AGAINST SUCH BIDDER/ SUPPLIER/ CONTRACTOR AS PER EXTANT GUIDELINES OF THE COMPANY AVAILABLE ON WWW. BHEL.COM AND/OR UNDER APPLICABLE LEGAL PROVISIONS".	
57	BID SECURITY OR EARNEST MONEY DEPOSIT (EMD): TO SAFE GUARD AGAINST A BIDDER'S WITHDRAWING OR ALTERING ITS/ HIS BID DURING THE BID VALIDITY PERIOD, BID SECURITY [ALSO KNOWN AS EARNEST MONEY DEPOSIT (EMD)] SHALL BE OBTAINED FROM THE BIDDERS ALONG WITH THEIR BIDS (EXCEPT MICRO AND SMALL ENTERPRISES (MSES) OR STARTUPS AS RECOGNIZED BY DEPARTMENT FOR PROMOTION OF INDUSTRY AND INTERNAL TRADE (DPIIT)). THE AMOUNT OF EMD SHALL BE AS MENTIONED IN ENQUIRY. 1. MODES OF DEPOSIT A) THE EMD MAY BE ACCEPTED ONLY IN THE FOLLOWING FORMS AND THE SAME MUST BE SUBMITTED BEFORE TENDER OPENING: (I) ELECTRONIC FUND TRANSFER CREDITED IN BHEL ACCOUNT. (II) BANKER'S CHEQUE/ PAY ORDER/ DEMAND DRAFT, IN FAVOUR OF BHEL. (III) FIXED DEPOSIT RECEIPT (FDR).(IN THE NAME OF " BIDDER'S NAME A/C BHEL") (IV) BANK GUARANTEE FROM ANY OF THE SCHEDULED BANKS. (V) INSURANCE SURETY BONDS. B) IN CASE THE EMD IS MORE THAN RUPEES TWO LAKH AND IN CASE OF FOREIGN BIDDERS, IT MAY BE IN THE FORM OF A BANK GUARANTEE (IN EQUIVALENT FOREIGN EXCHANGE AMOUNT, IN CASE OF FOREIGN BIDDERS) ISSUED/ CONFIRMED FROM ANY OF THE SCHEDULED COMMERCIAL BANK IN INDIA IN AN ACCEPTABLE FORM. THE EMD SHALL REMAIN VALID FOR A PERIOD OF 45 (FORTY-FIVE) DAYS BEYOND THE FINAL BID VALIDITY PERIOD. 2. FORFEITURE OF EMD I) A BIDDER'S EMD WILL BE FORFEITED IF THE BIDDER WITHDRAWS OR AMENDS ITS/HIS TENDER OR IMPAIRS OR DEROGATES FROM THE TENDER IN ANY RESPECT WITHIN THE PERIOD OF VALIDITY OF THE TENDER OR IF THE SUCCESSFUL BIDDER FAILS TO FURNISH THE REQUIRED PERFORMANCE SECURITY WITHIN THE SPECIFIED PERIOD MENTIONED IN THE TENDER. (II) EMD BY THE TENDERER SHALL BE WITHHELD IN CASE ANY ACTION ON THE BIDDER IS ENVISAGED UNDER THE PROVISIONS OF EXTANT "GUIDELINES ON SUSPENSION OF BUSINESS DEALINGS WITH SUPPLIERS/ CONTRACTORS" AND FORFEITED/ RELEASED BASED ON THE ACTION AS DETERMINED UNDER THESE GUIDELINES. 3. RETURN OF EMD (I) BID SECURITIES OF THE UNSUCCESSFUL BIDDERS SHALL BE RETURNED TO BIDDER AT THE EARLIEST AFTER EXPIRY OF THE FINAL BID VALIDITY PERIOD AND LATEST BY THE 30TH DAY AFTER THE AWARD OF THE CONTRACT. HOWEVER, IN CASE OF TWO PACKET OR TWO STAGE BIDDING, BID SECURITIES OF UNSUCCESSFUL BIDDERS DURING FIRST STAGE I.E. TECHNICAL EVALUATION ETC. SHALL BE RETURNED WITHIN 30 DAYS OF DECLARATION OF RESULT OF FIRST STAGE I.E. TECHNICAL EVALUATION ETC. (II) BID SECURITY SHALL BE REFUNDED TO THE SUCCESSFUL BIDDER ON CONCLUSION OF THE ORDER/ RECEIPT OF A PERFORMANCE SECURITY (IF CALLED IN THE TENDER). (III) EMD SHALL NOT CARRY ANY INTEREST.	
58	PERFORMANCE SECURITY (PS): TO ENSURE DUE PERFORMANCE OF THE CONTRACT, PERFORMANCE BANK GUARANTEE (PBG) OR SECURITY DEPOSIT (SD), HEREAFTER REFERRED AS PERFORMANCE SECURITY SHALL BE OBTAINED FROM THE SUCCESSFUL BIDDER AWARDED THE CONTRACT. THE PERFORMANCE SECURITY OF REQUIRED AMOUNT IS TO BE SUBMITTED BY THE DATE SPECIFIED IN THE PO/CONTRACT. 1. MODES OF DEPOSIT: A) PERFORMANCE SECURITY MAY BE FURNISHED IN THE FOLLOWING FORMS: (I) LOCAL CHEQUES OF SCHEDULED BANKS (SUBJECT TO REALIZATION)/ PAY ORDER/ DEMAND DRAFT/ ELECTRONIC FUND TRANSFER IN FAVOUR OF BHEL. (II) BANK GUARANTEE FROM SCHEDULED BANKS / PUBLIC FINANCIAL INSTITUTIONS AS DEFINED IN THE COMPANIES ACT. THE BANK GUARANTEE FORMAT SHOULD HAVE THE APPROVAL OF BHEL. (III) FIXED DEPOSIT RECEIPT ISSUED BY SCHEDULED BANKS / PUBLIC FINANCIAL INSTITUTIONS AS DEFINED IN THE COMPANIES ACT (FDR SHOULD BE IN THE NAME OF THE CONTRACTOR, A/C BHEL). (IV) SECURITIES AVAILABLE FROM INDIAN POST OFFICES SUCH AS NATIONAL SAVINGS CERTIFICATES, KISAN VIKAS PATRAS ETC. (HELD IN THE NAME OF CONTRACTOR FURNISHING THE SECURITY AND DULY ENDORSED/ HYPOTHECATED/ PLEDGED, AS APPLICABLE, IN FAVOUR OF BHEL). (V) INSURANCE SURETY BOND. (NOTE: BHEL WILL NOT BE LIABLE OR RESPONSIBLE IN ANY MANNER FOR THE COLLECTION OF INTEREST OR RENEWAL OF THE DOCUMENTS OR IN ANY OTHER MATTER CONNECTED THEREWITH) B) IN CASE OF GTE TENDERS, THE PERFORMANCE SECURITY SHALL BE IN THE SAME CURRENCY AS THE CONTRACT AND MUST CONFORM TO UNIFORM RULES FOR DEMAND GUARANTEES (URDG 758) - AN INTERNATIONAL CONVENTION REGULATING INTERNATIONAL SECURITIES. (C) PERFORMANCE SECURITY IS TO BE FURNISHED WITHIN A SPECIFIED DATE (GENERALLY 14(FOURTEEN) DAYS AFTER NOTIFICATION OF THE AWARD) AND IT SHOULD REMAIN VALID FOR A PERIOD OF 60 (SIXTY) DAYS BEYOND THE DATE OF COMPLETION OF ALL CONTRACTUAL OBLIGATIONS OF THE SUPPLIER, INCLUDING WARRANTY OBLIGATIONS. 2. FORFEITURE OF PERFORMANCE SECURITY: THE PERFORMANCE SECURITY WILL BE FORFEITED AND CREDITED TO BHEL'S ACCOUNT IN THE EVENT OF A BREACH OF CONTRACT BY THE SUPPLIER. 3. RETURN OF PERFORMANCE SECURITY (PS): PS SHALL BE REFUNDED TO THE BIDDER WITHOUT INTEREST, AFTER HE DULY PERFORMS AND COMPLETES THE CONTRACT IN ALL RESPECTS BUT NOT LATER THAN 60(SIXTY) DAYS OF COMPLETION OF ALL SUCH OBLIGATIONS INCLUDING THE WARRANTY UNDER THE CONTRACT. 4. THE PERFORMANCE SECURITY SHALL NOT CARRY ANY INTEREST.	
59	BREACH OF CONTRACT, REMEDIES AND TERMINATION: IN CASE OF BREACH OF CONTRACT, WHEREVER THE VALUE OF SECURITY INSTRUMENTS LIKE PERFORMANCE BANK GUARANTEE AVAILABLE WITH BHEL AGAINST THE SAID CONTRACT IS ATLEAST 10% OF THE CONTRACT VALUE, THE SAME BE ENCASHED. IN CASE THE VALUE OF THE SECURITY	

GENERAL COMMERCIAL TERMS & CONDITIONS OF ENQUIRY
(FOR INDIAN VENDORS)

Amendment- 24
ANNEXURE-A



	INSTRUMENTS AVAILABLE IS LESS THAN 10% OF THE CONTRACT VALUE, THE BALANCE AMOUNT BE RECOVERED FROM OTHER FINANCIAL REMEDIES (I.E. AVAILABLE BILLS OF THE CONTRACTOR, RETENTION AMOUNT, ETC. WITH BHEL) OR LEGAL REMEDIES BE PURSUED. FURTHER, LEVY OF LIQUIDATED DAMAGES, DEBARMENT, TERMINATION, DE-SCOPING, SHORT-CLOSURE, ETC., SHALL BE APPLIED AS PER PROVISIONS OF THE CONTRACT.	
--	---	--

NOTE:


1. PLEASE FILL IN THIS FORMAT AND SEND COMPULSORILY ALONG WITH QUOTATION WITH VENDOR'S SEAL, SIGNATURE AND DATE.

VENDOR SIGNATURE ALONG WITH SEAL AND DATE:


1. BREAK ALL SHARP EDGES AND CORNERS UNLESS OTHERWISE NOTED.
2. SUPPLY AS PER CUSTOMERS APPROVED QUALITY PLAN
3. ATTEST MATERIAL.



SECTION A-A
SCALE-1:2




SECTION B-B
SCALE-1:2




DETAIL-D

SCALE-1:1







DETAIL-E
SCALE-1:1



DETAIL-C

SCALE-1:1

	FORGING			3-61-000-90173	BA9413253137	790	036
					AA19332		
ITEM NO	DESCRIPTION	DRAWING NO.	VAR. NO.	RAW MATERIAL SIZE OR CASTING DRG.NO. OR FORGING DRG.NO.	MATERIAL CODE	NET WT.	GROSS WT.
					MATERIAL SPECN.	QUANTITY	

THE FOLLOWING CONDITIONS APPLY EXCEPT OTHERWISE STATED... 1. REF. TO HY0230261 FOR UNSPECIFIED TOLERANCES. 2. CHAMFER M/CD SHARP EDGES 1.2 TO 1.0 AT 45°. 3. INTERNAL M/CD CORNER RADI 1 TO 0.7. 4. THE SURFACE ROUGHNESS WHEREVER NOT SHOWN SHALL BE TAKEN FROM THE SURFACE ROUGHNESS SHOWN OUT SIDE BACK SLASHES GIVEN AT THE TOP MOST RIGHT CORNER OF THE DRG.	TYPE OF PRODUCT OR NAME OF CUSTOMER/PROJECT		1003 XRP BOWL MILL				
	 BHARAT HEAVY ELECTRICALS LTD. HYDERABAD		NAME	SIGN.	DATE	NO. OF VAR.	
		DRN.	N.D.S		15.4.99		
		CHD.	S.G		15.4.99		
		APPD.	K.M.RAO		15.4.99		
		DEPT. PULV. ENGG		SCALE	WEIGHT (KG)		REF. TO ASSY DRG.
CODE 446	1:5	790.036		C-101-01082/R1 CE-P/N-101-01082			
TITLE				DRAWING NO.		REV.	
JOURNAL SHAFT				1-61-000-00363		07	
				SHEET NO.		NO OF SHEETS	

DRG. NO. 1-61-004-01183

SH.01 OF 01
7

C

4

3








1

Q

"

10

12



NOTES:—


01. TAPER MUST FIT FULL CONTACT RING GAUGE WITH MIN OF 80% CONTACT BANDS OF NO CONTACT MUST NOT EXCEED 10° OF ARC.
02. ALL DIAMETERS TO BE CONCENTRIC WITH DATUMS A & B WITHIN 0.25 T.I.R UNLESS OTHERWISE SPECIFIED.
03. ALL FILLETS $\frac{\sqrt{r}}{2}$
04. REFER DRG. NO. 3-61-004-90184 FOR ROUGH FORGING.
05. BREAK ALL SHARP EDGES.
- 06 VAR. 01 METRIC THREADING & VAR. 02 INCH THREADING.

MATERIAL ATTESTATION


01	FORGING			VAR NO.	RAW MATERIAL SIZE OR CASTING DRG. NO. OR FORGING DRG. NO.	BA9413253242	799.00	
						AA193532	1	
						MATERIAL CODE	NET WT.	GROSS WT
						MATERIAL SPECN.	QUANTITY	

THE FOLLOWING CONDITIONS APPLY EXCEPT OTHERWISE STATED:					
1. REF. TO HY020261 FOR UNSPECIFIED TOLERANCES.					
2. CHAMFER M/C/D. SHARP EDGES 1.2 TO 1.0 AT .45°					
3. INTERNAL M/C/D. CORNER RADIUS 1 TO 0.7					
4. THE SURFACE ROUGHNESS WHERE-EVER NOT SHOWN SHALL BE TAKEN FROM THE SURFACE ROUGHNESS SHOWN OUT SIDE THE BACK SLASH GIVEN ON THE TOP MOST RIGHT CORNER OF THE DRG.					
TYPE OF PRODUCT NAME OF CUSTOMER-/PROJECT		BHAAT HEAVY ELECTRICALS LIMITED HYDERABAD			
1103 XRP BOWL MILL					
		DEPT. SCALE			TITLE
JOURNAL SHAFT		UNIT: DMS. OR. IN/FT		SCALE 799.00	JOURNAL SHAFT
DRAWING NO.		CADD CODE		REV.	
1-61-004-01183		KPD		NO.OF	
SHEET No. 01 / NO OF SHEETS 01		REF. TO ASSY DRG.		DATE	
02		1-61-004-01190		10.06.99	
		09		VAR.	
		30		-	

F	E	D	C	B	A
GENERAL DIMENSIONAL LIMITS, FITS & TOLERANCES AS PER HY0230261					



M30x3.5-65 DEEP 10 HOLES EQ. SPACED
(SEE DETAIL-A) $\oplus$ $\varnothing 0.4$ (M) B (M)



21 1/2"-4UNS-2A	
MAJOR DIA 21.4963	+0.000 -0.038
PITCH DIA 21.3339	+0.000 -0.0125
MINOR DIA 21.1933	REF.
	+0.000 -0.050

	DRILL THRU AND TAP 1" NPT.
	C'BORE $\phi 40$ - 10 DEEP
	NEAR SIDE AS SHOWN

1. TAPER MUST BE CHECKED WITH A RING GAUGE AND A MINIMUM OF 80% CONTACT SHALL BE OBTAINED. BANDS OF NO CONTACT MUST NOT EXCEED 10° OF ARC.
2. 100% INSPECTION OF ALL THREADS REQUIRED.
3. BREAK ALL SHARP EDGES & CORNERS UNLESS OTHERWISE NOTED.

REV.	DATE	ALTERED	APPD.
03	28.11.03	CHD.G.S.N.M.RAO	
ZONE	DRAWING REDRAWN BY		

THE FOLLOWING CONDITIONS APPLY
EXCEPT OTHERWISE STATED.

1. REF. TO HY0230261 FOR
UNSPECIFIED TOLERANCES.
2. CHAMFER M/CD. SHARP EDGES 1.2 TO 1.0
AT 45°.
3. INTERNAL M/CD. CORNER RADII 1 TO 0.7
4. THE SURFACE ROUGHNESS WHERE-EVER NOT
SHOWN SHALL BE TAKEN FROM THE SURFACE
ROUGHNESS SHOWN OUT SIDE THE BACK
SLASH GIVEN OR THE TOP MOST RIGHT
CORNER OF THE DRG.

883 XRP BOWL MILL

TITLE	CARD CODE	DRAWING NO.	REV.
LOWER JOURNAL HOUSING	U 01	2-61-088-02056	07


TITLE	LOWER JOURNAL HOUSING
-------	-----------------------

CARD CODE	DRAWING NO.	REV.
U 01	2-61-088-02056	07


SHEET NO. 01	NO OF SHEETS 01
--------------	-----------------

INVENTORY NO. SIGN. AND DATE REF. DRG. NO. C-94-851 REF. DRG. NO. 26102058.DWG

THE INFORMATION ON THIS DOCUMENT IS THE PROPERTY OF BHARAT HEAVY ELECTRICALS LIMITED. IT MUST NOT BE USED DIRECTLY OR INDIRECTLY IN ANY WAY DETRIMENTAL TO THE INTEREST OF THE COMPANY



INVENTORY NO
SIGN. AND DATE
REF. DRG. NO.
(C-94-852/03)
COMPUTER FILE NAME
26102059.DWG
THE INFORMATION ON THIS DOCUMENT IS THE PROPERTY OF BHARAT HEAVY ELECTRICALS LIMITED. IT MUST NOT BE USED DIRECTLY OR INDIRECTLY IN ANY WAY DETRIMENTAL TO THE INTEREST OF THE COMPANY




THE INFORMATION ON THIS DOCUMENT IS THE PROPERTY OF BHARAT HEAVY ELECTRICALS LTD.
IT MUST NOT BE USED DIRECTLY OR INDIRECTLY IN ANY WAY DETRIMENTAL TO THE INTEREST OF THE COMPANY.

FILE NAME

1-61-000-90168
REF.DRG.NO.

INVENTORY NO.

DRG.NO. 3-61-000-90168



LOCATE HEAR ATTESTATION DETAILS VIZ

SUPPLIERS CODE

FORGE NO

MAT SPECN

MELT NO

NOTE

1. FORGING TO BE ROUGH MACHINED TO DIMENSIONS INDICATED IN THE DRAWING
- 2.CHAMFER CORNERS TO R2 & FILLET RADIUS ARE TO BE R3
3. TEST ULTRASONICALLY AS PER SPECIFICATIONS AA0850118 CAT-3
4. FORGING SHOULD BE AS PER SPECIFICATIONS AA19332
5. TOLERENCE ON DIAMETERS AND LENGTHS±1MM
6. FOR FINISH MACHINING REFER 1-61-000-00365

12.5

FORGING				BA9413221235			
				AA 19332			
ITEM NO	DESCRIPTION	DRAWING NO.	VAR. NO.	RAW MATERIAL SIZE OR CASTING DRG.NO. OR FORGING DRG.NO.	MATERIAL CODE	NET WT.	GROSS WT.
					MATERIAL SPECN.	QUANTITY	

THE FOLLOWING CONDITIONS APPLY EXCEPT OTHERWISE STATED...

1. REF.TO HY0230261 FOR UNSPECIFIED TOLERANCES.
2. CHAMFER M/CD SHARP EDGES 1.2 TO 1.0 AT 45°.
3. INTERNAL M/CD CORNER RADII 1 TO 0.7.
4. THE SURFACE ROUGHNESS WHEREVER NOT SHOWN SHALL BE TAKEN FROM THE SURFACE ROUGHNESS SHOWN OUT SIDE BACK SLASHES GIVEN AT THE TOP MOST RIGHT CORNER OF THE DRG.

TYPE OF PRODUCT OR NAME OF CUSTOMER/PROJECT 1003 XRP BOWL MILL KORBA&RAMAGUNDAM 500MW




BHARAT HEAVY ELECTRICALS LTD.
HYDERABAD

DEPT. PULVE.ENG	SCALE 1:5	WEIGHT (KG) 854.00	REF. TO ASSY DRG. 1-61-000-90168	ITEM NO.	NO.OF ITEMS
CODE 446					
TITLE UPPER JOURNAL HOUSING			DRAWING NO. 3-61-000-90168	REV. 01	
			SHEET NO. 01	NO OF SHEETS 01	

THE INFORMATION ON THIS DOCUMENT IS THE PROPERTY OF BHARAT HEAVY ELECTRICALS LTD.
IT MUST NOT BE USED DIRECTLY OR INDIRECTLY IN ANY WAY DETRIMENTAL TO THE INTEREST OF THE COMPANY.

DRG.NO. 3-61-000-90173



LOCATE HARE ATTESTATION DETAILS VIZ.
SUPPLIERS CODE
FORGE No.
MAT. SPECN.
MELT.No.

NOTE

1. FORGING TO BE MACHINED TO DIMENSIONS INDICATED IN THE DRAWING
- 2 CHAMFER SHARP CORNERS TO R2 & ALL FILLET RADIUS TO R3
- 3TEST ULTRASONICALLY AS PER SPECIFICATIONS AA0850118 CAT-3
- 4.FORGING SHOULD BE AS PER SPECIFICATIONS AA19332
5. TOLERANCE ON DIAMETERS AND LENGTHS ± 1 MM
6. HOLE $\phi 32$ SHIULD BE CONCENTRIC WITH CENTRE LINE WITH ± 1 MM
7. FOR FINISH MACHINING REFER 1-61-000-00363

	FORGING			BA9413253226	876.00	
				AA19332		
ITEM NO	DESCRIPTION	DRAWING NO.	VAR. NO.	RAW MATERIAL SIZE OR CASTING DRG.NO. OR FORGING DRG.NO.	MATERIAL CODE	NET WT. GROSS WT.
					MATERIAL SPECN.	QUANTITY

THE FOLLOWING CONDITIONS APPLY EXCEPT OTHERWISE STATED...

1. REF.TO HY0230261 FOR UNSPECIFIED TOLERANCES.

2. CHAMFER M/CD SHARP EDGES 1.2 TO 1.0 AT 45°.

3. INTERNAL M/CD CORNER RADII 1 TO 0.7.

4. THE SURFACE ROUGHNESS WHEREVER NOT SHOWN SHALL BE TAKEN FROM THE SURFACE ROUGHNESS SHOWN OUT SIDE BACK SLASHES GIVEN AT THE TOP MOST RIGHT CORNER OF THE DRG.

TYPE OF PRODUCT
OR
NAME OF CUSTOMER/PROJECT

1003 XRP BOWL MILL
KORBA & RAMAGUNDAM 500 MW

भारत भारेल

BHEL

BHARAT HEAVY ELECTRICALS LTD.
HYDERABAD

DRN.

NARAYANA

CHD.

N.D.S

APPD.

S.GHATGE

DEPT.

PULVE.ENG

CODE

446

SCALE

1:10

WEIGHT (KG)

876.00

REF. TO ASSY DRG.

1-61-000-00363

ITEM NO.

NO.OF ITEMS

TITLE

JOURNAL SHAFT
(ROUGH MACHINED)

DRAWING NO.

3-61-000-90173

SHEET NO.

01

NO OF SHEETS

01

REV.

01

FIRST ANGLE PROJECTION

(ALL DIMENSIONS ARE IN mm)

78106-700-19-E 'ON'GRD

12.5 // 6.3 ✓

THE INFORMATION ON THIS DOCUMENT IS THE PROPERTY OF BHARAT HEAVY ELECTRICALS LTD. IT MUST NOT BE USED DIRECTLY OR INDIRECTLY IN ANY WAY DETRIMENTAL TO THE INTEREST OF THE COMPANY.

36190184.DWG
FILE NAME

1-61-004-01183
REF.DRG.NO.


INVENTORY NO.
ZONE

REV.	DATE	ALTERED	REV.	DATE	ALTERED	PKP
		CHD.	01	07.11.12	CHD.	CKP
		APPD.			APPD.	V KUMAR
ZONE			ZONE			

DRAWING DRAWN ON AUTOCAD
DIM. 120, 94.5, 250 WERE 105, 950
AND 260 RESPECTIVELY.

- NOTE
- FORGING TO BE MACHINED TO DIMENSIONS INDICATED IN THE DRAWING
 - CHAMFER SHARP CORNERS TO R2 & ALL FILLET RADIUS TO R3
 - TEST ULTRASONICALLY AS PER SPECIFICATIONS
 - AA0850118 CAT-3
 - FORGING SHOULD BE AS PER SPECIFICATIONS AA19332
 - TOLERANCE ON DIAMETERS AND LENGTHS ± 1MM
 - HOLE Ø32 SHOULD BE CONCENTRIC WITH CENTRE LINE WITH ± 1MM
 - FOR FINISH MACHINING REFER 1-61-004-01183

LOCATE HARE ATTESTATION DETAILS VIZ.
SUPPLIERS CODE
FORGE No.
MAT. SPECN.
MELT.No.




01	FORGING			BA9413253242	890	
				AA19332		
				MATERIAL CODE	NET WT.	GROSS WT.
ITEM NO	DESCRIPTION	DRAWING NO.	VAR. NO.	MATERIAL SPECN.	QUANTITY	

- THE FOLLOWING CONDITIONS APPLY
EXCEPT OTHERWISE STATED...
- REF.TO HY0230261 FOR UNSPECIFIED TOLERANCES.
 - CHAMFER M/CD SHARP EDGES
1.2 TO 1.0 AT 45°.
 - INTERNAL M/CD CORNER RADII
1 TO 0.7.
 - THE SURFACE ROUGHNESS WHEREVER NOT SHOWN SHALL BE TAKEN FROM THE SURFACE ROUGHNESS SHOWN OUT SIDE BACK SLASHES GIVEN AT THE TOP MOST RIGHT CORNER OF THE DRG.

TYPE OF PRODUCT		1043 XRP BOWL MILL	
OR		NAME OF CUSTOMER/PROJECT CHANDRAPUR 500 MW	
	NAME		DATE
	DRN.	PKP	07.11.12
	CHD.	CKP	07.11.12
	APPD.	V KUMAR	07.11.12
DEPT.	PULVE.ENG	SCALE	WEIGHT (KG)
		NTS	890.00
CODE	446	REF. TO ASSY DRG.	ITEM NO.
TITLE		DRAWING NO.	REV.
JOURNAL SHAFT		3-61-004-90184	01
(ROUGH MACHINED)		SHEET NO. 01	NO OF SHEETS 01

16320-088-19-61
DRG.NO. 3-61-088-02058



THE INFORMATION ON THIS DOCUMENT IS THE PROPERTY OF BHARAT HEAVY ELECTRICALS LTD.
IT MUST NOT BE USED DIRECTLY OR INDIRECTLY IN ANY WAY DETRIMENTAL TO THE INTEREST OF THE COMPANY.

INVENTORY NO.				REF.DRG.NO.				FILE NAME			
REV.				DATE				02			
CHD.				APPD.				15.11.03			
ZONE				REV.				DATE			
				CHD.				N.D.S.			
				APPD.				S.G.			
				ZONE				DRAWING DRAWN IN			
								AUTOCAD			

1.FORGING SHALL BE ROUGH MACHINED TO DIMENSIONS INDICATED IN THE DRAWING
2.BREAK ALL SHARP EDGES&ALL CORNER RADI TO BE R2
3.FORGING SHALL BELTESTED ULTRASONICALLY AS PER BH&EL CORP.STDA0850118 CAT-2
4.REFER DRG 2-61-088-02058 FOR FINISH MACHINING
5.HOLE ±32 SHOULD BE CONCENTRIC WITH RESPECT TO CENTRE LINE WITH IN 0.5MM

FORGING					
ITEM NO	DESCRIPTION	DRAWING NO.	VAR. NO.	RAW MATERIAL SIZE OR CASTING DRG.NO. OR FORGING DRG.NO.	AA19332,REV.10
				MATERIAL CODE	NET WT.
				MATERIAL SPECN.	GROSS WT.
				QUANTITY	

THE FOLLOWING CONDITIONS APPLY EXCEPT OTHERWISE STATED...
1. REF.TO HY0230261 FOR UNSPECIFIED TOLERANCES.
2. CHAMFER M/CD SHARP EDGES 1.2 TO 1.0 AT 45°.
3. INTERNAL M/CD CORNER RADI 1 TO 0.7.
4. THE SURFACE ROUGHNESS WHEREVER NOT SHOWN SHALL BE TAKEN FROM THE SURFACE ROUGHNESS SHOWN OUT SIDE BACK SLASHES GIVEN AT THE TOP MOST RIGHT CORNER OF THE DRG.

TYPE OF PRODUCT OR NAME OF CUSTOMER/PROJECT				883 XRP BOWL MILL			
भारत भारेल BH&EL		BHARAT HEAVY ELECTRICALS LTD.		HYDERABAD			
DEPT.	PULVE.ENG		SCALE	WEIGHT (KG)	REF. TO ASSY DRG.	ITEM NO.	NO.OF ITEMS
CODE	446		1:5	662	-		
TITLE				DRAWING NO.			
JOURNAL SHAFT				3-61-088-02391			
<ROUGH MACHINED>							
SHEET NO. 01		NO OF SHEETS		01		REV.	
						01	


THE INFORMATION ON THIS DOCUMENT IS THE PROPERTY OF BHARAT HEAVY ELECTRICALS LTD.
IT MUST NOT BE USED DIRECTLY OR INDIRECTLY IN ANY WAY DETRIMENTAL TO THE INTEREST OF THE COMPANY.

36102392.DWG
FILE NAME

REF.DRG.NO.

INVENTORY NO.

DRG.NO. 3-61-088-02392




- NOTE**
1. FORGING TO BE ROUGH MACHINED TO DIMENSIONS INDICATED IN THE DRG
 - 2.BREAK ALL SHARP EDGES &ALL CORNER RADII TO BE R2
 3. TEST ULTRASONICALLY AS PER SPECIFICATIONS AA0850118 CAT-3
 4. FOR FINISH MACHINING REFER 2-61-088-02056

FORGING					BA9413221316	990	
					AA 19332		1
ITEM NO	DESCRIPTION	DRAWING NO.	VAR. NO.	RAW MATERIAL SIZE OR CASTING DRG.NO. OR FORGING DRG.NO.	MATERIAL CODE	NET WT.	GROSS WT.
					MATERIAL SPECN.	QUANTITY	

THE FOLLOWING CONDITIONS APPLY EXCEPT OTHERWISE STATED...

1. REF.TO HY0230261 FOR UNSPECIFIED TOLERANCES.
2. CHAMFER M/CD SHARP EDGES 1.2 TO 1.0 AT 45°.
3. INTERNAL M/CD CORNER RADII 1 TO 0.7.
4. THE SURFACE ROUGHNESS WHEREVER NOT SHOWN SHALL BE TAKEN FROM THE SURFACE ROUGHNESS SHOWN OUT SIDE BACK SLASHES GIVEN AT THE TOP MOST RIGHT CORNER OF THE DRG.

TYPE OF PRODUCT OR NAME OF CUSTOMER/PROJECT 883 XRP BOWL MILL

 BHARAT HEAVY ELECTRICALS LTD. HYDERABAD				NAME		SIGN.	DATE	NO.OF VAR.	
				DRN.		NARAYANA			17.11.03
				CHD.		N.D.S			17.11.03
				APPD.		S.GHATGE			17.11.03
DEPT. PULVE.ENG			SCALE 1:5	WEIGHT (KG) 990	REF. TO ASSY DRG. 26108802056		ITEM NO. 1	NO.OF ITEMS 1	
CODE 446									
TITLE LOWER JOURNAL HOUSING (ROUGH MACHINED)					DRAWING NO. 3-61-088-02392			REV. 03	
					SHEET NO. 01		NO OF SHEETS 01		


THE INFORMATION ON THIS DOCUMENT IS THE PROPERTY OF BHARAT HEAVY ELECTRICALS LTD.
IT MUST NOT BE USED DIRECTLY OR INDIRECTLY IN ANY WAY DETRIMENTAL TO THE INTEREST OF THE COMPANY.

36102393.DWG
FILE NAME

REF.DRG.NO.

INVENTORY NO.

DRG.NO. 3-61-088-02393



NOTE

1. FORGING TO BE ROUGH MACHINED TO DIMENSIONS INDICATED IN THE DRAWING
- 2.BREAK ALL SHARP EDGES &ALL CORNER RADII TO BE R2
3. TEST ULTRASONICALLY AS PER SPECIFICATIONS AA0850118 CAT-3
4. FOR FINISH MACHINING REFER 2-61-088-02059

FORGING					BA9413221324	653.0	
					AA 19332		
ITEM NO	DESCRIPTION	DRAWING NO.	VAR. NO.	RAW MATERIAL SIZE OR CASTING DRG.NO. OR FORGING DRG.NO.	MATERIAL CODE	NET WT.	GROSS WT.
					MATERIAL SPECN.	QUANTITY	

THE FOLLOWING CONDITIONS APPLY EXCEPT OTHERWISE STATED...

1. REF.TO HY0230261 FOR UNSPECIFIED TOLERANCES.
2. CHAMFER M/CD SHARP EDGES 1.2 TO 1.0 AT 45°.
3. INTERNAL M/CD CORNER RADII 1 TO 0.7.
4. THE SURFACE ROUGHNESS WHEREVER NOT SHOWN SHALL BE TAKEN FROM THE SURFACE ROUGHNESS SHOWN OUT SIDE BACK SLASHES GIVEN AT THE TOP MOST RIGHT CORNER OF THE DRG.

TYPE OF PRODUCT OR NAME OF CUSTOMER/PROJECT 883 XRP BOWL MILL




BHARAT HEAVY ELECTRICALS LTD.
HYDERABAD

DEPT. PULVE.ENG	SCALE 1:5	WEIGHT (KG) 653	REF. TO ASSY DRG. 2.61.088.02059	ITEM NO. 1	NO.OF ITEMS 1
CODE 446			DRAWING NO. 3-61-088-02393	REV. 01	
TITLE UPPER JOURNAL HOUSING (ROUGH MACHINED)			SHEET NO. 01	NO OF SHEETS 01	

THE INFORMATION ON THIS DOCUMENT IS THE PROPERTY OF BHARAT HEAVY ELECTRICALS LTD.
IT MUST NOT BE USED DIRECTLY OR INDIRECTLY IN ANY WAY DETRIMENTAL TO THE INTEREST OF THE COMPANY.

DRG.NO. 3-61-376-90010

12.5



LOCATE HERE ATTESTATION DETAILS VIZ
SUPPLIERS CODE
FORGE No
MAT. SPECN
MELT No.

- NOTE:—
- 1.FORGING TO BE ROUGH MACHINED TO DIMERNSIONS INDICATED IN DRG
 - 2.FIGURE IN DASHED LINE REPRESENTS SHAPE OF FINAL MACHINED COMPONENT
 - 3.CORNER CHAMFERS –R2;FILLET RADIUS–R3.
 - 4.TOLERENCE ON DIAMETERS AND LENGTH ±1MM
 - 5.FORGING SHOULD BE AS PER CPS-AA19332
 - 6.TEST ULTRASONICALLY AS PER CORP ORATION STD AA-085-01-18-CAT-3

	FORGING			BA9413221022		
				AA 19332		
ITEM NO	DESCRIPTION	DRAWING NO.	VAR. NO.	RAW MATERIAL SIZE OR CASTING DRG.NO. OR FORGING DRG.NO.	MATERIAL CODE	NET WT. GROSS WT.
					MATERIAL SPECN.	QUANTITY

THE FOLLOWING CONDITIONS APPLY EXCEPT OTHERWISE STATED...

1. REF.TO HY0230261 FOR UNSPECIFIED TOLERANCES.
2. CHAMFER M/CD SHARP EDGES 1.2 TO 1.0 AT 45°.
3. INTERNAL M/CD CORNER RADII 1 TO 0.7.
4. THE SURFACE ROUGHNESS WHEREVER NOT SHOWN SHALL BE TAKEN FROM THE SURFACE ROUGHNESS SHOWN OUT SIDE BACK SLASHES GIVEN AT THE TOP MOST RIGHT CORNER OF THE DRG.


TYPE OF PRODUCT OR MATERIAL ATTEST
NAME OF CUSTOMER/PROJECT 76”BOWL MILL



BHARAT HEAVY ELECTRICALS LTD.
HYDERABAD

DEPT. PULVE.ENGG	SCALE N.T.S	WEIGHT (KG) 480	REF. TO ASSY DRG. 40-F-002-016	ITEM NO.	NO.OF ITEMS
CODE 446			DRAWING NO. 3-61-376-90010	REV. 08	
TITLE LOWERJOURNAL HOUSING			SHEET NO. 01	NO OF SHEETS 01	

INVENTORY NO.



NOTE

- | | | | | | | | |
|---------|-------------|-------------|----------|---|-----------------|----------|-----------|
| | FORGING | | | | BA9413253048 | 463 | |
| | | | | | AA19332 | | |
| ITEM NO | DESCRIPTION | DRAWING NO. | VAR. NO. | RAW MATERIAL SIZE OR
CASTING DRG.NO. OR
FORGING DRG.NO. | MATERIAL CODE | NET WT. | GROSS WT. |
| | | | | | MATERIAL SPECN. | QUANTITY | |

1. REF.TO HY0230261 FOR UNSPECIFIED TOLERANCES.
2. CHAMFER M/CD SHARP EDGES
1.2 TO 1.0 AT 45°.
3. INTERNAL M/CD CORNER RADII
1 TO 0.7.
4. THE SURFACE ROUGHNESS WHEREVER NOT SHOWN
SHALL BE TAKEN FROM THE SURFACE ROUGHNESS
SHOWN OUT SIDE BACK SLASHES GIVEN AT THE
TOP MOST RIGHT CORNER OF THE DRG.

TYPE OF PRODUCT OR NAME OF CUSTOMER/PROJECT	76" BOWL MILL 'MATERIAL ATTEST'
---	------------------------------------

 BHARAT HEAVY ELECTRICALS LTD. HYDERABAD				NAME	SIGN.	DATE	NO.OF VAR.
		DRN.	NARAYANA		17.11.03		
		CHD.	N.D.S		17.11.03		
		APPD.	S.GHATGE		17.11.03		
DEPT.	PULVE.ENGG		SCALE	WEIGHT (KG)	REF. TO ASSY DRG.	ITEM NO.	NO.OF ITEMS
CODE	446		NTS	463	—		
TITLE JOURNAL SHAFT (ROUGH MACHINED)					DRAWING NO.		REV.
					3-61-376-90011		03
					SHEET NO.	01	NO OF SHEETS
					01		


FIRST ANGLE PROJECTION

(ALL DIMENSIONS ARE IN mm)

REV.	DATE	ALTERED	REV.	DATE	ALTERED
		CHECKED			CHECKED
ZONE			ZONE		

12.5/6.3/

A



LOCATE HERE ATTESTATION

DETAILS VIZ.

SUPPLIER'S CODE.

FORGE NO.

MAT. SPECN

MELT. NO.

NOTE

1. FORGING TO BE ROUGH MACHINED TO DIMENSIONS INDICATED IN DRG.
2. HOLE $\phi 64$ SHOULD BE CONCENTRIC WITH CENTRE LINE WITH ± 1 MM
3. TEST ULTRASONICALLY AS PER SPEN. AA0850118 CAT-3.
4. TOLERANCE ON DIAMETERS AND LENGTH ± 1 MM.
5. FOR FINISH MACHINING REFER DRG. NO. I-61-004-01184

REFER PLANT STANDARD
HY 0230261 FOR
UNSPECIFIED TOLERANCES



SECTION AA

1003XRP BOWL MILL

REF. DRG. NO.

SIGN & DATE

INVENTORY NO.

DEPT	GRADE OF TOL. DIM.	SCALE	WEIGHT (Kg)	REF. TO ASSY. DRG.	ITEM NO.	NO. OF ITEMS
BMD	446	NTS	548.0	D-110-00767	75	77
CODE						

BHARAT HEAVY ELECTRICALS LTD
HYDERABAD

FORGING

REMARKS

DESCRIPTION

ITEM NO.

25

27

29

58

59

65

NAME	SIGN.	DATE	NO. OF VAR.
D.C.	Dr. C.	25.1.93	65
CHD.	N.D.S.	31.3.93	71
APPD.	Y S L. Rao	3.4.93	71

REF. TO ASSY. DRG.	ITEM NO.	NO. OF ITEMS
D-110-00767	75	77

TITLE

TRUNNION SHAFT
(ROUGH FORGING)

CARD CODE

DRAWING NO.
4-61-004-90249

REV. 1

SHEET NO.

NO. OF SHEETS

TD-152, REV. NO. 2

SIZE-A-4



CORPORATE PURCHASE SPECIFICATION

AA 193 32

Rev. No. 10

PAGE 1 OF 7

CARBON STEEL FORGINGS, CLASS-3

↑

1.0 GENERAL:

This specification governs the quality requirements of Carbon Steel Forgings, class 3.

↑

2.0 APPLICATION:

Suitable for general engineering purposes.

3.0 CONDITION OF DELIVERY:

Normalised/Normalised and tempered.

Rough machining of the forgings shall be carried out, unless otherwise specified in the BHEL order/drawing.

4.0 COMPLIANCE WITH NATIONAL STANDARDS:

The forgings shall comply, in general with the requirement of the following National standards and also meet the requirements of this specification.

IS::2004: 1991 (RA-2006) } Carbon Steel Forgings For General Engineering

Gr: 3 (30C8), } Purposes.

↑

5.0 DIMENSIONS AND TOLERANCES:

The dimensions and tolerances shall be as specified in the order/ drawing. Wherever these are not specified, specified, the machining allowances and tolerances shall be as specified below:

For finish machined drawings : 3 ± 1 mm

For rough machined drawings : ± 1 mm

Revisions : 36th MOM OF MRC FCF+HTM

APPROVED :
INTERPLANT MATERIAL RATIONALISATION
COMMITTEE-MRC (FC&F+HTM)

Rev. No. 10

Amd.No.

Reaffirmed

Prepared

Issued

Dt. of 1st Issue

Dt. 23.01.2007

Dt :

Year:04-11-2011

HARDWAR

Corp. R&D

JANUARY 1978

**6.0 MANUFACTURE:**

Forgings shall be manufactured from steel produced by the open hearth, electric or such other [↑] process as may be agreed to between BHEL and the manufacturer.

Steel shall be fully killed.

Sufficient discard shall be made from each ingot to ensure freedom from pipe, segregation and other defects.

The amount of hot working and finishing temperature shall be such as to ensure complete soundness and adequate uniformity of structure and mechanical properties after heat treatment. The forgings shall not be overheated.

The minimum reduction ratio when forgings are made out of ingots shall be 4:1.

For sizes above 250 mm ruling section, the minimum reduction ratio shall be 3.5:1

Note: Raw material like Ingots/Blooms/Billets required for forgings should be procured from BHEL approved sources along with test certificate."

7.0 HEAT TREATMENT:

Forgings shall be normalised / normalised and tempered at suitable temperature to achieve [↑] the mechanical properties specified.

Test pieces shall also be heat treated along with the forgings they represent.

8.0 FINISH:

As mentioned in the drawing.

9.0 FREEDOM FROM DEFECTS:

The forging shall be free from defects, such as cracks, fold, flakes, seams, segregation, nonmetallic inclusions and other defects which may affect the utility of the forging.

10.0 CHEMICAL COMPOSITION:

The melt analysis of steel and permissible variation in the composition of the forgings from the melt analysis shall be as follows:

Element	Melt analysis, percent		Permissible variation, percent
	Min.	Max.	
Carbon	0.25	0.35	± 0.03
Silicon	0.15	0.35	± 0.03
Manganese	0.60	0.90	± 0.04
Sulphur	---	0.040	+ 0.005
Phosphorus	---	0.040	+ 0.005



CORPORATE PURCHASE SPECIFICATION

AA 193 32

Rev. No. 10

PAGE 3 OF 7

Notes:

1. Elements not quoted above shall not be added to the steel, other than for the purpose of finishing the heat and shall not exceed the following limits:

Element	Percent, max.
Nickel	0.30
Chromium	0.30
Copper	0.25
Molybdenum	0.15
Vanadium	0.05
Tin	0.05
Boron	0.0003

2. When steel is aluminium killed or killed with both aluminium and silicon, the requirements of minimum silicon content shall not apply. For aluminium killed steel the total aluminium content shall be within 0.02 to 0.05 percent.
3. $Mo \leq 0.15\%$, limiting to meeting conditions of $Cr + Mo + Ni = 0.5\%$.

11.0 TEST SAMPLES:

- 11.1 Unless otherwise specified in the order/drawing, test samples shall be taken from each melt and each heat treatment batch. Test samples should be cut from the heat treated forgings by cold process only and shall not have further heat treatment.

Test samples shall be taken from locations indicated on the drawing, leaving enough material, if required for testing at BHEL's end, integral with forgings.

The samples shall be cylindrical or rectangular in shape and cut at a distance of 12.5mm below the heat treated surface.

- 11.2 When integral test pieces are not called for, a test sample, having similar reduction ratio and heat treatment, as the forgings it represents, shall be provided per heat, per heat treatment batch, for check testing at BHEL, along with the forgings. The samples shall be properly identified and correlated with the Heat/Heat treatment Batch No./ Test Certificate No. Test samples shall be taken, at a distance of 12.5mm below the heat-treated surface.
- 11.3 Test samples shall generally be taken in the longitudinal direction. However, for economic reasons or where the size/ configuration does not permit the same, test samples may be taken in the transverse or radial direction.

12.0 MECHANICAL PROPERTIES:

The test pieces, after being heat treated as per clause 7.0 above, shall show the following properties upto a limiting ruling section of 800 mm. Properties for thicker sections shall be subject to agreement between BHEL and the manufacturer. Test methods are specified below:

- 12.1 Tensile test : IS:1608
- 12.2 Hardness test (Brinell) : IS:1500
- 12.3 Charpy Impact Value (2mm U-Notch) : IS:1499

This test applicable for forgings of sizes above 16mm only.

Property	Sample (See Cl.11.3)	Limiting ruling section, mm			
		Upto & incl 100	>100 & upto 300	> 300 & upto 500	>500 & upto 800
Tensile strength N/mm ²	Longitudinal/	490	470	450	450
	Transverse/ Radial/Tangential	490	470	450	450
Yield strength min, N/mm ²	Longitudinal/	270	245	230	220
	Transverse/ Radial/Tangential				
Elongation on 5.65 $\sqrt{S_0}$ gauge length percent, min	Longitudinal	21	19	18	17
	Transverse	10	9	8	7
	Radial	14	12	11	10
	Tangential	16	14	13	12
Reduction in area, percent min.	Longitudinal	42	40	35	32
	Transverse	25	24	22	20
	Radial	27	26	24	22
	Tangential	34	32	32	30
*Hardness, Brinell, HB	—	140-192	140-192	135-190	135-190
Charpy Impact Value (2mm, U-Notch) min., Joules	Longitudinal	35	31	27	23
	Transverse	18	16	14	12
	Radial	21	19	17	15
	Tangential	26	23	20	17

Note: 1. Unless otherwise stated on the order/drawing, small forgings of non-critical nature weighing less than 300kg shall be accepted on the basis of chemical composition and hardness.

* 2. Hardness test can be conducted only, when tensile test can not be performed.



CORPORATE PURCHASE SPECIFICATION

AA 193 32

Rev. No. 10

PAGE 5 OF 7

13.0 ULTRASONIC TESTS:



- 13.1 For forgings ordered by BHEL, Hyderabad: Unless other wise specified on the drawing, ultrasonic test shall be carried out as per BHEL standard AA 085 01 18 and norms of acceptance shall be as per category 2.
- 13.13.2 For forgings ordered by other units: If specified on the drawing/order, ultrasonic test shall be carried out as per BHEL standard AA 085 01 18 and norms of acceptance shall be as per category 2, unless otherwise specified.

14.0 ADDITIONAL TESTS:

If specified in the drawing/order, the following tests shall be conducted:

14.1 Bend Test (Longitudinal):

The test pieces (230mm long and 32 mm square with edges rounded off, where the dimensions permit) shall be capable of being bent cold by direct pressure without fracture, until the sides are parallel, round a mandrel having a diameter of 44 mm when tested as per IS:1599.

14.2 Magnetic particle test.

14.3 Any other tests: Norms of acceptance shall be as specified in the drawing/order.

15.0 SCOPE OF THIRD PARTY INSPECTION:

Wherever, separate quality plan is not attached, the scope of third party inspection shall be as follows:

1. Review of supplier's declared chemical composition.
2. Selection of test samples for mechanical tests and witness of mechanical tests.
3. Witness of Non-destructive tests as applicable.
4. Review of HT charts.
5. Dimensional inspection.

16.0 TEST CERTIFICATE:

Three copies of test certificates shall be supplied unless otherwise stated in the order, preferably in the test certificate format annexed to this specification (Annexure 1).

In addition, the supplier shall ensure to enclose one copy of the test certificate along with their dispatch documents to facilitate quick clearance of the material.

The following details shall be furnished in the test certificate:

- i) Reduction ratio
- ii) Dimensional Inspection.
- iii) Chemical composition including trace elements.
- iv) Results of mechanical tests.
- v) Results of Ultrasonic test
- vi) Details of heat treatment
- vii) Results of additional tests called for in the drawing/order.

AA 193 32	CORPORATE PURCHASE SPECIFICATION	
Rev. No. 10		
PAGE 6 OF 7		

17.0 PACKING & MARKING:

Forgings shall be suitably packed to prevent corrosion and damage during transit.

Machined surfaces shall be properly protected with anticorrosive compounds.

Each package or forging (when supplied separately) shall be legibly marked with the following information:

AA 193 32 : Carbon Steel Forgings, Class 3 ↑

BHEL Order No.

Suppliers Name

Consignment/ Identification No.

Batch No.

Weight.

18.0 REFERRED STANDARDS (Latest publications Including Amendments):

1) AA 085 01 18	2) IS:1499	3) IS:1500	4) IS:1599
5) IS: 1608	6) 2004		



CORPORATE PURCHASE SPECIFICATION

AA 193 32

Rev. No. 10

PAGE 7 OF 7

ANNEXURE-I: RECOMMENDED TEST CERTIFICATE FORMAT FOR FORGINGS

SUPPLIER'S NAME AND ADDRESS													
TEST CERTIFICATE FOR FORGINGS													
1. Customer:							9. Reduction Ratio } Ingot to Bloom Bloom to Blank						
2. TC No. & Date:							10. Batch No.:						
3. PO No.:							11. Heat/Melt No.						
4. Process of Melting Ingot:							12. Spec. No.						
5. Deoxidisation Process:							13. Test Bar Size & Nos.						
6. Forging Method:							14. Supplier of the ingot/billet/ Bloom and TC reference.						
7. BHEL's Reference for Approval of Bloom													
8. Discard: Top %, Bottom %													
15. FORGINGS COVERED BY TEST CERTIFICATE													
S.No.		Drawing No. & Item No.			Description				Quantity & Weight				
16. CHEMICAL COMPOSITION (PERCENT)													
Element		C	Si	Mn	S	P							
As Per Specn.		Min.											
		Max.											
Actual Values													
17. HEAT TREATMENT (To be accompanied by Recorder Chart, Whenever called for)													
Condition		Heating Rate, °C/hr.		Temp. °C		Soaking Time, Hrs.		Cooling Rate, °C/hr		Cooling Medium			
18. MECHANICAL PROPERTIES													
		T.S. N/mm ²	Y.S. 0.5/0.2% Proof N/mm ²	% Elongation 5.65√So GL	% R.A. Min.	Hardness BHN (Min. 3 values)	Impact Value Joules	Bend Test					
								Angle of bend	Dia of mandrel	Result			
As Per Specn.		Min.											
		Max.											
Actual Values													
19. SURFACE FINISH (When called for in the order/drg.)													
20. DIMENSIONAL INSPECTION													
21. NON-DESTRUCTIVE TESTS													
Nature of Test		Acceptance level		Instrument used		Range		Results		Any other detail			
Ultrasonic													
Radiographic													
Dye penetrant/ Magnetic Particle													
22. METALLOGRAPHIC EXAMINATION (To be conducted if called for and photo micrographs to be attached along with a report)													
Location of Sample		Etchant used		Magnification		Constituent observed		Relative %					
Microstructure		Macroetch		Inclusion Rating									
23. OTHER TESTS IF ANY (MICROSCOPIC, SULPHUR PRINTS, ETC)													
24. IDENTIFICATION OF FORGINGS AS PER PURCHASE SPEC.													
We hereby certify that the items mentioned above have been tested and inspected in our presence and are found to be in accordance with drawings, specifications and purchase order.													
SIGNATURE, NAME & SEAL OF THE INSPECTING OFFICER DATE:							SIGNATURE, NAME & SEAL OF THE CHIEF OF QUALITY CONTROL/ CHIEF METALLURGIST OF THE SUPPLIER DATE:						
INSTRUCTIONS													
a) Details of all heat treatment processes carried out should be furnished sequentially in 17.													
b) Test certificates are to be furnished as per Purchase order and specification, in A4 size preferably in transparent paper.													
c) All the entries including signature should be in block colour ink.													
d) If testing is done by outside agencies, the original TCs shall be furnished.													
e) The actual TC may run into more than one A4 size paper, if needed, to facilitate filling up of details.													



CORPORATE STANDARD

AA 085 01 33

Rev. No. 03

PAGE 1 OF 7

PROCEDURE FOR MAGNETIC PARTICLE EXAMINATION

1.0 SCOPE:

- 1.1 This standard outlines the procedure for magnetic particle examination of ferro-magnetic materials.
- 1.2 Typical surface and subsurface discontinuities detectable by this method are cracks, seams, laps, cold shut, inclusions, etc.
- 1.3 This shall be applied to all forms of ferromagnetic material as formed and semiformal as well as, finished state, such as welds, forgings, castings, etc.
- 1.4 This standard is generally based on ASTM E 709.

2.0 PERSONNEL REQUIREMENT:

Personnel performing non-destructive examination and evaluation shall be qualified to the recommended practice SNT- TC-1A or any other recognised practice.

3.0 TEST METHOD:

-
4

Finely divided magnetic particles are applied to the surface of a part which has been suitably magnetised. The particles are attracted to regions of magnetic non-uniformity associated with defects and discontinuities, thus producing indications which are observed visually. The magnetic particle is applied either as dry powder or in a wet suspension in a liquid medium.

4.0 SURFACE CONDITION/PREPARATION:

The surface being inspected shall be clean and dry. It shall be free from dirt, oil, grease, sand, rust or loose scale. As cast or as welded surfaces are generally satisfactory if clean. A pressure blast is useful for this purpose. Thin paint does not interfere with the formation of indications but must be removed at points where electrical contact is to be made. If the surface is unusually rough, such as with burned in sand or very rough weld bead, interpretation may be difficult because the particle is being trapped mechanically. In case of doubt, light grinding may be necessary to determine if actual indications are present..

Revisions:

Cl. 12.8.8 of MOM of WG-NDT

APPROVED:
INTERPLANT STANDARDIZATION
COMMITTEE (WG-TOOLS)

Rev. No. 02

Amd.No.

Reaffirmed

Prepared
HYDERABAD

Issued
Corp. R&D

Dt. of 1st Issue
Sept.'79

Dt: 15-12-97

Dt:

Year:

**5 .0 SEQUENCE OF OPERATION:****5 .1 Method Of Examination:**

Examination shall be generally carried out by the continuous method, i.e., the magnetising current remains on, while the examination medium is being applied and excess being removed.

5 .2 Magnetisation:

Any suitable and appropriate means for establishing the necessary magnetic flux may be employed, such as passing current through the material (e.g. 'Prod' method) using magnetic yoke, or wrapping the part with a coil through which a magnetising current is passed.

5 .3 Examination Medium:

5 .3 .1 The finely divided ferromagnetic particles used for detection of discontinuities shall be of fine grain and the same shall be of high permeability and low retentivity. It shall be of dry powders (Fluorescent and nonfluorescent) ready for use, as supplied or powder concentrates (Fluorescent and non-fluorescent) for dispersion in water or suspending light petroleum distillates.

5 .3 .2 Dry Particles:

When dry particles are used, they shall be sprayed either by a low pressure pneumatic instrument or hand operated bulb blower. Colour of the powder shall be such as to provide adequate visual contrast with the back ground of the surface being examined. The temperature of the surface of the part under examination shall not exceed 315°C (600°F). Adequate lighting should be provided for easy observation of the indication. Some coloured organic coatings applied to dry particles to improve contrast lose their colour at higher temperatures- Fluorescent dry particles shall not be used at this high temperature. Manufacturer's recommendations for temperature limitation shall be followed.

5 .3 .3 Wet Particles:

When wet particles are used, the solid magnetic particles shall be suspended in a suitable liquid medium. The concentration of the particles in the liquid medium shall be 0.2 to 0.4 ml in a 100ml sample for fluorescent particles and from 1.2 to 2.4 ml in a 100 ml for non-fluorescent particles unless otherwise specified by the particle manufacturer.

5 .3 .4 Florescent Particlaes

5. 4. 3. 1 The fluorescent particle examination shall be performed using a black light in a darkned area.



CORPORATE STANDARD

AA 085 01 33

Rev. No. 02

PAGE 3 OF 7

- 5.3.4.2** The black light used for fluorescent particle testing shall be capable of developing the wave length of 365nm; in any case the wave length should be in the range of 330 to 390nm. with an intensity of not less than 1000 uw/cra² on t surface of the part.
- 5.3.4.3** The black light shall be allowed to warm up for a minimum of 5 min. prior to its use or measurement of the intensity of the ultraviolet light emission.
- 5.3.4.4** The examiner shall be in the darkened area for atleast 5 min. prior to examining the parts using black light so that his eyes will adopt to dark viewing. Photochromic or permanently tinted lenses shall not be worn during examination.
- 5.3.4.5** The black light intensity shall be measured with a black light meter at least once every 8 hours and whenever the work station is changed.
- 5.4** **Orientation of Discontinuities And Examination Coverage:**
Examination shall be conducted with sufficient overlap to ensure cent percent coverage at established test sensivity. To ensure most effective detection of discontinuities each area shall be examined at least twice with the lines of flux approximately perpendicular to each other.
- 5.5** **Demagnetisation:**
Demagnetisation following examination shall be carried out where residual magnetism can interfere with subsequent process or usage. Demagnetisation is not normally required on the type of parts where the dry powder Prod magnetisation is used.
- 6.0** **METHODS OF MAGNETISATION:**
- 6.1** **Prod Method:**
- 6.1.1** **Magnetising Technique:**
- 6.1.1.1** Magnetisation shall be accomplished by portable Prod type electrical contacts pressed against the surface in the area to be examined. To avoid arcing, a remote control switch may be provided to permit the current to be turned on after the prods have been properly positioned and turned off before they are removed.
- 6.1.2** **Prod Spacing:**
Prod Spacing shall be maximum of 200 mm. Shorter spacing may be used to meet the limitation of geometry or dimensions of the area being examined, or to increase the sensitivity, but prod spacing less than 75 mm usually is not recommended owing to banding of the particles around the prods

**6.1.3 Magnetising Current:**

Alternating, direct or rectified magnetising current shall be used. The current shall be 90 to 110 A per 25mm. of prod spacing for sections less than 19mm. thick and 110 to 125 A per 25mm. prod spacing for sections 19mm. and greater.'

- 6.1.4** Prod shall be kept free of iron pick up by frequent filing. Local areas of metal being tested which have been subjected to arcing shall be ground to clean metal wherever necessary.

6.2 Coil Method:**6.2.1 Magnetising Technique:**

Magnetisation shall be accomplished by pressing current through a multiturn coil looped around the part or section of the part to be examined to produce a magnetic field parallel to the axis of the coil.

6.2.2 Magnetising Current:**6.2.2.1 Encircling Coils:**

There are four empirical longitudinal magnetization formulas for using encircling coils, the formulas to be used depending on the fill factor.

- 6.2.2.1.1 Low Fill Factor Coils:** In this case, the cross sectional area of the fixed encircling coil greatly exceeds the cross sectional area of the part (Less than 10% coil inside diameter). The part shall be placed well within the coils and close to the inside wall of the coil. For parts with length over diameter ratio (L/D) between 3 and 15 is calculated from the following equations.

- (1) Parts with low fill factor positioned close to the inside wall of the coil in the center of the coil;

$$= \frac{45,000}{L/D} \text{ Ampere Turns } (\pm 10\%)$$

- (2) Parts with a low fill factor positioned in the center of the coils:

$$= \frac{43,000 \times R}{(6 L/D) - 5} \text{ Ampere Turns } (\pm 10\%)$$



CORPORATE STANDARD

AA 085 01 33

Rev. No. 02

PAGE 5 OF 7

6. 2. 2. 1.2 Intermediate Fill Factor Coils:

When the cross section of the coil is greater than twice and less than ten times the cross section of part being examined.

$$= (NI) hf (10-4) + (NI) lf (4-2)/8$$

Where

NIhf = Value calculated for high fill factor coils using

$$\frac{35000}{(L/D) + 2} \quad (10\%)$$

NIlf = Value Calculated for low fill factor coils using

$$\frac{43/000 \times R}{(L/D) - 5} \quad (10\%)$$

Where R = Coil Radius

Y = Ratio of the cross sectional area of the coil to the cross section of the part.

For example if the coil has an inside diameter of 24 cm. and part (a bar) has outside diameter of 12 cm.

$$Y = \frac{n(12)^2}{n(6)^2} = 4$$

$$n(6)^2$$

6. 2. 2. 1.3 High Fill Factor Coils:

In this case, when fixed coils or cable wraps used and the cross sectional area of the coil is less than twice the cross sectional area (Including hollow portions) of the part, the coil has a high fill factor.

For parts with in a high fill factor positional coil and for parts with L/D ratio equal or greater than 3.

$$= \frac{35,000}{(L/D)+2} \text{ Ampere turns (+ 10\%)}$$

L/D ratio for a hollow piece: When calculating L/D ratio for a hollow piece, D shall be replaced with an effective diameter Deff. Calculated using.

$$Deff. = [(At - Ah)/n]^{\frac{1}{2}}$$

Where

At = Total cross section area of part

Ah = Cross sectional area of hollow portion(s) of the part.

For a cylindrical piece this is equivalent to

$$Deff. = [(OD)^2 - (ID)^2]^{\frac{1}{2}}$$

Where

OD = Outside diameter of cylinder

ID = Inside diameter of cylinder.

**6.2.2.2 Through Coils:**

For through coils the current specified in para 6.3.2 divided by number of turns shall be used.

6.3 Direct Contact Method:**6.3.1 Magnetising Technique:**

Magnetising shall be accomplished by passing current end to end through the part to be tested to produce a circular magnetic field perpendicular to the current "flow through the part.

6.3.2 Magnetising Current :

Direct or rectified current shall be used at 280 to 360 amperes per centimeter of part for diameter upto 125 mm; 200 to 280 amperes per centimeter of part for diameter greater than 250mm.

(Note: A different means of magnetising shall be used for the second examination to fulfill the requirements specified in Cl.5.4).

6.4 Yoke Method:**6.4.1 Application:**

This method shall be used only to detect surface discontinuities which actually come to the surface.

6.4.2 Magnetising Technique:

6.4.2.1 Alternating current electromagnetic yoke shall be used to magnetise, provided the yoke has a lifting power of at least 4.5 Kg and a pole spacing of 75 to 150 mm.

6.4.2.2 Alternatively direct current electromagnetic or permanent magnetic yoke shall be used to magnetise, provided the yoke has a lifting power of at least 18 kg and a pole spacing of 75 to 150 mm.

6.5 Threading Bar and Coil Technique:

6.5.1 If the part is hollow, flaws in a longitudinal direction may be detected by passing the magnetising current through a bar or cable held within the bore of the part. Alternatively a threading coil may be used.

6.5.2 The current strength shall be equivalent to not less than 10500 ampere turns (a.c; r.m.s value) or 15000 ampere turns (d.c.) per metre of the maximum distance of the bar cable from the surface of the bore of the part.



CORPORATE STANDARD

AA 085 01 33

Rev. No. 02

PAGE 7 OF 7

- 6.5.3 Because of limitations of the equipment, it may be necessary to magnetise the part at several positions within the bore, with the bar or cable lying on the bore surface, in which case the distance between spacing of the conductor or coil for successive checks shall not be greater than 100 mm.

Note: Magnetising particle field indicator shall be used to establish adequacy of the magnetic field.

7.0 CALIBRATION:

Calibration of the ammeter shall be done as per BHEL Standard AA 085 01 59.

8.0 EVALUATION OF INDICATIONS & INTERPRETATION:

- 8.1 If the indication is caused by the surface discontinuity the particles are usually tightly held to the surface by a relatively strong magnetic leakage field. The line of particles will be sharp and well defined.
- 8.2 If the indication is caused by surface discontinuity, the particles are held in a broad fuzzy accumulation rather than being sharp and well-defined.
- 8.3 Non-relevant indications are caused by distortion of magnetic field resulting from magnetic writing, cold working, hard and soft spots, boundaries of heat affected zone, abrupt change of section, etc. Care shall be taken to identify and eliminate them as they may mask the actual defect.
- 8.4 Relevant indications are those which result from mechanical discontinuities. Linear indications are those in which the length is more than three times the width. Rounded indications are indications in which are circular or* elliptical with the length less than three times the width.

9.0 REFERRED STANDARDS (Latest Publication Including Amendments):

1. ASTM E 70

2. BHEL CS AA 085 01 59



CORPORATE STANDARD

AA 085 01 36

REV. No. 00

PAGE 1 OF 1

ACCEPTANCE STANDARDS FOR INDICATIONS REVEALED DURING MAGNETIC PARTICLE EXAMINATION OF STEEL FORGINGS

1.0 SCOPE:

This standard gives the acceptance norms for indications revealed during the magnetic particle inspection of steel forgings used for general applications.

2.0 PROCEDURE:

The procedure, requirement of equipment, consumables and personnel shall be as per BHEL standard AA 085 01 33 which is generally based on ASTM E 709.

3.0 ACCEPTANCE NORMS:

Following defects are unacceptable.

Category I:

- i) Any cracks/linear indication.
- ii) Rounded indication larger than 3mm size.
- iii) Groups of rounded indications with individual size of 3mm or less and separated by a distance of less than 2 times the largest defect.

Category II:

- i) Any cracks/linear indication.
- ii) Rounded indication larger than 6mm size.
- iii) Groups of rounded indications with individual size of 6mm or less and separated by a distance of less than 2 times the largest defect.

4.0 REFERRED STANDARDS(Latest Publications Including Amendments):

1. BHEL CS AA 085 01 33

2. ASTM E 709

Revision:			Approved: INTERPLANT STANDARDIZATION COMMITTEE-WG (WG-NDT)		
Rev.No.	Amd.No.	Reaffirmed	Prepared SSTP TRICHY	Issued CORP. R&D	Dt. of 1st issue 1-12-96
Dt.	Dt.	Year:			

TD-106-I Rev No. 5	Form No.		PRODUCT STANDARD PULVERISERS HYDERABAD		Product STD NO.	BA 76002
					Rev No	02
					Page	1 of 42

COPYRIGHT AND CONFIDENTIAL
 The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED,
 It must not be used directly or indirectly in any way detrimental to the interest of the company.

DOUBLE UPPER BEARING JOURNALS ASSEMBLY PROCEDURE

FOR 583-1103 PULVERIZERS

1.0 SCOPE:

This standard covers assembly procedure for Double Upper Bearing journals.

2.0 CONTENT:

a) ESTABLISH UPPER BEARING BENCH END PLAY
 Measure the upper journal-housing bore. Grind the bearing spacer.

b) ASSEMBLE BEARING HOUSING AND CHECK END –PLAY
 Install the double bearing in the upper journal housing. Install bearing keepers and shims. Check upper bearing end play.

c) ASSEMBLE THE LOWER JOURNAL HOUSING SUB-ASSEMBLY.

Grinding roll with lock nut (taper fit connection).
 Grinding roll with keeper plate (shrink fit connection).
 Grinding roll with keeper plates (taper fit connection).
 Install the lower journal-bearing cup.

d) JOURNAL SHAFT SUB-ASSEMBLY

Check shafts straightness and roundness
 Assembly of long spacer shaft journals.
 Install the oil seal wear ring.
 Install the upper bearing assembly.
 Install the lower journal-bearing cone.
 Install bearing keeper and shim assembly.
 Assembly of large diameter shaft journals.
 Install the lower bearing cone.
 Install bearing keeper and shim assembly.

e) ASSEMBLY THE JOURNAL SHAFT TO THE HOUSING ASSEMBLIES
CHECK JOURNAL ASSEMBLY END PLAY

Journal shaft and housing sub-assemblies.
 Check Journal assembly bearing end play.

Revisions: Refer to record of revisions:	Prepared: GK	Approved: JGK	Date: 01.03.06
---	------------------------	-------------------------	--------------------------

TD-106-1 Rev No. 5	Form No.		PRODUCT STANDARD PULVERISERS HYDERABAD	Product STD NO.	BA 76002
				Rev No.	02
				Page	3 of 42
The assembly of a pulverizer journal shaft with double upper bearings requires several distinct steps performed in the proper sequence to assure that proper clearances are obtained. Proper clearances must be obtained to ensure maximum bearing life. I. Establish the upper bearing bench end play by grinding the spacer supplied with the double bearing. II. Assemble the upper journal housing subassembly and check the bearing end play. III. Assemble the lower journal housing sub-assembly and install the journal roll. IV. Assemble the journal shaft sub-assembly. V. Assemble journal shaft sub-assembly and journal housing assemblies. Check the journal assembly bearing end play. NOTE: Extra sets of the Figures in this section should be available to record measurements, readings and settings made. These may be retained for an equipment maintenance history. CAUTION: Because the measurements taken during the assembly of the Bearings must be so precise, all of the components and measuring tools must be at 70° F. (21 ° C). If this is not practical, then the measurements must be corrected for Thermal expansion to 70 ° F. (21 ° C). CAUTION: Upper Journal Bearings are supplied in matched and serialized sets. The cups and cones are not interchangeable. Each cup must be kept with its mating cone. The bearing spacer is also matched with the cups and cone and should not be interchanged with other bearings. If an error occurs in the grinding and as a result the bench endplay is out of tolerance, the spacer may be reworked. Add material to the ground surface by welding, flame spraying or plating and regrind to the correct dimension.					

COPYRIGHT AND CONFIDENTIAL

The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED,
It must not be used directly or indirectly in any way detrimental to the interest of the company.

TD-106-1
Rev No. 5

Form No.

बी एच ई एल

BHEL

PRODUCT STANDARD

PULVERISERS

HYDERABAD

Product
STD NO.

Rev No.

Page

BA 76002

02

5 of 42

COPYRIGHT AND CONFIDENTIAL

The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED,
It must not be used directly or indirectly in any way detrimental to the interest of the company.

2.0

Grind the bearing spacer

2.1

Measure and record the spacer length, use procedure Figure 2.

2.2

Reference the average bore measurement made in step 1.0, grind the spacer.

2.3

Measure and record the spacer ground length.

CAUTION

THE BEARING, SPACER AND HOUSING ARE NOW A MATCHED SET. THE BEARING AND SPACER ARE NOT INTERCHANGEABLE WITH OTHER HOUSINGS.

II.

ASSEMBLE BEARING IN HOUSING AND CHECK END PLAY

3.0

Install the double bearing in the upper journal housing.

3.1

Measure and record the bearings outside diameter use procedures Figure.3

3.2

Calculate the bearing, bearing housing interference fit by subtracting the average housing bore diameter D, from the average bearing outside diameter FAVG. Figure 1 and 3.

For ease of assembly each 0.001” (0.0254 mm) of interference requires a 10 ° F (5.5° C) temperature differential between the bearing cups and bearing housing.

To facilitate future disassembly coat the O.D of the bearing cups with Molykote 41 or equal (If bearings are chilled for insertion coat the bearing housing bore).

3.3

Heat the upper journal housing to approximately (175 ° F) (80 ° C)

NOTE:

As an alternate assembly method, the bearing cups and spacer may be chilled in dry ice instead of heating the bearing housing. If the chilling method is used, the bearing cups, cones and roller bearings must be completely coated with the recommended journal oil immediately after assembly to prevent water etching. The assembly sequence is the same, see steps 3.4 and 3.5

TD-106-1 Rev No. 5	Form No.		PRODUCT STANDARD PULVERISERS HYDERABAD	Product STD NO.	BA 76002
				Rev No.	02
				Page	10 of 42
CAUTION. AS THE BEARING CUP RETURNS TO NORMAL TEMPERATURE. WIPE DRY AND COAT WITH JOURNAL OIL TO PREVENT WATER ETCHING. 7.6 After the cup has returned to room temperature, check beneath the cup with a feeler gauge to assure proper seating. A 0.001” (0.025 mm) feeler gauge must not fit between the bearing cup and the housing backing shoulder. IV <u>JOURNAL SHAFT SUB-ASSEMBLY:</u> NOTE Journals are supplied with two different styles of journal shaft, shafts with a long spacer between the upper and lower bearings and shafts with a large shaft diameter between the upper and lower bearings. Journal shaft sub-assembly and housing assembly techniques are different for the two styles. 8.0 Check the journal shaft for straightness and roundness. Measure and record the information, reference Figure 11. The shaft must be straight and round within 0.001” (0.025mm). 9.0 Assembly of long spacer shaft journals. 9.1. Install the oil seal wear ring. 9.1.1. Measure the I.D of the oil seal wear ring, reference procedures on Figure 1 compare with shaft O.D. measurements, N. recorded on figure 11. The interference must be between 0.004 “ and 0.011”. (0.102 to 0.28 mm) 9.1.2. Heat oil seal wear in an oven or in oil to 300 ° F maximum. 9.1.3 Locate oil seal wear ring on journal shaft as shown in the assembly drawing (either by a given dimension or against a shaft shoulder). Allow wear ring to cool. 9.2 Install the upper bearing assembly. 9.2.1 Lubricate the upper journal-bearing seat on the journal shaft with standard journal oil. 9.2.2 Install one oil seal facing inward into the upper journal housing and then the remaining two with the lip pointing outward. Coat the seal lips and fill the cavities between the seals with Molykote 33 or equal grease.					

COPYRIGHT AND CONFIDENTIAL

The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED, It must not be used directly or indirectly in any way detrimental to the interest of the company.

TD-106-1 Rev No. 5	Form No.		PRODUCT STANDARD PULVERISERS HYDERABAD	Product STD NO.	BA 76002
				Rev No.	02
				Page	11 of 42
COPYRIGHT AND CONFIDENTIAL The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED, It must not be used directly or indirectly in any way detrimental to the interest of the company. CAUTION AVOID MARRING THE SHAFT BLENDED RADIUS FINISH OR DAMAGING THE OIL SEAL DURING ASSEMBLY. 9.2.3 Assemble the upper bearing and housing on the journal shaft. A clearance of 0.002" to 0.004" should exist between the shaft and the upper bearing (0.051 to 0.102 mm) 9.2.4 Slip the journal-bearing sleeve (long spacer) onto the journal shaft. The bearing spacer is marked so that the slots are assembled toward the lower bearing. 9.3. Install the lower journal-bearing cone. 9.3.1 Assemble the lower bearing spacer (if applicable) on the journal shaft. The Chamfer on the spacer must clear the shaft fillet. 9.3.2 Coat the lower bearing seat on the journal shaft with Molykote 41 or equal. 9.3.3. Check the I.D of the bearing cone, use procedure Figure 1 and compare with shaft measurement K, Figure 11. The interference must be between 0.001" and 0.007" (0.025 to 0.178 mm) 9.3.4 Heat the bearing cone in an oven or oil bath to 250 ° F (120 ° C) maximum and install it on the journal shaft. 9.3.5 Install the bearing keeper and torque cap screws to 100 ft.lbs (14 kgm) 9.3.6 Allow bearing to return to room temperature. 9.3.7 Check with a feeler gauge to assure proper seating of the bearing. A 0.001" (0.025 mm) feeler gauge must not fit between the bearing spacer and cone or the shaft and cone. 9.4 Install bearing keeper and shim assembly. 9.4.1. Remove cap screws and journal bearing keeper. 9.4.2. Measure the gap between the shaft end and the bearing face with a depth, micrometer in four places. Reference figure 4. Average the readings. 9.4.3. Prepare a shim pack with a total thickness of 0.003" to 0.005" (0.076 to 0.127 mm) less than the average gap measured in step 9.4.2 Check Shims with a micrometer.					

TD-106-1 Rev No. 5	Form No.		PRODUCT STANDARD PULVERISERS HYDERABAD	Product STD NO.	BA 76002
				Rev No.	02
				Page	13 of 42
V <u>ASSEMBLY THE JOURNAL SHAFT TO THE HOUSING ASSEMBLIES,</u> <u>CHECK JOURNAL ASSEMBLY END PLAY</u> 11.0 Journal shaft and housing sub-assemblies. NOTE Prior to assembly coat all bearings with standard journal oil. 11.1 Install a lifting eye in the end of the journal shaft. 11.2 On Journal shafts with the long spacer, lower journal shaft and upper housing assembly without the “O” ring or the spring pins into the lower housing and seat the lower bearing cone in its cup. 11.3. On large diameter shaft journals, lower the journal shaft sub-assembly into the lower housing and seat the lower bearing cone in its cup. Install the bearing spacer on shaft, if applicable, then lower the upper housing sub-assembly, without the “O” ring or spring pins, over the shaft and into the lower housing. 11.4 Turn the shaft five complete revolutions in one direction. 11.5.Measure the gap between the upper and lower journal housing flanges in eight places. 45° increments, with feeler gauges. Record the reading, reference Figure 12. All readings should be alike within 0.003” . (0.076 mm) Average the readings. 11.6. Refer to item 5.0, Figure 6 and the assembly End Play Table, Table 6 . Prepare a shim pack with a thickness equal to the average housing gap, step 11.5, plus ½ the end play of the two row upper bearing, Figure 6, plus value “A” from the Assembly End Play Table, Table 6 . Check the shim pack with a micrometer. 11.7. Remove the journal shaft and upper housing assembly (or the upper housing sub-assembly) from the lower housing. 11.8. Install the “O” ring in the upper housing groove and grease lightly with Molykote 33 or equal. Install the spring pins in the lower housing. 11.9.Re-assemble the lower housing, shaft assembly and upper housing with the prepared shim stack. Do not pinch the “O” ring. 11.0 Apply loctite 277 or equal to the hex socket head cap screw threads. Install cap screws and torque to assembly drawing specifications.					

COPYRIGHT AND CONFIDENTIAL

The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED, It must not be used directly or indirectly in any way detrimental to the interest of the company.

TD-106-1 Rev No. 5	Form No.		PRODUCT STANDARD PULVERISERS HYDERABAD	Product STD NO.	BA 76002
				Rev No.	02
				Page	14 of 42
COPYRIGHT AND CONFIDENTIAL The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED, It must not be used directly or indirectly in any way detrimental to the interest of the company. 12.0 Check Journal assembly bearing end play. 12.1 Fasten two rods threaded at their lower ends in the lifting holes in the flange of the upper journal housing. 12.2 Lock the rods with hex nuts. 12.3. Install a dial indicator on each rod. Mark the indicator locations (180° apart) on the top of the journal shaft. 12.4. Rotate the journal five revolutions in one direction and return the dial indicators to their marked locations. 12.5. Zero the indicators. 12.6. Use a come-along and a five ton load cell, carefully lift the journal shaft to the lift load given in Table 6. 12.7. Rotate the shaft at least five revolutions in one direction and return the dial indicators to their original position. 12.8. Record the two indicator readings. Refer to Figure 13. 12.9. Lower the shaft to zero load on the load cell. 12.10. Rotate the journal shaft at least five revolutions in one direction and return the dial indicators to their original position. Record the indicator readings. 12.11. If both indicators have returned to zero $\pm 0.005''$ (± 0.0127 mm) in step 12.10 average the readings take in step 12.8 and record. 12.12. Zero the dial indicators and repeat steps 12.6 through 12.11 until three average indicator readings, within $0.001''$ (0.025 mm) are obtained. 12.13. Average the three average readings. 12.14. The value obtained in step 12.13 should be $\frac{1}{2}$ the end play of the two row bearing, Figure 6, plus value "A" from the Assembly End Play Table, Table 6. The acceptable tolerance is $\pm 0.001''$ (± 0.025 mm).					

TD-106-1 Rev No. 5	Form No.		PRODUCT STANDARD PULVERISERS HYDERABAD	Product STD NO.	BA 76002
				Rev No.	02
				Page	15 of 42
COPYRIGHT AND CONFIDENTIAL The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED, It must not be used directly or indirectly in any way detrimental to the interest of the company.		12.15 If the journal assembly and play is not within acceptable limits, disassemble the housing, and adjust shims (steps 11.4 through 11.10) as required. After shims are adjusted, recheck journal assembly end play by repeating steps 12.1 through 12.14. 12.16 If the journal assembly end play is within the acceptable limits, remove the rods installed in step 12.1 and plug the lifting and jack screw holes in the upper journal bearing with set screws.			



**PRODUCT STANDARD
PULVERISERS
HYDERABAD**

**Product
STD NO.**

Rev No.

Page

BA 76002

02

16 of 42

TABLE -1

				SPACER GRINDING VALUES		SPACER GRINDING VALUES	
HOUSING BORE (INCHE)		HOUSING BORE (MM)		TIMKEN		TORRINGTON	
				INCH	MM	INCH	MM
11.3700	11.3702	288.798	288.804	0.000	0.000	0.000	0.000
11.3703	11.3705	288.805	288.812	0.001	0.025	0.001	0.025
11.3706	11.3708	288.813	288.819	0.002	0.051	0.002	0.051
11.3709	11.3711	288.820	288.827	0.003	0.076	0.003	0.076
11.3712	11.3714	288.828	288.835	0.004	0.102	0.004	0.102
11.3715	11.3717	288.836	288.842	0.005	0.127	0.005	0.127
11.3718	11.3720	288.843	288.849	0.006	0.152	0.006	0.152

Spacer grinding Dimensions

Double upper bearing journals (Refer to figure 2)

643-663 pulverisers Upper journal housing P/N GP - 3325

Unner journal bearing P/N GP-3339



**PRODUCT STANDARD
PULVERISERS
HYDERABAD**

TABLE -2

HOUSING BORE (INCH)		HOUSING BORE (MM)		SPACER GRINDING VALUES (INCH)			
				TIMKEN		TORRINGTON	
				INCH	MM	INCH	MM
13.2450	13.2452	336.423	336.429	0.000	0.000	0.000	0.000
13.2453	13.2455	336.430	336.437	0.001	0.025	0.001	0.025
13.2456	13.2458	336.438	336.444	0.002	0.051	0.002	0.051
13.2459	13.2461	336.445	336.452	0.003	0.076	0.003	0.076
13.2462	13.2464	336.453	336.460	0.004	0.102	0.004	0.102
13.2465	13.2467	336.461	336.467	0.005	0.127	0.005	0.127
13.2468	13.2470	336.468	336.474	0.006	0.152	0.006	0.152

Spacer grinding dimensions.

Double upper bearing journals (Refer to figure 2)

683-743 Pulverisers – Upper journal housing P/N GP – 3988

Upper journal bearing P/N GP - 2908

763-803 Pulverisers – Upper journal housing P/N GP-3971

Upper journal bearing P/N GP - 2908

823-863 Pulverisers - Upper journal housing P/N GP - 922

Upper journal bearing P/N GP - 2908



**PRODUCT STANDARD
PULVERISERS
HYDERABAD**

TABLE -3

HOUSING BORE (INCH)		HOUSING BORE (MM)		SPACER GRINDING VALUES (INCH)			
				TIMKEN		TORRINGTON	
				INCH	MM	INCH	MM
15.1200	15.1202	384.046	384.054	0.000	0.000	0.000	0.000
15.1203	15.1205	384.055	384.062	0.001	0.025	0.001	0.025
15.1206	15.1208	384.063	384.069	0.002	0.051	0.002	0.051
15.1209	15.1211	384.070	384.077	0.003	0.076	0.003	0.076
15.1212	15.1214	384.078	384.085	0.004	0.102	0.004	0.102
15.1215	15.1217	384.086	384.092	0.005	0.127	0.005	0.127
15.1218	15.1220	384.093	384.099	0.006	0.152	0.006	0.152

Spacer grinding dimensions.

Double Upper Bearing Journals (Refer to figure 2)

883-943 Pulverisers Upper Journal Housing P/N GP - 3067

Upper Journal Bearing P/N GP-3064.

TD-106-1 Rev No. 5	Form No.		PRODUCT STANDARD PULVERISERS HYDERABAD	Product STD NO.	BA 76002																																																														
				Rev No.	02																																																														
				Page	19 of 42																																																														
COPYRIGHT AND CONFIDENTIAL The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED, It must not be used directly or indirectly in any way detrimental to the interest of the company. <table><tr><th colspan="6">TABLE -4A</th></tr><tr><th colspan="2" rowspan="2">HOUSING BORE (INCH)</th><th colspan="2" rowspan="2">HOUSING BORE (MM)</th><th colspan="2">SPACER OR VALUES</th></tr><tr><th>TIMKEN</th><th></th></tr><tr><th></th><th></th><th></th><th></th><th>INCH</th><th>MM</th></tr><tr><td>15.9950</td><td>15.9952</td><td>406.273</td><td>406.279</td><td>0.000</td><td>0.000</td></tr><tr><td>15.9953</td><td>15.9955</td><td>406.280</td><td>406.287</td><td>0.001</td><td>0.025</td></tr><tr><td>15.9956</td><td>15.9958</td><td>406.288</td><td>406.294</td><td>0.002</td><td>0.051</td></tr><tr><td>15.9959</td><td>15.9961</td><td>406.295</td><td>406.302</td><td>0.003</td><td>0.076</td></tr><tr><td>15.9962</td><td>15.9964</td><td>406.303</td><td>406.310</td><td>0.004</td><td>0.102</td></tr><tr><td>15.9965</td><td>15.9967</td><td>406.311</td><td>406.316</td><td>0.005</td><td>0.127</td></tr><tr><td>15.9968</td><td>15.9970</td><td>406.317</td><td>406.324</td><td>0.006</td><td>0.152</td></tr></table>						TABLE -4A						HOUSING BORE (INCH)		HOUSING BORE (MM)		SPACER OR VALUES		TIMKEN						INCH	MM	15.9950	15.9952	406.273	406.279	0.000	0.000	15.9953	15.9955	406.280	406.287	0.001	0.025	15.9956	15.9958	406.288	406.294	0.002	0.051	15.9959	15.9961	406.295	406.302	0.003	0.076	15.9962	15.9964	406.303	406.310	0.004	0.102	15.9965	15.9967	406.311	406.316	0.005	0.127	15.9968	15.9970	406.317	406.324	0.006	0.152
TABLE -4A																																																																			
HOUSING BORE (INCH)		HOUSING BORE (MM)		SPACER OR VALUES																																																															
				TIMKEN																																																															
				INCH	MM																																																														
15.9950	15.9952	406.273	406.279	0.000	0.000																																																														
15.9953	15.9955	406.280	406.287	0.001	0.025																																																														
15.9956	15.9958	406.288	406.294	0.002	0.051																																																														
15.9959	15.9961	406.295	406.302	0.003	0.076																																																														
15.9962	15.9964	406.303	406.310	0.004	0.102																																																														
15.9965	15.9967	406.311	406.316	0.005	0.127																																																														
15.9968	15.9970	406.317	406.324	0.006	0.152																																																														

TD-106-1 Rev No. 5		Form No.	बी एच ई एल BHEL			PRODUCT STANDARD PULVERISERS HYDERABAD		Product STD NO.	BA 76002																																																																								
								Rev No.	02																																																																								
								Page	20 of 42																																																																								
COPYRIGHT AND CONFIDENTIAL The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED, It must not be used directly or indirectly in any way detrimental to the interest of the company.			TABLE -4B <table><tr><th colspan="2">HOUSING BORE</th><th colspan="2">HOUSING BORE</th><th colspan="2">SPACER OR VALUES TORRINGTON</th></tr><tr><th>INCH</th><th>MM</th><th>INCH</th><th>MM</th><th>INCH</th><th>MM</th></tr><tr><td>15.9950</td><td>15.9952</td><td>406.273</td><td>406.279</td><td>0.000</td><td>0.000</td></tr><tr><td>15.9953</td><td>15.9954</td><td>406.280</td><td>406.284</td><td>0.001</td><td>0.025</td></tr><tr><td>15.9955</td><td>15.9956</td><td>406.285</td><td>406.289</td><td>0.002</td><td>0.051</td></tr><tr><td>15.9957</td><td>15.9958</td><td>406.290</td><td>406.294</td><td>0.003</td><td>0.076</td></tr><tr><td>15.9959</td><td>15.9960</td><td>406.295</td><td>406.299</td><td>0.004</td><td>0.102</td></tr><tr><td>15.9961</td><td>15.9962</td><td>406.300</td><td>406.305</td><td>0.005</td><td>0.127</td></tr><tr><td>15.9963</td><td>15.9964</td><td>406.306</td><td>406.310</td><td>0.006</td><td>0.152</td></tr><tr><td>15.9965</td><td>15.9966</td><td>406.311</td><td>406.315</td><td>0.007</td><td>0.127</td></tr><tr><td>15.9967</td><td>15.9968</td><td>406.316</td><td>406.320</td><td>0.008</td><td>0.203</td></tr><tr><td>15.9969</td><td>15.9970</td><td>406.321</td><td>406.324</td><td>0.009</td><td>0.229</td></tr></table> Spacer Grinding Dimensions. Double upper bearing journals (Refer to figure 2) 883 – 943 Pulverisers – Upper Journal Housing P/N 94 – 852 Upper Journal Bearing P/N GP – 2484 963-1003 Pulverisers - Upper Journal Housing P/N 101-00971 Upper Journal Bearing P/N GP – 2484.							HOUSING BORE		HOUSING BORE		SPACER OR VALUES TORRINGTON		INCH	MM	INCH	MM	INCH	MM	15.9950	15.9952	406.273	406.279	0.000	0.000	15.9953	15.9954	406.280	406.284	0.001	0.025	15.9955	15.9956	406.285	406.289	0.002	0.051	15.9957	15.9958	406.290	406.294	0.003	0.076	15.9959	15.9960	406.295	406.299	0.004	0.102	15.9961	15.9962	406.300	406.305	0.005	0.127	15.9963	15.9964	406.306	406.310	0.006	0.152	15.9965	15.9966	406.311	406.315	0.007	0.127	15.9967	15.9968	406.316	406.320	0.008	0.203	15.9969	15.9970	406.321	406.324	0.009	0.229
HOUSING BORE		HOUSING BORE		SPACER OR VALUES TORRINGTON																																																																													
INCH	MM	INCH	MM	INCH	MM																																																																												
15.9950	15.9952	406.273	406.279	0.000	0.000																																																																												
15.9953	15.9954	406.280	406.284	0.001	0.025																																																																												
15.9955	15.9956	406.285	406.289	0.002	0.051																																																																												
15.9957	15.9958	406.290	406.294	0.003	0.076																																																																												
15.9959	15.9960	406.295	406.299	0.004	0.102																																																																												
15.9961	15.9962	406.300	406.305	0.005	0.127																																																																												
15.9963	15.9964	406.306	406.310	0.006	0.152																																																																												
15.9965	15.9966	406.311	406.315	0.007	0.127																																																																												
15.9967	15.9968	406.316	406.320	0.008	0.203																																																																												
15.9969	15.9970	406.321	406.324	0.009	0.229																																																																												



**PRODUCT STANDARD
PULVERISERS
HYDERABAD**

Product
STD NO.

Rev No.

Page

BA 76002

02

21 of 42

TABLE -5A

HOUSING BORE (INCH)		HOUSING BORE (MM)		SPACER GRINDING VALUES			
				TIMKEN		TORRINGTON	
				INCH	MMS	INCH	MMS
17.9950	17.9952	457.073	457.079	0.000	0.000	0.000	0.000
17.9953	17.9955	457.080	457.087	0.001	0.025	0.001	0.025
17.9956	17.9958	457.088	457.094	0.002	0.051	0.002	0.051
17.9959	17.9961	457.095	457.102	0.003	0.076	0.003	0.076
17.9962	17.9964	457.103	457.110	0.004	0.102	0.004	0.102
17.9965	17.9967	457.111	457.117	0.005	0.107	0.005	0.127
17.9968	17.9970	457.118	457.124	0.006	0.152	0.006	0.152

Spacer Grinding Dimensions.

Double Upper Bearing Journals (Refer to figure -2)

963 -1003 Pulverisers Upper Journal Housing P/N 101-01081
Upper Journal Bearing P/N GP -1668

1023-1103 Pulverisers Upper Journal Housing P/N 111-00667
Upper Journal Bearing P/N GP-1668.

TD-106-1 Rev No. 5 Form No.		बी एच ई एल BHEL	PRODUCT STANDARD PULVERISERS HYDERABAD				Product STD NO.		BA 76002																																																																												
							Rev No.		02																																																																												
							Page		22 of 42																																																																												
COPYRIGHT AND CONFIDENTIAL The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED, It must not be used directly or indirectly in any way detrimental to the interest of the company.																																																																																					
TABLE -5B <table><tr><th colspan="2" rowspan="2">HOUSING BORE (INCHE)</th><th colspan="2" rowspan="2">HOUSING BORE (MM)</th><th colspan="4">SPACER GRINDING VALUES (INCHE)</th></tr><tr><th colspan="2">TIMKEN</th><th colspan="2">TORRINGTON</th></tr><tr><th></th><th></th><th></th><th></th><th>INCH</th><th>MM</th><th>INCH</th><th>MM</th></tr><tr><td>17.9950</td><td>17.9952</td><td>457.073</td><td>457.079</td><td>0.000</td><td>0.000</td><td>0.000</td><td>0.000</td></tr><tr><td>17.9953</td><td>17.9955</td><td>457.080</td><td>457.087</td><td>0.001</td><td>0.025</td><td>0.001</td><td>0.025</td></tr><tr><td>17.9956</td><td>17.9958</td><td>457.088</td><td>457.094</td><td>0.002</td><td>0.051</td><td>0.002</td><td>0.051</td></tr><tr><td>17.9959</td><td>17.9961</td><td>457.095</td><td>457.102</td><td>0.003</td><td>0.076</td><td>0.003</td><td>0.076</td></tr><tr><td>17.9962</td><td>17.9964</td><td>457.103</td><td>457.110</td><td>0.004</td><td>0.102</td><td>0.004</td><td>0.102</td></tr><tr><td>17.9965</td><td>17.9967</td><td>457.111</td><td>457.117</td><td>0.005</td><td>0.127</td><td>0.005</td><td>0.127</td></tr><tr><td>17.9968</td><td>17.9970</td><td>457.118</td><td>457.124</td><td>0.006</td><td>0.152</td><td>0.006</td><td>0.152</td></tr></table> Spacer Grinding Dimensions. Double Upper Bearing Journals (Refer to figure 2) 883 -1003 Pulverisers Upper journal housing P/N GP – 3810 Upper journal bearing P/N GP-1668. 1023-1103 Pulverisers Upper journal housing P/N 101 -00760 Upper journal bearing P/N GP – 1668.										HOUSING BORE (INCHE)		HOUSING BORE (MM)		SPACER GRINDING VALUES (INCHE)				TIMKEN		TORRINGTON						INCH	MM	INCH	MM	17.9950	17.9952	457.073	457.079	0.000	0.000	0.000	0.000	17.9953	17.9955	457.080	457.087	0.001	0.025	0.001	0.025	17.9956	17.9958	457.088	457.094	0.002	0.051	0.002	0.051	17.9959	17.9961	457.095	457.102	0.003	0.076	0.003	0.076	17.9962	17.9964	457.103	457.110	0.004	0.102	0.004	0.102	17.9965	17.9967	457.111	457.117	0.005	0.127	0.005	0.127	17.9968	17.9970	457.118	457.124	0.006	0.152	0.006	0.152
HOUSING BORE (INCHE)		HOUSING BORE (MM)		SPACER GRINDING VALUES (INCHE)																																																																																	
				TIMKEN		TORRINGTON																																																																															
				INCH	MM	INCH	MM																																																																														
17.9950	17.9952	457.073	457.079	0.000	0.000	0.000	0.000																																																																														
17.9953	17.9955	457.080	457.087	0.001	0.025	0.001	0.025																																																																														
17.9956	17.9958	457.088	457.094	0.002	0.051	0.002	0.051																																																																														
17.9959	17.9961	457.095	457.102	0.003	0.076	0.003	0.076																																																																														
17.9962	17.9964	457.103	457.110	0.004	0.102	0.004	0.102																																																																														
17.9965	17.9967	457.111	457.117	0.005	0.127	0.005	0.127																																																																														
17.9968	17.9970	457.118	457.124	0.006	0.152	0.006	0.152																																																																														

TD-106-1 Rev No. 5	Form No.		PRODUCT STANDARD PULVERISERS HYDERABAD	Product STD NO.	BA 76002
				Rev No.	02
				Page	23 of 42
COPYRIGHT AND CONFIDENTIAL The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED, It must not be used directly or indirectly in any way detrimental to the interest of the company. <u>USAGE</u> When using this table ensure that the upper bearing and upper housing part number you are working with match those listed in the table. The lift load in column 4 is used in determining upper bearing end play described in steps 5.1 through 5.12. The results obtained in step 5.12 should be compared with the values for the end play tolerance in column 5. The values in column 7 are used in determining journal housing flange gap shims 11.5 and 11.6 and figure 12 and journal assembly end play steps 12.6 through 12.14 and figure 13. Use the lift load values in column 6 in determining the journal assembly end play 12.6 through 12.14 and figure 13.					



PRODUCT STANDARD

PULVERISERS

HYDERABAD

Product
STD NO.

BA 76002


Rev No.

02

Page

25 of 42

COPYRIGHT AND CONFIDENTIAL
 The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED,
 It must not be used directly or indirectly in any way detrimental to the interest of the company.




1. Use dial bore to determine bore dimensions.
2. Measure at two depths, $1/4A$ and $3/4A$, on 45° increments, a equals the bearing length or bore depth which ever is smallest.
3. Record readings, B_U and B_L on the table below. All measurements must agree within $0.001''$ TIR (0.0254 mm TIR).
4. Average the upper, lower and total bore dimension C_U , C_L . The average reading D must meet blue print specifications, that is base dimension + $0.002''$ / $0.000''$. ($+0.051/0.000$ mm)

ORIENTATION	B_U UPPER DIMNS.	B_L LOWER. DIMNS.	AVERAGE
0°			
45°			
90°			
135°			
$B_0 + B_{45} + B_{90} + B_{135}$	C_U	C_L	
4			
$C_U + C_L$			
2			

FIGURE:1

TD-106-1 Rev No. 5	Form No.		PRODUCT STANDARD PULVERISERS HYDERABAD	Product STD NO.	BA 76002
				Rev No.	02
				Page	26 of 42

COPYRIGHT AND CONFIDENTIAL
 The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED,
 It must not be used directly or indirectly in any way detrimental to the interest of the company.




1. Use a micrometer to measure spacer length “E” at eight locations on 45° intervals prior to grinding.
2. Record and average readings.
3. Grind the spacer, remove material per tables-1-5.
4. Remeasure ground spacer, record and average readings.

OIRENTATION	DIMENSION E-NEW	DIMENSION E-GROUND
0°		
45°		
90°		
135°		
180°		
225°		
270°		
315°		
E. AVG.	E _{NEW} =	E _{GROUND} =

$$E_{AVG} = \frac{E_0 + E_{45} + E_{90} + E_{135} + E_{180} + E_{225} + E_{270} + E_{315}}{8}$$

Figure – 2: Journal Bearing Spacer Length Determination & Fig.A-3 for Avg.



1. Use a micrometer to measure the outside diameter of the brg. cups at four locations 0°, 45°, 90°, and 135°.
2. Record readings on the table below, all dimensions must agree within 0.001” TIR (0.025mm).
3. Average the dimensions for comparison with bore dimension “D” Fig. 1.


ORIENTATION	BRG. 1 DIMENSION	BRG. 2 DIMENSION
0°		
45°		
90°		
135°		
F AVG	F ¹ AVG =	F ² AVG =

$$F_{AVG} = \frac{F_0 + F_{45} + F_{90} + F_{135}}{4}$$

Figure. 3: Journal Bearing Outside Diameter & FigA-2 of Annexure.

TD-106-1 Rev No. 5 Form No.		PRODUCT STANDARD PULVERISERS HYDERABAD	Product STD NO.	BA 76002
			Rev No.	02
			Page	28 of 42

COPYRIGHT AND CONFIDENTIAL
 The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED,
 It must not be used directly or indirectly in any way detrimental to the interest of the company.



1. Measure clearance between the bearing housing and bearing keeper with a feeler gauge at four locations.
2. Record measurements on table below:
3. Calculate average gap measurement.

ORIENTATION	DIMENSION "G"
0°	
90°	
180°	
270°	
$G_{AVG} = \frac{G_0 + G_{90} + G_{180} + G_{270}}{4}$	

TD-106-1 Rev No. 5	Form No.	बी एच ई एल 	PRODUCT STANDARD PULVERISERS Figure.4. Bearing Keeper Shim Pack. HYDERABAD	Product STD NO.	BA 76002
				Rev No.	02
				Page	29 of 42

COPYRIGHT AND CONFIDENTIAL

The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED,
It must not be used directly or indirectly in any way detrimental to the interest of the company.

SIZE	GRADE (SAE)	TORQUE (FT-LB)
1" X 20 4	2	6
	5	10
	7	13
	8	14
5" X 18 16	2	12
	5	19
	7	25
	8	29
3" X 16 8	2	20
	5	33
	7	44
	8	47
1" X 13 2	2	47
	5	78
	7	110
	8	119
5" X 11 8	2	96
	5	154
	7	215
	8	230
3" X 10 4	2	155
	5	257
	7	360
	8	380
7" X 9 8	2	206
	5	382
	7	570
	8	600
1" X 8	2	310
	5	587
	7	840
	8	900
1 1" X 7 8	2	480
	5	794
	7	1325
	8	1430

TD-106-1 Rev No. 5	Form No.	बी एच ई एल BHEL	PRODUCT STANDARD PULVERISERS HYDERABAD	Product STD NO.	BA 76002																																													
				Rev No.	02																																													
				Page	30 of 42																																													
COPYRIGHT AND CONFIDENTIAL The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED, It must not be used directly or indirectly in any way detrimental to the interest of the company. <table><tr><td rowspan="4">1 1" X 7 — 4</td><td>2</td><td>675</td></tr><tr><td>5</td><td>1105</td></tr><tr><td>7</td><td>1825</td></tr><tr><td>8</td><td>1975</td></tr><tr><td rowspan="4">1 3" X 6 — 8</td><td>2</td><td>900</td></tr><tr><td>5</td><td>1500</td></tr><tr><td>7</td><td>2500</td></tr><tr><td>8</td><td>2650</td></tr><tr><td rowspan="4">1 1" X 6 — 2</td><td>2</td><td>1100</td></tr><tr><td>5</td><td>1775</td></tr><tr><td>7</td><td>3000</td></tr><tr><td>8</td><td>3200</td></tr><tr><td rowspan="4">1 3" X 5 — 4</td><td>2</td><td>1900</td></tr><tr><td>5</td><td>3150</td></tr><tr><td>7</td><td>5300</td></tr><tr><td>8</td><td>5650</td></tr><tr><td rowspan="4">2" X 4 1 — 2</td><td>2</td><td>2750</td></tr><tr><td>5</td><td>4550</td></tr><tr><td>7</td><td>7500</td></tr><tr><td>8</td><td>8200</td></tr></table>						1 1" X 7 — 4	2	675	5	1105	7	1825	8	1975	1 3" X 6 — 8	2	900	5	1500	7	2500	8	2650	1 1" X 6 — 2	2	1100	5	1775	7	3000	8	3200	1 3" X 5 — 4	2	1900	5	3150	7	5300	8	5650	2" X 4 1 — 2	2	2750	5	4550	7	7500	8	8200
1 1" X 7 — 4	2	675																																																
	5	1105																																																
	7	1825																																																
	8	1975																																																
1 3" X 6 — 8	2	900																																																
	5	1500																																																
	7	2500																																																
	8	2650																																																
1 1" X 6 — 2	2	1100																																																
	5	1775																																																
	7	3000																																																
	8	3200																																																
1 3" X 5 — 4	2	1900																																																
	5	3150																																																
	7	5300																																																
	8	5650																																																
2" X 4 1 — 2	2	2750																																																
	5	4550																																																
	7	7500																																																
	8	8200																																																

TD-106-1 Rev No. 5	Form No.		PRODUCT STANDARD PULVERISERS HYDERABAD	Product STD NO.	BA 76002
				Rev No.	02
				Page	31 of 42

COPYRIGHT AND CONFIDENTIAL
 The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED,
 It must not be used directly or indirectly in any way detrimental to the interest of the company.




FIG-6 End Play fixture.

TD-106-1 Rev No. 5 Form No.		PRODUCT STANDARD PULVERISERS HYDERABAD			Product STD NO.	BA 76002
					Rev No.	02
					Page	32 of 42

COPYRIGHT AND CONFIDENTIAL
 The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED,
 It must not be used directly or indirectly in any way detrimental to the interest of the company.

Trial	Indicator	Indicator Readings			AVG. Readings
		No Load	Lifted	No Load	Lifted Position
1	A		H _A		H ¹ AVG. = $\frac{H_A + H_B + H_C}{3}$
	B		H _B		
	C		H _C		
2	A		H _A		H ² AVG =
	B		H _B		
	C		H _C		
3	A		H _A		H ³ AVG =
	B		H _B		
	C		H _C		
4	A		H _A		H ⁴ AVG =
	B		H _B		
	C		H _C		
5	A		H _A		H ⁵ AVG =
	B		H _B		
	C		H _C		
$H_{AVG} = \frac{H1_{AVG} + \dots + HX_{AVG}}{X}$					

Note: Refer to Procedures in Text, items 5.5 to 5.10

Figure: 7 Upper Bearing End Play

TD-106-1 Rev No. 5 Form No.		PRODUCT STANDARD PULVERISERS HYDERABAD	Product STD NO.	BA 76002
			Rev No.	02
			Page	33 of 42

COPYRIGHT AND CONFIDENTIAL
 The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED,
 It must not be used directly or indirectly in any way detrimental to the interest of the company.

ORIENTATION	B ^U = UPP.DIMNS	B ^L = LWR DIMNS.	AVERAGE
0°			
45°			
90°			
135°			
$\frac{B_0 + B_{45} + B_{90} + B_{135}}{4}$	B ^U AVG	B ^L AVG	
$\frac{B_{AVG} = B^U_{AVG} + B^L_{AVG}}{2}$			B _{AVG}

Roll Bore (Reference figure -1)

ORIENTATION	F _u = UPP.DIMNS	F ^L = LWR DIMNS.	AVERAGE
0°			
45°			
90°			
135°			
$\frac{F_0 + F_{45} + F_{90} + F_{135}}{4}$	F ^U AVG	F ^L AVG	
$F_{AVG} = \frac{F^U_{AVG} + F^L_{AVG}}{2}$			F _{AVG}

Bearing Housing Outside Diameter (Reference figure -3)


INTERFERENCE = F_{AVG} - B_{AVG} =

NOTE: THE INTERFERENCES MUST BE AT LEAST 0.001” (.025mm)
AND LESS THAN 0.009” (0.229mm)

FIGURE 8. ROLL/BEARING HOUSING INTERFERENCE.

TD-106-1 Rev No. 5	Form No.		PRODUCT STANDARD PULVERISERS HYDERABAD		Product STD NO.	BA 76002
					Rev No.	02
					Page	34 of 42

COPYRIGHT AND CONFIDENTIAL
 The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED,
 It must not be used directly or indirectly in any way detrimental to the interest of the company.



1. USE A DEPTH MICROMETER TO MEASURE “J” AT SIX LOCATIONS.
2. RECORD J3, CALCULATE “J” AVG.

LOCATION	J DIMENSION			
	1 ST TRIAL	2 ND TRIAL	3 RD TRIAL	4 TH TRIAL
0°				
60°				
120°				
180°				
240°				
300°				
$\frac{J_0 + J_{60} + J_{120} + J_{180} + J_{240} + J_{300}}{6}$	J1 _{AVG} =	J2 _{AVG} =	J3 _{AVG} =	J4 _{AVG} =

SHIM PACK = J_{AVG} - 0.005”

SHIM PACK mm = J_{AVG} - 0.127 mm

TD-106-1 Rev No. 5	Form No.		PRODUCT STANDARD PULVERISERS HYDERABAD	Product STD NO.	BA 76002
				Rev No.	02
				Page	35 of 42

TD-106-1
Rev No. 5

Form No.

PRODUCT STANDARD

PULVERISERS

HYDERABAD

Product
STD NO.

BA 76002

FIGURE 9 ROLL BEARING HOUSING SHIM PACK.

Note:

For Bore determination use procedures Figure 1:

For Bearing O.D. use procedure Figure 3.

ORIENTATION	BRG. BORE	PILOT BORE	LWR. BRG. CUP
	B ^B _L B ^B _U	B ^P _L B ^P _U	F ³ OUTSIDE DIM
0°			
45°			
90°			
135°			
$\frac{B_0 + B_{45} + B_{90} + B_{135}}{4}$	C ^B L = C ^B U =	C ^P L = C ^P U =	F ³ AVG =
$\frac{C_L + C_U}{2}$	D ^B =	D ^P =	

$$F^3_{AVG} = \frac{F_0 + F_{45} + F_{90} + F_{135}}{4}$$

Bearing/ Bore Interference = F³_{AVG} - D^B = _____

Figure-10: Lower Journal Housing Bore Dimensions & Interference.

COPYRIGHT AND CONFIDENTIAL

The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED,
It must not be used directly or indirectly in any way detrimental to the interest of the company.



PRODUCT STANDARD

PULVERISERS

HYDERABAD

Product
STD NO.


BA 76002

Rev No.

02

Page

36 of 42



Shaft Outside Diameter Measurement. Use a Micrometer.

ORIENTATION	L.R. BRG. SEAT	UPP. BRG. SEAT		SEAL RING SEG
	K	L	M	N
0°				
45°				
90°				
135°				
AVG = $\frac{0 + 45 + 90 + 135}{4}$				

Shaft straightness measurements, mount shaft on live centers & use a dial indicator to check at K, L, M & N. Dial indicator reading should not vary more than 0.001" (0.025mm) for out of round.

ORIENTATION	K	L	M	N
0°				
45°				
90°				
135°				
180°				
225°				
270°				
315°				

Figure:11 Shaft out of Round and Straightness

TD-106-1 Rev No. 5 Form No.		PRODUCT STANDARD PULVERISERS HYDERABAD			Product STD NO.	BA 76002
					Rev No.	02
					Page	38 of 42

COPYRIGHT AND CONFIDENTIAL
 The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED,
 It must not be used directly or indirectly in any way detrimental to the interest of the company.

TRIAL	INDICATOR	INDICATOR READINGS			AVG. READINGS
		No Load	Lifted	No. Load	LIFTED POSITION
1	A		H _A		H ¹ AVG = $\frac{H_A + H_B}{2}$
	B		H _B		
2	A		H _A		H ² AVG =
	B		H _B		
3	A		H _A		H ³ AVG =
	B		H _B		
4	A		H _A		H ⁴ AVG =
	B		H _B		
5	A		H _A		H ⁵ AVG =
	B		H _B		
$H_{AVG} = \frac{H^1 AVG + H^2 AVG + H^3 AVG + H^4 AVG + H^5 AVG}{5} =$					

Note: Refer to Procedure in text, Item 12.0

Permitted Assembly End Play = $\frac{\text{Bearing End Play, Step 5.12}}{2} + (\text{End Play '2' Table 6})$

H_{AVG} = Permitted Assembly End Play ± 0.001 “

() = () + () ± 0.001”

If H_{AVG} is not within ± 0.001” of the permitted assembly endplay, the journal housing flange gap shims should be changed.

Figure 13: K Journal Assembly End - Play.

TD-106-I Rev No. 5 Form No.		PRODUCT STANDARD PULVERISERS HYDERABAD	Product STD NO.	BA 76002
			Rev No.	02
			Page	39 of 42

ORIENTATION	1st TRIAL GAP mm	2nd TRIAL GAP mm	3 rd TRIAL GAP mm
0°			
45°			
90°			
135°			
180°			
225°			
270°			
315°			
AVG GAP = $\frac{0 + 45 + \dots + 315}{8}$			

Upper Journal Head Skirt Flange Gap

Figure 14: Journal Head Skirt Flange Gap.

COPYRIGHT AND CONFIDENTIAL
 The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED,
 It must not be used directly or indirectly in any way detrimental to the interest of the company.

TD-106-1 Rev No. 5	Form No.		PRODUCT STANDARD PULVERISERS HYDERABAD	Product STD NO.	BA 76002
				Rev No.	02
				Page	40 of 42
<u>APPENDIX-A</u> <u>UPPER BEARING END PLAY</u> 1023 -1003 Pulveriser Journal Assy. 110-00333. 963 – 1003 Pulveriser Journal Assy. 101-00921 963 – 1003 Pulveriser Journal Assy. 101-00920 <u>SPACER GRINDING:</u> 1. Measure and record the upper journal housing bearing bore. Use procedures on figure A-1. Determination of Bore Diameters. 2. Measure and record the bearings outside diameter use procedures on figure A-2. Journal Bearing Outside diameter. The average measurements must be between 18.000” and 18.002” or the bearing must be rejected. 3. Measure and record the spacer length, use procedures figure A-3. Journal Bearing Spacer. Length determination. 4. Record the lateral clearance of the bearing on page A-5. The calculation sheet. The value is etched on the outside diameter of the spacer. 5. Follow the worksheet calculations to determine the spacer grind value. Grind this amount off the bearing spacer then measure and record the length of the ground spacer on fig A-3. Return to section II step 3.3 of the assembly procedures. 6. Retain the figures and calculation sheet for maintenance records.					

COPYRIGHT AND CONFIDENTIAL

The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED, It must not be used directly or indirectly in any way detrimental to the interest of the company.

TD-106-1 Rev No. 5 Form No.		PRODUCT STANDARD PULVERISERS HYDERABAD	Product STD NO.	BA 76002
			Rev No.	02
			Page	41 of 42

Spacer Grinding Calculations.

Lateral clearance = (etched on O.D. of Spacer)

Lateral clearance = _____

Fit = Average bearing O.D (figure 2-A) – Average housing bore (fig – 1A).

Fit = () – ()

Fit = _____

Spacer grind value = Lateral clearance – 0.007” – (2.62 x (fit)

Spacer grind value = () - 0.007” – (2.62 x ()

Spacer grind value = _____

THE INFORMATION ON THIS DOCUMENT IS THE PROPERTY OF BHARAT HEAVY ELECTRICALS LTD.
IT MUST NOT BE USED DIRECTLY OR INDIRECTLY IN ANY WAY DETRIMENTAL TO THE INTEREST OF THE COMPANY.


HY-312.A.02.F
FILE NAME

HERP MADE DRG
LOCATION:

INVENTORY NO.

REV.	DATE	ALTERED		REV.	DATE	ALTERED	
		CHD.	APPD.			CHD.	APPD.
ZONE				ZONE			

DRG.NO. HY-312.A.02.F



NOTES:-


1. FORGING SHOULD BE AS PER SPECN. AA19332
2. CHAMFER SHARP CORNERS TO R2 & FILLET RADIUS TO R3
3. TOLERANCE ON DIAMETER AND LENGTH ± 1 mm
4. TEST ULTRASONICALLY AS PER SPEC AA 0850118 CAT2

01	FORGING					1475	
					AA19332	1	
ITEM NO	DESCRIPTION	DRAWING NO.	VAR. NO.	RAW MATERIAL SIZE OR CASTING DRG.NO. OR FORGING DRG.NO.	MATERIAL CODE	NET WT.	GROSS WT.
					MATERIAL SPECN.	QUANTITY	

THE FOLLOWING CONDITIONS APPLY EXCEPT OTHERWISE STATED...

1. REF.TO HY0230261 FOR UNSPECIFIED TOLERANCES.
2. CHAMFER M/CD SHARP EDGES 1.2 TO 1.0 AT 45°.
3. INTERNAL M/CD CORNER RADII 1 TO 0.7.
4. THE SURFACE ROUGHNESS WHEREVER NOT SHOWN SHALL BE TAKEN FROM THE SURFACE ROUGHNESS SHOWN OUT SIDE BACK SLASHES GIVEN AT THE TOP MOST RIGHT CORNER OF THE DRG.

TYPE OF PRODUCT OR NAME OF CUSTOMER/PROJECT XRP-1003 MILL KORBA & RAMAGUNDEM



BHARAT HEAVY ELECTRICALS LTD.
VARANASI

DEPT. PULV ENGG.		SCALE	WEIGHT (KG)	REF. TO ASSY DRG.	ITEM NO.	NO.OF ITEMS
CODE 446		1:4	1475	16100000375	/	/
TITLE L.J.HOUSING R/MCD FORGING				DRAWING NO. HY-312.A.02.F		REV. 00
				SHEET NO. 01		NO OF SHEETS 01