

SCHEDULE-A (PART - B)**Name of the work: Renovation of Township - B quarters.**

SL.NO.	Description	Unit	Qty	Rate	Amount.
1.	Removing the Indian Water Closet and disposing it up to a distance of 200mts etc complete.	No	15.00		
2.	Labour charges for fixing European Water Closet set in CC 1:2:4 including fixing flush cistern, connecting pipe, stop cock, health foucet and making bores etc complete.Cement will be provided by BHEL for free of cost.	No	15.00		
3.	Supplying, Cutting to size & shape and laying of 20 mm thick Jet black one sided polised granite stone slab for kitchen plateforms. Fixed in CM 1:3.bedding. Thickness of the joints should not be more than 3mm., including rounding off corners, chamfering edges, pointing etc Complete. Cement will be provide by BHEL for free of cost.	Sqm	200.00		
4.	Dismantling of plastering in cement mortar/lime mortar of walls/ceiling and disposal of debris and shifting the debris up to near waste bins etc., Up to a working height/depth of 7.5 mtrs. Including cost of centering and shuttering etc complete.	Sqm	2,500.00		
5.	Labour charges for fixing the available ceramic glazed tiles 6 MM thick for flooring/walls/skirting etc by using Roff cement or with plastering in Cm 1:4 including cutting tiles to the required size, shape, chamfering tiles for corners, chipping flooring , removing plastering/skirting etc complete. Tiles will be supplied by BHEL for free of cost. Roff cement to be used when tiles are to laid on existing mosaic/tiled surface. Cement mortar to be used where tiles are to be laid on new surface. size of the tile to be fixed is upto 1.00 mtr x 1.00 mtr Etc., complete.	Sqm	3,292.25		
6.	Providing plastering in CM 1:4, 20 mm thick for new surface/patches in repair works ,including providing and removing scaffolding rounding of all corners with finishing of lime rendering / Sand finish/water proof addition as required including curing etc complete to burnt brick masonry/Concrete surface etc excluding the cost of cement, cement will be provided by BHEL for free of cost.	Sqm	25.00		

7.	Providing and laying granite jelly, cement concrete 1:2:4 using 20mm and downsize jelly including mixing, laying and tamping curing and excluding cost of centering , shuttering and plastering for flooring, sills, coping bond slab etc complete. Excluding cost of cement, cement will be provided by BHEL for free of cost.	Cum	5.00		
8.	Providing and constructing brick masonry for main walls /partition walls/chambers etc with approved quality of table moulded bricks of standard size in CM 1:4 with necessary scaffolding and curing etc complete., excluding the cost of cement, cement will be provided by BHEL for free of cost.	Cum	5.00		
9.	Labour charges for fabricating of grill above the compound wall as shown in drawing which will be issued during execution, with available new steel or by collecting from released structural members by welding/ gas cutting and applying two coats of enamel paint over a coat of red oxide including necessary scaffolding tools and plants up to working height of 9.00 mtrs, detailed fabrication drawings to be submitted by contractor before commencement of work. Steel will be provided by BHEL for free of cost.	Kg	1,407.00		
	TOTAL - NETT				
	Taxes if any	%			
	GRAND TOTAL				

Grand total amount in words - Rupees

Signature of the Contractor

Name:

Address:

NOTE : 1. Quantities indicated as above is approximate, the billing will be done at actuals.
2. Taxes if any is to be indicated in the table above; if taxes is not indicated, the rates quoted is assumed to be inclusive of taxes.