



भारत हेवी इलेक्ट्रिकल्स लिमिटेड
Bharat Heavy Electricals Limited
(A Govt. of India Undertaking)
Power Sector, Western Region,
345, Kingsway, Nagpur - 440 001
Phone : 0712-530641-45, Fax : 0712-530640



FAX (PCC by Courier/Speed post)

Ref: BHE/PW/PUR/BSJI-CRH/OJ-55/Amend-01

Dated-19/12/2005

To,
The Bidders

Dear Sir,

SUB: Amendment -I to T.S. No. BHE/PW/PUR/BSJI-CRH/OJ-55

Job: Services of Various Capacity Crawler Cranes on Monthly Leasing Basis at 2x250 MW Thermal Power Plant of M/s Bhilai Electric Supply Co. Pvt. Ltd. Near Purena Village, Bhilai, Dist-Durg, Chattishgarh

Please refer the subject Tender Specification (T.S.) for the job as stated above. We would like to amend certain clauses. Details of which are as follows.

I) Clause No. 1.2 (Page 11 of 46 of T.S.):

A new sub-clause being identified by serial number 5 under clause no 1.2 is being introduced as follows.

5 Bidder shall make available the complete set of Main Boom & Jib attachment with offset angle adjustment facility as specified for each crane in one go, that is at the time of mobilization. However the crane shall be initially and subsequently assembled as per the site requirement to be specified by BHEL site engineer. Bidder shall furnish the details of Main Boom & Jib configuration offered for respective crane in their technical bid.

II) Clause No. 1.3.3 (Page 12 of 46 of T.S.):

The existing clause is being replaced by the revised clause as under.

3. While erecting the Boiler Ceiling Structure, the Heavy Lift - High Reach (HLHR) crane has to erect a Ceiling Girder followed by the Girder interconnecting structure (built up & rolled sections) between the pair of Ceiling Girders prior to taking up erection of the next Ceiling Girder.

Similarly during and/or after the erection of Boiler Ceiling Structure, certain equipment/structure/assemblies such as Safety Valve Silencers, Roof Structure etc. have to be erected above the Ceiling Structure and the weight of single heaviest component would be about 10 MT. The final elevation of such components in erected position is expected to be about 75 M.

HLHR Crane with main boom or main boom & jib combination shall be in position to erect these equipment/structures/assemblies.

Bharat Heavy Electricals Limited
Power Sector : Western Region : Nagpur
Continuation Page (page 2 of 2)

Ref: BHE/PW/PUR/BSJI-CRH/OJ-55/Amend-01

Dated–19/12/2005

SUB: SUB: Amendment –I to T.S. No. BHE/PW/PUR/BSJI-CRH/OJ-55

III) Clause No. 1.3 (Page nos. 11 of 46 and 12 of 46 of T.S.):

A new sub-clause being identified by serial number 7 under clause no 1.3 is being introduced as follows.

7. Bidder shall provide at least 12 m long Jib with HLHR Crane in addition to the required Main Boom.

IV) Clause No. 6.5.1 - Payment Terms (Page no. 14 of 46 of T.S.):

The clause is being amended as under:

1. 50% of the agreed lump sum rate for mobilization and demobilization will be considered towards the mobilization charges. The same will be payable after deployment of all the assemblies, sub-assemblies, accessories & components of the crane complete in all respect and completion of assembly and BHEL's acceptance of load testing of concerned crane at BESCL Bhilai site.

Please enclose with your Technical Bid one copy of this letter duly counter-signed by your authorized signatory and stamped with your official seal as a token of your unqualified acceptance of this amendment.

Thanking you,
Yours faithfully,

For Bharat Heavy Electricals Limited

DGM (PURCHASE)