

ADDENDUM TO Annexure I :BOQ OF EXPANSION YARD**ADDITION OF NEW ITEMS :**

S.NO.	Description of Item	Quantity	Unit	Unit Rate(Rs)	Amount(Rs)
EW1	Clearing jungle including uprooting of rank vegetation,grass ,brush wood,trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	36500	100 sqm	173.6	63364
EW2	Felling of trees of girth (measured at a height of 1m above ground) including cutting of trunks and branches removing the roots and disposal of above as per direction of Engineer -in- Charge.				
(a)	Beyond 30 cm girth upto and including 60cm girth	30	each	53.6	1608
(b)	Beyond 60 cm girth upto and including 120cm girth	30	each	236.35	7090.5
©	Beyond 120 cm girth upto and including 240cm girth	10	each	1090.6	10906
(d)	Above 240 cm girth	5	each	2188.85	10944.25
EW3	Earth work in excavation over areas (exceeding 30 cm in depth,1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth,lead upto 500m and lift upto 3.5m:disposed earth to be levelled and neatly dressed.				
	Mass earth cutting in all kinds of soil	36500	cum	91.5	3339750

ADDENDUM TO Annexure II :BOQ OF EXTENSION YARD**ADDITION OF NEW ITEMS :**

S.NO.	Description of Item	Quantity	Unit	Unit Rate(Rs)	Amount(Rs)
EW1	Clearing jungle including uprooting of rank vegetation,grass ,brush wood,trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	22208	100 sqm	173.6	38553
EW2	Felling of trees of girth (measured at a height of 1m above ground) including cutting of trunks and branches removing the roots and disposal of above as per direction of Engineer -in- Charge.				
(a)	Beyond 30 cm girth upto and including 60cm girth	20	each	53.6	1072
(b)	Beyond 60 cm girth upto and including 120cm girth	20	each	236.35	4727
©	Beyond 120 cm girth upto and including 240cm girth	10	each	1090.6	10906
(d)	Above 240 cm girth	5	each	2188.85	10944.25
EW3	Earth work in excavation over areas (exceeding 30 cm in depth,1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth,lead upto 500m and lift upto 3.5m:disposed earth to be levelled and neatly dressed.				
	Mass earth cutting in all kinds of soil	11104	cum	91.5	1016016