TENDER SPECIFICATION

NO. PW/NGP/PUR/UKAI-CLE/459

FOR

COLLECTION OF MATERIALS FROM STORES/STORAGE YARD, TRANSPORTATION TO SITE OF WORK, DISMANTLING THE EXISTING COMPONENTS, RETURNING OF DISMANTLED MATERIALS TO BHEL/CLIENT'S YARD, SERVICING OF EXISTING EQUIPMENT, ERECTION OF NEW COMPONENTS, RENOVATION AND MODERNIZATION, TESTING, ASSISTANCE FOR COMMISSIONING AND HANDING OVER OF ELECTRICAL AND C&I PACKAGE FOR 1x 120 MW UNIT# 1

AT

UKAI TPS, P.O UKAI DAM GUJARAT- 394 680

PART-II (Price Bid)



BHARAT HEAVY ELECTRICALS LIMITED

(A GOVERNMENT OF INDIA UNDERTAKING)
POWER SECTOR - WESTERN REGION
345, KINGS WAY - NAGPUR 440 001

BHARAT HEAVY ELECTRICALS LIMITED

(A GOVERNMENT OF INDIA UNDERTAKING)
POWER SECTOR - WESTERN REGION
345, KINGS WAY - NAGPUR 440 001

TENDER SPECIFICATION NO. PW/NGP/PUR/UKAI-CLE/459

NAME OF THE WORK:

COLLECTION OF MATERIALS FROM STORES/STORAGE YARD, TRANSPORTATION TO SITE OF WORK, DISMANTLING THE EXISTING COMPONENTS, RETURNING OF DISMANTLED MATERIALS TO BHEL/CLIENT'S YARD, SERVICING OF EXISTING EQUIPMENT, ERECTION OF NEW COMPONENTS, RENOVATION AND MODERNIZATION, TESTING, COMMISSIONING, AND HANDING OVER OF ELECTRICAL AND C&I PACKAGE FOR 1X120 MW UNIT# 1

ΑT

UNIT-1 UKAI TPS, UKAI, P.O UKAI DAM – 394 680

EARNEST MONEY DEPOSIT: Please see Special Conditions of Contract.

LAST DATE FOR TENDER SUBMISSION

Please obtain updated information from web page "http://www.bhel.com"? Tender Notifications? View Corrigendums.

THESE TENDER SPECIFICATION DOCUMENTS CONTAINING PART-I AND PART- II (PRICE BID), ARE ISSUED TO:

| M/s | |
|-----|--|
| | |

PLEASE NOTE:

THESE TENDER SPECS DOCUMENTS ARE NOT TRANSFERABLE. BIDDER SHALL NOTE THAT THEIR OFFER WILL BE CONSIDERED SUBJECT TO THE APPROVAL OF BHEL'S CUSTOMER.

For Bharat Heavy Electricals Limited Dy. General Manager (Purchase) Place: Nagpur

Date:

Bharat Heavy Electricals Limited: PSWR: Nagpur Tender Specification No. BHE/PW/PUR/UKAI-CLE/459 (Part-II: Price Bid) Schedule of Rates and Quantities (Page 1 of 9)

| SN | DESCRIP TION | TOTAL QTY | UOM | UNIT RATE (Rs.) | TOTAL AMOUNT (Rs.) |
|-----|---|--------------|------|-----------------|--------------------|
| A-1 | Control Panel (approx L1000 X B1000 X H2500, 400Kg) – single panels (includes one interposing relay panel) | 5 | Nos | | |
| A-2 | Control Panel (approx L1001 to 1500 X B1000 X H2500, 800 Kg) - suit of two panels | 9 | Nos | | |
| A-3 | Control Panel (approx L1501 to 2250 X B1000 X H2500, 1200 Kg) - suit of three panels | 1 | No | | |
| A-4 | Back up Control panel (Two shipping sections each W2500 x D2000 x H2500 mm approx) | 1 | Set | | |
| A-5 | Master and Slave Clock system (One master clock and four numbers of slave clocks common for unit #1 and Unit #2). Panel dimension 900 x 800x 2415 mm with 3 kms of cabling. (Commissioning in Vendor's scope) | 1 | Set | | |
| A-6 | UPS, ACDB and Battery (Each set comprising of 5 UPS Panels + 2 ACDB Panels, total 7 panels. Each panel dimension is 1000 x 800 x 2415 mm. This also includes four sets of battery each set comprising of 180 / 192 cells, SMF VRLA battery arranged in mild steel rack of size 1000 x 800 x 1500 mm. (commissioning in vendor's scope) | 1 | Sets | | |

Bharat Heavy Electricals Limited: PSWR: Nagpur Tender Specification No. BHE/PW/PUR/UKAI-CLE/459 (Part-II: Price Bid) Schedule of Rates and Quantities (Page 2 of 9)

| SN | DESCRIP TION | TOTAL QTY | UOM | UNIT RATE (Rs.) | TOTAL AMOUNT (Rs.) |
|------|--|--------------|------|-----------------|--------------------|
| A-7 | Erection and commissioning of Gravimetric feeder remote panel (in panel room) and commissioning of feeder local electronics | 4 | sets | | |
| A-8 | Alarm Annunciation System (Comprising of suite of 2 panels of suite size 1600mm x 800 x 2415 mm) | 1 | Set | | |
| A-9 | DC motor starter box for scanner fan | 1 | No | | |
| A-10 | Hydrogen Purity analyzer | 1 | No | | |
| A-11 | Steam and Water Analysis System (SWAS) Sample handling system consisting of wet rack, dry panel and Analysers (Conductivity – 7, Dissolved Oxygen – 1, pH – 5 and Silica analyser – 2 numbers) | 1 | Set | | |
| A-12 | Furnace Temperature probe | 1 | Nos | | |
| A-13 | AC Control Supply Panel, DC Control Supply Panel (about 800 Kgs each) | 2 | Nos | | |
| A-14 | DCDB approximately (600x600x2300) | 1 | No | | |
| B-1 | Direct Water Level Gauge | 2 | Sets | | |

Bharat Heavy Electricals Limited: PSWR: Nagpur Tender Specification No. BHE/PW/PUR/UKAI-CLE/459 (Part-II: Price Bid) Schedule of Rates and Quantities (Page 3 of 9)

| SN | DESCRIP TION | TOTAL QTY | UOM | UNIT RATE (Rs.) | TOTAL AMOUNT (Rs.) |
|------|--|--------------|------|-----------------|--------------------|
| B-2 | Solenoid valves (3 way, AC/DC, 1/4", 1/2", 1", NPT/BSP, single/dual coil) | 15 | Nos | | |
| B-3 | HEA Exciter system | 12 | Sets | | |
| B-4 | Flame Scanner Head Assembly | 12 | Nos | | |
| B-5 | Air filter regulators / Lubricators (1/2", 1", 0-6KG, 0-10 KG) | 35 | Nos | | |
| B-7 | Speed Regulators / Air lock valves in oil gun corner rack | 12 | Nos | | |
| B-8 | MAX Engineering / operator / storian / LAN / WAN / Shift in charge / stn in charge / gateway / interface PC / HART etc., PC/Server Station with ASCII Keyboard, Mouse & 19" Colour Monitor, individual UPS, Ethernet switch, cabling etc with Work Station Desk (Operator and engineering) | 8 | Sets | | |
| B-9 | Printers (80/132 col Dot Matrix, A3 Inkjet, A3 Laserjet, etc) | 5 | Sets | | |
| B-10 | Flue gas analyzer system comprising of Sample handling system, Sox, Nox, CO and SPM analyzers | 1 | Set | | |

Bharat Heavy Electricals Limited: PSWR: Nagpur Tender Specification No. BHE/PW/PUR/UKAI-CLE/459 (Part-II: Price Bid) Schedule of Rates and Quantities (Page 4 of 9)

| SN | DESCRIP TION | TOTAL QTY | UOM | UNIT RATE (Rs.) | TOTAL AMOUNT (Rs.) |
|------|--|--------------|-----|-----------------|--------------------|
| B-11 | O2 (OXYGEN) Analyzer | 2 | Nos | | |
| C-1 | Console inserts (to be mounted on Backup desk) | 1 | Set | | |
| C-2 | Bar Graph Indicators (Single, Dual Channel) | 40 | Nos | | |
| C-3 | Digital indicators | 4 | Nos | | |
| C-4 | Recorder 18 Channel | 1 | Nos | | |
| C-5 | Recorder 3 /6/12 channel (new or relocation) | 40 | Nos | | |
| C-6 | Speed switch / Speed detector | 4 | Nos | | |
| C-7 | Moisture Sensor probe and dew point monitor | 1 | Set | | |
| C-8 | Rotor Earth fault Detector | 1 | Nos | | |
| C-9 | Pressure Switch / DP Switch / DP indicating switch/ Pressure gauge/ DP Gauge | 230 | Nos | | |

Bharat Heavy Electricals Limited: PSWR: Nagpur Tender Specification No. BHE/PW/PUR/UKAI-CLE/459 (Part-II: Price Bid) Schedule of Rates and Quantities (Page 5 of 9)

| SN | DESCRIP TION | TOTAL QTY | UOM | UNIT RATE (Rs.) | TOTAL AMOUNT (Rs.) |
|------|---|--------------|-----|-----------------|--------------------|
| C-10 | Temperature Switch / Thermostat / Temperature Gauge | 100 | Nos | | |
| C-11 | Float type/ Electronic Level Switch | 30 | Nos | | |
| C-12 | Electronic Level Transmitter (Displacer Type) | 3 | Nos | | |
| C-13 | Level Indicator / Level Gauge | 6 | Nos | | |
| C-14 | Flow indicator / Flow Gauge | 6 | Nos | | |
| C-15 | Pressure / DP / Flow (DP type) / Level - Transmitter | 200 | Nos | | |
| C-16 | Flow Transmitter (Pulse / mass flow / target / coriolis type) including flanges | 3 | Nos | | |
| | Thermocouple / RTDs with thermowell (all types) along with converters wherever applicable | 200 | Nos | | |
| C-18 | MTM Thermocouple | 25 | Nos | | |
| C-19 | I/P converters | 50 | Nos | | |

Bharat Heavy Electricals Limited: PSWR: Nagpur Tender Specification No. BHE/PW/PUR/UKAI-CLE/459 (Part-II: Price Bid) Schedule of Rates and Quantities (Page 6 of 9)

| SN | DESCRIP TION | TOTAL QTY | UOM | UNIT RATE (Rs.) | TOTAL AMOUNT (Rs.) |
|------|--|--------------|------|-----------------|--------------------|
| C-20 | Pneumatic Pressure controller with accessories | 1 | Nos | | |
| C-21 | Pneumatic Temperature controller with accessories | 1 | Nos | | |
| D-1 | Fan /Pulverizer/ pump Lube oil skid | 12 | Sets | | |
| D-2 | Electrical drives / actuators (regulating / On off type) | 70 | Nos | | |
| D-3 | Pneumatic drives: (Valve, damper) | 69 | Nos | | |
| D-4 | Commissioning of Hydraulic actuators | 2 | Nos | | |
| D-5 | ERV Controller | 2 | Nos | | |
| D-6 | Corner valve/ Trip valves commissioning | 40 | Nos | | |
| D-7 | Solenoid Valves | 30 | Nos | | |
| D-8 | Only healthiness checking of embedded RTD / T/C | 100 | Nos | | |

Bharat Heavy Electricals Limited: PSWR: Nagpur Tender Specification No. BHE/PW/PUR/UKAI-CLE/459 (Part-II: Price Bid) Schedule of Rates and Quantities (Page 7 of 9)

| SN | DESCRIP TION | TOTAL QTY | UOM | UNIT RATE (Rs.) | TOTAL AMOUNT (Rs.) |
|------|--|--------------|--------|-----------------|--------------------|
| D-9 | Limit Switches (checking and adjusting only). | 25 | Nos | | |
| D-10 | SADC Power cylinders (For these, erection of cylinders is also included although separate payment is not shown for erection in terms of payment. Erection and calibration charges to be within quoted rates) | 56 | Nos | | |
| E-1 | GI earthing wire | 1000 | Meters | | |
| E-2 | GI Pipe (1/2", 1") Heavy grade | 100 | Meters | | |
| E-3 | GI Pipe (1.5 ", 2") | 50 | Meters | | |
| E-4 | Copper tube 6mm/8mm / 1/4" (Sheathed / bare) | 2500 | Meters | | |
| E-5 | Perforated / ladder type cable tray and accessories (with or without cover) 50mm / 100mm / 150 mm | 4000 | Meters | | |
| E-6 | Perforated / ladder type cable tray and accessories (with or without cover) 200, 250, 300, 350, 450mm | 4000 | Meters | | |
| E-7 | Instrument, Control and Compensating Cable upto 8P/16C armoured / Un-armoured | 40000 | Meters | | |

Bharat Heavy Electricals Limited: PSWR: Nagpur Tender Specification No. BHE/PW/PUR/UKAI-CLE/459 (Part-II: Price Bid) Schedule of Rates and Quantities (Page 8 of 9)

| SN | DESCRIP TION | TOTAL QTY | UOM | UNIT RATE (Rs.) | TOTAL AMOUNT (Rs.) |
|------|--|--------------|--------|-----------------|--------------------|
| | 0.5/0.75/1.5/2.5 SQ.MM. | | | | |
| E-8 | Instrument, Control and Compensating Cable more than 8P/16C upto 32P/64C 0.5/0.75/1.5/2.5 SQ.MM. | 20000 | Meters | | |
| E-9 | Power Cable 3c / 4c up to 6sqmm | 5000 | Meters | | |
| E-10 | Power Cable 3c / 4c greater than 6sqmm, less than 25sqmm | 3000 | Meters | | |
| E-11 | Power Cable 3c 185sqmm | 3000 | Meters | | |
| E-12 | Network UTP Cables (special termination using UTP connectors involved) | 250 | Meters | | |
| E-13 | MS Flat 50 x 6 mm | 50 | Meters | | |
| F-1 | Junction boxes | 125 | Nos | | |
| F-2 | CS/AS/SS Impulse Pipe 1/2" Sch 40/80/160 | 2200 | Meters | | |
| F-3 | CS/AS Impulse Pipe 3/4", 1.0" Sch 40/80/160 | 800 | Meters | | |

Bharat Heavy Electricals Limited: PSWR: Nagpur Tender Specification No. BHE/PW/PUR/UKAI-CLE/459 (Part-II: Price Bid) Schedule of Rates and Quantities (Page 9 of 9)

| SN | DESCRIP TION | TOTAL QTY | UOM | UNIT RATE (Rs.) | TOTAL AMOUNT (Rs.) |
|-------|---|--------------|-------|-----------------|--------------------|
| F-4 | Plant Control Desk / CRT desk | 1 | Set | | |
| F-5 | Computer furniture for all Servers, PCs, Printers | 1 | Set | | |
| F-6 | Structural steel for fabrication | 5 | Tons | | |
| F-7 | Lumpsum charges for carrying out tests as per clause 4.23.9 of Technical specifications | 1 | Set | | |
| F-8 | Drilling hole in the floor, concrete slab etc for installation of panels with minimum opening of 1 square feet. | 200 | Sqft. | | |
| | Grand total in figures (Rs) | | | | |
| | | | | | |
| Grand | Total in words : Rupees | | | | |