



Ref: BHE/PW/PUR/BORLI-CVL/477/Amd-01

Dated: 31.01.2007

To,

All Bidders

Dear Sir,

SUB : Amendment- 01- Rate Schedule- Reg

JOB : CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS FOR STG, BOILER & AUXILIARIES, ESP,BUNKER, PLANT BUILDINGS ETC COMPLETE AT 3x33 MW, STG PROJECT,BHARAT OMAN REFINARY LIMITED (BORL),BINA (M P)

REF : T. S. No. – BHE/PW/PUR/BORLI-CVL/477.

Bidders may please refer Price Bid, Part-II, Vol- III (Rate Schedule).In this rate schedule two new items i.e. item no 8.16 & 8.17 are added. These two new items of rate schedule shall be as per Annexure-P1which is enclosed with this letter.

Bidders may also note that item no 3.4a, 3.4b, 7.4, 7.5, 8.4 & 8.11 are revised as per Annexure-P1 attached with this letter. As such bidders are requested not to quote rate for these revised items in Price bid, Part-II- Vol-III. In case the bidder quotes the rates for these revised items in Price Bid- Part-II-Vol-III, same shall not be considered for evaluation of bid.

Bidders should quote their rates for two new items and six revised items in Annex-P1. Annexure- P1 shall be part of Part-II-Price Bid Vol-III. The Annex-P1 with quoted rate should be enclosed with Part-II Price bid while submitting the offer.

Some bidders asked clarifications which are as below.

- 1) As per the preliminary soil investigation report, the depth of rock varies from 5.0m to 2.0m.
- 2) Bidders are not allowed to use stones available from excavation in soiling/WBM.

Bidders may please download these documents from web and enclose copy of same (un-priced) with technical bid duly signed by your authorized signatory and stamped with official seal as a token of your unqualified acceptance of this amendment.


We cannot further extend due date of offer submission, hence due date of offer submission shall be 06/02/2007/18.00Hrs .

All other terms & condition of the tender specification shall remain unchanged unless and otherwise expressly amended by BHEL.

Thanking you.

Yours faithfully

S. M. BORKAR
SR. MANAGER (PURCHASE)

STRUCTURAL AND ARCHITECTURAL WORKS FOR STG, BOILER & AUXILIARIES, JUNKER, PLANT BUILDINGS ETC COMPLETE AT 3x33 MW, STG PROJECT, BHARAT OMAN REFINARY LIMITED (BORL), BINA (M P)						
Item no.	 DESCRIPTION	Unit	Quantity	Rate	Amount	
	FOLLOWING ARE ADDITIONAL ITEMS					
8.16	Supplying and fixing Ceramic tiles of approved make of sizes 300X300X8mm for flooring and 300X200X6 for dado up to 2.5 m elevations including preparations of base laying underbed, finishing and rounding corners and junctions, curing etc. complete as per drawings and specifications.	SQ.M	1400			
8.17	Providing 50mm thick Granolithic Cement Concrete flooring comprising 35mm cement concrete base of M25 grade, laying underbed in panels bound by 3X40mm PVC / 4X40mm glass strips followed by 15mm thick wearing top layer of cement concrete, finishing, curing etc. all complete with dust protective coating (Using OPC/PPC/PSC/SRC cement) as per EIL Specifications No-C-3.2, Pg-9 of 9 , Spec No-6743-31-16-48-SP-0054, Rev-A	SQ.M	2600			
	FOLLOWING EXISTING ITEMS REVISED					
3.4a)	Providing and placing in position, compating , curing Reinforced concrete for paving of M25 grade with min. cement content of 350 kg/m3 (using OPC/PPC/PSC/SRC) including laying in approved size panels, leaving grooves for sealing joints, cost of form work, finishing of top surface as required but excluding cost of reinforcement which will be paid under relevant items, etc.all complete for floors and pavement as per EIL drawing No- 7-75-0404 and specifications.	CU.M	3000			
3.4b)	Providing and placing in position, compating , curing Reinforced concrete for paving of M30 grade with min. cement content of 375 kg/m3 (using OPC/PPC/PSC/SRC) including laying in approved size panels, leaving grooves for sealing joints, cost of form work, finishing of top surface as required but excluding cost of reinforcement which will be paid under relevant items, etc.all complete for floors and pavement as per drawing and specifications.	CU.M	1500			
7.4	Supplying and laying position minimum 75 kg/cm2 brickwork in half brick walls at various elevations in 1:4 cement sand mortar with HB netting at every fourth layer including mixing mortars, raking joints, curing etc all complete as per drawings and specifications. (Using OPC/PPC/PSC/SRC cement)	SQ.M	1300			

8.4	Supplying and fixing Vitrified ceramic tiles of approved make of sizes 600x600x8mm for flooring and 600X600X6 for dado up to 2.5 m elevations including pereparation of base laying underbed, finishing and rounding corners and junctions, curing etc. complete as per drawings and specifications.	SQ.M	1400		
8.11	Providing 50mm thick heavy duty cement Concrete flooring comprising 35mm cement concrete base of Concrete grade M25, laying underbed in panels bound by 3X40mm PVC/ stainless steel 4X40mm glass strips followed by 15mm thick wearing top layer of cement, metallic hardner and stone aggregate, finishing, curing etc. all complete with dust protective coating (Using OPC/PPC/PSC/SRC cement) as per EIL Specifications No- C-3.2, Pg-10 of 10 , Spec No- 6743-31-16-48-SP-0054, Rev-A	SQ.M	3963		

Signature of bidder with seal