

TENDER SPECIFICATION
No. BHE/PW/PUR/WR-CVL/507

FOR

**PLACING VITRIFIED TILES ON THE FLOORS IN
BHEL OFFICE LOCATED AT NAGPUR (M.S.)**

PART-I I –PRICE BID

(Volume-I I)

RATE SCHEDULE

Book No.



BHARAT HEAVY ELECTRICALS LIMITED

(A GOVERNMENT OF INDIA UNDERTAKING)

POWER SECTOR - WESTERN REGION

SHREEMOHINI COMPLEX

345, KINGS WAY - NAGPUR 440 001



BHARAT HEAVY ELECTRICALS LIMITED

(A GOVERNMENT OF INDIA UNDERTAKING)

POWER SECTOR - WESTERN REGION

SHREEMOHINI COMPLEX

345, KINGS WAY - NAGPUR 440 001

PH: 0712-530641, FAX: 0712-530640

TENDER SPECIFICATION No. BHE/PW/PUR/WR-CVL/507

**NAME OF WORK: PLACING VITRIFIED TILES ON THE FLOORS IN BHEL
OFFICE LOCATED AT NAGPUR (MS)**

EARNEST MONEY DEPOSIT: RS.1,00,000/- (Rupees one lakh only)

OFFERS SHALL BE RECEIVED UPTO 18:00 HOURS OF.....

These Tender Documents containing Part-I Technical Bid and Part-II Price Bid are
issued to

M/s

.....

.....

(THESE TENDER DOCUMENTS ARE NOT TRANSFERABLE)

For Bharat Heavy Electricals Limited

SENIOR MANAGER (PUR)

PLACE: NAGPUR

DATE:

TENDER SPECIFICATION No. BHE/PW/PUR/WR-CVL/507

NAME OF WORK: PLACING VITRIFIED TILES ON THE FLOORS IN BHEL OFFICE LOCATED AT NAGPUR (MS)

BILL OF MATERIAL

Item no.	Description	Qty.	UOM	Rate (INR)	Amount (INR)
1	Removing and Shifting the existing office furniture, Tables, Cupboards, Chairs, cubicles, documents, equipments from 5 th floor RHS to rented SAIL office premises at 5 th floor.	1	LUMP SUM		
2	Removing and Shifting the existing office furniture, Tables, Cupboards, Chairs, cubicles , documents, equipments from 6 th floor RHS to an identified place within the office premise.	1	LUMP SUM		
3	Removing and Shifting the existing office furniture, Tables , Cupboards, Chairs, cubicles, documents, equipments from 6 th floor LHS to an identified place within the office premise.	1	LUMP SUM		
4	Supply, Laying, Placing, pasting mirror polished vitrified tiles 60x60 cm. of Kajaria make, Model: KERRO 6028, 'Double Charged' on floor. Laying shall be on existing glazed tiles by removing the existing carpet, cleaning the surface and pasting the vitrified tiles with BAL make adhesive for pasting the vitrified tiles. The joint shall be filled with joint filler to match the color of the tile. Job shall be completed including necessary machine tools, cleaning of finished top, cutting partition doors from bottom to reduce its height etc. to the satisfaction of BHEL Engineer-in-charge.	12000	Sq.ft.		
5	Reassembling the shifted office furniture described in Item No. 1.	1	LUMP SUM		
6	Reassembling the shifted office furniture described in Item No. 2.	1	LUMP SUM		
7	Reassembling the shifted office furniture described in Item No. 3.	1	LUMP SUM		
		TOTAL AMOUNT IN RS			
	TOTAL IN WORDS RS.....				

- Note: 1. Item no. 5, 6, 7 are optional.
2. Evaluation will be done based on the total amount of item no. 1 to 7.