T E N D E R   S P E C I F I C A T I O N
No. BHE/PW/PUR/WR-QTR-CVL/524

FOR

PLACING VITRIFIED TILES ON THE FLOORS IN BHEL OWNED FLATS LOCATED AT VARIOUS AREAS IN NAGPUR (M.S.)

PART-I I –PRICE BID

(Volume-I I)

RATE SCHEDULE
Book No.

BHARAT HEAVY ELECTRICALS   LIMITED
(A GOVERNMENT OF INDIA UNDERTAKING)
POWER SECTOR - WESTERN   REGION
SHREEMOHINI COMPLEX
345, KINGS WAY - NAGPUR 440 001

BHARAT HEAVY ELECTRICALS   LIMITED
(A GOVERNMENT OF INDIA UNDERTAKING)
POWER SECTOR - WESTERN   REGION
SHREEMOHINI COMPLEX
345, KINGS WAY - NAGPUR 440 001
PH: 0712-530641, FAX: 0712-530640

TENDER SPECIFICATION No. BHE/PW/PUR/WR-QTR-CVL/524

NAME OF WORK: PLACING VITRIFIED TILES ON THE FLOORS IN BHEL OWNED FLATS LOCATEDIN VARIOUS AREAS AT NAGPUR (MS)

EARNEST MONEY DEPOSIT: RS.1,50,000/- (Rupees One lakh fifty thousand only)

OFFERS SHALL BE RECEIVED UPTO 18:00 HOURS OF……………….…………

These Tender Documents containing Part-I Technical Bid and Part-II Price Bid are issued to

M/s …………………………………………………

……………………………………………….…

……………………………………………………

(THESE TENDER DOCUMENTS ARE NOT TRANSFERABLE)

For Bharat Heavy Electricals Limited

SENIOR MANAGER (PUR)

PLACE: NAGPUR
DATE:

TENDER SPECIFICATION No. BHE/PW/PUR/WR-QTR-CVL/524

NAME OF WORK: PLACING VITRIFIED TILES ON THE FLOORS IN BHEL OWNED FLATS LOCATED AT VARIOUS AREAS IN NAGPUR (MS)

BILL OF MATERIAL

Item no.	Description	Qty.	UOM	Rate (INR)	Amount (INR)
1	**Supply, Laying, Placing, pasting mirror polished vitrified tiles 60x60 cm. of Kajaria make, Model: KERRO 6014,** 'Double Charged' on floor. Laying shall be on existing glazed tiles / Cement Floor by cleaning the surface and pasting the vitrified tiles with BAL make adhesive for pasting the vitrified tiles. The joint shall be filled with joint filler to match the color of the tile. Job shall be completed including necessary machine tools, cleaning of finished top,. to the satisfaction of BHEL Engineer-in-charge. This work also includes the work of vacating the area and rearrangement of items as per occupants instructions to facilitate to carry out the above work.	**21650**	**Sq.ft.**		
		TOTAL AMOUNT IN RS			
	TOTAL IN WORDS RS……………………………………………………………………				