

REF : PSER: PUR: PMX: 164: 110:02:

DATE : 16-11-2007

M/s _____

TCN-02

Dear Sir,

SUB: DESIGN, MANUFACTURING, SUPPLY, RECEIPT AT SITE, ERECTION, SITE PAINTING ETC. AND HANDING OVER OF THREE NOS. REMOVABLE/RE-ERECTABLE TYPE PREFABRICATED STEEL STORE SHED AS PER ENCLOSED PLAN AT 4X150 MW NEEPCO, KAMENG HEP PROJECT, ARUNACHAL PRADESH.

REF: Tender document no PSER: PUR: PMX: 164:110 dated 22.10.2007

With reference to above, the following design conditions shall be considered while quoting for the above mentioned covered storage shed. These shall prevail over respective data in original document:

- a) Design ambient dry- bulb Temperature
 - High : 50 Deg.C maximum,
 - Low : 5 Deg.C minimum,
- b) Maximum relative humidity : 100%
- c) Average relative humidity : 69%
- d) Average annual rainfall : 1641.4mm
- e) Seismic zone : Zone-IV as per IS-1893 latest revision
- f) Wind load : In accordance with IS-875 for a max. wind speed of 50 m/sec.
- g) All design to be done as per relevant I S Code.

All other terms & conditions of the tender shall remain unchanged.

Thanking you

Yours faithfully,
For & on behalf of

BHEL,

Encl: Annexure-I

(Sr. Manager – PUR)