

**BHEL: PS WR**  
**TS NO : BHE/PW/PUR/BORLI-LDEV/535**  
**REVISED PRICE BID- PART-II - VOL-II**  
**(REVISION-01 )**

**RATE SCHEDULE ( REV-01 )**

<b>BHARAT HEAVY ELECTRICALS LIMITED</b>						
<b>3X33 MW/CPP/BORL/BINA</b>						
<b>Name of work:</b> Development of storage yard with murrum and stone soling at BHEL store yard/ BORL/ Bina.						
<b>Rate Schedule</b>						
<b>Sl. No.</b>	<b>Description of work</b>	<b>Qty.</b>	<b>Unit</b>	<b>RATE IN RS IN FIGURE</b>	<b>Rate IN WORDS IN RS</b>	<b>Amount In Rs.</b>
1	Cutting, leveling and filling the top soil area up to 100mm average thick and including removing grass, bushes etc. and consolidating with road roller 10 to 12 MT capacity road roller.	16500	SQM			
2	Providng and laying murrum filling 200mm thick and compacting with power roller 10-12 MT capacity.	3300.00	CUM			
3	Providing and laying stone soling 230 thick using 100mm to 150mm size of stones and filling the voids with hand broken metal 40 to 60mm size including spreading binding materials (morrum/sand) watering and rolling with road roller 10 to 12 MT capacity power road roller.	3795.00	CUM			
	<b>TOTAL OF ABOVE IN RS</b>					
	TOTAL OF ABOVE IN WORDS ( RS ..... )					