BOQ OF, NMDC KUMARASWAMY DOWNHILL CONVEYOR SYSTEM

Note: BHEL Reserves the Right to take the full scope or fix the scope after discussion with Vendor.

SI No	ITEM	Quantity	Basic Price.	Lot Basic Firm Price.	Taxes & Duties,Insurance etc as per NMDC's format, Vol-II	LSTK, FORD Prices.
A.	MECHANICALS					
1	Conveyor#718,Straight ,1200mm Belt Width , 37M long, Secondary Crusher House to TH-1.	1Lot				
2	#718A, Inline Magnetic Separator at TH-1, on Conveyor #718.	1Lot				
3	#718B, Electric Hoist at TH-1	1Lot				
4	#718C, <u>Belt Weigh Scale</u> , on Conveyor#718	1Lot				
5	#719, <u>Belt Conveyor</u> Inclined,1200mm Belt Width , 171M Long.	1Lot				
6	#719A, <u>Metal Detector</u> , on conveyor#719	1Lot				
7	#719B, <u>Electric Hoist</u> at Top of Storage Silo, 1000MT, Ore Storage.	1Lot				
8	#719D, <u>Needle Gate</u> ,at Bottom of , above Storage Silo.	1Lot				
9	#720, <u>Belt Feeder</u> , 8.5M long with <u>VVVF Controls</u> . below RCC Silo.	1Lot				
10	#720A, <u>In Line Magnetic</u> <u>Separator</u> , on above Belt Feeder.	1Lot				
11	#720B, Electric Hoist, at TH-2	1Set				
12	#721, <u>Belt Conveyor</u> ,Inclined, ,1200mm Belt Width, 30M	1Lot				

	long. Between TH-2 to TH-2A.			
13	#721A, Metal Detector, on	1Lot		
	conveyor-721.			
14	#721B, Belt Weigh Scale, on	1Set		
	conveyor-721.			
15	#721C, Electric Hoist in TH-2A.	1Set		
46	#700 45/5 AT D. 11. 0'.1.	46.1		
16	#722 , <u>15/5 MT Double Girder</u> <u>EOT Crane</u> , at Tail Drive House	1Set		
	of Down Hill Conveyor.			
17	#722A Manual Haist for	1Set		
17	#722A, <u>Manual Hoist</u> for maintenance of above EOT	1561		
	Crane. Located as above.			
18	#723 <u>DOWNHILL CONVEYOR</u> ,	1 Set with 02		
10	Inclined, 1050m belt width,	nos Self		
	Steel Cord type, 4.9 KM Long	Propelled		
	apppx. With VVVF Drives.	Maintenance		
	Between Tail Drive House to	Trolleys,		
	TH-3.	moving on		
		Triangular Or		
		Rectangular Gantry		
		Structures.		
19	#723A, 5MT Under Slung EOT	1Set		
	<u>Crane</u> , at PS-1(Parking Station) at Tail End of Down			
	Hill Conveyor.			
20	#723B, <u>5MT Under Slung EOT</u>	1Set		
	<u>Crane</u> , at PS-2(Parking Station) at Head End of Down			
	Hill Conveyor.			
21	#724 , Surge Hopper, 50 CuM	1Lot		
	<u>Water Volume</u> ,in TH-3.			
22	#724A, Hydraulically Operated	1Set		
	Gate. At Bottom of Surge			
	Hopper in TH-3.			
23	#725, Belt Feeder with VVVF	1Lot		
	drive. 8 M long ,at bottom of			
	Surge Hopper in TH-3.			
24	#726 Manual Hoist in TU 2 for	1Set		
24	#726 <u>. Manual Hoist</u> in TH-3 for maintenance of Head Pulley of	1261		
<u> </u>	maintenance of fleat Fulley Of			

	DHC.			
25	#726A, <u>Electric Hoist</u> in TH-	1Set		
	3,formaintenance of Belt			
	Feeder/Head Pulley of DHC.			
26	#726B, Electric Hoist in TH-	1Set		
	3,for maintenance of Tail			
	Pulley of Reversible			
	Conveyor#727.			
27	#727, REVERSIBLE BELT	1Lot		
	CONVEYOR, Inclined, Steel			
	Cord Belt, 1050mm belt width,			
	295 Metre Long, Inclined,			
	with VVVF Drive.Located			
	between TH-3 to TH-4.			
20	#7074 Flore to the to the THE	46.1		
28	#727A, <u>Electric Hoist</u> in TH-5	1Set		
29	#727B, 7.5 MT Single Girder	1Set		
	EOT Crane in TH-4.			
30	#727-1, Inclined <u>,Belt</u>	1Lot		
	Conveyor ,1200mm Belt			
	Width, 13M long appx,			
	between transfer station at			
	Tail end and TH-6.			
31	#727-2, Inclined Belt Conveyor	1Lot		
	,1200mm Belt Width ,73M			
	long appx. Between TH-5 to			
	TH-6.			
32	#727C, Electric Hoist in TH-6.	1Set		
	#432 EVICTING Tolor	41		
33	#122,EXISTING Tripper	1Lot.		
	Conveyor Modifications Works .(Tail End to be			
	 '			
	extended & Tripper travel to be increased)			
	be increased)			
	1.Existing Tripper Conveyor			
	#122 at the existing Transfer			
	House at Donimalai (Also			
	having the Existing Down Hill			
	Conveyor Head End there in)			
	shall be extended by appx			
	12M towards TH-4 upto			
	Head End of Reversible			
	Conveyor #727.			

		T	1	1	
	2. <u>To Extend the Travel of the</u>				
	existing Tripper #122 by appx				
	28 Meters towards the Tail				
	End to Enable Feeding				
	Reversible Conveyor #727				
	through NEW TRANSER				
	STATION(TS), Conveyors #				
	727-1, 727-2 . <u>Finally in this</u>				
	<u> </u>				
	mode Iron Ore can be				
	Conveyed upto the Future &				
	New Screening Plant at				
	<u>Donimalai.</u>				
	3. In view of above two points				
	-				
	, proper care must be taken				
	at the Planning Stage about				
	the Civil works at TH-5,TH-				
	3,TH-4,TH-6, Existing Transer				
	House and NEW TRANSFER				
	STATION.				
B.	CIVIL & STRUCTURALS.				
<mark></mark>	CIVIL & STRUCTURALS.				
1	Presence during Soil	LS.			
	investigation and survey.				
	-				
2	Foundations for the tail pulley	1Lot Design			
	& short posts of conveyor	Data.			
	no. 718 inside the secondary				
	crusher building(Package-I				
	Scope) and the				
	conveyor gallery with gallery support & foundation up to				
	2m				
	from axis 2 of secondary				
	crusher building is included in				
	the				
	scope of package-I Tenderer.				
	Package-II Tenderer shall				
	furnish the load data and				
	other information for the				
	above				
	foundations & gallery of				
	conveyor no. 718 to Package-I				
	Tenderer for providing the				
	same.				
3	1000MT Effective Storage Silo	1Lot.			
	for Iron Ore , With Structural				
	Roof.				
ı					

		1		4.004.0.0	
4	<u>Transfer Houses</u> (TH#) with	1Lot.		1.PS-1 & 2 are	
	RCC Columns & RCC			Parking cum	
	Foundation (considering Soil			Maintenance Shed	
	Settlement)at the Terrain			for Self Propelled	
	Placed.			Maintenance	
				Trolleys at Tail &	
	, <u>Civil Structures</u> :			Head End of the	
				Down Hill Conveyor	
	TH-1, Tail Drive House, TH-2,			System.	
	TH-2A, PS-1, PS-2, TH-3, TH-5,			System.	
	TH-4, TH-6, Modification at			2.TH-3 Height	
	Existing Transfer House,			,Width , Depth to	
	Transfer Station.			be Suitable and	
				Ready for	
				considering future	
				conveying of	
				Materials to NEW	
				SCREENING PLANT	
				AT DONIMALAI	
				through a New	
				BeltFeeder & New	
				Conveyor.	
				,	
5	TUBULAR	1Lot appx	 	In Modular	
	Triangular/Rectangular	4.9 KMs. As		Shippable Lengths	
	GANTRY Structure enclosing	Per the Final		by Trucks travelling	
	the Conveyor Canopy, Belt,	Ascertained		the Hill Path at site	
	Idlers, Fire Sprinkler Pipes,	DHC Path,		and supported on	
	Chequered plate walkway	Contour,		RCC /STRUCTURAL	
	support if any .	Profile with		SUPPORT TRESSLES	
	ouppoint in unit	Curvatures			
		after			
		Resurvey at			
		Site.			
6	Foundation Works of RCC /	1Lot.			
•	Fabricated <u>Tressle Support</u>				
	Structures of Down Hill &				
	Reversible Conveyor , as				
	determined after site				
	Resurvey.				
7	TAIL END 6.6 KV INDOOR TYPE	1Lot.			
′	SUB STATION BUILDING for	1200			
	SWITCHGEAR, TRANSFORMERS				
	,6.6KV CAPACITOR BANK etc.				
8.	TAIL END CABLE TRENCHES	1Lot.			
0.		1100.			
	(Appx 700metre long),BURIED				
1	HUME PIPES FOR ROAD				

		ı		
	CROSSINGS @EL+1036 FGL			
	between 33/6.6KV SS to SS			
	Building as above.			
9	HEAD END 11KV SINGLE	1Lot.		
	STORY SS BUILDING AT TH-3.			
	Single Storied Indoor type			
	11KV SS Building			
10	HEAD END 11KV DOUBLE	1Lot.		
	STORIED SS Cum Office			
	Building At TH-5. For			
	Locating HMI Computer			
	Controls of DHC with VVVF			
	&AUTOMATION PANELS.			
	GAOTOWATION PANELS.			
11	11KV CABLE TRENCH FROM	1 Lot.		
	11 KV EXISTING CICO PANEL			
	AT DONIMALAI 11 KV			
	_			
	SWITCHYARD TO 11 KV DP-1			
	STRUCTURE TUBULAR/			
	FABRICATED SECTION ,Appx			
	600 Meter Cable Trench.			
12	11 KV TUBULAR/FAB	1 Lot.		
	SECTION TRANSMISSION			
	TOWERS / STRUCTURES FROM			
	DP-1 at HEAD END TO DP			
	STRUCTURE NEAR TH-3 TO			
	CARRY 11KV OVERHEAD			
	CONDUCTORS , APPX 03 KM			
	<u>-</u>			
	Length.			
13	Foundation Works, Support	1Lot.		
13	Jib & Stays, Tie Rope /Guy	1200.		
	Wire Turn Buckled Stays <u>for</u>			
	above 11 KV Towers between			
	Donimalai to Kumaraswamy			
	Head End.			
14	New Approach Roads to	1Lot		
	TH-1, Silo area, Tail / drive			
	house of Down			
	Hill Conveyor, TH-2, TH-2A,			
	PS-1 and Electrical, control			
	cum			
	office building <u>from the</u>			
	Approach Road Made by			
	Package-I Secondary Crusher			

	Contractor.				
15	Approach road to TH-3 from the kachcha road already developed by NMDC	1Lot			
16	Approach road to take-up area of down hill conveyor no. 723 and PS-2 near head end of down hill conveyor.	1Lot			
17	Approach road to TH-4, TH-5 & TH-6 from the roads available already.				
18	Approach road to belt lay down area(Appx, 300x10)Sq Meter at two locations. (Between Jeepable Road ,Donimalai to Kumaraswamy hilltop to be made to Avoid Tree Cutting Approvals from Forest Dept)	1Lot			
19	<u>Creating Hard Top area,</u> For Conveyor Belts Laydown and	2 Nos Each (300x10) Sq			
	further handling during Erection .	Metre.			
20	Complete structural work including structures for transfer houses, maintenance platforms, technological structures, conveyor galleries, trestles, etc.,	1Lot			
21	Water supply shall be from a take off point near outlet flange of the main hill top reservoir located near the service center, Kumaraswamy (at FGL 1042.00 m (Abs) for dust suppression system, drinking water, sanitary purpose, etc.	1Lot		Fire Water Sub distribution is in scope of FDSS Sub Vendor. Other water sub distribution by BHEL, The Main & Fire Water Storage Tanks are being done by NMDC.	
	Water Supply ,(sub distribution from Main Potable Water Storage Tank at Kumaraswamy Hill Top, to be done by NMDC)and sewerage disposal system as required at TH-1, TH-2, TH-2A, RCC Silo,				

	Tail/ drive house of down hill				
	conveyor, TH-3, TH-4, TH-5,				
	TH-6 Control Room/MCC				
	rooms,				
	etc				
C.	ELECTRICS.				
<u> </u>	ELECTRICO.				
1	Illumination of plant and,				
-	Ilumination of all conveyor				
	•				
	galleries, Transfer Houses,				
	electrical room. Outdoor area				
	illumination.				
2	HT/LT switchgear, LT				
	Transformers and shop				
	electrics.Fixed P.F				
	improvement Capacitor				
	Banks.				
	Control and power cables,				
	signal cables, data cables, etc.				
	Control panels, desks, PLC				
	panel, VDU etc. ,Intra plant				
	communication (PA System)				
3	Field safety switches, Control,				
	PLC based automation,				
	instrumentation and				
	SCADA,HMI.				
4	Electronic Belt Rip Protection	1Lot.			
	System for DHC#723,				
	Reversible Conveyot#727.				
	With interface to Plant				
	Control HMI.				
5	Braking system for controlled	1Lot			
	starting, stopping of downhill				
	conveyor under varying				
	patterns of load and braking				
	under				
	no-power conditions				
<u>_</u>	Bushing and the first way	41			
6	Braking system for reversible	1Lot.			
	conveyor no. 727., with				
	dedicated PLC Panel &				
	Controller.				
7	VFD(VVVF) Regenerative	1Lot.			
	System for 2x750 KW,690 V				
	ac/1000RPM Down Hill				
	Conveyor#723.				
	33				
8	1x400KW/1000RPM,	1Lot.			
1	, 2000,				
	1	i .		İ	l .

D.	Reversible VFD,Regenerative system for Reversible Conveyor#727. OTHER MISCELLANEOUS			
1	ENGINEERING ASSISTANCE ASPER CL#4 of ISG/DHC-001, Dt2nd April10.	LS with Break Up.		
2	Drawing & Documentation , O&M Manuals Hard & Soft Copies.			
3	Training of NMDC Personnel			
E.	ERECTION & COMMISIONING.			
F.	SPARES: 2Years Applicable Normal &Maintenance Spares.	1Lot		
1	Commissioning& Insurance Spares.	1Lot		
2	Special Tools & Tackles, Instruments for Commissioning.	1Lot.		