

Scope of Works/BOQ/Price Format

Annexure-I(1/2)

SPECIFICATION OF OBD WORK IIN HRDI OFFICES, HOSTEL ROOMS & OTHER AREAS.

<u>1</u>	<u>2</u>	<u>3</u>	<u>4</u>	<u>5</u>	<u>6</u>
SI No.	DESCRIPTION OF WORK	QTY.	UNIT	Unit Rate (IN Rs.)	Amount (IN Rs.)
	FOR HRDI OFFICES:				
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sandpapering and preparing the surface smooth including necessary repairs to scatches etc. complete	11000	SQM*		
2	Applying one coat of cement primer of approved brand and manufacture on wall surface: 13.43.1 Cement primer.	11000	SQM*		
3	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete	11000	SQM*		
4	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: 13.60.1 Two or more coats on new work	11000	SQM*		

Annexure-I(2/2)

<u>1</u>	<u>2</u>	<u>3</u>	<u>4</u>	<u>5</u>	<u>6</u>
	FOR WOODEN WORK:				
5	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: 13.61.1 Two or more coats on new work	1300	SQM*		
	FOR LT PANEL ROOM, DG ROOM, AC PLANT, METER ROOM & PUMP HOUSE				
6	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	2000	SQM*		
7	White washing with lime to give an even shade: 14.42.1 Old work (two or more coats)	2000	SQM*		
8	Distempering with dry distemper of approved brand and manufacture (one or more coats) and of required shade on old work to give an even shade.	2000	SQM*		
9	Providing and fixing scaffolding upto height 40 ft for 3 months	350	SQM*		
10	TOTAL (in Rs.) Excluding Service Tax				
11	Taxes, if any (with %age)				

Note: * : The quantity is indicative and may change during execution of work.