



BHARAT HEAVY ELECTRICALS LIMITED
RAMACHANDRAPURAM::HYDERABAD::32
FACTORY CIVIL ENGINEERING DEPARTMENT

SCHEDULE- A

Tender Notice No:

HY/FCD/OT-03/2012-13, Dt: 18.05.2012

PRICE BID

Item no.: 9

Name of work: Providing of cement concrete flooring for the existing yard at 41 stores
(South side of 12 stores office).

S. No.	Description of the item	Qty	Unit	Rate (₹)	Amount (₹)
1	Earth work in excavation in all soils by mechanical means (Hydraulic Excavators) / manual means in foundations trenches or drains (not exceeding 1.5m in width or 10 Sq.m on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50M etc. complete as directed by Engineer- in- charge.	219.00	Cu.m	103.40	22,644.60
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering including consolidation by vibrations for all works up to plinth level with 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate of 20 mm nominal size) etc. complete as directed by Engineer- in- charge. (Cement will be issued by BHEL on free of cost)	88.00	Cu.M	1,560.50	1,37,324.00
3	Providing and laying in position specified grade, of Reinforced cement concrete excluding the cost of centering, shuttering, finishing and reinforcement - all work up to plinth level with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate of 20 mm nominal size) etc. complete as directed by Engineer- in- charge. (Cement will be issued by BHEL on free of cost)	132.00	cu.m	1,687.00	2,22,684.00
4	Conveyance of excavated spoil up to a lead of 2 Kms, including loading, unloading and spreading etc. complete as directed by Engineer- in- charge.	219.00	Cu.M	56.41	12,353.79
5	Granolithic topping of 25 mm thick using 1 cement 1 granite chips of 10mm down graded laid over base concrete when it is green conditions and ironite finishing 12mm thick using a mix of 50Kg of ironite, 200 Kg of cement and 0.30 Cu.m of granite metal 6mm down graded including cost of form work, curing etc. complete etc. complete as directed by Engineer- in- charge.	875.00	Sq,m	295.50	2,58,562.50

S. No.	Description of the item	Qty	Unit	Rate (₹)	Amount (₹)
6	Centering and shuttering including strutting, propping etc.; and removal of form work, for columns, pillars, piers, abutments, machine foundations, posts and struts etc. complete as directed by Engineer- in- charge.	28.00	Sq.m	180.40	5,051.20
	Sub Total			₹	6,58,620.09
	Add increase in Vat 1% over the material cost (70% of contractor scope)			₹	4,610.34
	Total value of work			₹	6,63,230.43
Total : ₹ Six lakhs sixty three thousand two hundred thirty and forty three paise only					

Note:- The required cement and steel will be issued on free of cost at BHEL stores other than Ready mix concrete items.

1	A penalty of 0.5% of the gross value of work will be levied for every week's delay of work subject to a maximum penalty of 10% of the gross value of work.
2	Service tax is extra as applicable, which will be reimbursable to the agency on production of paid proof documents.
3	The rates are inclusive of all taxes and duties.

Note : The bidders are required to quote the tender value on percentage (%) basis at excess or less or on par with estimate value in figures and words.

Tender %	In figure	In words
Excess		
Less		
Estimated value		

Name of the Contractor :

Signature of the Contractor