



**BHARAT HEAVY ELECTRICALS LIMITED**  
**RAMACHANDRAPURAM::HYDERABAD::32**  
**FACTORY CIVIL ENGINEERING DEPARTMENT**

SCHEDULE- A

Tender Notice No:

HY/FCD/OT-03/2012-13, Dt: 18.05.2012

PRICE BID

Item no.: 10

**Name of work: Repairs to gulley chambers & approach road areas at railway lines.**

S. No.	Description of the item	Qty	Unit	Rate (₹)	Amount (₹)
1	Dismantling reinforced cement concrete / plain cement concrete of gulley chambers including dismantling concrete, removal of chambers jolleys & storing jolleys in safe custody for providing the same after modification of chambers and disposing of debris upto to a lead of 2 KM including loading, unloading and spreading as directed by Engineer-in-charge etc., complete.	25.00	Cu.m	582.68	14,567.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering including consolidation by vibrations for all works up to plinth level with <b>1:2:4</b> (1 cement : 2 coarse sand : 4 graded stone aggregate of 20 mm nominal size) as directed by Engineer-in-charge etc., complete. <b>(Cement will be issued by BHEL on free of cost)</b>	536.50	Cu.M	1,585.00	8,50,352.50
3	<b>Centering</b> and shuttering including strutting, propping etc.; and removal of form work, for columns, pillars, piers, abutments, machine foundations, posts and struts as directed by Engineer-in-charge etc., complete.	296.50	Sq.M	180.40	53,488.60
4	Dismantling reinforced cement concrete / plain cement concrete and disposing of debris upto to a lead of 2 KM including loading, unloading and spreading as directed by Engineer-in-charge etc., complete.	54.00	Cu.m	582.68	31,464.72
5	Providing and laying in position specified grade, of <b>Reinforced cement concrete</b> excluding the cost of centering, shuttering, finishing and reinforcement - <b>all work up to plinth level with 1:2:4</b> (1 cement : 2 coarse sand : 4 graded stone aggregate of 20 mm nominal size) including fixing of gulley chambers jolly in position, pouring concrete, finishing into neat finish with proper slope, so that rain water should drained from gully chamber as directed by Engineer-in-charge etc., complete. <b>(Cement will be issued on free of cost)</b>	54.00	cu.m	1,687.00	91,098.00

S. No.	Description of the item	Qty	Unit	Rate (₹)	Amount (₹)
6	Fabrication and fixing <b>angles</b> with lugs of required dia welded to the insert plates. (Structural Steel, electrodes and gas required for work will be issued on free of cost by BHEL at their stores) as directed by Engineer-in-charge etc., complete.	1.44	MT	3,500.00	5,040.00
<b>Sub Total</b>				₹	<b>10,46,010.82</b>
<b>Add increase in Vat 1% over the material cost (70% of contractor scope)</b>				₹	7322.08
<b>Total value of work</b>				₹	<b>10,53,332.90</b>
<b>Total : ₹ Ten lakhs fifty three thousand three hundred thirty two and ninety paise only</b>					

**Note:-** The required cement and steel will be issued on free of cost at BHEL stores other than Ready mix concrete items.

1	A penalty of 0.5% of the gross value of work will be levied for every week's delay of work subject to a maximum penalty of 10% of the gross value of work.
2	Service tax is extra as applicable, which will be reimbursable to the agency on production of paid proof documents.
3	The rates are inclusive of all taxes and duties.

**Note :** The bidders are required to quote the tender value on percentage (%) basis at excess or less or on par with estimate value in figures and words.

Tender %	In figure	In words
Excess		
Less		
Estimated value		

Name of the Contractor :

Signature of the Contractor